

Introduction	Introduction	3
	Morrison System Finishes	4
	Knoll Color Program	5
	Morrison System Legacy Finishes	6
Panel Planning	Panels	8
	Doors	40
	Windows	42
	Markerboard and combination add-on panels	44
	Upholstered add-on panels	45
	Upholstered Options add-on panels	46
	Veneer and combination add-on panels	47
	Add-on connectors, post assemblies	49
	Connectors, post assemblies	53
	High-low connectors	59
	High-low post assemblies	61
	Panel accessories	67
	Trim covers for reconfiguration	69
	Morrison Access	71
	Currents trim for Morrison	77
	Top cap and raceway cover kits	78
	High-low top caps	80
	PDC and multiple outlet covers	81
	Stackable add-up panels	82
	Stackable add-up connectors and trim caps	85
	Power distribution components	88
	Power distribution	101
	Worksurface Planning	Worksurfaces, 1 3/4"
Conference worksurfaces, 1 3/4"		110
Worksurfaces, 1 1/4"		111
Morrison Options worksurfaces, 1 1/4"		126
Currents worksurfaces for Morrison		137
Cascade edge worksurfaces		143
Universal and conference desk end panels		150
VDT corner and transitional end panels		151
Kneehole filler and transitional filler panels		152
Return and bridge filler panels		153
Brackets		154
Morrison Network Desk System		160
Power distribution components		166

Storage	Floorstanding pedestals	174
	Double-width floorstanding pedestals and cabinets	175
	Mobile pedestals	177
	Pedestal accessories	178
	Intermediate shelves	179
	Aluminum shelf	180
	Shelves and flush counter surfaces, 1 3/4"	181
	Shelves and flush counter surfaces, 1 1/4"	183
	Morrison overhead cabinets	185
	Task lights for panel or wall mounted storage	186
	Morrison Network overhead storage	187
	Overhead Storage	190
	Morrison Options overhead cabinets and shelves	191
	Morrison Options	192
	Reuter open shelf	194
	Reuter open overhead	195
	Reuter overhead cabinet	196
	Reuter overhead storage	200
	Reuter flat front overhead cabinet	202
	T5 Task Light for Reuter Overhead Storage	203
	Morrison Network privacy screens	204
	Kiosk vertical storage	207
Accessories	Accessories	208
Alpha-Numeric Index		209
Selling Policy		218
KnollKey Lock Program		220
General Ordering Information		221

This price list provides you with the product information you need to specify and order Knoll Morrison.

Morrison is a completely integrated office system, capable of all types of office planning. Morrison may plan as a panel system, with panel mounted components, or as a freestanding desk system. Morrison can also be combined with the Currents service wall for superior wire management, cable access and off-module planning. Major components – panels, worksurfaces and storage – may be configured or reconfigured in all types of planning listed above.

Information about Morrison is found in three companion books: this Price List, the Planning Guide and the Brochure.

The Price List arranges components in a logical sequence.

The first section includes all major components required for panel system planning: Morrison and Options panels, add-on panels, connectors, doors, Morrison Access, top cap kits, stackable add-up panels and power distribution.

The second section includes those components required for worksurface planning and support: Morrison and Options worksurfaces, Currents worksurfaces for Morrison, desk panels, Morrison Network desk supports, brackets, and power components.

The third section includes storage components for panel based or freestanding planning: pedestals, Intermediate shelves, Morrison, Options and Reuter overhead storage and lighting, screens, and vertical storage.

The fourth section includes accessories. The complete range of computer support and accessories can be found in the KnollExtra price list.

#### How to order Morrison

Morrison is a component-based system. To ensure a complete order for a workstation or project, specify components in the same order as the price list.

You will find that Morrison pattern numbers contain a logical, alphanumeric sequence describing the type, size, features, and finish of the component.

To specify components, consult the ordering code examples and application notes provided.

For example, to order a 1<sup>3</sup>/<sub>4</sub>" light grey laminate worksurface with grommets, 48"W by 24"D specify: **MW2-S4824A114**. Details follow:

<b>MW2</b>	1 <sup>3</sup> / <sub>4</sub> " worksurface
<b>S</b>	Straight
<b>48</b>	Width
<b>24</b>	Depth
<b>A</b>	With grommets
<b>114</b>	Folkstone Grey laminate

For further assistance with ordering or specifying Morrison, consult your Knoll representative or Knoll dealer.

Please note that pattern numbers beginning with the letter **A-** are Currents pattern numbers.

**KNOLLTEXTILES**

**Approved for vertical panels and privacy screens.**

*Fabric Group 10*

Bailey II (W359)  
Broadcloth (W288)  
Element (W1077)  
Foundation (W351)  
Growth Spurt (W692)  
Newbury (W812)  
Solid Crepe (W257)  
Symbolic Details (W693)  
Tailor Made (W133)  
Versatility (W432)

*Fabric Group 15*

Belgrade (W256)  
Marche (W321)  
Regency/Fairfield (W210/B)

*Fabric Group 20*

Banyan (W443)  
Bauhaus Block (W296)  
Boardwalk (W911)  
Clarity (W281)  
Criss Cross (W305)  
Devon (W809)  
Frequency (W340)  
Labyrinth (W352)  
Litchfield (W808)  
Melbourne (W228)  
Outback (W229)  
Reflect (W884)  
Resolution (W280)  
Walkabout (W230)  
Weave Three (W298)

*Fabric Group 30*

Basket Draft (W249)  
Elan (W444)  
Flow (W565)  
Harmony (W232)  
Micro (W465)  
Peano (W234)  
Progression (W403)  
Progression Striae (W463)  
Promenade (W913)  
Raku Cloth (W566)  
Relay (W1020)  
Walls of Rain (W923)

*Fabric Group 35*

Saxony Plus (S)

*Fabric Group 40*

Analogy (K614)  
Bardo (W284)  
Boxstep (W325)  
Eurythmic (W268)  
Foil Rap (W535)  
Freefall (W922)  
Hard Rock (W1007)  
Metaphor (K612)  
Ornament (W1078)  
Palladium (W1030)  
Sennit (W337)  
Sierra ( R )  
Spinoff Nuance (W319)

*Fabric Group 45*

Backdrop (W302) \*  
Casual Elegance (W920)  
Digital Tape (W304)\*  
Dristi (K872) with backing only  
Fast Forward (W301)\*

**\*Not available for upholstered connector trim covers**

The following textiles are approved for use on Morrison panels. Consult your Knoll representative for pricing:

Breakers  
Double Dash  
Glo  
Ingot  
Jump Rope Poly  
Mesh Poly  
Presto  
Ricochet  
Stacked Boxes  
Transition

**Ported panels can only be upholstered with textiles approved for application on Reff panels.**

Customer's Own Material is subject to an application testing fee of \$750 per fabric and a \$2500 fee for UL testing. Fabric requirements - application test, 10 yards; UL test, 15 yards. COM is also subject to extended leadtimes. COM panels are priced at Group 10 plus cost of fabric.

# Knoll Color Program

## Morrison System Finishes

Morrison

### Core finishes

Specify Core finishes for all new customers

Core	Legacy	Top caps and trim, Panels (veneer only)	Glazed panel, window, door frames (textured)	Desk panels, storage fronts Hinged doors	Desk supports, stanchion, storage, brackets, raceway covers	Work-surfaces and shelves (all)	Work-surfaces and shelves (post-formed)	Cascade Edge work-surfaces	Pedestals and Reuter Over-head
611	Beige Mist Metallic	•	•	•	•				P2
118	Bright White	•	•	•	•	•	•	•	P3
112	Brown	•	•	•	•				P1
113	Dark Grey	Y3	•	•	•				P1
114	Folkstone Grey	LA	•	•	•	•	•	•	P1
111	Jet Black		•	•	•	•	•		P1
115	Medium Grey	Y2	•	•	•	•			P1
612	Medium Metallic Grey	J	•	•	•	•			P2
119	Pumice	F				•	•	•	
116	Sandstone		•	•	•	•			P1
613	Silver	3	•	•	•	•			P3
117	Soft Grey	E/M42	•	•	•	•		•	P1
128	Fog	G				•	•		
129	Micro Sand						•		
121	Micro Grey						•		
122	Brushed Sand						•		
123	Brushed Grey						•		
124	Medium Cherry						•	•	
125	Natural Maple						•	•	
126	Natural Cherry						•	•	
127	Walnut						•	•	
	Natural Techgrain®	V1	T		T		T		T
	Maple Techgrain®	V2	4		M		4		M
	Cherry Techgrain®	V2	6		R		6		R
	Medium brown mahogany Techgrain®	V2	7		I		7		I
	Medium red mahogany Techgrain®	V2	8		C		8		C
	American cherry Techgrain®	V2	9		P		9		P
	Maple	V3	K		K		K		K
	American cherry	V3	X		X		X		X
	Medium red mahogany	V3	Z		Z		Z		Z

This price list contains pricing for Core finishes. For detailed pricing of Legacy finishes, please refer to the latest release of CAP worksheet or contact your customer service representative.

The new, Core P1 finishes in Morrison have the same list prices as P2. Additionally, Pedestals and Reuter overhead storage have a separate P3 price point for Silver and Bright White.

The new Core finish 113 Dark Grey is not a match to the Morrison Legacy finish NV. It is a match to the Dividends Legacy finish Y3.

The new Core finish 115 Medium Grey is not a match to the Morrison Legacy finish NJ. It is a match to the Dividends Legacy finish Y2.

Patterned laminates (Micro, Brushed and Wood grain laminates) are available on Morrison postformed worksurfaces and shelves (straight, trapezoidal, VDT).

		Work-surfaces	Panels	Desk Panels	Shelves	Top caps/ Trim covers	Glazed Panel/ Window/ Door Frames*	Storage fronts	Storage Cases	Desk Supports, Stanchions, Steel shelves, brackets, raceway covers
Plastic Laminates	Light Grey	L			L					
	Medium Grey	G			G					
	Sand	D			D					
	Pumice	F			F					
	Snow	B			B					
Wood Grain Laminates	Clear Maple (Currents for Morrison worksurfaces only)	CM								
Veneer Group 1	Natural Techgrain®	T	T	T	T	T		T		
Veneer Group 2	Maple Techgrain®	4	4	M	4	4		M		
	Cherry Techgrain®	6	6	R	6	6		R		
	Medium brown mahogany Techgrain®	7	7	I	7	7		I		
	Medium red mahogany Techgrain®	8	8	C	8	8		C		
	American cherry Techgrain®	9	9	P	9	9		P		
Veneer Group 3	Maple	K	K	K	K	K		K		
	American cherry	X	X	X	X	X		X		
	Medium red mahogany	Z	Z	Z	Z	Z		Z		
Paint Group 1 and Integral Colors for Top caps and Trim covers	Flint			N2		N2		N2		
	Light grey			NU		NU		NU		
	Medium grey			NJ		NJ		NJ		
	Dark grey			NV		NV		NV		
	Light tan			NW		NW		NW		
	Beige			NH		NH		NH		
Paint Group 2	Metallic Flint			2		2	2	2	2	2
	Light metallic grey			U		U	U	U	U	U
	Medium metallic grey			J		J	J	J	J	J
	Dark metallic grey			V		V	V	V	V	V
	Light metallic tan			W		W	W	W	W	W
	Metallic beige			H		H	H	H	H	H
Paint Group 3	Silver			3		3	3	3	3	3
	White			B		B	B	B	B	B

\* Paint finishes for glazed panels, window and door frames are textured only. Specify legacy finishes to match existing product only. Legacy finishes are not available for new customers.



This price list contains pricing for Core finishes. For detailed pricing of Legacy finishes, please refer to the latest release of CAP worksheet or contact your customer service representative.

**This page intentionally left blank**

# Panels

## 30" H upholstered

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	30"	<b>MP2-3018-()</b>	\$304.	\$334.	\$343.	\$396.	\$418.	\$457.	\$486.
	24"	2 1/4"	30"	<b>MP2-3024-()</b>	332.	380.	393.	452.	467.	498.	540.
	30"	2 1/4"	30"	<b>MP2-3030-()</b>	374.	417.	432.	495.	509.	540.	599.
	36"	2 1/4"	30"	<b>MP2-3036-()</b>	415.	467.	482.	552.	572.	614.	672.
	42"	2 1/4"	30"	<b>MP2-3042-()</b>	471.	527.	540.	621.	642.	682.	757.
	48"	2 1/4"	30"	<b>MP2-3048-()</b>	513.	574.	591.	678.	712.	770.	826.
	60"	2 1/4"	30"	<b>MP2-3060-()</b>	595.	671.	689.	791.	820.	884.	954.
 Options panels, upholstered both sides	18"	2 1/4"	30"	<b>MP2-3018-N()</b>	287.	306.	316.	363.	385.	417.	445.
	24"	2 1/4"	30"	<b>MP2-3024-N()</b>	314.	350.	362.	414.	428.	458.	497.
	30"	2 1/4"	30"	<b>MP2-3030-N()</b>	350.	382.	396.	454.	465.	497.	550.
	36"	2 1/4"	30"	<b>MP2-3036-N()</b>	390.	428.	442.	507.	525.	563.	616.
	42"	2 1/4"	30"	<b>MP2-3042-N()</b>	444.	483.	497.	570.	589.	627.	695.
	48"	2 1/4"	30"	<b>MP2-3048-N()</b>	483.	527.	540.	622.	652.	707.	758.
	60"	2 1/4"	30"	<b>MP2-3060-N()</b>	559.	614.	632.	725.	754.	812.	875.

Order Code	Specification Information	Application Notes
Example: <b>MP2-3030-15-W210/20</b> <b>MP2</b> Panel <b>30</b> Height <b>30</b> Width <b>15</b> Surface type and group no. <b>W210/20</b> Upholstery	<i>Surface type/finish suffixes</i> For upholstered panels, specify upholstery pattern number after the fabric group number. 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  Fabric Groups can be found on page 4.  Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.  For combinations of fabrics list both suffixes (e.g. 10/20) and upholstery pattern numbers.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  <i>High performance panel acoustical ratings:</i> NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.



# Panels

## 30" H glazed




description	w	d	h	pattern no.	C/T
Glazed panels 	18"	2 1/4"	30"	<b>MP2-3018-C/T-( )</b>	\$678.
	24"	2 1/4"	30"	<b>MP2-3024-C/T-( )</b>	758.
	30"	2 1/4"	30"	<b>MP2-3030-C/T-( )</b>	842.
	36"	2 1/4"	30"	<b>MP2-3036-C/T-( )</b>	909.
	42"	2 1/4"	30"	<b>MP2-3042-C/T-( )</b>	1,017.
	48"	2 1/4"	30"	<b>MP2-3048-C/T-( )</b>	1,096.

Order Code	Specification Notes	Application Notes
Example: <b>MP2-3030-T-3</b> <b>MP2</b> Panel <b>30</b> Height <b>30</b> Width <b>T</b> Translucent acrylic glazing <b>613</b> Frame finish	For glazed panels specify: C- Clear tempered glass T- Translucent acrylic  Frame finish	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  Glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.  High performance panel acoustical ratings: NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 30"H combination veneer/upholstery

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	30"	<b>MP2-3018-(-)(-)</b>	\$431.	\$443.	\$446.	\$472.	\$486.	\$502.	\$518.
	24"	2 1/4"	30"	<b>MP2-3024-(-)(-)</b>	474.	496.	501.	532.	538.	554.	575.
	30"	2 1/4"	30"	<b>MP2-3030-(-)(-)</b>	528.	541.	550.	582.	589.	606.	636.
	36"	2 1/4"	30"	<b>MP2-3036-(-)(-)</b>	585.	606.	613.	648.	657.	679.	705.
	42"	2 1/4"	30"	<b>MP2-3042-(-)(-)</b>	651.	673.	680.	722.	730.	753.	789.
	48"	2 1/4"	30"	<b>MP2-3048-(-)(-)</b>	725.	748.	758.	798.	817.	846.	875.
 Combination Veneer 2/upholstery	18"	2 1/4"	30"	<b>MP2-3018-(-)(-)</b>	474.	488.	490.	518.	531.	548.	563.
	24"	2 1/4"	30"	<b>MP2-3024-(-)(-)</b>	511.	533.	538.	568.	575.	591.	613.
	30"	2 1/4"	30"	<b>MP2-3030-(-)(-)</b>	571.	588.	595.	626.	633.	650.	679.
	36"	2 1/4"	30"	<b>MP2-3036-(-)(-)</b>	627.	649.	655.	694.	702.	724.	753.
	42"	2 1/4"	30"	<b>MP2-3042-(-)(-)</b>	725.	748.	758.	798.	817.	846.	875.
	48"	2 1/4"	30"	<b>MP2-3048-(-)(-)</b>	818.	847.	858.	909.	924.	956.	991.
 Combination Veneer 3/upholstery	18"	2 1/4"	30"	<b>MP2-3018-(-)(-)</b>	570.	585.	589.	622.	636.	656.	675.
	24"	2 1/4"	30"	<b>MP2-3024-(-)(-)</b>	614.	640.	647.	681.	689.	710.	735.
	30"	2 1/4"	30"	<b>MP2-3030-(-)(-)</b>	686.	704.	713.	752.	761.	781.	816.
	36"	2 1/4"	30"	<b>MP2-3036-(-)(-)</b>	754.	779.	788.	831.	843.	869.	903.
	42"	2 1/4"	30"	<b>MP2-3042-(-)(-)</b>	870.	899.	908.	959.	980.	1,016.	1,049.
	48"	2 1/4"	30"	<b>MP2-3048-(-)(-)</b>	981.	1,017.	1,030.	1,091.	1,109.	1,146.	1,188.

Order Code	Specification Information	Application Notes														
Example: <b>MP2-3030-8-15-W210/20</b>	When specifying combination panels, follow panel size with veneer finish code, the upholstery finish code and pattern number.	<p><i>Surface type/finish suffixes</i></p> For upholstered panels, specify upholstery pattern number after the fabric group number.														
<table border="0"> <tr><td><b>MP2</b></td><td>Panel</td></tr> <tr><td><b>30</b></td><td>Height</td></tr> <tr><td><b>30</b></td><td>Width</td></tr> <tr><td><b>8</b></td><td>Veneer finish</td></tr> <tr><td><b>15</b></td><td>Fabric group</td></tr> <tr><td><b>W210/20</b></td><td>Upholstery</td></tr> </table>			<b>MP2</b>	Panel	<b>30</b>	Height	<b>30</b>	Width	<b>8</b>	Veneer finish	<b>15</b>	Fabric group	<b>W210/20</b>	Upholstery		
<b>MP2</b>	Panel															
<b>30</b>	Height															
<b>30</b>	Width															
<b>8</b>	Veneer finish															
<b>15</b>	Fabric group															
<b>W210/20</b>	Upholstery															
	<table border="0"> <tr><td>10-</td><td>Fabric group 10</td></tr> <tr><td>15-</td><td>Fabric group 15</td></tr> <tr><td>20-</td><td>Fabric group 20</td></tr> <tr><td>30-</td><td>Fabric group 30</td></tr> <tr><td>35-</td><td>Fabric group 35</td></tr> <tr><td>40-</td><td>Fabric group 40</td></tr> <tr><td>45-</td><td>Fabric group 45</td></tr> </table>	10-	Fabric group 10	15-	Fabric group 15	20-	Fabric group 20	30-	Fabric group 30	35-	Fabric group 35	40-	Fabric group 40	45-	Fabric group 45	<p>Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.</p> <p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>Veneer Group 1 vertical panels are quartered Techgrain®.</p> <p>Veneer Group 2 vertical panels are rift cut Techgrain®.</p> <p>Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.</p> <p>60"W panels are not available with veneer surfaces.</p>
10-	Fabric group 10															
15-	Fabric group 15															
20-	Fabric group 20															
30-	Fabric group 30															
35-	Fabric group 35															
40-	Fabric group 40															
45-	Fabric group 45															

# Panels

## 30" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
 Veneer both sides	18"	2 1/4"	30"	<b>MP2-3018-V-( )</b>	\$550.	\$640.	\$765.
	24"	2 1/4"	30"	<b>MP2-3024-V-( )</b>	610.	682.	820.
	30"	2 1/4"	30"	<b>MP2-3030-V-( )</b>	671.	759.	911.
	36"	2 1/4"	30"	<b>MP2-3036-V-( )</b>	742.	832.	998.
	42"	2 1/4"	30"	<b>MP2-3042-V-( )</b>	819.	922.	1,107.
	48"	2 1/4"	30"	<b>MP2-3048-V-( )</b>	922.	1,026.	1,233.



Panel Planning

Order Code	Specification Information	Application Notes
Example: <b>MP2-3030-V-8</b>	<i>For veneer panels specify:</i>	<p>Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.</p> <p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>Veneer Group 1 vertical panels are quartered Techgrain®.</p> <p>Veneer Group 2 vertical panels are rift cut Techgrain®.</p> <p>Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.</p> <p>60"W panels are not available with veneer surfaces</p>
<b>MP2</b> Panel	<i>Veneer finish</i>	
<b>30</b> Height		
<b>30</b> Width		
<b>V</b> Veneer both sides		
<b>8</b> Veneer finish		

# Panels

## 39"H upholstered

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	39"	<b>MP2-3918-( )</b>	\$330.	\$364.	\$373.	\$431.	\$455.	\$495.	\$528.
	24"	2 1/4"	39"	<b>MP2-3924-( )</b>	362.	415.	429.	491.	508.	541.	589.
	30"	2 1/4"	39"	<b>MP2-3930-( )</b>	407.	454.	469.	537.	553.	589.	652.
	36"	2 1/4"	39"	<b>MP2-3936-( )</b>	451.	508.	525.	598.	622.	669.	729.
	42"	2 1/4"	39"	<b>MP2-3942-( )</b>	512.	572.	589.	675.	698.	742.	820.
	48"	2 1/4"	39"	<b>MP2-3948-( )</b>	558.	624.	643.	737.	772.	839.	900.
	60"	2 1/4"	39"	<b>MP2-3960-( )</b>	648.	727.	751.	859.	892.	960.	1,038.
 Options panels, upholstered both sides	18"	2 1/4"	39"	<b>MP2-3918-N( )</b>	314.	333.	342.	393.	416.	454.	484.
	24"	2 1/4"	39"	<b>MP2-3924-N( )</b>	339.	379.	392.	450.	465.	497.	539.
	30"	2 1/4"	39"	<b>MP2-3930-N( )</b>	380.	415.	431.	492.	507.	539.	598.
	36"	2 1/4"	39"	<b>MP2-3936-N( )</b>	424.	465.	481.	550.	570.	612.	670.
	42"	2 1/4"	39"	<b>MP2-3942-N( )</b>	483.	526.	539.	620.	641.	680.	754.
	48"	2 1/4"	39"	<b>MP2-3948-N( )</b>	526.	572.	589.	676.	709.	769.	822.
	60"	2 1/4"	39"	<b>MP2-3960-N( )</b>	608.	669.	687.	789.	818.	881.	951.

Order Code	Specification Information	Application Notes
Example: <b>MP2-3930-15-W210/20</b> <b>MP2</b> Panel <b>39</b> Height <b>30</b> Width <b>15</b> Surface type and group no. <b>W210/20</b> Upholstery	<i>Surface type/finish suffixes</i>  For upholstered panels, specify upholstery pattern number after the fabric group number.  10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.  For combinations of fabrics list both suffixes (e.g. 10/20) and upholstery pattern numbers.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  <i>High performance panel acoustical ratings:</i> NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 39"H glazed

Morrison

description	w	d	h	pattern no.	C/T	F
Glazed panels 	18"	2 1/4"	39"	<b>MP2-3918-C/T/F- ( )</b>	\$753.	\$1,052.
	24"	2 1/4"	39"	<b>MP2-3924-C/T/F- ( )</b>	832.	1,165.
	30"	2 1/4"	39"	<b>MP2-3930-C/T/F- ( )</b>	924.	1,294.
	36"	2 1/4"	39"	<b>MP2-3936-C/T/F- ( )</b>	1,001.	1,403.
	42"	2 1/4"	39"	<b>MP2-3942-C/T/F- ( )</b>	1,117.	1,563.
	48"	2 1/4"	39"	<b>MP2-3948-C/T/F- ( )</b>	1,206.	1,689.

### Order Code

Example:	<b>MP2-3930-C-3</b>
<b>MP2</b>	Panel
<b>39</b>	Height
<b>30</b>	Width
<b>C</b>	Clear acrylic glazing
<b>613</b>	Frame finish

### Specification Information

*For glazed panels specify:*

C- Clear tempered glass  
 T- Translucent acrylic  
 F- Divided translucent fiberglass

*Frame finish*

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.




*High performance panel acoustical ratings:*  
 NRC .80, STC 24

Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 39"H combination veneer/upholstery

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	39"	<b>MP2-3918-</b> (-)(-)	\$468.	\$482.	\$487.	\$513.	\$528.	\$547.	\$564.
	24"	2 1/4"	39"	<b>MP2-3924-</b> (-)(-)	516.	538.	545.	578.	585.	601.	624.
	30"	2 1/4"	39"	<b>MP2-3930-</b> (-)(-)	574.	590.	597.	632.	641.	657.	691.
	36"	2 1/4"	39"	<b>MP2-3936-</b> (-)(-)	634.	657.	668.	703.	715.	738.	766.
	42"	2 1/4"	39"	<b>MP2-3942-</b> (-)(-)	709.	732.	740.	784.	793.	817.	855.
	48"	2 1/4"	39"	<b>MP2-3948-</b> (-)(-)	788.	814.	822.	870.	887.	921.	951.
 Combination Veneer 2/upholstery	18"	2 1/4"	39"	<b>MP2-3918-</b> (-)(-)	516.	531.	533.	564.	576.	595.	612.
	24"	2 1/4"	39"	<b>MP2-3924-</b> (-)(-)	556.	578.	585.	619.	624.	643.	668.
	30"	2 1/4"	39"	<b>MP2-3930-</b> (-)(-)	621.	640.	648.	679.	688.	707.	738.
	36"	2 1/4"	39"	<b>MP2-3936-</b> (-)(-)	681.	705.	713.	753.	763.	786.	817.
	42"	2 1/4"	39"	<b>MP2-3942-</b> (-)(-)	788.	814.	822.	870.	887.	921.	951.
	48"	2 1/4"	39"	<b>MP2-3948-</b> (-)(-)	888.	922.	932.	990.	1,004.	1,039.	1,077.
 Combination Veneer 3/upholstery	18"	2 1/4"	39"	<b>MP2-3918-</b> (-)(-)	620.	636.	640.	676.	691.	713.	734.
	24"	2 1/4"	39"	<b>MP2-3924-</b> (-)(-)	669.	696.	702.	741.	751.	770.	798.
	30"	2 1/4"	39"	<b>MP2-3930-</b> (-)(-)	744.	765.	776.	816.	825.	847.	885.
	36"	2 1/4"	39"	<b>MP2-3936-</b> (-)(-)	818.	846.	855.	903.	915.	943.	980.
	42"	2 1/4"	39"	<b>MP2-3942-</b> (-)(-)	944.	974.	988.	1,042.	1,065.	1,106.	1,139.
	48"	2 1/4"	39"	<b>MP2-3948-</b> (-)(-)	1,067.	1,107.	1,120.	1,187.	1,205.	1,247.	1,293.

Order Code	Specification Information	Application Notes
Example: <b>MP2-3930-8-15-W210/20</b>	When specifying combination panels, follow panel size with veneer finish code, the upholstery finish code and pattern number.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  Veneer Group 1 vertical panels are quartered Techgrain®.  Veneer Group 2 vertical panels are rift cut Techgrain®.  Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.  60"W panels are not available with veneer surfaces.
<b>MP2</b> Panel <b>39</b> Height <b>30</b> Width <b>8</b> Veneer finish <b>15</b> Fabric group <b>W210/20</b> Upholstery		
	<i>Surface type/finish suffixes</i> For upholstered panels, specify upholstery pattern number after the fabric group number.  10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45	

# Panels

## 39" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
 Veneer both sides	18"	2 1/4"	39"	<b>MP2-3918-V-( )</b>	\$597.	\$696.	\$833.
	24"	2 1/4"	39"	<b>MP2-3924-V-( )</b>	663.	742.	891.
	30"	2 1/4"	39"	<b>MP2-3930-V-( )</b>	727.	823.	990.
	36"	2 1/4"	39"	<b>MP2-3936-V-( )</b>	808.	904.	1,085.
	42"	2 1/4"	39"	<b>MP2-3942-V-( )</b>	889.	1,001.	1,203.
	48"	2 1/4"	39"	<b>MP2-3948-V-( )</b>	1,001.	1,117.	1,339.


Panel Planning


Order Code	Specification Information	Application Notes
Example: <b>MP2-3930-V-8</b>	<i>For veneer panels specify:</i>	<p>Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.</p> <p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>Veneer Group 1 vertical panels are quartered Techgrain®.</p> <p>Veneer Group 2 vertical panels are rift cut Techgrain®.</p> <p>Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.</p> <p>60"W panels are not available with veneer surfaces.</p>
<b>MP2</b> Panel	<i>Veneer finish</i>	
<b>39</b> Height		
<b>30</b> Width		
<b>V</b> Veneer both sides		
<b>8</b> Veneer finish		

# Panels

## 42" H upholstered

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	42"	<b>MP2-4218-( )</b>	\$348.	\$385.	\$392.	\$452.	\$480.	\$521.	\$555.
	24"	2 1/4"	42"	<b>MP2-4224-( )</b>	379.	439.	451.	517.	534.	571.	620.
	30"	2 1/4"	42"	<b>MP2-4230-( )</b>	428.	478.	493.	566.	581.	620.	686.
	36"	2 1/4"	42"	<b>MP2-4236-( )</b>	474.	534.	552.	629.	654.	702.	766.
	42"	2 1/4"	42"	<b>MP2-4242-( )</b>	539.	601.	620.	711.	734.	783.	864.
	48"	2 1/4"	42"	<b>MP2-4248-( )</b>	588.	656.	676.	775.	815.	881.	946.
	60"	2 1/4"	42"	<b>MP2-4260-( )</b>	680.	765.	789.	905.	939.	1,011.	1,091.

Options panels, upholstered both sides	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options panels, upholstered both sides	18"	2 1/4"	42"	<b>MP2-4218-N( )</b>	328.	351.	359.	415.	440.	478.	509.
	24"	2 1/4"	42"	<b>MP2-4224-N( )</b>	357.	401.	414.	473.	490.	525.	568.
	30"	2 1/4"	42"	<b>MP2-4230-N( )</b>	402.	439.	452.	518.	533.	568.	629.
	36"	2 1/4"	42"	<b>MP2-4236-N( )</b>	446.	490.	506.	578.	599.	644.	703.
	42"	2 1/4"	42"	<b>MP2-4242-N( )</b>	508.	553.	568.	652.	674.	716.	793.
	48"	2 1/4"	42"	<b>MP2-4248-N( )</b>	553.	601.	620.	712.	744.	810.	866.
	60"	2 1/4"	42"	<b>MP2-4260-N( )</b>	641.	702.	724.	830.	861.	928.	1,000.

Order Code	Specification Information	Application Notes
Example: <b>MP2-4230-15-W210/20</b> <b>MP2</b> Panel <b>42</b> Height <b>30</b> Width <b>15</b> Surface type and group no. <b>W210/20</b> Upholstery	<p><i>Surface type/finish suffixes</i></p> <p>For upholstered panels, specify upholstery pattern number after the fabric group number.</p> <p>10- Fabric group 10            15- Fabric group 15            20- Fabric group 20            30- Fabric group 30            35- Fabric group 35            40- Fabric group 40            45- Fabric group 45</p> <p>Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.</p> <p>For combinations of fabrics list both suffixes (e.g. 10/20) and upholstery pattern numbers.</p>	<p>Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.</p> <p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>Acrylic glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.</p> <p><i>High performance panel acoustical ratings:</i>            NRC .80, STC 24</p> <p>Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.</p>




# Panels

## 42" H glazed

Morrison

Panel Planning




description	w	d	h	pattern no.	C/T
Glazed panels 	18"	2 1/4"	42"	<b>MP2-4218-C/T-( )</b>	\$792.
	24"	2 1/4"	42"	<b>MP2-4224-C/T-( )</b>	876.
	30"	2 1/4"	42"	<b>MP2-4230-C/T-( )</b>	972.
	36"	2 1/4"	42"	<b>MP2-4236-C/T-( )</b>	1,054.
	42"	2 1/4"	42"	<b>MP2-4242-C/T-( )</b>	1,175.
	48"	2 1/4"	42"	<b>MP2-4248-C/T-( )</b>	1,270.

Order Code	Specification Notes	Application Notes
Example: <b>MP2-4230-T-613</b> <hr/> <b>MP2</b> Panel <hr/> <b>42</b> Height <hr/> <b>30</b> Width <hr/> <b>T</b> Translucent acrylic glazing <hr/> <b>613</b> Frame finish	For glazed panels specify: C- Clear tempered glass T- Translucent acrylic  Frame finish	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  Glazed glazed panels may not be powered. 60"W glazed panels are not available.  High performance panel acoustical ratings: NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 42"H combination veneer/upholstery

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	42"	MP2-4218-(-)(-)	\$492.	\$507.	\$511.	\$540.	\$555.	\$575.	\$594.
	24"	2 1/4"	42"	MP2-4224-(-)(-)	542.	567.	574.	609.	617.	633.	657.
	30"	2 1/4"	42"	MP2-4230-(-)(-)	604.	621.	628.	668.	674.	695.	727.
	36"	2 1/4"	42"	MP2-4236-(-)(-)	670.	695.	701.	739.	754.	776.	808.
	42"	2 1/4"	42"	MP2-4242-(-)(-)	744.	769.	781.	823.	835.	860.	902.
	48"	2 1/4"	42"	MP2-4248-(-)(-)	828.	857.	866.	915.	933.	969.	1,001.
 Combination Veneer 2/upholstery	18"	2 1/4"	42"	MP2-4218-(-)(-)	542.	558.	562.	594.	606.	626.	644.
	24"	2 1/4"	42"	MP2-4224-(-)(-)	585.	610.	617.	651.	657.	676.	701.
	30"	2 1/4"	42"	MP2-4230-(-)(-)	653.	673.	680.	715.	725.	743.	776.
	36"	2 1/4"	42"	MP2-4236-(-)(-)	717.	742.	752.	791.	803.	826.	860.
	42"	2 1/4"	42"	MP2-4242-(-)(-)	828.	857.	866.	915.	933.	969.	1,001.
	48"	2 1/4"	42"	MP2-4248-(-)(-)	935.	970.	981.	1,040.	1,056.	1,092.	1,133.
 Combination Veneer 3/upholstery	18"	2 1/4"	42"	MP2-4218-(-)(-)	652.	670.	674.	712.	727.	752.	771.
	24"	2 1/4"	42"	MP2-4224-(-)(-)	702.	733.	739.	782.	791.	812.	841.
	30"	2 1/4"	42"	MP2-4230-(-)(-)	785.	807.	817.	859.	870.	892.	932.
	36"	2 1/4"	42"	MP2-4236-(-)(-)	861.	891.	901.	950.	963.	994.	1,034.
	42"	2 1/4"	42"	MP2-4242-(-)(-)	995.	1,027.	1,040.	1,097.	1,121.	1,163.	1,203.
	48"	2 1/4"	42"	MP2-4248-(-)(-)	1,122.	1,165.	1,177.	1,248.	1,270.	1,310.	1,360.

Order Code	Specification Information	Application Notes
Example: <b>MP2-4230-8-15-W210/20</b> <hr/> <b>MP2</b> Panel <hr/> <b>42</b> Height <hr/> <b>30</b> Width <hr/> <b>8</b> Veneer finish <hr/> <b>15</b> Fabric group <hr/> <b>W210/20</b> Upholstery	When specifying combination panels, follow panel size with veneer finish code, then upholstery finish code and pattern number.	<i>Surface type/finish suffixes</i> For upholstered panels, specify upholstery pattern number after the fabric group number. 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45
		Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  Veneer Group 1 vertical panels are quartered Techgrain®.  Veneer Group 2 vertical panels are rift cut Techgrain®.  Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.  60"W panels are not available with veneer surfaces.

# Panels

## 42" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
 Veneer both sides	18"	2 1/4"	42"	<b>MP2-4218-V-( )</b>	\$628.	\$732.	\$877.
	24"	2 1/4"	42"	<b>MP2-4224-V-( )</b>	699.	783.	938.
	30"	2 1/4"	42"	<b>MP2-4230-V-( )</b>	765.	869.	1,041.
	36"	2 1/4"	42"	<b>MP2-4236-V-( )</b>	850.	953.	1,143.
	42"	2 1/4"	42"	<b>MP2-4242-V-( )</b>	936.	1,054.	1,265.
	48"	2 1/4"	42"	<b>MP2-4248-V-( )</b>	1,054.	1,175.	1,410.


Panel Planning


Order Code	Specification Information	Application Notes
Example: <b>MP2-4230-V-8</b>	<i>For veneer panels specify:</i>	<p>Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.</p> <p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>Veneer Group 1 vertical panels are quartered Techgrain®.</p> <p>Veneer Group 2 vertical panels are rift cut Techgrain®.</p> <p>Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.</p> <p>60"W panels are not available with veneer surfaces</p>
<b>MP2</b> Panel	<i>Veneer finish</i>	
<b>42</b> Height		
<b>30</b> Width		
<b>V</b> Veneer both sides		
<b>8</b> Veneer finish		

# Panels

## 48" H upholstered

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	48"	<b>MP2-4818(-)</b>	\$382.	\$420.	\$432.	\$497.	\$527.	\$574.	\$610.
	24"	2 1/4"	48"	<b>MP2-4824(-)</b>	418.	481.	496.	568.	589.	627.	681.
	30"	2 1/4"	48"	<b>MP2-4830(-)</b>	470.	526.	541.	622.	642.	681.	756.
	36"	2 1/4"	48"	<b>MP2-4836(-)</b>	524.	589.	606.	696.	718.	771.	844.
	42"	2 1/4"	48"	<b>MP2-4842(-)</b>	594.	661.	681.	783.	807.	860.	952.
	48"	2 1/4"	48"	<b>MP2-4848(-)</b>	647.	723.	743.	853.	896.	970.	1,040.
	60"	2 1/4"	48"	<b>MP2-4860(-)</b>	724.	842.	869.	996.	1,020.	1,113.	1,200.

Options panels, upholstered both sides	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options panels, upholstered both sides	18"	2 1/4"	48"	<b>MP2-4818N( )</b>	359.	387.	396.	457.	483.	527.	559.
	24"	2 1/4"	48"	<b>MP2-4824N( )</b>	392.	441.	455.	521.	539.	575.	626.
	30"	2 1/4"	48"	<b>MP2-4830N( )</b>	442.	482.	497.	571.	588.	626.	694.
	36"	2 1/4"	48"	<b>MP2-4836N( )</b>	491.	539.	555.	636.	658.	709.	773.
	42"	2 1/4"	48"	<b>MP2-4842N( )</b>	558.	608.	626.	716.	739.	789.	873.
	48"	2 1/4"	48"	<b>MP2-4848N( )</b>	608.	661.	681.	783.	820.	889.	954.
	60"	2 1/4"	48"	<b>MP2-4860N( )</b>	679.	772.	795.	913.	935.	1,021.	1,099.


Order Code	Specification Information	Application Notes
Example: <b>MP2-4830-15-W210/20</b> <b>MP2</b> Panel <b>48</b> Height <b>30</b> Width <b>15</b> Surface type and group no. <b>W210/20</b> Upholstery	<i>Surface type/finish suffixes</i>  For upholstered panels, specify upholstery pattern number after the fabric group number.  10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.  For combinations of fabrics list both suffixes (e.g., 15/40) and upholstery pattern numbers.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  <i>High performance panel acoustical ratings:</i> NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 48" H glazed

Morrison

Panel Planning

description	w	d	h	pattern no.	C/T	F
Glazed panels 	18"	2 1/4"	48"	<b>MP2-4818-C/T/F- ( )</b>	\$823.	\$1,154.
	24"	2 1/4"	48"	<b>MP2-4824-C/T/F- ( )</b>	912.	1,276.
	30"	2 1/4"	48"	<b>MP2-4830-C/T/F- ( )</b>	1,013.	1,418.
	36"	2 1/4"	48"	<b>MP2-4836-C/T/F- ( )</b>	1,097.	1,537.
	42"	2 1/4"	48"	<b>MP2-4842-C/T/F- ( )</b>	1,223.	1,712.
	48"	2 1/4"	48"	<b>MP2-4848-C/T/F- ( )</b>	1,323.	1,852.

### Order Code

Example:	<b>MP2-4830-C-613</b>
<b>MP2</b>	Panel
<b>48</b>	Height
<b>30</b>	Width
<b>C</b>	Clear acrylic glazing
<b>613</b>	Frame finish

### Specification Information

*For glazed panels specify:*

C- Clear tempered glass  
 T- Translucent acrylic  
 F- Divided translucent fiberglass

*Frame finish*

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.




*High performance panel acoustical ratings:*  
 NRC .80, STC 24

Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 48"H combination veneer/upholstery

Morrison


description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	48"	<b>MP2-4818-(-)(-)</b>	\$525.	\$538.	\$542.	\$576.	\$591.	\$616.	\$630.
	24"	2 1/4"	48"	<b>MP2-4824-(-)(-)</b>	576.	604.	612.	648.	655.	676.	703.
	30"	2 1/4"	48"	<b>MP2-4830-(-)(-)</b>	637.	657.	669.	709.	715.	737.	773.
	36"	2 1/4"	48"	<b>MP2-4836-(-)(-)</b>	711.	737.	744.	790.	803.	828.	864.
	42"	2 1/4"	48"	<b>MP2-4842-(-)(-)</b>	793.	826.	836.	885.	899.	924.	970.
	48"	2 1/4"	48"	<b>MP2-4848-(-)(-)</b>	878.	915.	925.	979.	1,001.	1,039.	1,075.
 Combination Veneer 2/upholstery	18"	2 1/4"	48"	<b>MP2-4818-(-)(-)</b>	566.	580.	585.	619.	632.	656.	674.
	24"	2 1/4"	48"	<b>MP2-4824-(-)(-)</b>	612.	634.	646.	678.	691.	710.	737.
	30"	2 1/4"	48"	<b>MP2-4830-(-)(-)</b>	678.	701.	710.	752.	759.	781.	817.
	36"	2 1/4"	48"	<b>MP2-4836-(-)(-)</b>	754.	781.	788.	832.	845.	872.	906.
	42"	2 1/4"	48"	<b>MP2-4842-(-)(-)</b>	839.	873.	881.	931.	946.	971.	1,016.
	48"	2 1/4"	48"	<b>MP2-4848-(-)(-)</b>	930.	970.	980.	1,036.	1,055.	1,093.	1,130.
 Combination Veneer 3/upholstery	18"	2 1/4"	48"	<b>MP2-4818-(-)(-)</b>	679.	697.	702.	741.	759.	789.	808.
	24"	2 1/4"	48"	<b>MP2-4824-(-)(-)</b>	734.	762.	772.	815.	830.	851.	884.
	30"	2 1/4"	48"	<b>MP2-4830-(-)(-)</b>	815.	841.	851.	901.	911.	935.	980.
	36"	2 1/4"	48"	<b>MP2-4836-(-)(-)</b>	904.	935.	944.	998.	1,015.	1,045.	1,087.
	42"	2 1/4"	48"	<b>MP2-4842-(-)(-)</b>	1,005.	1,047.	1,056.	1,118.	1,136.	1,166.	1,218.
	48"	2 1/4"	48"	<b>MP2-4848-(-)(-)</b>	1,117.	1,165.	1,176.	1,243.	1,267.	1,313.	1,356.

Order Code	Specification Information	Application Notes
Example: <b>MP2-4830-8-15-W210/20</b>	When specifying combination panels, follow panel size with veneer finish code, then upholstery finish code and pattern number.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.
<b>MP2</b> Panel		
<b>48</b> Height	<i>Surface type/finish suffixes</i> For upholstered panels, specify upholstery pattern number after the fabric group number.	Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.
<b>30</b> Width		
<b>8</b> Veneer finish		
<b>15</b> Fabric group		
<b>W210/20</b> Upholstery		
		Veneer Group 1 vertical panels are quartered Techgrain®.
		Veneer Group 2 vertical panels are rift cut Techgrain®.
		Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.
		60"W panels are not available with veneer surfaces.

# Panels

## 48" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
 Veneer both sides	18"	2 1/4"	48"	<b>MP2-4818-V-( )</b>	\$655.	\$739.	\$887.
	24"	2 1/4"	48"	<b>MP2-4824-V-( )</b>	725.	791.	950.
	30"	2 1/4"	48"	<b>MP2-4830-V-( )</b>	793.	877.	1,052.
	36"	2 1/4"	48"	<b>MP2-4836-V-( )</b>	884.	969.	1,163.
	42"	2 1/4"	48"	<b>MP2-4842-V-( )</b>	991.	1,083.	1,299.
	48"	2 1/4"	48"	<b>MP2-4848-V-( )</b>	1,108.	1,217.	1,462.

Panel Planning

### Order Code

Example:	<b>MP2-4830-V-8</b>
<b>MP2</b>	Panel
<b>48</b>	Height
<b>30</b>	Width
<b>V</b>	Veneer both sides
<b>8</b>	Veneer finish

### Specification Information

For veneer panels specify:  
Veneer finish

### Application Notes

Panel pricing includes panel, surface selection, integral color top cap, raceway covers and, 4"-high empty raceway. Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Veneer Group 1 vertical panels are quartered Techgrain®.

Veneer Group 2 vertical panels are rift cut Techgrain®.


Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.


60"W panels are not available with veneer surfaces.

# Panels

## 56" H upholstered

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	56"	<b>MP2-5618(-)</b>	\$396.	\$467.	\$480.	\$552.	\$567.	\$605.	\$653.
	24"	2 1/4"	56"	<b>MP2-5624(-)</b>	457.	518.	534.	614.	641.	686.	751.
	30"	2 1/4"	56"	<b>MP2-5630(-)</b>	508.	589.	608.	697.	717.	766.	831.
	36"	2 1/4"	56"	<b>MP2-5636(-)</b>	555.	646.	661.	759.	796.	864.	930.
	42"	2 1/4"	56"	<b>MP2-5642(-)</b>	600.	699.	716.	822.	861.	930.	1,011.
	48"	2 1/4"	56"	<b>MP2-5648(-)</b>	649.	765.	789.	905.	939.	1,011.	1,092.
	60"	2 1/4"	56"	<b>MP2-5660(-)</b>	742.	878.	903.	1,036.	1,077.	1,158.	1,251.

Options panels, upholstered both sides	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options panels, upholstered both sides	18"	2 1/4"	56"	<b>MP2-5618N( )</b>	373.	428.	440.	506.	520.	554.	598.
	24"	2 1/4"	56"	<b>MP2-5624N( )</b>	429.	474.	490.	563.	587.	629.	687.
	30"	2 1/4"	56"	<b>MP2-5630N( )</b>	477.	539.	556.	637.	657.	703.	762.
	36"	2 1/4"	56"	<b>MP2-5636N( )</b>	521.	591.	608.	696.	732.	793.	854.
	42"	2 1/4"	56"	<b>MP2-5642N( )</b>	565.	641.	656.	757.	790.	854.	928.
	48"	2 1/4"	56"	<b>MP2-5648N( )</b>	610.	702.	724.	830.	861.	928.	1,001.
	60"	2 1/4"	56"	<b>MP2-5660N( )</b>	699.	805.	826.	950.	986.	1,062.	1,147.

### Order Code

Example:	<b>MP2-5630-15-W210/20</b>
<b>MP2</b>	Panel
<b>56</b>	Height
<b>30</b>	Width
<b>15</b>	Surface type and group no.
<b>W210/20</b>	Upholstery

### Specification Information

*Surface type/finish suffixes*  
*Upholstered panels:*

For upholstered panels, specify upholstery pattern number after the fabric group number.

- 10- Fabric group 10
- 15- Fabric group 15
- 20- Fabric group 20
- 30- Fabric group 30
- 35- Fabric group 35
- 40- Fabric group 40
- 45- Fabric group 45

Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.

For combinations of fabrics list both suffixes (e.g., 20/40) and upholstery pattern numbers.

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

*High performance panel acoustical ratings:*  
NRC .80, STC 24


Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.



# Panels

## 56"H glazed

Morrison

description	w	d	h	pattern no.	C/T
Glazed panels 	18"	2 1/4"	56"	<b>MP2-5618-C/T-( )</b>	\$885.
	24"	2 1/4"	56"	<b>MP2-5624-C/T-( )</b>	988.
	30"	2 1/4"	56"	<b>MP2-5630-C/T-( )</b>	1,090.
	36"	2 1/4"	56"	<b>MP2-5636-C/T-( )</b>	1,192.
	42"	2 1/4"	56"	<b>MP2-5642-C/T-( )</b>	1,327.
	48"	2 1/4"	56"	<b>MP2-5648-C/T-( )</b>	1,431.

### Order Code

Example:	<b>MP2-5630-C-613</b>
<b>MP2</b>	Panel
<b>56</b>	Height
<b>30</b>	Width
<b>C</b>	Clear acrylic glazing
<b>613</b>	Frame finish

### Specification Information

*For glazed panels specify:*  
 C- Clear tempered glass  
 T- Translucent acrylic

*Frame finish*  
 Panel stiffeners should be specified with glazed panels in straight or corner configurations. See page 40 .

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.


*High performance panel acoustical ratings:*  
 NRC .80, STC 24


Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.


# Panels

## 56" H combination veneer/upholstery

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
	18"	2 1/4"	56"	<b>MP2-5618-(-)(-)</b>	\$541.	\$574.	\$578.	\$617.	\$623.	\$644.	\$668.
	24"	2 1/4"	56"	<b>MP2-5624-(-)(-)</b>	609.	633.	644.	681.	696.	716.	751.
	30"	2 1/4"	56"	<b>MP2-5630-(-)(-)</b>	670.	703.	712.	757.	769.	793.	823.
	36"	2 1/4"	56"	<b>MP2-5636-(-)(-)</b>	744.	783.	791.	840.	859.	891.	925.
	42"	2 1/4"	56"	<b>MP2-5642-(-)(-)</b>	826.	870.	878.	930.	952.	983.	1,024.
	48"	2 1/4"	56"	<b>MP2-5648-(-)(-)</b>	912.	962.	973.	1,034.	1,050.	1,085.	1,125.

description	w	d	h	pattern no.	10	15	20	30	35	40	45
	18"	2 1/4"	56"	<b>MP2-5618-(-)(-)</b>	576.	609.	614.	651.	657.	676.	701.
	24"	2 1/4"	56"	<b>MP2-5624-(-)(-)</b>	633.	658.	669.	707.	717.	742.	773.
	30"	2 1/4"	56"	<b>MP2-5630-(-)(-)</b>	703.	737.	746.	790.	803.	826.	859.
	36"	2 1/4"	56"	<b>MP2-5636-(-)(-)</b>	779.	817.	823.	874.	891.	925.	959.
	42"	2 1/4"	56"	<b>MP2-5642-(-)(-)</b>	870.	912.	921.	972.	994.	1,026.	1,066.
	48"	2 1/4"	56"	<b>MP2-5648-(-)(-)</b>	963.	1,013.	1,024.	1,083.	1,099.	1,136.	1,177.

description	w	d	h	pattern no.	10	15	20	30	35	40	45
	18"	2 1/4"	56"	<b>MP2-5618-(-)(-)</b>	691.	732.	736.	782.	791.	812.	841.
	24"	2 1/4"	56"	<b>MP2-5624-(-)(-)</b>	761.	792.	799.	847.	861.	891.	929.
	30"	2 1/4"	56"	<b>MP2-5630-(-)(-)</b>	844.	884.	898.	948.	963.	994.	1,032.
	36"	2 1/4"	56"	<b>MP2-5636-(-)(-)</b>	933.	980.	990.	1,048.	1,070.	1,111.	1,152.
	42"	2 1/4"	56"	<b>MP2-5642-(-)(-)</b>	1,042.	1,093.	1,106.	1,167.	1,192.	1,233.	1,280.
	48"	2 1/4"	56"	<b>MP2-5648-(-)(-)</b>	1,158.	1,216.	1,228.	1,299.	1,323.	1,363.	1,413.

### Order Code

Example:	<b>MP2-5630-8-15-W210/20</b>
<b>MP2</b>	Panel
<b>56</b>	Height
<b>30</b>	Width
<b>8</b>	Veneer finish
<b>15</b>	Fabric group no.
<b>W210/20</b>	Upholstery

### Specification Information

When specifying combination panels, follow panel size with veneer finish code, then upholstery finish code and pattern number.

#### Surface type/finish suffixes

For upholstered panels, specify upholstery pattern number after the fabric group number.

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

### Application Notes

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

60"W panels are not available with veneer surfaces.

Veneer Group 1 vertical panels are quartered Techgrain®.

Veneer Group 2 vertical panels are rift cut Techgrain®.


Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.

# Panels

## 56" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
Veneer both sides	18"	2 1/4"	56"	<b>MP2-5618-V( )</b>	\$680.	\$751.	\$900.
	24"	2 1/4"	56"	<b>MP2-5624-V( )</b>	751.	799.	960.
	30"	2 1/4"	56"	<b>MP2-5630-V( )</b>	818.	885.	1,063.
	36"	2 1/4"	56"	<b>MP2-5636-V( )</b>	921.	988.	1,185.
	42"	2 1/4"	56"	<b>MP2-5642-V( )</b>	1,039.	1,123.	1,348.
	48"	2 1/4"	56"	<b>MP2-5648-V( )</b>	1,159.	1,261.	1,515.




Panel Planning


Specification Information		Application Notes
Example: <b>MP2-5630-V-8</b>	<i>For veneer panels specify:</i>	<p>Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.</p> <p>60"W panels are not available with veneer surfaces.</p> <p>Veneer Group 1 vertical panels are quartered Techgrain®.</p> <p>Veneer Group 2 vertical panels are rift cut Techgrain®.</p> <p>Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.</p>
<b>MP2</b> Panel	<i>Veneer finish</i>	
<b>56</b> Height	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.	
<b>30</b> Width		
<b>V</b> Veneer both sides		
<b>8</b> Veneer finish		

# Panels

## 64" H upholstered

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	64"	<b>MP2-6418(-)</b>	\$428.	\$493.	\$509.	\$580.	\$621.	\$686.	\$751.
	24"	2 1/4"	64"	<b>MP2-6424(-)</b>	474.	548.	564.	648.	683.	751.	817.
	30"	2 1/4"	64"	<b>MP2-6430(-)</b>	539.	617.	632.	729.	764.	831.	899.
	36"	2 1/4"	64"	<b>MP2-6436(-)</b>	588.	671.	694.	791.	837.	913.	978.
	42"	2 1/4"	64"	<b>MP2-6442(-)</b>	633.	739.	762.	874.	911.	978.	1,061.
	48"	2 1/4"	64"	<b>MP2-6448(-)</b>	680.	793.	817.	935.	980.	1,061.	1,158.
	60"	2 1/4"	64"	<b>MP2-6460(-)</b>	793.	903.	928.	1,065.	1,133.	1,239.	1,336.

Options panels, upholstered both sides	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options panels, upholstered both sides	18"	2 1/4"	64"	<b>MP2-6418N( )</b>	402.	452.	467.	533.	570.	629.	687.
	24"	2 1/4"	64"	<b>MP2-6424N( )</b>	446.	502.	516.	594.	628.	687.	748.
	30"	2 1/4"	64"	<b>MP2-6430N( )</b>	508.	565.	581.	670.	701.	762.	822.
	36"	2 1/4"	64"	<b>MP2-6436N( )</b>	553.	614.	634.	726.	767.	837.	898.
	42"	2 1/4"	64"	<b>MP2-6442N( )</b>	595.	678.	699.	799.	836.	898.	972.
	48"	2 1/4"	64"	<b>MP2-6448N( )</b>	641.	727.	748.	858.	900.	972.	1,062.
	60"	2 1/4"	64"	<b>MP2-6460N( )</b>	743.	826.	851.	976.	1,038.	1,136.	1,227.

### Order Code

Example:	<b>MP2-6430-15-W210/20</b>
<b>MP2</b>	Panel
<b>64</b>	Height
<b>30</b>	Width
<b>15</b>	Surface type
<b>W210/20</b>	Upholstery

### Specification Information

*Surface type/finish suffixes*  
*Upholstered panels:*

For upholstered panels, specify upholstery pattern number after the fabric group number.

- 10- Fabric group 10
- 15- Fabric group 15
- 20- Fabric group 20
- 30- Fabric group 30
- 35- Fabric group 35
- 40- Fabric group 40
- 45- Fabric group 45

Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.

For combinations of fabrics list both suffixes (e.g., 20/40) and upholstery pattern numbers.

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

*High performance panel acoustical ratings:*  
 NRC .80, STC 24


Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Panels

## 64" H glazed

Morrison

Panel Planning

description	w	d	h	pattern no.	C/T	F
Glazed panels 	18"	2 1/4"	64"	<b>MP2-6418-C/T/F( )</b>	\$953.	\$1,333.
	24"	2 1/4"	64"	<b>MP2-6424-C/T/F( )</b>	1,071.	1,500.
	30"	2 1/4"	64"	<b>MP2-6430-C/T/F( )</b>	1,175.	1,646.
	36"	2 1/4"	64"	<b>MP2-6436-C/T/F( )</b>	1,293.	1,810.
	42"	2 1/4"	64"	<b>MP2-6442-C/T/F( )</b>	1,396.	1,953.
	48"	2 1/4"	64"	<b>MP2-6448-C/T/F( )</b>	1,548.	2,167.

### Order Code

Example:	<b>MP2-6430-T-613</b>
<b>MP2</b>	Panel
<b>64</b>	Height
<b>30</b>	Width
<b>T</b>	Translucent acrylic glazing
<b>613</b>	Frame finish

### Specification Information

*For glazed panels specify:*

C- Clear tempered glass  
 T- Translucent acrylic  
 F- Divided translucent fiberglass

Frame finish

Panel stiffeners should be specified with glazed panels in all straight or corner configurations. See page 40

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Glazed panels may not be powered. Divided translucent fiberglass glazed panels may be powered. 60"W glazed panels are not available.


*High performance panel acoustical ratings:*  
 NRC .80, STC 24


Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.


# Panels

## 64" H combination veneer/upholstery

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	64"	<b>MP2-6418-(-)(-)</b>	\$604.	\$628.	\$637.	\$674.	\$696.	\$727.	\$759.
	24"	2 1/4"	64"	<b>MP2-6424-(-)(-)</b>	653.	681.	691.	733.	752.	784.	817.
	30"	2 1/4"	64"	<b>MP2-6430-(-)(-)</b>	744.	776.	785.	832.	850.	884.	918.
	36"	2 1/4"	64"	<b>MP2-6436-(-)(-)</b>	837.	873.	881.	931.	956.	994.	1,024.
	42"	2 1/4"	64"	<b>MP2-6442-(-)(-)</b>	921.	967.	976.	1,034.	1,051.	1,085.	1,125.
	48"	2 1/4"	64"	<b>MP2-6448-(-)(-)</b>	1,012.	1,061.	1,071.	1,133.	1,154.	1,193.	1,243.

 Combination Veneer 2/upholstery	18"	2 1/4"	64"	<b>MP2-6418-(-)(-)</b>	647.	672.	678.	715.	736.	769.	799.
	24"	2 1/4"	64"	<b>MP2-6424-(-)(-)</b>	703.	735.	742.	784.	803.	835.	870.
	30"	2 1/4"	64"	<b>MP2-6430-(-)(-)</b>	795.	826.	836.	882.	903.	933.	969.
	36"	2 1/4"	64"	<b>MP2-6436-(-)(-)</b>	879.	914.	924.	973.	999.	1,036.	1,068.
	42"	2 1/4"	64"	<b>MP2-6442-(-)(-)</b>	959.	1,016.	1,026.	1,083.	1,099.	1,135.	1,177.
	48"	2 1/4"	64"	<b>MP2-6448-(-)(-)</b>	1,071.	1,120.	1,133.	1,192.	1,214.	1,254.	1,301.


 Combination Veneer 3/upholstery	18"	2 1/4"	64"	<b>MP2-6418-(-)(-)</b>	775.	805.	815.	859.	882.	923.	960.
	24"	2 1/4"	64"	<b>MP2-6424-(-)(-)</b>	844.	881.	891.	941.	963.	1,001.	1,042.
	30"	2 1/4"	64"	<b>MP2-6430-(-)(-)</b>	956.	994.	1,002.	1,061.	1,084.	1,121.	1,163.
	36"	2 1/4"	64"	<b>MP2-6436-(-)(-)</b>	1,054.	1,096.	1,109.	1,168.	1,199.	1,243.	1,282.
	42"	2 1/4"	64"	<b>MP2-6442-(-)(-)</b>	1,152.	1,218.	1,233.	1,299.	1,323.	1,362.	1,413.
	48"	2 1/4"	64"	<b>MP2-6448-(-)(-)</b>	1,286.	1,344.	1,360.	1,430.	1,459.	1,504.	1,563.

Order Code	Specification Information	Application Notes
Example: <b>MP2-6430-T-15-W210/20</b>	When specifying combination panels, follow panel size with veneer finish code, then upholstery finish code and pattern number.	Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.
<b>MP2</b> Panel		
<b>64</b> Height	For upholstered panels, specify upholstery pattern number after the fabric group number.  10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45	60"W panels are not available with veneer surfaces.
<b>30</b> Width		
<b>T</b> Veneer finish		
<b>15</b> Fabric group		
<b>W210/20</b> Upholstery		
	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.	Veneer Group 1 vertical panels are quartered Techgrain®.
		Veneer Group 2 vertical panels are rift cut Techgrain®.
		Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.

# Panels

## 64" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
 Veneer both sides	18"	2 1/4"	64"	<b>MP2-6418-V-( )</b>	\$765.	\$850.	\$1,021.
	24"	2 1/4"	64"	<b>MP2-6424-V-( )</b>	818.	921.	1,106.
	30"	2 1/4"	64"	<b>MP2-6430-V-( )</b>	936.	1,039.	1,247.
	36"	2 1/4"	64"	<b>MP2-6436-V-( )</b>	1,071.	1,159.	1,389.
	42"	2 1/4"	64"	<b>MP2-6442-V-( )</b>	1,192.	1,293.	1,550.
	48"	2 1/4"	64"	<b>MP2-6448-V-( )</b>	1,327.	1,446.	1,736.

Panel Planning

### Order Code

Example:	<b>MP2-6430-V-8</b>
<b>MP2</b>	Panel
<b>64</b>	Height
<b>30</b>	Width
<b>V</b>	Veneer both sides
<b>8</b>	Veneer finish

### Specification Information

*For veneer panels specify:*  
*Veneer finish*

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

### Application Notes

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

60"W panels are not available with veneer surfaces.

Veneer Group 1 vertical panels are quartered Techgrain®.


Veneer Group 2 vertical panels are rift cut Techgrain®.


Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.

# Panels

## 80" H upholstered

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 High performance panels, upholstered both sides	18"	2 1/4"	80"	<b>MP2-8018-( )</b>	\$612.	\$724.	\$742.	\$853.	\$896.	\$970.	\$1,040.
	24"	2 1/4"	80"	<b>MP2-8024-( )</b>	659.	797.	820.	942.	972.	1,040.	1,113.
	30"	2 1/4"	80"	<b>MP2-8030-( )</b>	733.	859.	884.	1,013.	1,044.	1,113.	1,203.
	36"	2 1/4"	80"	<b>MP2-8036-( )</b>	785.	916.	945.	1,083.	1,122.	1,203.	1,328.
	42"	2 1/4"	80"	<b>MP2-8042-( )</b>	837.	979.	1,007.	1,157.	1,203.	1,293.	1,417.
	48"	2 1/4"	80"	<b>MP2-8048-( )</b>	887.	1,054.	1,084.	1,245.	1,298.	1,401.	1,506.

Options panels, upholstered both sides	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options panels, upholstered both sides	18"	2 1/4"	80"	<b>MP2-8018-N( )</b>	574.	661.	681.	784.	820.	889.	954.
	24"	2 1/4"	80"	<b>MP2-8024-N( )</b>	621.	733.	754.	863.	892.	954.	1,021.
	30"	2 1/4"	80"	<b>MP2-8030-N( )</b>	688.	788.	812.	930.	957.	1,021.	1,099.
	36"	2 1/4"	80"	<b>MP2-8036-N( )</b>	738.	841.	865.	994.	1,029.	1,099.	1,217.
	42"	2 1/4"	80"	<b>MP2-8042-N( )</b>	786.	898.	924.	1,061.	1,099.	1,183.	1,300.
	48"	2 1/4"	80"	<b>MP2-8048-N( )</b>	835.	968.	996.	1,139.	1,189.	1,283.	1,381.

Order Code	Specification Information	Application Notes
Example: <b>MP2-8030-15-W210/20</b> <b>MP2</b> Panel <b>80</b> Height <b>30</b> Width <b>15</b> Surface type and group no. <b>W210/20</b> Upholstery	<i>Surface type/finish suffixes</i> <i>Upholstered panels:</i> For upholstered panels, specify upholstery pattern number after the fabric group number. 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45 Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades. For combinations of fabrics list both suffixes (e.g., 20/40) and upholstery pattern numbers.	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation. Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed. <i>High performance panel acoustical ratings:</i> NRC .80, STC 24 Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.




# Panels

## 80"H glazed

Morrison

Panel Planning


description	w	d	h	pattern no.	C/T
Glazed panels 	18"	2 1/4"	80"	<b>MP2-8018-C/T-( )</b>	\$1,237.
	24"	2 1/4"	80"	<b>MP2-8024-C/T-( )</b>	1,330.
	30"	2 1/4"	80"	<b>MP2-8030-C/T-( )</b>	1,480.
	36"	2 1/4"	80"	<b>MP2-8036-C/T-( )</b>	1,610.
	42"	2 1/4"	80"	<b>MP2-8042-C/T-( )</b>	1,779.
	48"	2 1/4"	80"	<b>MP2-8048-C/T-( )</b>	1,948.


Order Code	Specification Information	Application Notes
Example: <b>MP2-8030-C-613</b> <b>MP2</b> Panel <b>80</b> Height <b>30</b> Width <b>C</b> Clear acrylic glazing <b>613</b> Frame finish	<p><i>For glazed panels specify:</i></p> C- Clear tempered glass T- Translucent acrylic	Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.  Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.  Glazed panels may not be powered. 60"W glazed panels are not available.  <i>High performance panel acoustical ratings:</i> NRC .80, STC 24  Upholstered panels may be specified to achieve ASTM E-84 Class "A" flamespread rating.
	Frame finish  Panel stiffeners should be specified with glazed panels in all straight or corner configurations. See page 40.  60"W panels are not available.	


# Panels

## 80"H combination veneer/upholstery

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Combination Veneer 1/upholstery	18"	2 1/4"	80"	<b>MP2-8018-(-)(-)</b>	\$808.	\$878.	\$886.	\$942.	\$962.	\$1,001.	\$1,036.
	24"	2 1/4"	80"	<b>MP2-8024-(-)(-)</b>	887.	970.	981.	1,044.	1,056.	1,092.	1,125.
	30"	2 1/4"	80"	<b>MP2-8030-(-)(-)</b>	970.	1,048.	1,061.	1,123.	1,138.	1,171.	1,218.
	36"	2 1/4"	80"	<b>MP2-8036-(-)(-)</b>	1,061.	1,141.	1,157.	1,224.	1,246.	1,286.	1,347.
	42"	2 1/4"	80"	<b>MP2-8042-(-)(-)</b>	1,158.	1,247.	1,260.	1,334.	1,359.	1,404.	1,465.
	48"	2 1/4"	80"	<b>MP2-8048-(-)(-)</b>	1,265.	1,369.	1,385.	1,465.	1,492.	1,542.	1,596.

 Combination Veneer 2/upholstery	18"	2 1/4"	80"	<b>MP2-8018-(-)(-)</b>	861.	932.	945.	999.	1,020.	1,056.	1,092.
	24"	2 1/4"	80"	<b>MP2-8024-(-)(-)</b>	932.	1,016.	1,027.	1,090.	1,107.	1,138.	1,171.
	30"	2 1/4"	80"	<b>MP2-8030-(-)(-)</b>	1,024.	1,105.	1,117.	1,180.	1,198.	1,233.	1,275.
	36"	2 1/4"	80"	<b>MP2-8036-(-)(-)</b>	1,123.	1,208.	1,222.	1,293.	1,310.	1,349.	1,413.
	42"	2 1/4"	80"	<b>MP2-8042-(-)(-)</b>	1,233.	1,324.	1,338.	1,411.	1,436.	1,480.	1,542.
	48"	2 1/4"	80"	<b>MP2-8048-(-)(-)</b>	1,348.	1,453.	1,468.	1,550.	1,577.	1,628.	1,680.

 Combination Veneer 3/upholstery	18"	2 1/4"	80"	<b>MP2-8018-(-)(-)</b>	1,035.	1,120.	1,135.	1,199.	1,222.	1,270.	1,310.
	24"	2 1/4"	80"	<b>MP2-8024-(-)(-)</b>	1,120.	1,218.	1,234.	1,306.	1,327.	1,367.	1,408.
	30"	2 1/4"	80"	<b>MP2-8030-(-)(-)</b>	1,228.	1,325.	1,339.	1,416.	1,438.	1,479.	1,529.
	36"	2 1/4"	80"	<b>MP2-8036-(-)(-)</b>	1,348.	1,449.	1,466.	1,550.	1,574.	1,619.	1,696.
	42"	2 1/4"	80"	<b>MP2-8042-(-)(-)</b>	1,479.	1,586.	1,607.	1,693.	1,721.	1,775.	1,852.
	48"	2 1/4"	80"	<b>MP2-8048-(-)(-)</b>	1,618.	1,744.	1,763.	1,860.	1,892.	1,953.	2,018.


Order Code	Specification Information	Application Notes
Example: <b>MP2-8030-8-15-W210/20</b>	When specifying combination panels, follow panel size with veneer finish code, the upholstery finish code and pattern number.	Surface type/finish suffixes  For upholstered panels, specify upholstery pattern number after the fabric group number.
<b>MP2</b> Panel <b>80</b> Height <b>30</b> Width <b>8</b> Veneer finish <b>15</b> Fabric group <b>W210/20</b> Upholstery		
		10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

# Panels

## 80" H veneer both sides

Morrison

description	w	d	h	pattern no.	V1	V2	V3
Veneer both sides	18"	2 1/4"	80"	<b>MP2-8018-V-( )</b>	\$1,005.	\$1,143.	\$1,373.
	24"	2 1/4"	80"	<b>MP2-8024-V-( )</b>	1,115.	1,237.	1,483.
	30"	2 1/4"	80"	<b>MP2-8030-V-( )</b>	1,206.	1,348.	1,618.
	36"	2 1/4"	80"	<b>MP2-8036-V-( )</b>	1,332.	1,499.	1,798.
	42"	2 1/4"	80"	<b>MP2-8042-V-( )</b>	1,478.	1,667.	2,001.
	48"	2 1/4"	80"	<b>MP2-8048-V-( )</b>	1,646.	1,855.	2,226.



Panel Planning

### Order Code

Example:	<b>MP2-8030-V-8</b>
<b>MP2</b>	Panel
<b>80</b>	Height
<b>30</b>	Width
<b>V</b>	Veneer both sides
<b>8</b>	Veneer finish

### Specification Information

*For veneer panels specify:*

*Veneer finishes*

Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

### Application Notes

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.


Veneer Group 1 vertical panels are quartered Techgrain®.

Veneer Group 2 vertical panels are rift cut Techgrain®.

Veneer Group 3 vertical panels are narrow heart, flat cut natural veneers.

60"W panels are not available with veneer surfaces

Panels  
ported panel  
39", 42" and 48" H

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
 Ported panels, upholstered both sides	39"H	18"	2 1/4"	39"	<b>MP2-3918-P()</b>	\$413.	\$457.	\$465.	\$538.	\$568.	\$619.	\$658.
		24"	2 1/4"	39"	<b>MP2-3924-P()</b>	452.	518.	536.	616.	628.	677.	736.
		30"	2 1/4"	39"	<b>MP2-3930-P()</b>	509.	567.	587.	672.	691.	736.	816.
		36"	2 1/4"	39"	<b>MP2-3936-P()</b>	564.	634.	655.	746.	776.	835.	911.
		42"	2 1/4"	39"	<b>MP2-3942-P()</b>	642.	715.	736.	844.	872.	929.	1,026.
		48"	2 1/4"	39"	<b>MP2-3948-P()</b>	698.	782.	803.	922.	968.	1,048.	1,123.
	42"H	18"	2 1/4"	42"	<b>MP2-4218-P()</b>	435.	481.	491.	565.	599.	652.	695.
		24"	2 1/4"	42"	<b>MP2-4224-P()</b>	474.	548.	564.	647.	669.	714.	773.
		30"	2 1/4"	42"	<b>MP2-4230-P()</b>	535.	597.	618.	709.	727.	773.	858.
		36"	2 1/4"	42"	<b>MP2-4236-P()</b>	594.	669.	688.	788.	818.	877.	958.
		42"	2 1/4"	42"	<b>MP2-4242-P()</b>	675.	753.	773.	888.	916.	977.	1,081.
		48"	2 1/4"	42"	<b>MP2-4248-P()</b>	735.	821.	845.	970.	1,018.	1,104.	1,183.
	48"H	18"	2 1/4"	48"	<b>MP2-4818-P()</b>	478.	527.	539.	622.	657.	716.	763.
		24"	2 1/4"	48"	<b>MP2-4824-P()</b>	524.	600.	621.	711.	736.	786.	852.
		30"	2 1/4"	48"	<b>MP2-4830-P()</b>	588.	656.	677.	776.	799.	852.	944.
		36"	2 1/4"	48"	<b>MP2-4836-P()</b>	653.	736.	759.	869.	900.	966.	1,055.
		42"	2 1/4"	48"	<b>MP2-4842-P()</b>	741.	827.	852.	977.	1,008.	1,076.	1,191.
		48"	2 1/4"	48"	<b>MP2-4848-P()</b>	810.	903.	930.	1,067.	1,120.	1,212.	1,300.

Order Code

Example: **MP2-3918-P-15-W210/20**

<b>MP2</b>	Panel
<b>39</b>	Height
<b>18</b>	Width
<b>P</b>	Ported panel
<b>15</b>	Fabric group
<b>W210/20</b>	Upholstery

Specification Information

*Surface type/finish suffixes*  
*Upholstered panels:*

For upholstered panels, specify upholstery pattern number after the fabric group number.

- 10- Fabric group 10
- 15- Fabric group 15
- 20- Fabric group 20
- 30- Fabric group 30
- 35- Fabric group 35
- 40- Fabric group 40
- 45- Fabric group 45

Application Notes

Ported panels are upholstered both sides and may be upholstered with textiles approved for application on Reff panels only.  
For combination of fabrics list both suffixes and upholstery pattern numbers. List price is the average of the two fabric grades.


Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Vertical duplexes, power and data ports and connectors are specified separately.

# Panels

## ported panel

### 56", 64" and 80" H

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
 Ported panels, upholstered both sides	56"H	18"	2 1/4"	56"	<b>MP2-5618-P( )</b>	\$495.	\$583.	\$599.	\$688.	\$710.	\$758.	\$817.
		24"	2 1/4"	56"	<b>MP2-5624-P( )</b>	570.	648.	669.	767.	798.	858.	938.
		30"	2 1/4"	56"	<b>MP2-5630-P( )</b>	634.	736.	760.	870.	899.	958.	1,039.
		36"	2 1/4"	56"	<b>MP2-5636-P( )</b>	695.	807.	827.	948.	997.	1,081.	1,163.
		42"	2 1/4"	56"	<b>MP2-5642-P( )</b>	752.	874.	898.	1,028.	1,077.	1,163.	1,264.
		48"	2 1/4"	56"	<b>MP2-5648-P( )</b>	812.	957.	986.	1,133.	1,175.	1,264.	1,364.
	64"H	18"	2 1/4"	64"	<b>MP2-6418-P( )</b>	535.	618.	636.	725.	775.	858.	938.
		24"	2 1/4"	64"	<b>MP2-6424-P( )</b>	594.	684.	705.	811.	855.	938.	1,022.
		30"	2 1/4"	64"	<b>MP2-6430-P( )</b>	675.	769.	791.	911.	956.	1,039.	1,122.
		36"	2 1/4"	64"	<b>MP2-6436-P( )</b>	735.	839.	865.	989.	1,047.	1,141.	1,223.
		42"	2 1/4"	64"	<b>MP2-6442-P( )</b>	792.	924.	952.	1,091.	1,138.	1,223.	1,326.
		48"	2 1/4"	64"	<b>MP2-6448-P( )</b>	851.	993.	1,022.	1,169.	1,226.	1,326.	1,446.
	80"H	18"	2 1/4"	80"	<b>MP2-8018-P( )</b>	764.	904.	929.	1,067.	1,120.	1,212.	1,300.
		24"	2 1/4"	80"	<b>MP2-8024-P( )</b>	826.	998.	1,026.	1,177.	1,215.	1,300.	1,391.
		30"	2 1/4"	80"	<b>MP2-8030-P( )</b>	915.	1,075.	1,106.	1,268.	1,304.	1,391.	1,503.
		36"	2 1/4"	80"	<b>MP2-8036-P( )</b>	980.	1,146.	1,181.	1,353.	1,404.	1,503.	1,662.
		42"	2 1/4"	80"	<b>MP2-8042-P( )</b>	1,047.	1,224.	1,259.	1,445.	1,503.	1,615.	1,772.

#### Order Code

Example: **MP2-6418-P-15-W210/20**

<b>MP2</b>	Panel
<b>64</b>	Height
<b>18</b>	Width
<b>P</b>	Ported panel
<b>15</b>	Fabric group
<b>W210/20</b>	Upholstery

#### Specification Information

*Surface type/finish suffixes*  
*Upholstered panels:*

For upholstered panels, specify upholstery pattern number after the fabric group number.

- 10- Fabric group 10
- 15- Fabric group 15
- 20- Fabric group 20
- 30- Fabric group 30
- 35- Fabric group 35
- 40- Fabric group 40
- 45- Fabric group 45

#### Application Notes

Ported panels are upholstered both sides and may be upholstered with textiles approved for application on Reff panels only.  
For combination of fabrics list both suffixes and upholstery pattern numbers. List price is the average of the two fabric grades.


Top caps/raceway covers are specified as separate kits, and are bulk shipped to facilitate installation.

Vertical duplexes, power and data ports and connectors are specified separately.

# Panels

## combination upholstered/markerboard

Morrison

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
	48"H	24"	2"	48"	<b>MP2-4824-M-( )</b>	\$536.	\$566.	\$575.	\$612.	\$621.	\$641.	\$669.
		30"	2"	48"	<b>MP2-4830-M-( )</b>	593.	620.	628.	670.	677.	699.	735.
		36"	2"	48"	<b>MP2-4836-M-( )</b>	658.	694.	701.	744.	759.	785.	820.
		42"	2"	48"	<b>MP2-4842-M-( )</b>	742.	776.	788.	837.	849.	877.	922.
		48"	2"	48"	<b>MP2-4848-M-( )</b>	821.	859.	872.	925.	946.	983.	1,020.
	56"H	24"	2"	56"	<b>MP2-5624-M-( )</b>	566.	597.	605.	646.	656.	680.	712.
		30"	2"	56"	<b>MP2-5630-M-( )</b>	622.	661.	673.	715.	727.	753.	784.
		36"	2"	56"	<b>MP2-5636-M-( )</b>	694.	737.	744.	793.	814.	846.	879.
		42"	2"	56"	<b>MP2-5642-M-( )</b>	767.	817.	826.	879.	900.	932.	973.
		48"	2"	56"	<b>MP2-5648-M-( )</b>	845.	904.	915.	973.	993.	1,027.	1,067.
	64"H	24"	2"	64"	<b>MP2-6424-M-( )</b>	606.	643.	650.	694.	711.	742.	776.
		30"	2"	64"	<b>MP2-6430-M-( )</b>	694.	730.	738.	786.	804.	837.	872.
		36"	2"	64"	<b>MP2-6436-M-( )</b>	775.	817.	828.	878.	901.	939.	971.
		42"	2"	64"	<b>MP2-6442-M-( )</b>	853.	905.	916.	972.	993.	1,025.	1,066.
		48"	2"	64"	<b>MP2-6448-M-( )</b>	938.	995.	1,006.	1,065.	1,087.	1,127.	1,176.
	80"H	24"	2"	80"	<b>MP2-8024-M-( )</b>	833.	902.	913.	972.	990.	1,023.	1,058.
		30"	2"	80"	<b>MP2-8030-M-( )</b>	909.	972.	985.	1,050.	1,065.	1,097.	1,143.
		36"	2"	80"	<b>MP2-8036-M-( )</b>	994.	1,058.	1,074.	1,140.	1,162.	1,202.	1,264.
		42"	2"	80"	<b>MP2-8042-M-( )</b>	1,084.	1,156.	1,168.	1,244.	1,265.	1,310.	1,375.
		48"	2"	80"	<b>MP2-8048-M-( )</b>	1,185.	1,269.	1,282.	1,363.	1,388.	1,441.	1,494.

### Order Code

Example:	<b>MP2-6436-M-15-W210/2</b>
<b>MP2</b>	Panel
<b>64</b>	Height
<b>36</b>	Width
<b>M</b>	Markerboard
<b>15</b>	Fabric group
<b>W210/2</b>	Upholstery

### Specification Information

When specifying combination panels, follow panel size with markerboard code, then the upholstery finish code and pattern number.

#### Surface type/finish suffixes:

M-	Markerboard surface
10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk packed to facilitate installation.

Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.


Markerboard surface is non-metallic.

# Panels

## markerboard both sides

Morrison

Panel Planning

description	type	w	d	h	pattern no.	markerboard both sides
 Markerboard both sides	48"H	24"	2"	48"	<b>MP2-4824-M</b>	\$652.
		30"	2"	48"	<b>MP2-4830-M</b>	713.
		36"	2"	48"	<b>MP2-4836-M</b>	795.
		42"	2"	48"	<b>MP2-4842-M</b>	891.
		48"	2"	48"	<b>MP2-4848-M</b>	997.
	56"H	24"	2"	56"	<b>MP2-5624-M</b>	675.
		30"	2"	56"	<b>MP2-5630-M</b>	736.
		36"	2"	56"	<b>MP2-5636-M</b>	828.
		42"	2"	56"	<b>MP2-5642-M</b>	935.
		48"	2"	56"	<b>MP2-5648-M</b>	1,042.
	64"H	24"	2"	64"	<b>MP2-6424-M</b>	736.
		30"	2"	64"	<b>MP2-6430-M</b>	843.
		36"	2"	64"	<b>MP2-6436-M</b>	963.
		42"	2"	64"	<b>MP2-6442-M</b>	1,071.
		48"	2"	64"	<b>MP2-6448-M</b>	1,195.
	80"H	24"	2"	80"	<b>MP2-8024-M</b>	1,004.
		30"	2"	80"	<b>MP2-8030-M</b>	1,085.
		36"	2"	80"	<b>MP2-8036-M</b>	1,200.
		42"	2"	80"	<b>MP2-8042-M</b>	1,329.
		48"	2"	80"	<b>MP2-8048-M</b>	1,480.

### Order Code

Example:	<b>MP2-6436-M</b>
<b>MP2</b>	Panel
<b>64</b>	Height
<b>36</b>	Width
<b>M</b>	Markerboard

### Specification Information

For markerboard surface on both sides, no finish code is required.

*Surface type/finish suffixes:*

M- Markerboard surface

### Application Notes

Top caps/raceway covers are specified as separate kits, and are bulk packed to facilitate installation.


Non-powered panel raceways accommodate 96 or more 4-pair unshielded twisted pair cables (Category 5, 5E or 6). Powered panel raceways accommodate up to 48 4-pair cables. Power components are ordered separately and field-installed.

Markerboard surface is non-metallic.

# Doors

## rolling door

Morrison

description	type	w	d	h	pattern no.	paint	RC	C	T
 (right hand shown)	64"H with lock	36"	2"	64"	<b>MRD-6436-(L/R)-( )-( )-L</b>		\$2,175.	\$2,268.	\$2,445.
		42"	2"	64"	<b>MRD-6442-(L/R)-( )-( )-L</b>		2,256.	2,375.	2,578.
		48"	2"	64"	<b>MRD-6448-(L/R)-( )-( )-L</b>		2,285.	2,403.	2,605.
	64"H no lock	36"	2"	64"	<b>MRD-6436-(L/R)-( )-( )-N</b>		2,016.	2,112.	2,288.
		42"	2"	64"	<b>MRD-6442-(L/R)-( )-( )-N</b>		2,100.	2,218.	2,421.
		48"	2"	64"	<b>MRD-6448-(L/R)-( )-( )-N</b>		2,129.	2,246.	2,450.
	80"H with lock	36"	2"	80"	<b>MRD-8036-(L/R)-( )-( )-L</b>		2,293.	2,556.	2,823.
		42"	2"	80"	<b>MRD-8042-(L/R)-( )-( )-L</b>		2,385.	2,578.	2,836.
		48"	2"	80"	<b>MRD-8048-(L/R)-( )-( )-L</b>		2,423.	2,606.	2,874.
	80"H no lock	36"	2"	80"	<b>MRD-8036-(L/R)-( )-( )-N</b>		2,135.	2,397.	2,667.
		42"	2"	80"	<b>MRD-8042-(L/R)-( )-( )-N</b>		2,227.	2,421.	2,679.
		48"	2"	80"	<b>MRD-8048-(L/R)-( )-( )-N</b>		2,267.	2,451.	2,718.
Threshold for rolling door	36" door	73 1/4"	3"	3/8"	<b>MRD-FT36</b>				164.
	42" door	85 1/4"	3"	3/8"	<b>MRD-FT42</b>				174.
	48" door	97 1/4"	3"	3/8"	<b>MRD-FT48</b>				189.
Panel stiffeners for 80"H doors	90° 2-way L				<b>MM1-DSL2</b>				37.
	In-line post				<b>MM1-DSP1</b>				37.
	Straight				<b>MM1-DSS1</b>				37.
Masts for doors (set of 2)				<b>AYI-DMK</b>					37.
Post trim covers for 64"H door	90° 2-way L	2 1/4"	-	64"	<b>MT1-64XL2-( )</b>		57.		
	90° 3-way T	2 1/4"	-	64"	<b>MT1-64XT3-( )</b>		42.		
Post trim covers for 80"H door	90° 2-way L	2 1/4"	-	80"	<b>MT1-80XL2-( )</b>		66.		
	90° 3-way T	2 1/4"	-	80"	<b>MT1-80XT3-( )</b>		53.		


Order Code	Specification Information	Application Notes
Example: <b>MRD-6436-L-C-613-N</b>	<i>Specify:</i>	64"H rolling door kit includes door panel, post with mounting bracket, and door jamb (for door side opposite to mounting bracket). Specify post high-low top cap (see page ) for Morrison panel adjacent to the door jamb.
<b>M</b> Morrison	<i>Left / Right Hand</i>	Rolling door post with mounting bracket must attach to a Morrison panel, or panel run, of width equal or greater than the nominal width of the door. When fully open, the door will extend 1 3/16" (half the width of a universal post) beyond a panel of corresponding width.
<b>RD</b> Rolling door	<i>Glazing for rolling door:</i>	
<b>64</b> Height	C- Clear tempered glass	80"H rolling door kit includes door panel, post with mounting bracket, door jamb (for door side opposite to mounting bracket), header, top cap for header and two corner brackets. Top caps for panels adjacent to 80" rolling doors must be modified in the field. Header for 80" door mounts with two corner brackets.
<b>36</b> Width	T- Translucent acrylic	
<b>L</b> Left	RC- Ribbed polycarbonate	Door jamb may be attached to a Morrison panel or to a universal post. When attaching to a post, specify separately dedicated vertical trims for 90° 2-way L or 3-way T connections.
<b>C</b> Door finish	<i>Frame finish</i>	
<b>613</b> Frame finish	<i>Lock / No Lock</i>	Masts for doors combine with panel stiffeners for 80" doors to mount stackable add-up panels over Morrison doors.
<b>N</b> No lock	Rolling doors mount to the outside of Morrison workstations.	
		Specify separately straight connector tracks to connect door post and door jamb to adjacent panels.



# Doors

## *hinged door*

Morrison

description	type	w	d	h	pattern no.	laminate	paint	V1	V2	V3
	no lock	36"	2"	80"	<b>MHD-8036-(L/R)-(P/L/V)-( )-( )-N</b>	\$1,751.	\$1,922.	\$2,079.	\$2,264.	\$2,713.
		42"	2"	80"	<b>MHD-8042-(L/R)-(P/L/V)-( )-( )-N</b>	1,850.	1,983.	2,274.	2,476.	2,969.
	with lock	36"	2"	80"	<b>MHD-8036-(L/R)-(P/L/V)-( )-( )-L</b>	2,359.	2,531.	2,688.	2,871.	3,321.
		42"	2"	80"	<b>MHD-8042-(L/R)-(P/L/V)-( )-( )-L</b>	2,458.	2,591.	2,884.	3,084.	3,576.

*left hand shown*

Panel stiffeners for 80"H doors	90° 2-way L				<b>MM1-DSL2</b>			37.		
	In-line post				<b>MM1-DSP1</b>			37.		
	Straight				<b>MM1-DSS1</b>			37.		
Post trim covers for 80"H door	90° 2-way L	2 1/4"	-	80"	<b>MT1-80XL2-( )</b>			66.		
	90° 3-way T	2 1/4"	-	80"	<b>MT1-80XT3-( )</b>			53.		
Masts for doors (set of 2)					<b>AYI-DMK</b>			37.		

### Order Code

Example:	<b>MHD-8042-L-V-4-613-L</b>
<b>M</b>	Morrison
<b>HD</b>	Hinged door
<b>80</b>	Height
<b>42</b>	Width
<b>L</b>	Left
<b>V</b>	Veneer
<b>4</b>	Door finish
<b>613</b>	Frame finish
<b>L</b>	With lock

### Specification Information

*Specify:*

Left / Right hand.
Door Panel finish type:
P Paint
L Laminate
V Veneer
Door panel finish
Frame finish
Lock/ No lock

### Application Notes

Specify separately two straight connector tracks to connect door to adjacent panels or posts. When attaching to a post, specify separately dedicated vertical trims for 90° 2-way L or 3-way T connections.





Hinged door with no lock is a solid panel. It is not drilled for lock assembly. Lock and handle must be field drilled and installed.

Masts for doors combine with panel stiffeners for 80" doors to mount stackable add-up panels over Morrison doors.

# Windows

## 9", 16", 18", 22" and 32"H


Morrison

description	w	d	h	pattern no.	C	T	F
Windows, 9"H 	18"	2 1/4"	9"	<b>MP3-W0918-C/T(-)</b>	\$336.	\$377.	n/a
	24"	2 1/4"	9"	<b>MP3-W0924-C/T(-)</b>	377.	419.	n/a
	30"	2 1/4"	9"	<b>MP3-W0930-C/T(-)</b>	419.	462.	n/a
	36"	2 1/4"	9"	<b>MP3-W0936-C/T(-)</b>	462.	518.	n/a
	42"	2 1/4"	9"	<b>MP3-W0942-C/T(-)</b>	504.	560.	n/a
	48"	2 1/4"	9"	<b>MP3-W0948-C/T(-)</b>	547.	618.	n/a
	60"	2 1/4"	9"	<b>MP3-W0960-C/T(-)</b>	629.	715.	n/a
Windows, 16"H 	18"	2 1/4"	16"	<b>MP3-W1618-C/T/F(-)</b>	356.	399.	558.
	24"	2 1/4"	16"	<b>MP3-W1624-C/T/F(-)</b>	399.	443.	620.
	30"	2 1/4"	16"	<b>MP3-W1630-C/T/F(-)</b>	443.	488.	681.
	36"	2 1/4"	16"	<b>MP3-W1636-C/T/F(-)</b>	488.	547.	764.
	42"	2 1/4"	16"	<b>MP3-W1642-C/T/F(-)</b>	531.	590.	825.
	48"	2 1/4"	16"	<b>MP3-W1648-C/T/F(-)</b>	575.	650.	909.
	60"	2 1/4"	16"	<b>MP3-W1660-C/T/F(-)</b>	661.	754.	1,053.
Windows, 18"H 	18"	2 1/4"	18"	<b>MP3-W1818-C/T(-)</b>	370.	414.	n/a
	24"	2 1/4"	18"	<b>MP3-W1824-C/T(-)</b>	414.	460.	n/a
	30"	2 1/4"	18"	<b>MP3-W1830-C/T(-)</b>	460.	507.	n/a
	36"	2 1/4"	18"	<b>MP3-W1836-C/T(-)</b>	507.	567.	n/a
	42"	2 1/4"	18"	<b>MP3-W1842-C/T(-)</b>	552.	613.	n/a
	48"	2 1/4"	18"	<b>MP3-W1848-C/T(-)</b>	598.	676.	n/a
	60"	2 1/4"	18"	<b>MP3-W1860-C/T(-)</b>	691.	785.	n/a
Windows, 22"H 	18"	2 1/4"	22"	<b>MP3-W2218-C/T/F(-)</b>	396.	443.	620.
	24"	2 1/4"	22"	<b>MP3-W2224-C/T/F(-)</b>	443.	491.	688.
	30"	2 1/4"	22"	<b>MP3-W2230-C/T/F(-)</b>	491.	540.	759.
	36"	2 1/4"	22"	<b>MP3-W2236-C/T/F(-)</b>	540.	608.	850.
	42"	2 1/4"	22"	<b>MP3-W2242-C/T/F(-)</b>	590.	655.	918.
	48"	2 1/4"	22"	<b>MP3-W2248-C/T/F(-)</b>	642.	722.	1,008.
	60"	2 1/4"	22"	<b>MP3-W2260-C/T/F(-)</b>	740.	835.	1,167.

Order Code	Specification Information	Application Notes
Example: <b>MP3-W2230-C-613</b> <b>MP3</b> Panel <b>W</b> Window <b>22</b> Height <b>30</b> Width <b>C</b> Window finish <b>613</b> Frame finish	Specify glazing for windows: C- Clear tempered glass T- Translucent acrylic F- Divided translucent fiberglass  Frame finish	Windows mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.  All windows are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.  9"H windows may be mounted on 30"H and 39"H vertical panels and connected, respectively, with standard 39"H and 48"H connector tracks and post assemblies.  16"H windows may be mounted on 48"H and 64"H vertical panels and connected, respectively, with standard 64"H and 80"H connector tracks and post assemblies.  18"H windows may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74"H connector tracks and post assemblies.
		22"H windows may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.  32"H windows may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.  Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets.  Two 16"H windows may be mounted on a 48"H upholstered panel only when using 80"H full height connector tracks and post assemblies.

# Windows

9", 16", 18", 22" and 32"H

description	w	d	h	pattern no.	C	T	F
 Windows, 32"H	18"	2 1/4"	32"	<b>MP3-W3218-C/T-( )</b>	\$574.	\$643.	n/a
	24"	2 1/4"	32"	<b>MP3-W3224-C/T-( )</b>	643.	712.	n/a
	30"	2 1/4"	32"	<b>MP3-W3230-C/T-( )</b>	712.	785.	n/a
	36"	2 1/4"	32"	<b>MP3-W3236-C/T-( )</b>	785.	880.	n/a
	42"	2 1/4"	32"	<b>MP3-W3242-C/T-( )</b>	855.	952.	n/a
	48"	2 1/4"	32"	<b>MP3-W3248-C/T-( )</b>	929.	1,045.	n/a
	60"	2 1/4"	32"	<b>MP3-W3260-C/T-( )</b>	1,075.	1,210.	n/a

**Order Code**

Example:	<b>MP3-W2230-C-613</b>
<b>MP3</b>	Panel
<b>W</b>	Window
<b>22</b>	Height
<b>30</b>	Width
<b>C</b>	Window finish
<b>613</b>	Frame finish

**Specification Information**

*Specify glazing for windows:*  
 C- Clear tempered glass  
 T- Translucent acrylic  
 F- Divided translucent fiberglass

*Frame finish*

**Application Notes**

Windows mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.

All windows are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.

9"H windows may be mounted on 30"H and 39"H vertical panels and connected, respectively, with standard 39"H and 48"H connector tracks and post assemblies.

16"H windows may be mounted on 48"H and 64"H vertical panels and connected, respectively, with standard 64"H and 80"H connector tracks and post assemblies.

18"H windows may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74"H connector tracks and post assemblies.

22"H windows may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.





32"H windows may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.

Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets.

Two 16"H windows may be mounted on a 48"H upholstered panel only when using 80"H full height connector tracks and post assemblies.





# Markerboard and combination add-on panels 16", 18", 22" and 32"H

Morrison

description	w	d	h	pattern no.	combination							marker both sides
					10	15	20	30	35	40	45	
 16"H	24"	2"	16"	<b>MP3-A1624-M( )</b>	\$359.	\$377.	\$380.	\$405.	\$417.	\$435.	\$452.	\$435.
	30"	2"	16"	<b>MP3-A1630-M( )</b>	400.	419.	425.	452.	465.	486.	506.	480.
	36"	2"	16"	<b>MP3-A1636-M( )</b>	443.	467.	471.	501.	516.	538.	562.	532.
	42"	2"	16"	<b>MP3-A1642-M( )</b>	495.	521.	528.	563.	578.	605.	629.	587.
	48"	2"	16"	<b>MP3-A1648-M( )</b>	549.	577.	585.	621.	640.	668.	695.	657.
 18"H	24"	2"	18"	<b>MP3-A1824-M( )</b>	376.	396.	401.	424.	437.	455.	472.	458.
	30"	2"	18"	<b>MP3-A1830-M( )</b>	418.	441.	445.	473.	487.	508.	528.	504.
	36"	2"	18"	<b>MP3-A1836-M( )</b>	463.	488.	493.	526.	539.	564.	587.	559.
	42"	2"	18"	<b>MP3-A1842-M( )</b>	517.	545.	553.	589.	605.	632.	657.	617.
	48"	2"	18"	<b>MP3-A1848-M( )</b>	575.	605.	613.	651.	670.	698.	726.	695.
 22"H	24"	2"	22"	<b>MP3-A2224-M( )</b>	400.	418.	424.	450.	463.	483.	502.	483.
	30"	2"	22"	<b>MP3-A2230-M( )</b>	444.	467.	472.	502.	516.	538.	562.	532.
	36"	2"	22"	<b>MP3-A2236-M( )</b>	491.	517.	525.	556.	572.	597.	622.	589.
	42"	2"	22"	<b>MP3-A2242-M( )</b>	549.	577.	585.	623.	642.	672.	699.	649.
	48"	2"	22"	<b>MP3-A2248-M( )</b>	609.	642.	649.	689.	709.	739.	769.	730.
 32"H	24"	2"	32"	<b>MP3-A3224-M( )</b>	449.	474.	482.	512.	520.	536.	559.	549.
	30"	2"	32"	<b>MP3-A3230-M( )</b>	497.	521.	528.	562.	568.	587.	617.	601.
	36"	2"	32"	<b>MP3-A3236-M( )</b>	553.	580.	588.	623.	634.	656.	687.	670.
	42"	2"	32"	<b>MP3-A3242-M( )</b>	617.	646.	653.	696.	705.	727.	765.	737.
	48"	2"	32"	<b>MP3-A3248-M( )</b>	683.	715.	764.	770.	790.	819.	849.	830.

Order Code	Specification Information	Application Notes
Example: <b>MP3-A1636-M15</b>		
<b>MP3</b> Panel		
<b>A</b> Add-on		
<b>16</b> Height		
<b>36</b> Width		
<b>M</b> Markerboard		
<b>15</b> Surface type and group no.		
<b>W210/2</b> Upholstery		
	<p><i>Surface type/finish suffixes:</i></p> <p>For markerboard surface on both sides, follow add-on panel size with finish code M.</p> <p>When specifying combination panels, follow add-on panel size with markerboard code, then upholstery finish code and pattern number.</p> <p>M- Markerboard surface            10- Fabric group 10            15- Fabric group 15            20- Fabric group 20            30- Fabric group 30            35- Fabric group 35            40- Fabric group 40            45- Fabric group 45</p>	<p>Add-on panels mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.</p> <p>All add-on panels are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.</p> <p>16"H add-on panels may be mounted on 48"H and 74"H vertical panels and connected, respectively, with standard 64"H and 80" connector tracks and post assemblies.</p> <p>18"H add-on panels may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74" connector tracks and post assemblies.</p>
		<p>22"H add-on panels may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.</p> <p>32"H add-on panels may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.</p> <p>Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets. Add-on panels may also span two lower panels of the same total width.</p> <p>Markerboard surface is non-metallic.</p>

# Upholstered add-on panels 16", 18", 22" and 32"H





description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Add-on panels, upholstered, 16"H	18"	2 1/4"	16"	<b>MP3-A1618(-)</b>	\$260.	\$295.	\$304.	\$350.	\$371.	\$404.	\$437.
	24"	2 1/4"	16"	<b>MP3-A1624(-)</b>	283.	320.	328.	375.	400.	435.	469.
	30"	2 1/4"	16"	<b>MP3-A1630(-)</b>	320.	362.	372.	425.	451.	491.	531.
	36"	2 1/4"	16"	<b>MP3-A1636(-)</b>	355.	401.	412.	471.	501.	547.	590.
	42"	2 1/4"	16"	<b>MP3-A1642(-)</b>	403.	455.	469.	538.	570.	622.	673.
	48"	2 1/4"	16"	<b>MP3-A1648(-)</b>	440.	496.	511.	583.	619.	674.	729.
	60"	2 1/4"	16"	<b>MP3-A1660(-)</b>	509.	574.	593.	676.	716.	782.	844.
 Add-on panels, upholstered, 18"H	18"	2 1/4"	18"	<b>MP3-A1818(-)</b>	272.	306.	318.	364.	386.	419.	454.
	24"	2 1/4"	18"	<b>MP3-A1824(-)</b>	294.	332.	342.	390.	415.	451.	488.
	30"	2 1/4"	18"	<b>MP3-A1830(-)</b>	332.	376.	387.	443.	469.	510.	552.
	36"	2 1/4"	18"	<b>MP3-A1836(-)</b>	369.	416.	428.	490.	521.	567.	613.
	42"	2 1/4"	18"	<b>MP3-A1842(-)</b>	418.	472.	488.	560.	593.	648.	700.
	48"	2 1/4"	18"	<b>MP3-A1848(-)</b>	457.	516.	532.	608.	644.	701.	759.
	60"	2 1/4"	18"	<b>MP3-A1860(-)</b>	529.	597.	617.	703.	744.	813.	878.
 Add-on panels, upholstered, 22"H	18"	2 1/4"	22"	<b>MP3-A2218(-)</b>	291.	328.	339.	389.	412.	449.	484.
	24"	2 1/4"	22"	<b>MP3-A2224(-)</b>	316.	356.	365.	417.	444.	483.	521.
	30"	2 1/4"	22"	<b>MP3-A2230(-)</b>	356.	402.	413.	472.	501.	547.	590.
	36"	2 1/4"	22"	<b>MP3-A2236(-)</b>	393.	445.	458.	525.	556.	606.	654.
	42"	2 1/4"	22"	<b>MP3-A2242(-)</b>	447.	507.	521.	598.	633.	694.	746.
	48"	2 1/4"	22"	<b>MP3-A2248(-)</b>	488.	552.	567.	650.	687.	751.	810.
	60"	2 1/4"	22"	<b>MP3-A2260(-)</b>	565.	637.	656.	753.	796.	869.	936.
 Add-on panels, upholstered, 32"H	18"	2 1/4"	32"	<b>MP3-A3218(-)</b>	320.	351.	361.	415.	441.	480.	509.
	24"	2 1/4"	32"	<b>MP3-A3224(-)</b>	349.	401.	414.	474.	490.	525.	568.
	30"	2 1/4"	32"	<b>MP3-A3230(-)</b>	392.	440.	452.	520.	534.	568.	629.
	36"	2 1/4"	32"	<b>MP3-A3236(-)</b>	437.	490.	506.	578.	600.	646.	704.
	42"	2 1/4"	32"	<b>MP3-A3242(-)</b>	495.	553.	568.	652.	674.	716.	793.
	48"	2 1/4"	32"	<b>MP3-A3248(-)</b>	539.	601.	700.	712.	748.	810.	869.
	60"	2 1/4"	32"	<b>MP3-A3260(-)</b>	624.	703.	725.	831.	861.	928.	1,001.

Order Code	Specification Information	Application Notes
Example: <b>MP3-A2230-15-W210/2</b>	<i>Surface type/finish suffixes</i>	Add-on panels mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.
<b>MP3</b> Panel	For upholstered panels, specify upholstery pattern number after the fabric group number.	22"H add-on panels may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.
<b>A</b> Add-on	10- Fabric group 10	All add-on panels are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.
<b>22</b> Height	15- Fabric group 15	16"H add-on panels may be mounted on 48"H and 64"H vertical panels and connected, respectively, with standard 64"H and 80"H connector tracks and post assemblies.
<b>30</b> Width	20- Fabric group 20	18"H add-on panels may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74"H connector tracks and post assemblies.
<b>15</b> Surface type and group no.	30- Fabric group 30	
<b>W210/2</b> Upholstery	35- Fabric group 35	
	40- Fabric group 40	
	45- Fabric group 45	
	Upholstered add-on panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.	Two 16"H add-on panels may be mounted on a 48"H upholstered panel only when using 80"H full height connector track and post assemblies.
	For combinations of fabrics list both suffixes (e.g. 10/20) and upholstery pattern numbers.	

# Upholstered Options add-on panels

## 16", 18", 22" and 32"H

Morrison

description	w	d	h	pattern no.	10	15	20	30	35	40	45
 Options add-on panels, upholstered, 16"H	18"	2 1/4"	16"	<b>MP3-A1618N-()</b>	\$245.	\$270.	\$277.	\$320.	\$335.	\$369.	\$399.
	24"	2 1/4"	16"	<b>MP3-A1624N-()</b>	265.	291.	298.	342.	363.	398.	427.
	30"	2 1/4"	16"	<b>MP3-A1630N-()</b>	300.	329.	336.	387.	411.	447.	483.
	36"	2 1/4"	16"	<b>MP3-A1636N-()</b>	332.	364.	374.	429.	457.	497.	536.
	42"	2 1/4"	16"	<b>MP3-A1642N-()</b>	378.	414.	427.	490.	518.	566.	612.
	48"	2 1/4"	16"	<b>MP3-A1648N-()</b>	413.	451.	465.	532.	563.	613.	661.
	60"	2 1/4"	16"	<b>MP3-A1660N-()</b>	480.	524.	538.	616.	652.	711.	767.
 Options add-on panels, upholstered, 18"H	18"	2 1/4"	18"	<b>MP3-A1818N-()</b>	254.	280.	288.	331.	350.	382.	413.
	24"	2 1/4"	18"	<b>MP3-A1824N-()</b>	277.	303.	310.	356.	377.	411.	444.
	30"	2 1/4"	18"	<b>MP3-A1830N-()</b>	315.	343.	351.	403.	427.	463.	501.
	36"	2 1/4"	18"	<b>MP3-A1836N-()</b>	346.	378.	389.	446.	473.	516.	558.
	42"	2 1/4"	18"	<b>MP3-A1842N-()</b>	393.	431.	444.	510.	538.	589.	637.
	48"	2 1/4"	18"	<b>MP3-A1848N-()</b>	429.	470.	484.	553.	587.	637.	689.
	60"	2 1/4"	18"	<b>MP3-A1860N-()</b>	497.	542.	562.	641.	678.	738.	798.
 Options add-on panels, upholstered, 22"H	18"	2 1/4"	22"	<b>MP3-A2218N-()</b>	274.	298.	309.	355.	374.	409.	441.
	24"	2 1/4"	22"	<b>MP3-A2224N-()</b>	295.	323.	332.	379.	404.	440.	473.
	30"	2 1/4"	22"	<b>MP3-A2230N-()</b>	333.	365.	375.	431.	457.	497.	536.
	36"	2 1/4"	22"	<b>MP3-A2236N-()</b>	371.	405.	416.	477.	507.	552.	596.
	42"	2 1/4"	22"	<b>MP3-A2242N-()</b>	419.	460.	473.	545.	576.	629.	679.
	48"	2 1/4"	22"	<b>MP3-A2248N-()</b>	459.	501.	516.	591.	624.	681.	737.
	60"	2 1/4"	22"	<b>MP3-A2260N-()</b>	532.	580.	598.	683.	725.	790.	851.
 Options add-on panels, upholstered, 32"H	18"	2 1/4"	32"	<b>MP3-A3218N-()</b>	300.	321.	328.	377.	401.	435.	462.
	24"	2 1/4"	32"	<b>MP3-A3224N-()</b>	328.	364.	376.	433.	446.	477.	517.
	30"	2 1/4"	32"	<b>MP3-A3230N-()</b>	370.	400.	412.	472.	486.	517.	574.
	36"	2 1/4"	32"	<b>MP3-A3236N-()</b>	411.	446.	460.	527.	548.	587.	642.
	42"	2 1/4"	32"	<b>MP3-A3242N-()</b>	465.	502.	517.	594.	613.	652.	723.
	48"	2 1/4"	32"	<b>MP3-A3248N-()</b>	508.	549.	637.	649.	680.	737.	790.
	60"	2 1/4"	32"	<b>MP3-A3260N-()</b>	588.	641.	658.	757.	785.	844.	912.

### Order Code

Example:	<b>MP3-A2230-15-W210/2</b>
<b>MP3</b>	Panel
<b>A</b>	Add-on
<b>22</b>	Height
<b>30</b>	Width
<b>15</b>	Surface type and group no.
<b>W210/2</b>	Upholstery

### Specification Information

*Surface type/finish suffixes*

For upholstered panels, specify upholstery pattern number after the fabric group number.

10- Fabric group 10  
 15- Fabric group 15  
 20- Fabric group 20  
 30- Fabric group 30  
 35- Fabric group 35  
 40- Fabric group 40  
 45- Fabric group 45

Upholstered add-on panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.

For combinations of fabrics list both suffixes (e.g. 10/20) and upholstery pattern numbers.

### Application Notes

Add-on panels mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.

All add-on panels are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.

16"H add-on panels may be mounted on 48"H and 64"H vertical panels and connected, respectively, with standard 64"H and 80"H connector tracks and post assemblies.

18"H add-on panels may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74"H connector tracks and post assemblies.

22"H add-on panels may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.

32"H add-on panels may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.

Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets.





Two 16"H add-on panels may be mounted on a 48"H upholstered panel only when using 80"H full height connector track and post assemblies.

# Veneer and combination add-on panels

Morrison

## veneer group 1

### 16", 18", 22" and 32"H

description	w	d	h	pattern no.	combination						veneer both sides	
					10	15	20	30	35	40		45
 16"H	18"	2"	16"	MP3-A1618-()()	\$349.	\$366.	\$372.	\$393.	\$404.	\$420.	\$439.	\$439.
	24"	2"	16"	MP3-A1624-()()	385.	402.	407.	431.	442.	460.	477.	484.
	30"	2"	16"	MP3-A1630-()()	427.	447.	452.	480.	492.	512.	532.	533.
	36"	2"	16"	MP3-A1636-()()	472.	495.	501.	532.	547.	568.	590.	590.
	42"	2"	16"	MP3-A1642-()()	528.	554.	560.	595.	612.	637.	661.	651.
	48"	2"	16"	MP3-A1648-()()	587.	616.	622.	657.	676.	703.	732.	733.
 18"H	18"	2"	18"	MP3-A1818-()()	365.	385.	389.	413.	422.	441.	458.	460.
	24"	2"	18"	MP3-A1824-()()	402.	420.	425.	450.	462.	481.	498.	509.
	30"	2"	18"	MP3-A1830-()()	446.	469.	473.	501.	515.	535.	556.	560.
	36"	2"	18"	MP3-A1836-()()	495.	518.	526.	556.	571.	595.	618.	621.
	42"	2"	18"	MP3-A1842-()()	553.	578.	587.	622.	640.	668.	694.	683.
	48"	2"	18"	MP3-A1848-()()	614.	644.	651.	689.	707.	736.	764.	770.
 22" H	18"	2"	22"	MP3-A2218-()()	388.	407.	412.	437.	447.	467.	484.	484.
	24"	2"	22"	MP3-A2224-()()	425.	446.	451.	478.	490.	510.	529.	536.
	30"	2"	22"	MP3-A2230-()()	472.	496.	501.	532.	547.	568.	590.	590.
	36"	2"	22"	MP3-A2236-()()	525.	550.	556.	589.	605.	629.	654.	653.
	42"	2"	22"	MP3-A2242-()()	585.	614.	621.	658.	677.	707.	735.	722.
	48"	2"	22"	MP3-A2248-()()	650.	680.	689.	732.	751.	782.	812.	812.
 32" H	18"	2"	32"	MP3-A3218-()()	435.	451.	455.	483.	495.	515.	531.	550.
	24"	2"	32"	MP3-A3224-()()	481.	506.	512.	541.	550.	567.	590.	610.
	30"	2"	32"	MP3-A3230-()()	532.	555.	562.	595.	601.	620.	650.	671.
	36"	2"	32"	MP3-A3236-()()	590.	618.	624.	659.	673.	696.	725.	742.
	42"	2"	32"	MP3-A3242-()()	656.	686.	696.	736.	746.	767.	807.	819.
	48"	2"	32"	MP3-A3248-()()	732.	762.	812.	817.	836.	865.	896.	922.

#### Order Code

Example: **MP3-A2230-T-15-W210/20**

<b>MP3</b>	Panel
<b>A</b>	Add-on
<b>22</b>	Height
<b>30</b>	Width
<b>T</b>	Veneer finish
<b>15</b>	Fabric group
<b>W210/20</b>	Upholstery

#### Specification Information

##### Surface type/finish suffixes:

When specifying combination panels, follow panel size with veneer finish code, the upholstery finish code and pattern number. For upholstered panels, specify upholstery pattern number after the fabric group number.

- 10- Fabric group 10
- 15- Fabric group 15
- 20- Fabric group 20
- 30- Fabric group 30
- 35- Fabric group 35
- 40- Fabric group 40
- 45- Fabric group 45

To order veneer on both sides, follow panel size with suffix V- and veneer finish code.  
Example: MP3-A2230-V-T.

#### Application Notes

Add-on panels mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.

All add-on panels are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.

16"H add-on panels may be mounted on 48"H and 74"H vertical panels and connected, respectively, with standard 64"H and 80" connector tracks and post assemblies.

18"H add-on panels may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74" connector tracks and post assemblies.

22"H add-on panels may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.

32"H add-on panels may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.

Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets.

Veneer Group 1 add-on panels are quartered Techgrain®.







# Veneer and combination add-on panels

Morrison

## veneer group 2

### 16", 18", 22" and 32"H

description	w	d	h	pattern no.	combination						Veneer both sides	
					10	15	20	30	35	40		45
 16"H	18"	2"	16"	MP3-A1618-()()	\$385.	\$402.	\$407.	\$429.	\$440.	\$457.	\$472.	\$508.
	24"	2"	16"	MP3-A1624-()()	413.	432.	435.	459.	471.	489.	507.	541.
	30"	2"	16"	MP3-A1630-()()	461.	483.	488.	513.	528.	548.	566.	601.
	36"	2"	16"	MP3-A1636-()()	508.	532.	536.	566.	581.	604.	626.	659.
	42"	2"	16"	MP3-A1642-()()	567.	594.	600.	636.	651.	677.	702.	733.
	48"	2"	16"	MP3-A1648-()()	627.	655.	663.	700.	716.	743.	771.	816.
 18"H	18"	2"	18"	MP3-A1818-()()	403.	419.	425.	449.	460.	478.	493.	534.
	24"	2"	18"	MP3-A1824-()()	433.	452.	457.	482.	493.	511.	531.	571.
	30"	2"	18"	MP3-A1830-()()	484.	506.	510.	538.	552.	572.	593.	633.
	36"	2"	18"	MP3-A1836-()()	533.	556.	563.	594.	609.	632.	654.	697.
	42"	2"	18"	MP3-A1842-()()	595.	622.	629.	668.	681.	710.	736.	770.
	48"	2"	18"	MP3-A1848-()()	656.	687.	696.	734.	752.	781.	808.	858.
 22"H	18"	2"	22"	MP3-A2218-()()	427.	445.	451.	477.	488.	506.	525.	563.
	24"	2"	22"	MP3-A2224-()()	458.	480.	484.	510.	524.	541.	562.	600.
	30"	2"	22"	MP3-A2230-()()	511.	535.	539.	570.	585.	608.	628.	669.
	36"	2"	22"	MP3-A2236-()()	564.	589.	595.	628.	646.	671.	695.	733.
	42"	2"	22"	MP3-A2242-()()	629.	657.	668.	704.	723.	753.	781.	812.
	48"	2"	22"	MP3-A2248-()()	697.	727.	736.	776.	795.	826.	857.	903.
 32"H	18"	2"	32"	MP3-A3218-()()	480.	495.	500.	528.	539.	559.	574.	640.
	24"	2"	32"	MP3-A3224-()()	516.	541.	549.	580.	588.	604.	626.	682.
	30"	2"	32"	MP3-A3230-()()	576.	598.	606.	641.	647.	663.	696.	759.
	36"	2"	32"	MP3-A3236-()()	634.	659.	670.	705.	716.	738.	767.	832.
	42"	2"	32"	MP3-A3242-()()	709.	737.	744.	788.	797.	819.	858.	922.
	48"	2"	32"	MP3-A3248-()()	784.	815.	863.	870.	887.	918.	948.	1,026.







Order Code	Specification Information	Application Notes
Example: <b>MP3-A2230-8-15-W210/20</b> <hr/> <b>MP3</b> Panel <hr/> <b>A</b> Add-on <hr/> <b>22</b> Height <hr/> <b>30</b> Width <hr/> <b>8</b> Veneer finish <hr/> <b>15</b> Fabric group <hr/> <b>W210/20</b> Upholstery	<p><i>Surface type/finish suffixes:</i></p> <p>When specifying combination panels, follow panel size with veneer finish code, the upholstery finish code and pattern number. For upholstered panels, specify upholstery pattern number after the fabric group number.</p> <p>10- Fabric group 10                      15- Fabric group 15                      20- Fabric group 20                      30- Fabric group 30                      35- Fabric group 35                      40- Fabric group 40                      45- Fabric group 45</p> <p>To order veneer on both sides, follow panel size with suffix V- and veneer finish code.                      Example: MP3-A2230-V-8.</p>	<p>Add-on panels mount on any height Morrison vertical panel of the same width with add-on connectors or full height connectors.</p> <p>All add-on panels are 1/4" less than nominal height to allow for a 1/4" horizontal reveal with light seal.</p> <p>16"H add-on panels may be mounted on 48"H and 74"H vertical panels and connected, respectively, with standard 64"H and 80" connector tracks and post assemblies.</p> <p>18"H add-on panels may be mounted on 30"H and 56"H vertical panels and connected, respectively, with standard 48"H and 74" connector tracks and post assemblies.</p> <p>22"H add-on panels may be mounted on 42"H vertical panels and connected with standard 64"H connector tracks and post assemblies.</p> <p>32"H add-on panels may be mounted on 48"H vertical panels and connected with standard 80"H connector tracks and post assemblies.</p> <p>Full height 48" and 64" connectors permit cantilevered shelves and overhead cabinets.</p> <p>Veneer Group 2 add-on panels are rift cut Techgrain®.</p>



# Add-on connectors, post assemblies upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	no trim	10	15	20	30	35	40	45
 Connector track	No trim	-	-	9"	<b>MC1-A09S1</b>	\$37.							
		-	-	16"	<b>MC1-A16S1</b>	37.							
		-	-	18"	<b>MC1-A18S1</b>	38.							
		-	-	22"	<b>MC1-A22S1</b>	38.							
		-	-	32"	<b>MC1-A32S1</b>	40.							
 90° 2-way, "L"	Upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09L2-( )</b>		130.	144.	144.	144.	155.	155.	155.
		2 1/4"	2 1/4"	16"	<b>MC1-A16L2-( )</b>		130.	144.	144.	144.	155.	155.	155.
		2 1/4"	2 1/4"	18"	<b>MC1-A18L2-( )</b>		132.	147.	147.	147.	158.	158.	158.
		2 1/4"	2 1/4"	22"	<b>MC1-A22L2-( )</b>		132.	147.	147.	147.	158.	158.	158.
		2 1/4"	2 1/4"	32"	<b>MC1-A32L2-( )</b>		138.	155.	155.	155.	165.	165.	165.
 90° 3-way, "T"	Upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09T3-( )</b>		159.	173.	173.	173.	183.	183.	199.
		2 1/4"	2 1/4"	16"	<b>MC1-A16T3-( )</b>		159.	173.	173.	173.	183.	183.	199.
		2 1/4"	2 1/4"	18"	<b>MC1-A18T3-( )</b>		163.	179.	179.	179.	188.	188.	202.
		2 1/4"	2 1/4"	22"	<b>MC1-A22T3-( )</b>		163.	179.	179.	179.	188.	188.	202.
		2 1/4"	2 1/4"	32"	<b>MC1-A32T3-( )</b>		169.	189.	189.	189.	196.	196.	211.
 90° 4-way, "X"	No trim	2 1/4"	2 1/4"	9"	<b>MC1-A09X4</b>	176.							
		2 1/4"	2 1/4"	16"	<b>MC1-A16X4</b>	176.							
		2 1/4"	2 1/4"	18"	<b>MC1-A18X4</b>	182.							
		2 1/4"	2 1/4"	22"	<b>MC1-A22X4</b>	182.							
		2 1/4"	2 1/4"	32"	<b>MC1-A32X4</b>	192.							
 End	Upholstered	2 1/4"	1"	9"	<b>MC1-A09E1-( )</b>		61.	70.	70.	70.	79.	79.	91.
		2 1/4"	1"	16"	<b>MC1-A16E1-( )</b>		61.	70.	70.	70.	79.	79.	91.
		2 1/4"	1"	18"	<b>MC1-A18E1-( )</b>		63.	72.	72.	72.	80.	80.	92.
		2 1/4"	1"	22"	<b>MC1-A22E1-( )</b>		63.	72.	72.	72.	80.	80.	92.
		2 1/4"	1"	32"	<b>MC1-A32E1-( )</b>		65.	76.	76.	76.	84.	84.	97.
 End Post	Upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09P1-( )</b>		130.	144.	144.	144.	155.	155.	155.
		2 1/4"	2 1/4"	16"	<b>MC1-A16P1-( )</b>		130.	144.	144.	144.	155.	155.	155.
		2 1/4"	2 1/4"	18"	<b>MC1-A18P1-( )</b>		132.	147.	147.	147.	158.	158.	158.
		2 1/4"	2 1/4"	22"	<b>MC1-A22P1-( )</b>		132.	147.	147.	147.	158.	158.	158.
		2 1/4"	2 1/4"	32"	<b>MC1-A32P1-( )</b>		138.	155.	155.	155.	165.	165.	165.

Order Code	Specification Information	Application Notes
Example: <b>MC1-A16L2-15-W210/20</b> <hr/> <b>MC1</b> Connector <hr/> <b>A</b> Add-on <hr/> <b>16</b> Height <hr/> <b>L2</b> 2 way "L" <hr/> <b>15</b> Surface type and group no. <hr/> <b>W210/20</b> Upholstery	<b>Assembly:</b> S1- Straight connector track L2- 90° 2-way post assembly T3- 90° 3-way post assembly X4- 4-way post assembly E1- End connector assembly P1- End post assembly S2- Straight post assembly  <b>Surface type:</b> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45	Post assembly pricing includes connector tracks, posts, and trim covers when required. Top caps/raceway covers are specified as separate kits and bulk shipped to facilitate installation.  Add-on connectors include brackets to add panels or windows to the top of any Morrison vertical panel except glazed panels.  Add-on connectors must be specified in the same height as the add-on panel or window.


Add-on connectors do not support cantilevered shelves or overhead cabinets. For these applications, specify full height connectors.

Add-on end post should be specified when add-on panels end over L or T post.

2-way straight post should be specified when add-on panels connect in a straight line over an X or T post.

# Add-on connectors, post assemblies upholstered

Morrison

description	type	w	d	h	pattern no.	no trim	10	15	20	30	35	40	45
	Upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09S2-( )</b>		\$159.	\$173.	\$173.	\$173.	\$183.	\$183.	\$199.
		2 1/4"	2 1/4"	16"	<b>MC1-A16S2-( )</b>		159.	173.	173.	173.	183.	183.	199.
		2 1/4"	2 1/4"	18"	<b>MC1-A18S2-( )</b>		163.	179.	179.	179.	188.	188.	202.
		2 1/4"	2 1/4"	22"	<b>MC1-A22S2-( )</b>		163.	179.	179.	179.	188.	188.	202.
		2 1/4"	2 1/4"	32"	<b>MC1-A32S2-( )</b>		169.	189.	189.	189.	196.	196.	211.

Order Code	Specification Information	Application Notes
Example: <b>MC1-A16L2-15-W210/20</b> <hr/> <b>MC1</b> Connector <hr/> <b>A</b> Add-on <hr/> <b>16</b> Height <hr/> <b>L2</b> 2 way "L" <hr/> <b>15</b> Surface type and group no. <hr/> <b>W210/20</b> Upholstery	<i>Assembly:</i> S1- Straight connector track L2- 90° 2-way post assembly T3- 90° 3-way post assembly X4- 4-way post assembly E1- End connector assembly P1- End post assembly S2- Straight post assembly  <i>Surface type:</i> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45	Post assembly pricing includes connector tracks, posts, and trim covers when required. Top caps/raceway covers are specified as separate kits and bulk shipped to facilitate installation.  Add-on connectors include brackets to add panels or windows to the top of any Morrison vertical panel except glazed panels.  Add-on connectors must be specified in the same height as the add-on panel or window.

Add-on connectors do not support cantilevered shelves or overhead cabinets. For these applications, specify full height connectors.







Add-on end post should be specified when add-on panels end over L or T post.

2-way straight post should be specified when add-on panels connect in a straight line over an X or T post.

# Add-on connectors, post assemblies non-upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	no trim	Paint	V1	V2
 Connector track	No trim	-	-	9"	<b>MC1-A09S1</b>	\$37.			
		-	-	16"	<b>MC1-A16S1</b>	37.			
		-	-	18"	<b>MC1-A18S1</b>	38.			
		-	-	22"	<b>MC1-A22S1</b>	38.			
		-	-	32"	<b>MC1-A32S1</b>	40.			
 90° 2-way, "L"	Non-upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09L2-( )</b>		126.	169.	178.
		2 1/4"	2 1/4"	16"	<b>MC1-A16L2-( )</b>		126.	169.	178.
		2 1/4"	2 1/4"	18"	<b>MC1-A18L2-( )</b>		130.	172.	182.
		2 1/4"	2 1/4"	22"	<b>MC1-A22L2-( )</b>		130.	172.	182.
		2 1/4"	2 1/4"	32"	<b>MC1-A32L2-( )</b>		136.	182.	192.
 90° 3-way, "T"	Non-upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09T3-( )</b>		159.	210.	219.
		2 1/4"	2 1/4"	16"	<b>MC1-A16T3-( )</b>		159.	210.	219.
		2 1/4"	2 1/4"	18"	<b>MC1-A18T3-( )</b>		163.	216.	228.
		2 1/4"	2 1/4"	22"	<b>MC1-A22T3-( )</b>		163.	216.	228.
		2 1/4"	2 1/4"	32"	<b>MC1-A32T3-( )</b>		170.	227.	238.
 90° 4-way, "X"	No trim	2 1/4"	2 1/4"	9"	<b>MC1-A09X4</b>	176.			
		2 1/4"	2 1/4"	16"	<b>MC1-A16X4</b>	176.			
		2 1/4"	2 1/4"	18"	<b>MC1-A18X4</b>	182.			
		2 1/4"	2 1/4"	22"	<b>MC1-A22X4</b>	182.			
		2 1/4"	2 1/4"	32"	<b>MC1-A32X4</b>	192.			
 End	Non-upholstered	2 1/4"	1"	9"	<b>MC1-A09E1-( )</b>		54.	88.	91.
		2 1/4"	1"	16"	<b>MC1-A16E1-( )</b>		54.	88.	91.
		2 1/4"	1"	18"	<b>MC1-A18E1-( )</b>		55.	90.	94.
		2 1/4"	1"	22"	<b>MC1-A22E1-( )</b>		55.	90.	94.
		2 1/4"	1"	32"	<b>MC1-A32E1-( )</b>		57.	93.	98.
 End Post	Non-upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09P1-( )</b>		126.	206.	215.
		2 1/4"	2 1/4"	16"	<b>MC1-A16P1-( )</b>		126.	206.	215.
		2 1/4"	2 1/4"	18"	<b>MC1-A18P1-( )</b>		130.	209.	218.
		2 1/4"	2 1/4"	22"	<b>MC1-A22P1-( )</b>		130.	209.	218.
		2 1/4"	2 1/4"	32"	<b>MC1-A32P1-( )</b>		136.	219.	233.

**Order Code**

Example: <b>MC1-A16L2-613</b>	
<b>MC1</b>	Connector
<b>A</b>	Add-on
<b>16</b>	Height
<b>L2</b>	2 way "L"
<b>613</b>	Paint finish

**Specification Information**

*Assembly:*


S1-	Straight connector track
L2-	90° 2-way post assembly
T3-	90° 3-way post assembly
X4-	4-way post assembly
E1-	End connector assembly
P1-	End post assembly
S2-	Straight post assembly

**Application Notes**

Please see previous page for Application Notes.

# Add-on connectors, post assemblies non-upholstered

Morrison

description	type	w	d	h	pattern no.	no trim	Paint	V1	V2
	Non-upholstered	2 1/4"	2 1/4"	9"	<b>MC1-A09S2-( )</b>		\$159.	\$256.	\$270.
		2 1/4"	2 1/4"	16"	<b>MC1-A16S2-( )</b>		159.	256.	270.
		2 1/4"	2 1/4"	18"	<b>MC1-A18S2-( )</b>		163.	263.	277.
		2 1/4"	2 1/4"	22"	<b>MC1-A22S2-( )</b>		163.	263.	277.
		2 1/4"	2 1/4"	32"	<b>MC1-A32S2-( )</b>		170.	276.	289.

## Order Code

Example: **MC1-A16L2-613**

<b>MC1</b>	Connector
<b>A</b>	Add-on
<b>16</b>	Height
<b>L2</b>	2 way "L"
<b>613</b>	Paint finish

## Specification Information

*Assembly:*

S1-	Straight connector track
L2-	90° 2-way post assembly
T3-	90° 3-way post assembly
X4-	4-way post assembly
E1-	End connector assembly
P1-	End post assembly
S2-	Straight post assembly






## Application Notes

Please see previous page for Application Notes.

# Connectors, post assemblies upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	no trim	10	15	20	30	35	40	45	
 Connector track	No trim	-	-	30"	<b>MC1-30S1</b>	\$38.								
		-	-	39"	<b>MC1-39S1</b>	39.								
		-	-	42"	<b>MC1-42S1</b>	39.								
		-	-	48"	<b>MC1-48S1</b>	44.								
		-	-	56"	<b>MC1-56S1</b>	47.								
		-	-	64"	<b>MC1-64S1</b>	48.								
		-	-	80"	<b>MC1-80S1</b>	56.								
 90° 2-way, "L"	Upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30L2(-)</b>		131.	144.	144.	144.	155.	155.	168.	
		2 1/4"	2 1/4"	39"	<b>MC1-39L2(-)</b>		137.	148.	148.	148.	159.	159.	171.	
		2 1/4"	2 1/4"	42"	<b>MC1-42L2(-)</b>		135.	150.	150.	150.	160.	160.	172.	
		2 1/4"	2 1/4"	48"	<b>MC1-48L2(-)</b>		138.	157.	157.	157.	164.	164.	185.	
		2 1/4"	2 1/4"	56"	<b>MC1-56L2(-)</b>		142.	160.	160.	160.	167.	167.	192.	
		2 1/4"	2 1/4"	64"	<b>MC1-64L2(-)</b>		148.	167.	167.	167.	172.	172.	200.	
		2 1/4"	2 1/4"	80"	<b>MC1-80L2(-)</b>		190.	208.	208.	208.	226.	226.	259.	
 90° 3-way, "T"	Upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30T3(-)</b>		161.	178.	178.	178.	185.	185.	200.	
		2 1/4"	2 1/4"	39"	<b>MC1-39T3(-)</b>		165.	182.	182.	182.	189.	189.	203.	
		2 1/4"	2 1/4"	42"	<b>MC1-42T3(-)</b>		166.	183.	183.	183.	192.	192.	206.	
		2 1/4"	2 1/4"	48"	<b>MC1-48T3(-)</b>		172.	192.	192.	192.	200.	200.	218.	
		2 1/4"	2 1/4"	56"	<b>MC1-56T3(-)</b>		180.	200.	200.	200.	206.	206.	228.	
		2 1/4"	2 1/4"	64"	<b>MC1-64T3(-)</b>		189.	206.	206.	206.	214.	214.	238.	
		2 1/4"	2 1/4"	80"	<b>MC1-80T3(-)</b>		238.	263.	263.	263.	283.	283.	309.	
 90° 4-way, "X"	No trim	2 1/4"	2 1/4"	30"	<b>MC1-30X4</b>	180.								
		2 1/4"	2 1/4"	39"	<b>MC1-39X4</b>	185.								
		2 1/4"	2 1/4"	42"	<b>MC1-42X4</b>	188.								
		2 1/4"	2 1/4"	48"	<b>MC1-48X4</b>	205.								
		2 1/4"	2 1/4"	56"	<b>MC1-56X4</b>	216.								
		2 1/4"	2 1/4"	64"	<b>MC1-64X4</b>	228.								
		2 1/4"	2 1/4"	80"	<b>MC1-80X4</b>	282.								
 End	Upholstered	2 1/4"	1"	30"	<b>MC1-30E1(-)</b>		61.	70.	70.	70.	79.	79.	91.	
		2 1/4"	1"	39"	<b>MC1-39E1(-)</b>		63.	72.	72.	72.	80.	80.	92.	
		2 1/4"	1"	42"	<b>MC1-42E1(-)</b>		64.	73.	73.	73.	82.	82.	93.	
		2 1/4"	1"	48"	<b>MC1-48E1(-)</b>		69.	79.	79.	79.	86.	86.	98.	
		2 1/4"	1"	56"	<b>MC1-56E1(-)</b>		72.	82.	82.	82.	88.	88.	105.	
		2 1/4"	1"	64"	<b>MC1-64E1(-)</b>		75.	84.	84.	84.	90.	90.	113.	
		2 1/4"	1"	80"	<b>MC1-80E1(-)</b>		98.	98.	98.	98.	118.	118.	152.	

### Order Code

Example:	<b>MC1-42L2-15-W210/20</b>
<b>MC1</b>	Connector
<b>42</b>	Height
<b>L2</b>	2 way "L"
<b>15</b>	Surface type and group no.
<b>W210/20</b>	Upholstery

### Specification Information






<i>Assembly:</i>		<i>Surface type:</i>	
<i>S1-</i>	<i>Straight connector</i>	10-	Fabric group 10
<i>L2-</i>	<i>90° 2-way post assembly</i>	15-	Fabric group 15
<i>T3-</i>	<i>90° 3-way post assembly</i>	20-	Fabric group 20
<i>X4-</i>	<i>90° 4-way post assembly</i>	30-	Fabric group 30
<i>E1-</i>	<i>End connector assembly</i>	35-	Fabric group 35
		40-	Fabric group 40
		45-	Fabric group 45

### Application Notes

Post assembly pricing includes connector tracks, posts and trim covers when required. Top caps and raceway covers are specified as separate kits and bulk shipped to facilitate installation.

# Connectors, post assemblies non-upholstered

Morrison

description	type	w	d	h	pattern no.	no trim	Paint	V1	V2	V3
 Connector track	No trim	-	-	30"	<b>MC1-30S1</b>	\$38.				
		-	-	39"	<b>MC1-39S1</b>	39.				
		-	-	42"	<b>MC1-42S1</b>	39.				
		-	-	48"	<b>MC1-48S1</b>	44.				
		-	-	56"	<b>MC1-56S1</b>	47.				
		-	-	64"	<b>MC1-64S1</b>	48.				
		-	-	80"	<b>MC1-80S1</b>	56.				
 90° 2-way, "L"	Non-upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30L2-(-)</b>		129.	170.	180.	216.
		2 1/4"	2 1/4"	39"	<b>MC1-39L2-(-)</b>		131.	173.	185.	222.
		2 1/4"	2 1/4"	42"	<b>MC1-42L2-(-)</b>		132.	175.	186.	224.
		2 1/4"	2 1/4"	48"	<b>MC1-48L2-(-)</b>		137.	186.	195.	234.
		2 1/4"	2 1/4"	56"	<b>MC1-56L2-(-)</b>		140.	194.	203.	245.
		2 1/4"	2 1/4"	64"	<b>MC1-64L2-(-)</b>		147.	203.	209.	252.
		2 1/4"	2 1/4"	80"	<b>MC1-80L2-(-)</b>		186.	253.	270.	323.
 90° 3-way, "T"	Non-upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30T3-(-)</b>		161.	198.	203.	245.
		2 1/4"	2 1/4"	39"	<b>MC1-39T3-(-)</b>		165.	201.	207.	248.
		2 1/4"	2 1/4"	42"	<b>MC1-42T3-(-)</b>		166.	203.	209.	252.
		2 1/4"	2 1/4"	48"	<b>MC1-48T3-(-)</b>		173.	215.	222.	266.
		2 1/4"	2 1/4"	56"	<b>MC1-56T3-(-)</b>		179.	226.	234.	280.
		2 1/4"	2 1/4"	64"	<b>MC1-64T3-(-)</b>		189.	234.	241.	289.
		2 1/4"	2 1/4"	80"	<b>MC1-80T3-(-)</b>		236.	304.	321.	385.
 90° 4-way, "X"	No trim	2 1/4"	2 1/4"	30"	<b>MC1-30X4</b>	180.				
		2 1/4"	2 1/4"	39"	<b>MC1-39X4</b>	185.				
		2 1/4"	2 1/4"	42"	<b>MC1-42X4</b>	188.				
		2 1/4"	2 1/4"	48"	<b>MC1-48X4</b>	205.				
		2 1/4"	2 1/4"	56"	<b>MC1-56X4</b>	216.				
		2 1/4"	2 1/4"	64"	<b>MC1-64X4</b>	228.				
		2 1/4"	2 1/4"	80"	<b>MC1-80X4</b>	282.				
 End	Non-upholstered	2 1/4"	1"	30"	<b>MC1-30E1-(-)</b>		55.	93.	100.	120.
		2 1/4"	1"	39"	<b>MC1-39E1-(-)</b>		56.	94.	105.	124.
		2 1/4"	1"	42"	<b>MC1-42E1-(-)</b>		56.	96.	107.	125.
		2 1/4"	1"	48"	<b>MC1-48E1-(-)</b>		63.	100.	112.	134.
		2 1/4"	1"	56"	<b>MC1-56E1-(-)</b>		66.	107.	115.	137.
		2 1/4"	1"	64"	<b>MC1-64E1-(-)</b>		70.	115.	121.	147.
		2 1/4"	1"	80"	<b>MC1-80E1-(-)</b>		87.	154.	160.	193.

## Order Code

Example: **MC1-42L2-V-4**

<b>MC1</b>	Connector
<b>42</b>	Height
<b>L2</b>	2 way "L"
<b>V</b>	Surface type
<b>4</b>	Veneer

## Specification Information

*Assembly:*  
*S1- Straight connector*  
*L2- 90° 2-way post assembly*  
*T3- 90° 3-way post assembly*  
*X4- 90° 4-way post assembly*  
*E1- End connector assembly*

## Application Notes

Post assembly pricing includes connector tracks, posts and trim covers when required. Top caps and raceway covers are specified as separate kits and bulk shipped to facilitate installation.

Veneer Group 1 trim covers are quartered Techgrain®.

Veneer Group 2 trim covers are rift cut Techgrain®.

Veneer Group 3 trim covers are narrow heart, flat cut natural veneer.



# Connectors, post assemblies

## 120-degree

### upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	Paint	10	15	20	30	35	40	45
	Upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30V2-( ) ( )</b>		\$142.	\$157.	\$157.	\$157.	\$167.	\$167.	\$180.
		2 1/4"	2 1/4"	39"	<b>MC1-39V2-( ) ( )</b>		147.	161.	161.	161.	170.	170.	183.
		2 1/4"	2 1/4"	42"	<b>MC1-42V2-( ) ( )</b>		145.	163.	163.	163.	171.	171.	185.
		2 1/4"	2 1/4"	48"	<b>MC1-48V2-( ) ( )</b>		148.	168.	168.	168.	175.	175.	196.
		2 1/4"	2 1/4"	56"	<b>MC1-56V2-( ) ( )</b>		154.	171.	171.	171.	179.	179.	203.
		2 1/4"	2 1/4"	64"	<b>MC1-64V2-( ) ( )</b>		161.	179.	179.	179.	185.	185.	211.
		2 1/4"	2 1/4"	80"	<b>MC1-80V2-( ) ( )</b>		202.	219.	219.	219.	237.	237.	271.
Post assemblies	120° 2-way, "V"	-	-	-	<b>MT5-CV2-( ) ( )</b>	4.							
	120° 3-way, "Y"	-	-	-	<b>MT5-CY3-( ) ( )</b>	4.							

#### Order Code

Example:	<b>MC1-64V2-15-W210/20</b>
	<b>613</b>
<b>MC1</b>	Connector
<b>64</b>	Height
<b>V2</b>	120° 2 way "V"
<b>15</b>	Fabric grade
<b>W210/20</b>	Upholstery
<b>613</b>	Inside trim finish

#### Specification Information

*Assembly:*  
V2- 120-° 2-way connector

*Surface type:*  
10- Fabric group 10  
15- Fabric group 15  
20- Fabric group 20  
30- Fabric group 30  
35- Fabric group 35  
40- Fabric group 40  
45- Fabric group 45

*Inside trim Finish*

#### Application Notes

Post assembly pricing includes connector tracks, posts and trim covers when required.

2-way "V" post assemblies include one outside trim, upholstered, and one inside trim, painted.




3-way "Y" post assemblies include three inside trims, painted.

Top caps and raceway covers are specified separately.

Veneer trim finishes are not available on 120° post assemblies.

Connectors, post assemblies  
120-degree  
non-upholstered

Morrison

description	type	w	d	h	pattern no.	Paint
	Non-upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30V2-( )()</b>	\$140.
		2 1/4"	2 1/4"	39"	<b>MC1-39V2-( )()</b>	142.
		2 1/4"	2 1/4"	42"	<b>MC1-42V2-( )()</b>	143.
		2 1/4"	2 1/4"	48"	<b>MC1-48V2-( )()</b>	147.
		2 1/4"	2 1/4"	56"	<b>MC1-56V2-( )()</b>	152.
		2 1/4"	2 1/4"	64"	<b>MC1-64V2-( )()</b>	160.
		2 1/4"	2 1/4"	80"	<b>MC1-80V2-( )()</b>	198.
	Non-upholstered	2 1/4"	2 1/4"	30"	<b>MC1-30Y3-( )</b>	172.
		2 1/4"	2 1/4"	39"	<b>MC1-39Y3-( )</b>	176.
		2 1/4"	2 1/4"	42"	<b>MC1-42Y3-( )</b>	178.
		2 1/4"	2 1/4"	48"	<b>MC1-48Y3-( )</b>	186.
		2 1/4"	2 1/4"	56"	<b>MC1-56Y3-( )</b>	190.
		2 1/4"	2 1/4"	64"	<b>MC1-64Y3-( )</b>	201.
		2 1/4"	2 1/4"	80"	<b>MC1-80Y3-( )</b>	248.
	120° 2-way, "V"	—	—	—	<b>MT5-CV2-( )()</b>	4.
	120° 3-way, "Y"	—	—	—	<b>MT5-CY3-( )</b>	4.

Order Code

Example:	<b>MC1-64V2-613-613</b>
<b>MC1</b>	Connector
<b>64</b>	Height
<b>V2</b>	120° 2-way "V"
<b>613</b>	Outside trim finish
<b>613</b>	Inside trim finish

Specification Information

Assembly:  
V2- 120° 2-way  
Y3- 120° 3-way

Outside and inside trim paint finish.

Veneer trim finishes are not available on 120° post assemblies.

Application Notes

Post assembly pricing includes connector tracks, posts and trim covers when required.

2-way "V" post assemblies include one outside trim and one inside trim, painted.

3-way "Y" post assemblies include three inside trims, painted.

Top caps and raceway covers are specified separately.




# Connectors, post assemblies

## *variable angles*

### *upholstered*

Morrison

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
Variable angle	Upholstered	2 1/4"	2 1/4"	64"	<b>MC1-64H1-( )</b>	\$496.	\$504.	\$504.	\$504.	\$521.	\$521.	\$542.




Panel Planning

Order Code	Specification Information	Application Notes
Example: <b>MC1-64H1-15-W210/20</b>	<i>Finishes for variable angle:</i>	Variable angle connector includes connector tracks, continuous hinge, and trim covers. Specify top cap and raceway cover kit separately.
<b>MC1</b> Morrison accessory	<i>Upholstered:</i>	
<b>64</b> Height	10- Fabric group 10	
<b>H1</b> Variable angle	15- Fabric group 15	
<b>15</b> Surface type and group no.	20- Fabric group 20	
<b>W210/20</b> Upholstery	30- Fabric group 30	
	35- Fabric group 35	
	40- Fabric group 40	
	45- Fabric group 45	

Connectors, post assemblies  
*variable angles*  
*non-upholstered*

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
Variable angle	Non-upholstered	2 1/4"	2 1/4"	64"	<b>MC1-64H1-( )</b>	\$497.	\$553.	\$567.	\$680.



**Order Code**

Example:	<b>MC1-64H1-613</b>
<b>MC1</b>	Morrison accessory
<b>64</b>	Height
<b>H1</b>	Variable angle
<b>613</b>	Painted finish

**Specification Information**

Specify painted finish.


**Application Notes**

Variable angle connector includes connector tracks, continuous hinge, and trim covers. Specify top cap and raceway cover kit separately.

# High-low connectors

*straight*  
*upholstered*

Morrison

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
Straight high-low connectors 	39" H	2 1/4"	-	39"	<b>M2-9030-( )-( )</b>	\$120.	\$130.	\$130.	\$130.	\$137.	\$137.	\$161.
	48" H	2 1/4"	-	48"	<b>M2-8030-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	48"	<b>M2-8040-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	48"	<b>M2-8090-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
	56" H	2 1/4"	-	56"	<b>M2-5030-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	56"	<b>M2-5040-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	56"	<b>M2-5080-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
	64" H	2 1/4"	-	64"	<b>M2-6030-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	64"	<b>M2-6040-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	64"	<b>M2-6050-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
		2 1/4"	-	64"	<b>M2-6080-( )-( )</b>	120.	130.	130.	130.	137.	137.	161.
	80" H	2 1/4"	-	80"	<b>M2-1060-( )-( )</b>	165.	182.	182.	182.	209.	209.	241.
		2 1/4"	-	80"	<b>M2-1080-( )-( )</b>	165.	182.	182.	182.	209.	209.	241.

Panel Planning

## Order Code

Example: **M2-5040-613-15-W210/20**

<b>M2</b>	Connector
<b>5040</b>	Configuration
<b>613</b>	Top cap finish
<b>15</b>	Surface type and group no.
<b>W210/20</b>	Upholstery

## Specification Information

First finish suffix is for top cap, second is surface type.

### Surface type:

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.

Specify finish for top cap as shown (included in high-low post assemblies).

## Application Notes

High-low connectors are used to join panels of two heights in a straight line. Assemblies come complete with connector track, hardware and trim as required.

Order dedicated high-low top caps separately for the lower panel in a straight high-low configuration.

All high-low pattern numbers contain a logical four digit code to accommodate the range of high-low connections in which 30," is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1. To specify a straight high-low connection between a 54" panel and a 42" panel:


1. Start with the highest panel, 56" = "5".
2. Proceed either clockwise or counter-clockwise; hold this digit with a "0".
3. Denote the next highest panel, 42" = "4".
4. Hold the next place with a "0".

The correct code is M2-5040.

# High-low connectors

*straight*  
*non-upholstered*

Morrison

description	type	w	d	h	pattern no.	Painted	V1	V2	V3	
	Straight high-low connectors	39" H	2 1/4"	–	39"	<b>M2-9030-(-)(-)</b>	\$116.	\$165.	\$171.	\$207.
	48" H	2 1/4"	–	48"	<b>M2-8030-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	48"	<b>M2-8040-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	48"	<b>M2-8090-(-)(-)</b>	116.	165.	171.	207.	
	56" H	2 1/4"	–	56"	<b>M2-5030-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	56"	<b>M2-5040-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	56"	<b>M2-5080-(-)(-)</b>	116.	165.	171.	207.	
	64" H	2 1/4"	–	64"	<b>M2-6030-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	64"	<b>M2-6040-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	64"	<b>M2-6050-(-)(-)</b>	116.	165.	171.	207.	
		2 1/4"	–	64"	<b>M2-6080-(-)(-)</b>	116.	165.	171.	207.	
	80" H	2 1/4"	–	80"	<b>M2-1060-(-)(-)</b>	159.	238.	247.	296.	
		2 1/4"	–	80"	<b>M2-1080-(-)(-)</b>	159.	238.	247.	296.	

## Order Code

Example: **M2-5040-613-V-T**

<b>M2</b>	Connector
<b>5040</b>	Configuration
<b>613</b>	Top cap finish
<b>V</b>	Surface type
<b>T</b>	Veneer

## Specification Information

First finish suffix is for top cap, second is surface type.

When ordering non-upholstered trims, surface type must match top cap type.

*Non-upholstered surface type:*

( ) Painted (finish code)  
V( ) Veneer (finish code)

For a high-low configuration with wood top caps, change pattern number prefix to M3. Painted high-low connectors are not available with wood top caps. For V3 finishes, add \$60 to the price listed above.

Specify finish for top cap as shown (included in high-low post assemblies).

## Application Notes

High-low connectors are used to join panels of two heights in a straight line. Assemblies come complete with connector track, hardware and trim as required.

Order dedicated high-low top caps separately for the lower panel in a straight high-low configuration.

All high-low pattern numbers contain a logical four digit code to accommodate the range of high-low connections in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1. To specify a straight high-low connection between a 54" panel and a 42" panel:

1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise; hold this digit with a "0".
3. Denote the next highest panel, 42"="4".
4. Hold the next place with a "0".


The correct code is M2-5040.

# High-low post assemblies

## 90° 2-way, “L” upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
 90° 2-way, “L” high-low assemblies	39" H	2 1/4"	2 1/4"	39"	<b>M2-9300-( )-( )-( )</b>	\$234.	\$243.	\$243.	\$243.	\$251.	\$251.	\$274.
	48" H	2 1/4"	2 1/4"	48"	<b>M2-8300-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
		2 1/4"	2 1/4"	48"	<b>M2-8400-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
		2 1/4"	2 1/4"	48"	<b>M2-8900-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
	56" H	2 1/4"	2 1/4"	56"	<b>M2-5300-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
		2 1/4"	2 1/4"	56"	<b>M2-5400-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
		2 1/4"	2 1/4"	56"	<b>M2-5800-( )-( )-( )</b>	234.	243.	243.	243.	251.	251.	274.
	64" H	2 1/4"	2 1/4"	64"	<b>M2-6300-( )-( )-( )</b>	243.	251.	251.	251.	256.	256.	282.
		2 1/4"	2 1/4"	64"	<b>M2-6400-( )-( )-( )</b>	243.	251.	251.	251.	256.	256.	282.
		2 1/4"	2 1/4"	64"	<b>M2-6500-( )-( )-( )</b>	243.	251.	251.	251.	256.	256.	282.
		2 1/4"	2 1/4"	64"	<b>M2-6800-( )-( )-( )</b>	243.	251.	251.	251.	256.	256.	282.
	80" H	2 1/4"	2 1/4"	80"	<b>M2-1600-( )-( )-( )</b>	314.	314.	314.	314.	358.	358.	398.
		2 1/4"	2 1/4"	80"	<b>M2-1800-( )-( )-( )</b>	314.	314.	314.	314.	358.	358.	398.

### Order Code

Example: **M2-5400-613-613-15-W210/20**

<b>M2</b>	Connector
<b>5400</b>	Configuration
<b>613</b>	Top cap finish
<b>613</b>	Raceway finish
<b>15</b>	Surface type and group no.
<b>W210/20</b>	Upholstery

### Specification Information

First suffix is for top cap finish, second is for raceway cover finish. Final suffix is for trim covers surface type. When ordering non-upholstered trims, surface type must match top cap type.

#### Surface type:

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.

Painted high-low connectors are not available with wood top caps. Specify finish for top cap and raceway covers, as shown (included in high-low post assemblies).

### Application Notes

High-low post assemblies are used to join panels of two heights in a corner configuration. Assemblies come complete with post, hardware, and trim as required.

Order dedicated high-low top caps separately for the lower panel in a corner high-low configuration.

All high-low pattern numbers contain a logical four digit code to accommodate the range of high-low connections in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1. To specify an L high-low connection between a 54" panel and a 42" panel:

1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise to the lower panel, 42"="4".
3. Hold the next two places with a "0".


The correct code is M2-5400.

# High-low post assemblies

## 90° 2-way, "L"

### non-upholstered

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
	39" H	2 1/4"	2 1/4"	39"	<b>M2-9300-</b> (-)(-)(-)	\$227.	\$282.	\$291.	\$349.
	48" H	2 1/4"	2 1/4"	48"	<b>M2-8300-</b> (-)(-)(-)	227.	282.	291.	349.
		2 1/4"	2 1/4"	48"	<b>M2-8400-</b> (-)(-)(-)	227.	282.	291.	349.
		2 1/4"	2 1/4"	48"	<b>M2-8900-</b> (-)(-)(-)	227.	282.	291.	349.
	56" H	2 1/4"	2 1/4"	56"	<b>M2-5300-</b> (-)(-)(-)	227.	282.	291.	349.
		2 1/4"	2 1/4"	56"	<b>M2-5400-</b> (-)(-)(-)	227.	282.	291.	349.
		2 1/4"	2 1/4"	56"	<b>M2-5800-</b> (-)(-)(-)	227.	282.	291.	349.
	64" H	2 1/4"	2 1/4"	64"	<b>M2-6300-</b> (-)(-)(-)	235.	291.	296.	357.
		2 1/4"	2 1/4"	64"	<b>M2-6400-</b> (-)(-)(-)	235.	291.	296.	357.
		2 1/4"	2 1/4"	64"	<b>M2-6500-</b> (-)(-)(-)	235.	291.	296.	357.
		2 1/4"	2 1/4"	64"	<b>M2-6800-</b> (-)(-)(-)	235.	291.	296.	357.
	80" H	2 1/4"	2 1/4"	80"	<b>M2-1600-</b> (-)(-)(-)	322.	398.	414.	496.
		2 1/4"	2 1/4"	80"	<b>M2-1800-</b> (-)(-)(-)	322.	398.	414.	496.

#### Order Code

Example:	<b>M2-5400-613-613-V-T</b>
<b>M2</b>	Connector
<b>5400</b>	Configuration
<b>613</b>	Top cap finish
<b>613</b>	Raceway finish
<b>V</b>	Surface type
<b>T</b>	Veneer

#### Specification Information

First suffix is for top cap finish, second is for raceway cover finish. Final suffix is for trim covers surface type. When ordering non-upholstered trims, surface type must match top cap type.

*Non-upholstered surface types:*

( ) Painted (finish code)  
V( ) Veneer (finish code)

For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.

Painted high-low connectors are not available with wood top caps.

Specify finish for top cap and raceway covers, as shown (included in high-low post assemblies).

#### Application Notes

High-low post assemblies are used to join panels of two heights in a corner configuration. Assemblies come complete with post, hardware, and trim as required.

Order dedicated high-low top caps separately for the lower panel in a corner high-low configuration.

All high-low pattern numbers contain a logical four digit code to accommodate the range of high-low connections in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1. To specify an L high-low connection between a 54" panel and a 42" panel:


1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise to the lower panel, 42"="4".
3. Hold the next two places with a "0".

The correct code is M2-5400.

# High-low post assemblies

## 90° 3-way, "T" upholstered

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
90° 3-way, "T" high-low assemblies (code 5404 shown)	39" H	2 1/4"	2 1/4"	39"	<b>M2-9303</b> (-)(-)(-)	\$300.	\$316.	\$316.	\$316.	\$332.	\$332.	\$356.
		2 1/4"	2 1/4"	39"	<b>M2-9330</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	39"	<b>M2-9390</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	39"	<b>M2-9930</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
	48" H	2 1/4"	2 1/4"	48"	<b>M2-8**0</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	48"	<b>M2-8*0*</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	48"	<b>M2-8*80</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	48"	<b>M2-88*0</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
	56" H	2 1/4"	2 1/4"	56"	<b>M2-5**0</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	56"	<b>M2-5*0*</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	56"	<b>M2-5*50</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
		2 1/4"	2 1/4"	56"	<b>M2-55*0</b> (-)(-)(-)	300.	316.	316.	316.	332.	332.	356.
64" H	2 1/4"	2 1/4"	64"	<b>M2-6**0</b> (-)(-)(-)	316.	332.	332.	332.	339.	339.	363.	
	2 1/4"	2 1/4"	64"	<b>M2-6*0*</b> (-)(-)(-)	316.	332.	332.	332.	339.	339.	363.	
	2 1/4"	2 1/4"	64"	<b>M2-6*60</b> (-)(-)(-)	316.	332.	332.	332.	339.	339.	363.	
	2 1/4"	2 1/4"	64"	<b>M2-66*0</b> (-)(-)(-)	316.	332.	332.	332.	339.	339.	363.	
80" H	2 1/4"	2 1/4"	80"	<b>M2-1**0</b> (-)(-)(-)	437.	444.	444.	444.	465.	465.	501.	
	2 1/4"	2 1/4"	80"	<b>M2-1*0*</b> (-)(-)(-)	437.	444.	444.	444.	465.	465.	501.	
	2 1/4"	2 1/4"	80"	<b>M2-1*10</b> (-)(-)(-)	437.	444.	444.	444.	465.	465.	501.	
	2 1/4"	2 1/4"	80"	<b>M2-11*0</b> (-)(-)(-)	437.	444.	444.	444.	465.	465.	501.	



Order Code	Specification Information
Example: <b>M2-5404-613-613-15-W210/20</b>	
<b>M2</b> Connector	
<b>5404</b> Configuration	
<b>613</b> Top cap finish	
<b>613</b> Raceway finish	
<b>15</b> Fabric group	
<b>W210/20</b> Upholstery	

All high-low pattern numbers contain a logical four digit code in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1.

*\*Indicate height of lower panels replace \* with one of the following:*

3	30"H
9	39"H
4	42"H
8	48"H
5	56"H
6	64"H
1	80"H

The following high-low connections are available as standard product:

<i>panel</i>	<i>connection to</i>
<i>ht.</i>	<i>ht.</i>
39"	30"
48"	42", 39", 30"
56"	48", 42", 30"
64"	56", 48", 42", 30"
80"	64", 48"

For all other connections, please contact your Custom Product Development representative.

First suffix is for top cap finish (integral color or P2), second is for raceway cover finish. Final suffix is for trim covers surface type. *Surface type:*

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

Fabrics Groups can be found on page 4.

*Specify finish for top cap and cover.*

For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.

**Application Notes**

High-low post assemblies are used to join panels of two heights in a T configuration. Assemblies come complete with post, hardware, and trim as required.

Order dedicated high-low top caps separately for the lower panels in a T-configuration.

To specify a 90° 3-way high-low connection of 42" panels with a 56" panel between:

1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise to the next highest panel, 42"="4".
3. Hold the next digit with a "0".
4. Continue in the same direction to the last panel, 42"="4".


The correct code is M2-5404.

# High-low post assemblies

## 90° 3-way, "T" non-upholstered

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
90° 3-way, "T" high-low assemblies (code 5404 shown)	39" H	2 1/4"	2 1/4"	39"	<b>M2-9303</b> -( )-( )	\$292.	\$364.	\$372.	\$446.
		2 1/4"	2 1/4"	39"	<b>M2-9330</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	39"	<b>M2-9390</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	39"	<b>M2-9930</b> -( )-( )	292.	364.	372.	446.
	48" H	2 1/4"	2 1/4"	48"	<b>M2-8**0</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	48"	<b>M2-8*0*</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	48"	<b>M2-8*80</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	48"	<b>M2-88*0</b> -( )-( )	292.	364.	372.	446.
	56" H	2 1/4"	2 1/4"	56"	<b>M2-5**0</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	56"	<b>M2-5*0*</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	56"	<b>M2-5*50</b> -( )-( )	292.	364.	372.	446.
		2 1/4"	2 1/4"	56"	<b>M2-55*0</b> -( )-( )	292.	364.	372.	446.
	64" H	2 1/4"	2 1/4"	64"	<b>M2-6**0</b> -( )-( )	307.	372.	378.	455.
		2 1/4"	2 1/4"	64"	<b>M2-6*0*</b> -( )-( )	307.	372.	378.	455.
		2 1/4"	2 1/4"	64"	<b>M2-6*60</b> -( )-( )	307.	372.	378.	455.
		2 1/4"	2 1/4"	64"	<b>M2-66*0</b> -( )-( )	307.	372.	378.	455.
80" H	2 1/4"	2 1/4"	80"	<b>M2-1**0</b> -( )-( )	439.	480.	524.	627.	
	2 1/4"	2 1/4"	80"	<b>M2-1*0*</b> -( )-( )	439.	480.	524.	627.	
	2 1/4"	2 1/4"	80"	<b>M2-1*10</b> -( )-( )	439.	480.	524.	627.	
	2 1/4"	2 1/4"	80"	<b>M2-11*0</b> -( )-( )	439.	480.	524.	627.	



Order Code	Specification Information	Application Notes
Example: <b>M2-5404-613-613-V-T</b>	All high-low pattern numbers contain a logical four digit code in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1.  *Indicate height of lower panels replace * with one of the following:	The following high-low connections are available as standard product:  <i>panel connection to ht.</i> 39" 30" 48" 42", 39", 30" 56" 48", 42", 30" 64" 56", 48", 42", 30" 80" 64", 48"
<b>M2</b> Connector		
<b>5404</b> Configuration	3 30"H 9 39"H 4 42"H 8 48"H 5 56"H 6 64"H 1 80"H	For all other connections, please contact your Custom Product Development representative. First suffix is for top cap finish, second is for raceway cover finish. Final suffix is for trim covers surface type. When ordering non-upholstered trims, surface type must match top cap type. <i>Surface type:</i> V( ) Veneer (finish code) ( ) Painted (finish code)
<b>613</b> Top cap finish		
<b>613</b> Raceway finish	High-low post assemblies are used to join panels of two heights in a T configuration. Assemblies come complete with post, hardware, and trim as required.  For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.  Painted high-low connectors are not available with wood top caps.  Order dedicated high-low top caps separately for the lower panels in a T-configuration.  To specify a 90° 3-way high-low connection of 42" panels with a 56" panel between:	
<b>V</b> Surface type		
<b>T</b> Veneer	1. Start with the highest panel, 56"="5". 2. Proceed either clockwise or counter-clockwise to the next highest panel, 42"="4". 3. Hold the next digit with a "0". 4. Continue in the same direction to the last panel, 42"="4".	
		The correct code is M2-5404.




# High-low post assemblies

## 90° 4-way, "X" upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
90° 4-way, "X" high-low assemblies (code 5454 shown)	39" H	2 1/4"	2 1/4"	39"	<b>M2-9333-(-)(-)</b>	\$347.	\$363.	\$363.	\$363.	\$370.	\$370.	\$393.
		2 1/4"	2 1/4"	39"	<b>M2-9393-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	39"	<b>M2-9933-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	39"	<b>M2-9993-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
48" H	48" H	2 1/4"	2 1/4"	48"	<b>M2-8***-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	48"	<b>M2-8*8*-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	48"	<b>M2-88**-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	48"	<b>M2-888*-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
56" H	56" H	2 1/4"	2 1/4"	56"	<b>M2-5***-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	56"	<b>M2-5*5*-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	56"	<b>M2-55**-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
		2 1/4"	2 1/4"	56"	<b>M2-555*-(-)(-)</b>	347.	363.	363.	363.	370.	370.	393.
64" H	64" H	2 1/4"	2 1/4"	64"	<b>M2-6***-(-)(-)</b>	363.	370.	370.	370.	377.	377.	402.
		2 1/4"	2 1/4"	64"	<b>M2-6*6*-(-)(-)</b>	363.	370.	370.	370.	377.	377.	402.
		2 1/4"	2 1/4"	64"	<b>M2-66**-(-)(-)</b>	363.	370.	370.	370.	377.	377.	402.
		2 1/4"	2 1/4"	64"	<b>M2-666*-(-)(-)</b>	363.	370.	370.	370.	377.	377.	402.
80" H	80" H	2 1/4"	2 1/4"	80"	<b>M2-1***-(-)(-)</b>	492.	511.	511.	511.	531.	531.	560.
		2 1/4"	2 1/4"	80"	<b>M2-1*1*-(-)(-)</b>	492.	511.	511.	511.	531.	531.	560.
		2 1/4"	2 1/4"	80"	<b>M2-11**-(-)(-)</b>	492.	511.	511.	511.	531.	531.	560.
		2 1/4"	2 1/4"	80"	<b>M2-111*-(-)(-)</b>	492.	511.	511.	511.	531.	531.	560.



### Order Code

Example:	<b>M2-5444-613-15-W210/5</b>
<b>M2</b>	Connector
<b>5444</b>	Configuration
<b>613</b>	Top cap finish
<b>15</b>	Fabric group
<b>W210/5</b>	Upholstery

### Specification Information

All high-low pattern numbers contain a logical four digit code in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1.

\* Indicate height of lower panels replace \* with one of the following:

3	30"H
9	39"H
4	42"H
8	48"H
5	56"H
6	64"H
1	80"H

The following high-low connections are available as standard product:

<i>panel</i>	<i>connection to</i>
39"	30"
48"	42", 39", 30"
56"	48", 42", 30"
64"	56", 48", 42", 30"
80"	64", 48"

For all other connections, please contact your Custom Product Development representative. First suffix is for top cap finish, second is for raceway cover finish. Raceway covers will always be matched with the metallic finish corresponding to top cap finish. Final suffix is for trim covers surface type. When ordering non-upholstered trims, surface type must match top cap type.

#### Surface type:

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45

For a high-low configuration with wood top caps, change pattern number prefix to M3. For V3 finishes, add \$60 to the price listed above.

### Application Notes

High-low post assemblies are used to join panels of two heights in an X configuration. Assemblies come complete with post, hardware, and trim as required.

Order dedicated high-low top caps separately for the lower panel in an X configuration.

To specify a 90° 4-way high-low connection of a 56" panel and three 42" panels:


1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise to the next highest panel, 42"="4".
3. Continue in the same direction to the next panel, 42"="4".
4. Continue in the same direction to the last panel, 42"="4".

The correct code is M2-5444.

# High-low post assemblies

## 90° 4-way, "X" non-upholstered

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
90° 4-way, "X" high-low assemblies (code 5404 shown) 	39" H	2 1/4"	2 1/4"	39"	<b>M2-9333</b> -( )-( )	\$346.	\$398.	\$404.	\$486.
		2 1/4"	2 1/4"	39"	<b>M2-9393</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	39"	<b>M2-9933</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	39"	<b>M2-9993</b> -( )-( )	346.	398.	404.	486.
	48" H	2 1/4"	2 1/4"	48"	<b>M2-8***</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	48"	<b>M2-8*8*</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	48"	<b>M2-88**</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	48"	<b>M2-888*</b> -( )-( )	346.	398.	404.	486.
	56" H	2 1/4"	2 1/4"	56"	<b>M2-5***</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	56"	<b>M2-5*5*</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	56"	<b>M2-55**</b> -( )-( )	346.	398.	404.	486.
		2 1/4"	2 1/4"	56"	<b>M2-555*</b> -( )-( )	346.	398.	404.	486.
	64" H	2 1/4"	2 1/4"	64"	<b>M2-6***</b> -( )-( )	363.	404.	412.	493.
		2 1/4"	2 1/4"	64"	<b>M2-6*6*</b> -( )-( )	363.	404.	412.	493.
		2 1/4"	2 1/4"	64"	<b>M2-66**</b> -( )-( )	363.	404.	412.	493.
		2 1/4"	2 1/4"	64"	<b>M2-666*</b> -( )-( )	363.	404.	412.	493.
	80" H	2 1/4"	2 1/4"	80"	<b>M2-1***</b> -( )-( )	491.	563.	572.	687.
		2 1/4"	2 1/4"	80"	<b>M2-1*1*</b> -( )-( )	491.	563.	572.	687.
		2 1/4"	2 1/4"	80"	<b>M2-11**</b> -( )-( )	491.	563.	572.	687.
		2 1/4"	2 1/4"	80"	<b>M2-111*</b> -( )-( )	491.	563.	572.	687.

### Order Code

Example: **M2-5444-613-V-8**

<b>M2</b>	Connector
<b>5444</b>	Configuration
<b>613</b>	Top cap finish
<b>V</b>	Veneer
<b>8</b>	Finish

### Specification Information

All high-low pattern numbers contain a logical four digit code in which 30" is 3, 39" is 9, 42" is 4, 48" is 8, 56" is 5, 64" is 6, and 80" is 1.

\*Indicate height of lower panels replace \* with one of the following:

3	30"H
9	39"H
4	42"H
8	48"H
5	56"H
6	64"H
1	80"H

The following high-low connections are available as standard product:

<i>panel</i>	<i>connection to</i>
39"	30"
48"	42", 39", 30"
56"	48", 42", 30"
64"	48", 42", 30"
80"	64", 48"

For all other connections, please contact your Custom Product Development representative. First suffix is for top cap finish (integral color or P2), second is for raceway cover finish. Raceway covers will always be matched with the metallic finish corresponding to top cap finish. Final suffix is for trim covers surface type. When ordering non-upholstered trims, surface type must match top cap type (integral color or P2). *Surface type:*

( )	Painted (finish code)
V( )	Veneer (finish code)

### Application Notes

For a high-low configuration with wood top caps, change pattern number prefix to M3. Painted high-low connectors are not available with wood top caps. For V3 finishes, add \$60 to the price listed above.

High-low post assemblies are used to join panels of two heights in an X configuration. Assemblies come complete with post, hardware, and trim as required.

Order dedicated high-low top caps separately for the lower panel in an X configuration.

To specify a 90° 4-way high-low connection of a 56" panel and three 42" panels:


1. Start with the highest panel, 56"="5".
2. Proceed either clockwise or counter-clockwise to the next highest panel, 42"="4".
3. Continue in the same direction to the next panel, 42"="4".
4. Continue in the same direction to the last panel, 42"="4".

The correct code is M2-5444.

# Panel accessories

## *wall starters*

Morrison

description	type	w	d	h	pattern no.	Paint
 Wall starter		1"	2 1/4"	30"	<b>MM1-WS30( )</b>	\$153.
		1"	2 1/4"	39"	<b>MM1-WS39( )</b>	157.
		1"	2 1/4"	42"	<b>MM1-WS42( )</b>	158.
		1"	2 1/4"	48"	<b>MM1-WS48( )</b>	175.
		1"	2 1/4"	56"	<b>MM1-WS56( )</b>	190.
		1"	2 1/4"	64"	<b>MM1-WS64( )</b>	208.
		1"	2 1/4"	80"	<b>MM1-WS80( )</b>	235.

Panel Planning

### Order Code

Example:	<b>MM1-WS56-613</b>
<b>MM1</b>	Morrison accessory
<b>WS</b>	Wall starter
<b>56</b>	Height
<b>613</b>	Finish

### Specification Information

*Specify painted finishes for wall starter.*




### Application Notes

Wall starters connect a panel run perpendicular to a fixed wall. Wall starter includes connector track, wall mount bracket, and painted end top cap.

For wood top caps, order wood end trim top cap (MT5-CE1) separately.

# Panel accessories accessories

Morrison

description	type	w	d	h	pattern no.	list price
Panel stiffeners 	Corner	-	-	-	<b>MM1-PSL2</b>	\$37.
	Straight	-	-	-	<b>MM1-PSS1</b>	19.
Stabilizer foot 		2"	13"	14"	<b>MM1-SF( )</b>	226.
Carpet grips (10) 					<b>MM2-CG</b>	17.

## Order Code

Example: <b>MM1-PSS1</b>
<b>MM1</b> Morrison accessory
<b>PSS1</b> Panel stiffener

## Specification Information

Specify paint finish for stabilizer foot.

## Applicatin Notes

Panel stiffeners add rigidity to straight or corner connections, and should be used with glazed panels. Bracket is concealed under top caps.




Stabilizer foot attaches to connector track to stabilize panel runs.

Carpet grips snap onto panel glides to prevent panel runs from shifting on carpet. Glide rotates in carpet grip to permit leveling

# Trim covers for reconfiguration upholstered

Morrison

Panel Planning

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
90° 2-way, "L" 	Upholstery	2 1/4"	-	9"	<b>MT1-09L2-(-)</b>	\$48.	\$55.	\$55.	\$55.	\$66.	\$66.	\$73.
		2 1/4"	-	16"	<b>MT1-16L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	18"	<b>MT1-18L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	22"	<b>MT1-22L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	30"	<b>MT1-30L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	32"	<b>MT1-32L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	39"	<b>MT1-39L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	42"	<b>MT1-42L2-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	48"	<b>MT1-48L2-(-)</b>	52.	59.	59.	59.	70.	70.	78.
		2 1/4"	-	56"	<b>MT1-56L2-(-)</b>	55.	64.	64.	64.	73.	73.	82.
		2 1/4"	-	64"	<b>MT1-64L2-(-)</b>	64.	72.	72.	72.	82.	82.	89.
		2 1/4"	-	80"	<b>MT1-80L2-(-)</b>	76.	84.	84.	84.	93.	93.	100.
		90° 3-way, "T" 	Upholstery	2 1/4"	-	9"	<b>MT1-09T3-(-)</b>	33.	40.	40.	40.	49.
2 1/4"	-			16"	<b>MT1-16T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			18"	<b>MT1-18T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			22"	<b>MT1-22T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			30"	<b>MT1-30T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			32"	<b>MT1-32T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			39"	<b>MT1-39T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			42"	<b>MT1-42T3-(-)</b>	33.	40.	40.	40.	49.	49.	56.
2 1/4"	-			48"	<b>MT1-48T3-(-)</b>	37.	46.	46.	46.	52.	52.	61.
2 1/4"	-			56"	<b>MT1-56T3-(-)</b>	40.	48.	48.	48.	56.	56.	66.
2 1/4"	-			64"	<b>MT1-64T3-(-)</b>	48.	55.	55.	55.	66.	66.	73.
2 1/4"	-			80"	<b>MT1-80T3-(-)</b>	57.	67.	67.	67.	77.	77.	85.
End 	Upholstery			2 1/4"	-	9"	<b>MT1-09E1-(-)</b>	40.	48.	48.	48.	56.
		2 1/4"	-	16"	<b>MT1-16E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	18"	<b>MT1-18E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	22"	<b>MT1-22E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	30"	<b>MT1-30E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	32"	<b>MT1-32E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	39"	<b>MT1-39E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	42"	<b>MT1-42E1-(-)</b>	40.	48.	48.	48.	56.	56.	66.
		2 1/4"	-	48"	<b>MT1-48E1-(-)</b>	46.	52.	52.	52.	61.	61.	70.
		2 1/4"	-	56"	<b>MT1-56E1-(-)</b>	48.	55.	55.	55.	66.	66.	73.
		2 1/4"	-	64"	<b>MT1-64E1-(-)</b>	55.	64.	64.	64.	73.	73.	82.
		2 1/4"	-	80"	<b>MT1-80E1-(-)</b>	67.	76.	76.	76.	87.	87.	96.

### Order Code

Example:	<b>MT1-42L2-15-W210/2</b>
<b>MT1</b>	Trim cover
<b>42</b>	Height
<b>L2</b>	Assembly
<b>15</b>	Surface type
<b>W210/2</b>	Upholstery

### Specification Information

*Surface type:*

10-	Fabric group 10
15-	Fabric group 15
20-	Fabric group 20
30-	Fabric group 30
35-	Fabric group 35
40-	Fabric group 40
45-	Fabric group 45




### Application Notes

Order trim covers for replacement or reconfiguration only.

Trim covers are included in all connector kits.

# Trim covers for reconfiguration non-upholstered

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
90° 2-way, "L" 	Non-upholstered	2 1/4"	–	9"	<b>MT1-09L2-()</b>	\$42.	\$75.	\$83.	n/a
		2 1/4"	–	16"	<b>MT1-16L2-()</b>	42.	75.	83.	n/a
		2 1/4"	–	18"	<b>MT1-18L2-()</b>	42.	75.	83.	n/a
		2 1/4"	–	22"	<b>MT1-22L2-()</b>	42.	75.	83.	n/a
		2 1/4"	–	30"	<b>MT1-30L2-()</b>	42.	75.	83.	97.
		2 1/4"	–	32"	<b>MT1-32L2-()</b>	42.	75.	83.	n/a
		2 1/4"	–	39"	<b>MT1-39L2-()</b>	42.	75.	83.	97.
		2 1/4"	–	42"	<b>MT1-42L2-()</b>	42.	75.	83.	97.
		2 1/4"	–	48"	<b>MT1-48L2-()</b>	46.	79.	87.	107.
		2 1/4"	–	56"	<b>MT1-56L2-()</b>	50.	83.	90.	111.
		2 1/4"	–	64"	<b>MT1-64L2-()</b>	56.	90.	96.	117.
		2 1/4"	–	80"	<b>MT1-80L2-()</b>	66.	102.	111.	132.
90° 3-way, "T" 	Non-upholstered	2 1/4"	–	9"	<b>MT1-09T3-()</b>	29.	56.	67.	n/a
		2 1/4"	–	16"	<b>MT1-16T3-()</b>	29.	56.	67.	n/a
		2 1/4"	–	18"	<b>MT1-18T3-()</b>	29.	56.	67.	n/a
		2 1/4"	–	22"	<b>MT1-22T3-()</b>	29.	56.	67.	n/a
		2 1/4"	–	30"	<b>MT1-30T3-()</b>	29.	56.	67.	82.
		2 1/4"	–	32"	<b>MT1-32T3-()</b>	29.	56.	67.	n/a
		2 1/4"	–	39"	<b>MT1-39T3-()</b>	29.	56.	67.	82.
		2 1/4"	–	42"	<b>MT1-42T3-()</b>	29.	56.	67.	82.
		2 1/4"	–	48"	<b>MT1-48T3-()</b>	31.	63.	72.	85.
		2 1/4"	–	56"	<b>MT1-56T3-()</b>	36.	67.	75.	88.
		2 1/4"	–	64"	<b>MT1-64T3-()</b>	42.	75.	83.	97.
		2 1/4"	–	80"	<b>MT1-80T3-()</b>	52.	86.	94.	115.
End 	Non-upholstered	2 1/4"	–	9"	<b>MT1-09E1-()</b>	36.	67.	75.	n/a
		2 1/4"	–	16"	<b>MT1-16E1-()</b>	36.	67.	75.	n/a
		2 1/4"	–	18"	<b>MT1-18E1-()</b>	36.	67.	75.	n/a
		2 1/4"	–	22"	<b>MT1-22E1-()</b>	36.	67.	75.	n/a
		2 1/4"	–	30"	<b>MT1-30E1-()</b>	36.	67.	75.	88.
		2 1/4"	–	32"	<b>MT1-32E1-()</b>	36.	67.	75.	n/a
		2 1/4"	–	39"	<b>MT1-39E1-()</b>	36.	67.	75.	88.
		2 1/4"	–	42"	<b>MT1-42E1-()</b>	36.	67.	75.	88.
		2 1/4"	–	48"	<b>MT1-48E1-()</b>	39.	72.	79.	93.
		2 1/4"	–	56"	<b>MT1-56E1-()</b>	42.	75.	83.	97.
		2 1/4"	–	64"	<b>MT1-64E1-()</b>	50.	83.	90.	111.
		2 1/4"	–	80"	<b>MT1-80E1-()</b>	59.	94.	102.	121.

## Order Code

Example: <b>MT1-22E1-613</b>
<b>MT1</b> Trim cover
<b>22</b> Height
<b>E1</b> Configuration
<b>613</b> Finish

## Specification Information

Specify paint surface or veneer finish.

## Application Notes

Order trim covers for replacement or reconfiguration only. Trim covers are included in all connector kits.

Veneer Group 1 trim covers are quartered Techgrain®.


Veneer Group 2 trim covers are rift cut Techgrain®.


Veneer Group 3 trim covers are narrow heart, flat cut natural veneer.

# Morrison Access

## vertical raceway panels


### frame and face plates


description	type	w	d	h	pattern no.	no finish	paint
 Vertical raceway panel frame		6"	2 1/4"	42"	<b>MA1-V4206</b>	\$257.	
		6"	2 1/4"	48"	<b>MA1-V4806</b>	296.	
		6"	2 1/4"	56"	<b>MA1-V5606</b>	321.	
		6"	2 1/4"	64"	<b>MA1-V6406</b>	348.	
		6"	2 1/4"	80"	<b>MA1-V8006</b>	405.	

description	type	w	d	h	pattern no.	no finish	paint
 Face plates kit for vertical raceway	4 openings one side	6"	–	42"	<b>MA1-F4240( )</b>		n/c
		6"	–	48"	<b>MA1-F4840( )</b>		n/c
		6"	–	56"	<b>MA1-F5640( )</b>		n/c
		6"	–	64"	<b>MA1-F6440( )</b>		n/c
		6"	–	80"	<b>MA1-F8040( )</b>		n/c
	4 openings two sides (or 8 one side)	6"	–	42"	<b>MA1-F4244( )</b>		n/c
		6"	–	48"	<b>MA1-F4844( )</b>		n/c
		6"	–	56"	<b>MA1-F5644( )</b>		n/c
		6"	–	64"	<b>MA1-F6444( )</b>		n/c
		6"	–	80"	<b>MA1-F8044( )</b>		n/c
	8 openings two sides	6"	–	42"	<b>MA1-F4288( )</b>		n/c
		6"	–	48"	<b>MA1-F4888( )</b>		n/c
		6"	–	56"	<b>MA1-F5688( )</b>		n/c
		6"	–	64"	<b>MA1-F6488( )</b>		n/c
		6"	–	80"	<b>MA1-F8088( )</b>		n/c
	No openings	6"	–	42"	<b>MA1-F4200( )</b>		n/c
		6"	–	48"	<b>MA1-F4800( )</b>		n/c
		6"	–	56"	<b>MA1-F5600( )</b>		n/c
		6"	–	64"	<b>MA1-F6400( )</b>		n/c
		6"	–	80"	<b>MA1-F8000( )</b>		n/c

Order Code	Specification Information	Application Notes
Example: <b>MA1-V4206</b> <b>MA1</b> Morrison Access <b>V</b> Vertical raceway <b>42</b> Height <b>06</b> Width	<i>For face plates, specify surface paint finish. n/c = No charge.</i>	<p>Vertical raceway extends panel base raceway to top cap, providing desk-height access and continuity with Highway and top cap raceway.</p> <p>Vertical raceway plans as 6" wide panel, requiring standard connectors to join to adjacent vertical panels. Specify 6" top cap and raceway cover kit separately.</p> <p>Vertical raceway panel has two full 2" x 2" lay-in channels for power track, PDC connectors or lay-in cable management, and one center easy-access channel.</p>
		<p>Specify face plates kit with covers for all vertical raceway panels, with outlets one or both sides. Kit with four openings has two outlet openings just above worksurface and two outlets below the worksurface, in one channel. Other channel and all other covers have no outlet openings. Face plates kit with eight openings has four outlets above and four below, in two channels.</p> <p>All kits include covers for both sides of vertical raceway.</p> <p>Outlet openings accept PDC modules, blank filler plates, or power outlets (specify outlets and power components separately).</p>

Morrison Access  
vertical raceway panels  
fabric covers

description	w	d	h	pattern no.	10	15	20	30	35	40	45
Full fabric cover, no outlets (one side of panel only) 	6"	2 1/4"	42"	<b>MA1-F42F()</b>	\$122.	\$129.	\$132.	\$141.	\$147.	\$155.	\$160.
	6"	2 1/4"	48"	<b>MA1-F48F()</b>	134.	139.	143.	155.	160.	166.	170.
	6"	2 1/4"	56"	<b>MA1-F56F()</b>	144.	149.	154.	166.	171.	179.	186.
	6"	2 1/4"	64"	<b>MA1-F64F()</b>	155.	161.	164.	181.	188.	194.	201.
	6"	2 1/4"	80"	<b>MA1-F80F()</b>	174.	182.	189.	204.	211.	220.	230.

Fabric covers with center channel, no outlets (one side of panel only) 	6"	2 1/4"	14"	<b>MA1-F14C()</b>	149.	159.	161.	170.	181.	189.	196.
	6"	2 1/4"	22"	<b>MA1-F22C()</b>	166.	177.	182.	195.	202.	209.	218.
	6"	2 1/4"	32"	<b>MA1-F32C()</b>	189.	200.	203.	218.	227.	234.	242.
	6"	2 1/4"	38"	<b>MA1-F38C()</b>	195.	205.	209.	226.	234.	242.	249.
	6"	2 1/4"	42"	<b>MA1-F42C()</b>	205.	218.	221.	239.	247.	255.	265.
	6"	2 1/4"	48"	<b>MA1-F48C()</b>	220.	234.	240.	257.	265.	273.	284.
	6"	2 1/4"	56"	<b>MA1-F56C()</b>	240.	253.	258.	276.	286.	294.	303.
	6"	2 1/4"	64"	<b>MA1-F64C()</b>	257.	271.	277.	296.	303.	312.	321.
	6"	2 1/4"	80"	<b>MA1-F80C()</b>	291.	310.	315.	348.	348.	355.	364.

Order Code	Specification Information	Application Notes
Example: <b>MA1-F42-F10</b>	<i>Specify fabric grade for fabric covers:</i>	Full fabric cover replaces standard painted covers on one side of vertical raceway panel, with no outlet openings and no access to center channel.
<b>MA1</b> Morrison Access	10- Fabric group 10	
<b>F</b> Facecover	15- Fabric group 15	Fabric covers with center channel replace the standard painted covers above outlet openings, from 42"H to the top of the panel. Specify 14"H covers for 56"H panel, 22"H covers for 64"H panel, or 38"H covers for 80"H panel.
<b>42</b> Height	20- Fabric group 20	
<b>F</b> Full cover	25- Fabric group 25	
<b>10</b> Fabric group	30- Fabric group 30	
	35- Fabric group 35	
	40- Fabric group 40	
	45- Fabric group 45	




# Morrison Access

## ceiling infeed panels

Morrison

description	w	d	h	pattern no.	paint
Ceiling infeed panel	6"	2 1/4"	48"	<b>MA1-CI48( )</b>	\$321.
	6"	2 1/4"	60"	<b>MA1-CI60( )</b>	360.
	6"	2 1/4"	72"	<b>MA1-CI72( )</b>	398.



Panel Planning

### Order Code

Example:	<b>MA1-CI48-613</b>
<b>MA1</b>	Morrison Access
<b>CI</b>	Ceiling infeed
<b>48</b>	Height
<b>613</b>	Finish




### Specification Information

*Specify painted finish for ceiling infeed panel.*

### Application Notes

Ceiling infeed panel mounts between vertical raceway panel and ceiling, and may be trimmed on site.

Morrison Access  
*Highway*  
*horizontal channels*

description	type	w	d	h	pattern no.	black
	Panels	6"	2 1/4"	1"	<b>MA1-H6</b>	\$30.
		18"	2 1/4"	1"	<b>MA1-H18</b>	32.
		24"	2 1/4"	1"	<b>MA1-H24</b>	36.
		30"	2 1/4"	1"	<b>MA1-H30</b>	41.
		36"	2 1/4"	1"	<b>MA1-H36</b>	49.
		42"	2 1/4"	1"	<b>MA1-H42</b>	55.
		48"	2 1/4"	1"	<b>MA1-H48</b>	64.
		60"	2 1/4"	1"	<b>MA1-H60</b>	82.
	Highway for high/low panels	5"	2 1/4"	1"	<b>MA1-HHL6</b>	30.
		17"	2 1/4"	1"	<b>MA1-HHL18</b>	32.
		23"	2 1/4"	1"	<b>MA1-HHL24</b>	36.
		29"	2 1/4"	1"	<b>MA1-HHL30</b>	41.
		35"	2 1/4"	1"	<b>MA1-HHL36</b>	49.
		41"	2 1/4"	1"	<b>MA1-HHL42</b>	55.
		47"	2 1/4"	1"	<b>MA1-HHL48</b>	64.
		59"	2 1/4"	1"	<b>MA1-HHL60</b>	82.
	Corner connector				<b>MA1-CL</b>	7.
	End connector				<b>MA1-CE</b>	7.
	End post				<b>MA1-CP</b>	7.
	Straight post				<b>MA1-CS</b>	7.
	T connector				<b>MA1-CT</b>	7.
	X connector				<b>MA1-CX</b>	7.

**Order Code**

Example: <b>MA1-H42</b>	
<b>MA1</b>	Morrison Access
<b>H</b>	Highway
<b>42</b>	Width

**Specification Information**

Highway for panels is black anodized aluminum with black vinyl flaps. Highway connectors are black color-integral molded plastic.

Highway snaps onto top of vertical panel to provide accessible horizontal cable channel on each side of panel.

Highway may be planned on all same-height panels in a cluster or only on center spine panels.

Highway accepts standard top caps.

Highway capacity is approximately thirty-two Category 5 4-pair UTP cables (3/16" dia. or equivalent), or sixteen each side.


Highways for high-low panels are sized for the lower panel in straight high-low configurations.


**Application Notes**

When Highway is planned only on the center spine of a cluster specify straight post Highway connectors at T and X connections; specify Highway end post connector at corner or T at end of spine. Specify straight post or end post top caps separately (see page 0). for all L, T and X connections.

Highway connectors permit continuous lay-in cabling at all post connections. For full cable enclosure over L or T connections specify top cap raceway connectors (page 76).

Morrison Access  
*Highway*  
*vertical wire management*

description	type	w	d	h	pattern no.	black	paint
 Change of height highway	Straight	1"	2 1/4"	6"	<b>MA1-HCS6( )</b>		\$12.
		1"	2 1/4"	8"	<b>MA1-HCS8( )</b>		17.
		1"	2 1/4"	9"	<b>MA1-HCS9( )</b>		18.
		1"	2 1/4"	10"	<b>MA1-HCS10( )</b>		19.
		1"	2 1/4"	14"	<b>MA1-HCS14( )</b>		23.
		1"	2 1/4"	16"	<b>MA1-HCS16( )</b>		26.
		1"	2 1/4"	18"	<b>MA1-HCS18( )</b>		28.
		1"	2 1/4"	22"	<b>MA1-HCS22( )</b>		32.
		1"	2 1/4"	26"	<b>MA1-HCS26( )</b>		36.
1"	2 1/4"	32"	<b>MA1-HCS32( )</b>		45.		


description	type	w	d	h	pattern no.	black	paint
 Vertical wire manager	39"H panel	2"	3/8"	35"	<b>MA1-VWM39( )</b>	5.	7.
	42"H panel	2"	3/8"	38"	<b>MA1-VWM42( )</b>	6.	8.
	48"H panel	2"	3/8"	44"	<b>MA1-VWM48( )</b>	7.	9.
	56"H panel	2"	3/8"	52"	<b>MA1-VWM56( )</b>	8.	10.
	64"H panel	2"	3/8"	60"	<b>MA1-VWM64( )</b>	9.	11.
	80"H panel	2"	3/8"	76"	<b>MA1-VWM80( )</b>	11.	16.






Order Code	Specification Information	Application Notes
Example: <b>MA1-VWM42-612</b> <b>MA1</b> Morrison Access <b>V</b> Vertical raceway <b>WM</b> Wire manager <b>42</b> Height <b>612</b> Finish	Change of height Highway are painted finish.  Vertical wire managers are black (N) or painted finish:	Change of height Highway manages cables from one panel height to another in high-low straight configurations. Specify kit to match height difference in panels (e.g., MA1-HCS22 for change of height from 64" to 42").  Specify Highway for high/low panels (see page 74) for lower panel in straight high/low connection.  Vertical wire manager attaches to Highway rim anywhere along face of panel to control cables from Highway to worksurface, panel base raceway, or lower panels in corner T, or X configurations.  Vertical wire manager is dimensioned to fit in the 3/8" cable clearance behind the worksurface.

# Morrison Access

## top cap raceway

Morrison

description	type	w	d	h	pattern no.	black
	Panels	6"	2 1/4"	1"	<b>MA1-TC6</b>	\$30.
		18"	2 1/4"	1"	<b>MA1-TC18</b>	32.
		24"	2 1/4"	1"	<b>MA1-TC24</b>	36.
		30"	2 1/4"	1"	<b>MA1-TC30</b>	41.
		36"	2 1/4"	1"	<b>MA1-TC36</b>	49.
		42"	2 1/4"	1"	<b>MA1-TC42</b>	55.
		48"	2 1/4"	1"	<b>MA1-TC48</b>	64.
		60"	2 1/4"	1"	<b>MA1-TC60</b>	82.





Top cap raceway connectors			
    	Corner	<b>MA1-TCL</b>	7.
	End	<b>MA1-TCE</b>	7.
	End post	<b>MA1-TCP</b>	7.
	Straight post	<b>MA1-TCS</b>	7.
	T	<b>MA1-TCT</b>	7.

Order Code	Specification Information	Application Notes
Example: <b>MA1-TC42</b> <b>MA1</b> Morrison Access <b>TC</b> Top Cap Raceway <b>42</b> Width	<p>Top Cap Raceway for panels is black anodized aluminum. Connectors are black color-integral molded plastic.</p> <p>Top Cap Raceway snaps onto top of vertical panel to provide horizontal cable channel.</p> <p>Top Cap Raceway accepts standard panel top caps.</p> <p>With top caps removed, unobstructed, lay-in cable capacity is approximately thirty three 4-pair UTP cables (3/16" diameter). Cross-section area is 1 1/2 square inches.</p> <p>Top Cap Raceway connectors provide full cable enclosure above any panel connection. No connector is required above X posts. Top cap raceway connectors may also be used with Highway (see page 74) for full cable enclosure over L or T connections.</p>	<p>When Top Cap Raceway is planned only on the center spine of a cluster specify straight post top cap raceway connectors at T and X connections; specify end post connector at corner or T at end of spine. Specify straight post or end post top caps separately (see pages 0-79).</p> <p>Specify Vertical Raceway (see page 75) to distribute cables from top cap raceway to worksurface height or panel base raceway. Cables also may pass from Top Cap Raceway to panel base raceway in L, T, or X connector post (six 25-pair cables).</p> <p>Top Cap Raceway does not accept power components.</p>

# Currents trim for Morrison trim covers for reconfiguration

Morrison

Panel Planning

description	type	w	d	h	pattern no.	list price
Top trim 		6"	2"	–	<b>AA1 T06</b>	\$8.
		18"	2"	–	<b>AA1 T18</b>	11.
		24"	2"	–	<b>AA1 T24</b>	13.
		30"	2"	–	<b>AA1 T30</b>	18.
		36"	2"	–	<b>AA1 T36</b>	20.
		42"	2"	–	<b>AA1 T42</b>	21.
		48"	2"	–	<b>AA1 T48</b>	23.
		60"	2"	–	<b>AA1 T60</b>	26.
	72"	2"	–	<b>AA1 T72</b>	29.	
Top caps for Morrison post assemblies (90° 4-way "X" shown) 	End post				<b>AA1 TMP1</b>	10.
	Straight post				<b>AA1 TMS2</b>	10.
	90° 2-way "L"				<b>AA1 TML2</b>	10.
	90° 3-way "I"				<b>AA1 TMT3</b>	10.
	90° 4-way "X"				<b>AA1 TMX4</b>	10.
End connector (with connector track) 		1"	2"	39"	<b>AC1-39E1</b>	56.
		1"	2"	48"	<b>AC1-48E1</b>	60.
		1"	2"	64"	<b>AC1-64E1</b>	67.
End trim (no connector) 	39" panel	–	2"	39"	<b>AA1 39E</b>	37.
	48" panel	–	2"	48"	<b>AA1 48E</b>	38.
	64" panel	–	2"	64"	<b>AA1 64E</b>	39.
Raceway cover for end trim on Morrison panel					<b>AA1 RE( )</b>	24.

## Order Code

Example: <b>AA1 T36</b>
<b>AA1 T</b> Top trim, panel
<b>36</b> Width

## Specification Information

End and top trims are trim grey integral finish.  
*Specify painted finish for raceway cover.*

## Application Notes

Currents-style trim covers found on this page may be retrofitted to new and existing Morrison panels.

When using Currents top trims, Currents for Morrison end correctors or end trims must also be used.

Top trim corresponds in width to Morrison panels.

Top cap for post assemblies can be retrofitted to Morrison post assemblies.

End connector includes top cap and connector track.




End trim may be specified instead of an end connector if cantilever capability is not required. End trim includes top cap.

Raceway cover encloses end of Morrison panel raceway under Currents end trim.

# Top cap and raceway cover kits

## *painted finish top caps*

Morrison

description	type	w	d	h	pattern no.	Paint
	Straight - no outlet plates	6"	–	4"	<b>MT5-N6-( ) ( )</b>	\$7.
		18"	–	4"	<b>MT5-N18-( ) ( )</b>	8.
		24"	–	4"	<b>MT5-N24-( ) ( )</b>	9.
		30"	–	4"	<b>MT5-N30-( ) ( )</b>	10.
		36"	–	4"	<b>MT5-N36-( ) ( )</b>	11.
		42"	–	4"	<b>MT5-N42-( ) ( )</b>	13.
		48"	–	4"	<b>MT5-N48-( ) ( )</b>	13.
		60"	–	4"	<b>MT5-N60-( ) ( )</b>	18.
	Straight - with outlet plates	24"	–	4"	<b>MT5-E24-( ) ( )</b>	9.
		30"	–	4"	<b>MT5-E30-( ) ( )</b>	10.
		36"	–	4"	<b>MT5-E36-( ) ( )</b>	11.
		42"	–	4"	<b>MT5-E42-( ) ( )</b>	13.
		48"	–	4"	<b>MT5-E48-( ) ( )</b>	13.
		60"	–	4"	<b>MT5-E60-( ) ( )</b>	18.
	Post assemblies	90° 2-way, "L"	–	–	<b>MT5-CL2-( ) ( )</b>	2.
		90° 3-way, "T"	–	–	<b>MT5-CT3-( ) ( )</b>	2.
		90° 4-way, "X"	–	–	<b>MT5-CX4-( )</b>	2.
		End	–	–	<b>MT5-CE1-( ) ( )</b>	2.
		End post (top cap only)	–	–	<b>MT5-CP1-( )</b>	2.
		Straight post (top cap only)	–	–	<b>MT5-CS2-( )</b>	2.
		Variable angle	–	–	<b>MT5-CH1-( ) ( )</b>	2.




Order Code	Specification Information	Application Notes
Example: <b>MT5-N36-612-612</b>	N- No outlet filler plates E- With outlet filler plates C- Post assembly	Top caps/raceway covers are specified as separate kits and bulk shipped to facilitate installation.
<b>MT5</b>	Top cap/raceway cover kit	High-low post assemblies come with connector top cap/raceway cover kits; they do not have to be specified separately.
<b>N</b>	Type	18" powered panels can transmit power but do not accept outlets.
<b>36</b>	Panel width	24"W panels accept only one receptacle each side. All powered panels over 24"W have two receptacles on each side (4 duplex outlets per panel).
<b>612</b>	Paint finish	Raceway covers with additional receptacle openings on panels over 42"W may be specified separately (in addition to top cap/covers kit).
<b>612</b>	Raceway finish	See Multiple outlet covers, page 81.

# Top cap and raceway cover kits

## wood top caps

Morrison



Panel Planning

description	type	w	d	h	pattern no.	PV1	PV2	PV3	
	Straight - no outlet plates	6"	–	4"	<b>MT5-N6-( ) ( )</b>	\$7.	\$7.	\$48.	
		18"	–	4"	<b>MT5-N18-( ) ( )</b>	8.	8.	130.	
		24"	–	4"	<b>MT5-N24-( ) ( )</b>	9.	9.	138.	
		30"	–	4"	<b>MT5-N30-( ) ( )</b>	10.	10.	144.	
		36"	–	4"	<b>MT5-N36-( ) ( )</b>	11.	11.	155.	
		42"	–	4"	<b>MT5-N42-( ) ( )</b>	13.	13.	164.	
		48"	–	4"	<b>MT5-N48-( ) ( )</b>	13.	13.	170.	
		60"	–	4"	<b>MT5-N60-( ) ( )</b>	18.	18.	189.	
	Straight - with outlet plates	24"	–	4"	<b>MT5-E24-( ) ( )</b>	9.	9.	138.	
		30"	–	4"	<b>MT5-E30-( ) ( )</b>	10.	10.	144.	
		36"	–	4"	<b>MT5-E36-( ) ( )</b>	11.	11.	155.	
		42"	–	4"	<b>MT5-E42-( ) ( )</b>	13.	13.	164.	
		48"	–	4"	<b>MT5-E48-( ) ( )</b>	13.	13.	170.	
		60"	–	4"	<b>MT5-E60-( ) ( )</b>	18.	18.	189.	
	Post assemblies	90°, 2-way, "L"	–	–	–	<b>MT5-CL2-( ) ( )</b>	2.	2.	92.
		90°, 3-way, "T"	–	–	–	<b>MT5-CT3-( ) ( )</b>	2.	2.	92.
		90°, 4-way, "X"	–	–	–	<b>MT5-CX4-( )</b>	2.	2.	92.
		End	–	–	–	<b>MT5-CE1-( ) ( )</b>	2.	2.	87.
		End post (top cap only)	–	–	–	<b>MT5-CP1-( )</b>	2.	2.	92.
		Straight post (top cap only)	–	–	–	<b>MT5-CS2-( )</b>	2.	2.	92.
		Variable angle	–	–	–	<b>MT5-CH1-( ) ( )</b>	2.	2.	130.

Order Code	Specification Information	Application Notes
Example: <b>MT5-N36-T-612</b>		
<b>MT5</b> Top cap/raceway cover kit	N- No outlet filler plates E- With outlet filler plates C- Post assembly	For Chicago code raceway covers with outlet plates, see page 102.
<b>N</b> Type	Specify top cap veneer suffix, then raceway cover finish suffix.	Top caps/raceway covers are specified as separate kits and bulk shipped to facilitate installation. High-low post assemblies come with connector top cap/raceway cover kits; order top caps for lower panels separately.
<b>36</b> Panel width		
<b>T</b> Top cap	PV1- Painted covers, V1 top cap PV2- Painted covers, V2 top cap PV3- Painted covers, V3 top cap	
<b>612</b> Raceway cover paint finish		18" powered panels can transmit power but do not accept outlets. 24"W powered panels accept one receptacle each side.

All powered panels over 24"W have two receptacles on each side (4 per panel).

Raceway covers with additional receptacle openings on panels over 42"W may be specified separately (in addition to top cap/covers kit). See multiple outlet covers, page 81.

description	w	d	h	pattern no.	Paint	V1	V2	V3
High-low dedicated width top cap - Straight 	17"	2 1/4"	1/4"	<b>MT5-HLS18(-)</b>	\$34.	\$34.	\$34.	\$171.
	23"	2 1/4"	1/4"	<b>MT5-HLS24(-)</b>	37.	37.	37.	180.
	29"	2 1/4"	1/4"	<b>MT5-HLS30(-)</b>	40.	40.	40.	189.
	35"	2 1/4"	1/4"	<b>MT5-HLS36(-)</b>	47.	47.	47.	199.
	41"	2 1/4"	1/4"	<b>MT5-HLS42(-)</b>	49.	49.	49.	205.
	47"	2 1/4"	1/4"	<b>MT5-HLS48(-)</b>	51.	51.	51.	211.
	59"	2 1/4"	1/4"	<b>MT5-HLS60(-)</b>	56.	56.	56.	228.
High-low dedicated width top cap - Post 	17 1/2"	2 1/4"	1/4"	<b>MT5-HLC18(-)</b>	34.	34.	34.	171.
	23 1/2"	2 1/4"	1/4"	<b>MT5-HLC24(-)</b>	37.	37.	37.	180.
	29 1/2"	2 1/4"	1/4"	<b>MT5-HLC30(-)</b>	40.	40.	40.	189.
	35 1/2"	2 1/4"	1/4"	<b>MT5-HLC36(-)</b>	47.	47.	47.	199.
	41 1/2"	2 1/4"	1/4"	<b>MT5-HLC42(-)</b>	49.	49.	49.	205.
	47 1/2"	2 1/4"	1/4"	<b>MT5-HLC48(-)</b>	51.	51.	51.	211.
	59 1/2"	2 1/4"	1/4"	<b>MT5-HLC60(-)</b>	56.	56.	56.	228.

**Order Code**

Example:	<b>MT5-HLC36-612</b>
<b>MT5</b>	Top cap kit
<b>HLC</b>	Type
<b>36</b>	Panel width
<b>612</b>	Paint finish

**Specification Information**

*Specify finish for top cap and raceway covers.*


**Application Notes**


For panels used in high-low configurations, order standard top cap/raceway cover kits on previous pages. Then order one dedicated width top cap for each of the lower panels in the high-low configuration. Install the standard raceway covers, but replace the standard top cap with the high-low top cap. Save the standard top cap for future reconfiguration.

High-low top caps for straight configurations are used only with high-low straight connectors. High-low top caps for post configurations are used with all corner, T, or X high-low post assemblies.

Top caps are painted, Techgrain® or natural veneer.



description	type	w	d	h	pattern no.	price
Power, data, and communications (PDC) outlets 		24"	–	4"	<b>MT5-PDC-24-( )</b>	\$25.
		30"	–	4"	<b>MT5-PDC-30-( )</b>	28.
		36"	–	4"	<b>MT5-PDC-36-( )</b>	30.
		42"	–	4"	<b>MT5-PDC-42-( )</b>	32.
		48"	–	4"	<b>MT5-PDC-48-( )</b>	34.
		60"	–	4"	<b>MT5-PDC-60-( )</b>	39.

Multiple power outlets 	Four outlets	48"	–	4"	<b>MT5-EX48-( )</b>	34.
	Four outlets	60"	–	4"	<b>MT5-EX60-( )</b>	39.

Order Code	Specification Information
Example: <b>MT5-PDC-48612</b>	
<b>M</b> Morrison	
<b>T5</b> Top cap	
<b>PDC</b> PDC raceway	
<b>48</b> Width	
<b>612</b> Finish	

**Specification Information**

Specify paint finish.

**Application Notes**

Specify PDC covers when planning voice/data outlets in a powered panel. PDC covers provide one protected opening for PDC modules 6" from each end of panel, in addition to standard power outlet openings.

Specify multiple power outlet covers in addition to standard panel top cap/raceway cover kits, when planning more than two duplex outlets on a panel face.



Multiple outlet covers have openings for four duplex outlets.

Power, data and communications outlets covers cannot be used with Morrison panels produced prior to 1995; specify standard powered or multiple outlet covers and plan data/communications outlets in pass-through or non-powered panels.

For Chicago code PDC covers, refer to page 102.

# Stackable add-up panels upholstered

Morrison



description	h	w	d	pattern no.	10	15	20	30	35	40	45
First up panel on Morrison panels 	16"	18"	2"	<b>AY1-1618M-A()</b>	\$383.	\$417.	\$424.	\$468.	\$487.	\$519.	\$550.
		24"	2"	<b>AY1-1624M-A()</b>	404.	439.	447.	492.	514.	549.	580.
		30"	2"	<b>AY1-1630M-A()</b>	439.	478.	488.	540.	563.	603.	638.
		36"	2"	<b>AY1-1636M-A()</b>	471.	515.	525.	582.	611.	655.	695.
		42"	2"	<b>AY1-1642M-A()</b>	518.	567.	580.	646.	677.	723.	773.
		48"	2"	<b>AY1-1648M-A()</b>	552.	606.	621.	689.	721.	775.	826.
	25"	18"	2"	<b>AY1-2518M-A()</b>	420.	457.	467.	515.	539.	575.	608.
		24"	2"	<b>AY1-2524M-A()</b>	443.	483.	494.	545.	569.	607.	644.
		30"	2"	<b>AY1-2530M-A()</b>	483.	527.	540.	598.	626.	668.	712.
		36"	2"	<b>AY1-2536M-A()</b>	520.	571.	582.	647.	679.	726.	775.
		42"	2"	<b>AY1-2542M-A()</b>	574.	630.	644.	719.	753.	812.	865.
		48"	2"	<b>AY1-2548M-A()</b>	612.	672.	691.	771.	806.	867.	925.
		60"	2"	<b>AY1-2560M-A()</b>	687.	757.	777.	870.	913.	983.	1,052.
		Next up panel on stackable add-up panels 	16"	18"	2"	<b>AY1-1618S-A()</b>	383.	417.	424.	468.	487.
24"	2"			<b>AY1-1624S-A()</b>	404.	439.	447.	492.	514.	549.	580.
30"	2"			<b>AY1-1630S-A()</b>	439.	478.	488.	540.	563.	603.	638.
36"	2"			<b>AY1-1636S-A()</b>	471.	515.	525.	582.	611.	655.	695.
42"	2"			<b>AY1-1642S-A()</b>	518.	567.	580.	646.	677.	723.	773.
48"	2"			<b>AY1-1648S-A()</b>	552.	606.	621.	689.	721.	775.	826.
60"	2"		<b>AY1-1660S-A()</b>	618.	680.	697.	776.	816.	877.	936.	

Order Code	Specification Information	Application Notes
Example: <b>AY1-1618M-A-15-W210/2</b> <hr/> <b>AY1</b> Stackable panel <hr/> <b>16</b> Height <hr/> <b>18</b> Width <hr/> <b>M</b> Mounting kit <hr/> <b>A</b> Surface type <hr/> <b>15</b> Fabric group <hr/> <b>W210/2</b> Upholstery	<p><i>First suffix indicates application:</i></p> <p>M Morrison panels S Stackable add-up panels</p> <p><i>Surface type:</i></p> <p>A Tackable upholstered</p> <p><i>Specify fabric group:</i></p> <p>10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45</p> <p>Fabric groups can be found on page 4.</p> <p>Upholstered panels may be ordered in a combination of fabrics. List price is the average of the two fabric grades.</p>	<p>For combinations of fabrics, list both suffixes (e.g. 20/40) and upholstery pattern numbers.</p> <p>Specify trim caps and connectors separately (see page 85).</p> <p>Stackable add-up panels provide adaptable privacy on Morrison panels.</p> <p>First up panels include top trim, edge trim in Currents trim grey and bayonet supports that bolt on to top of a Morrison panel.</p> <p>Next up panels include intermediate masts that engage into the sides of first up (or next up) panels of corresponding width. All stackable add-up panels may be removed without tools.</p> <p>Currents for Morrison end connector or end trim (page 77) must be specified when stacking over a Morrison panel in end condition.</p> <p>Top and edge trims are Currents trim grey.</p>

# Stackable add-up panels *glazed*

Morrison

Panel Planning



description	h	w	d	pattern no.	C/S	T
First up panel on Morrison panels 	16"	18"	2"	AY1-1618M-W( ) ( )	\$472.	\$513.
		24"	2"	AY1-1624M-W( ) ( )	513.	557.
		30"	2"	AY1-1630M-W( ) ( )	555.	606.
		36"	2"	AY1-1636M-W( ) ( )	599.	655.
		42"	2"	AY1-1642M-W( ) ( )	638.	698.
		48"	2"	AY1-1648M-W( ) ( )	681.	746.
		60"	2"	AY1-1660M-W( ) ( )	740.	806.
	25"	18"	2"	AY1-2518M-W( ) ( )	601.	657.
		24"	2"	AY1-2524M-W( ) ( )	657.	718.
		30"	2"	AY1-2530M-W( ) ( )	714.	783.
		36"	2"	AY1-2536M-W( ) ( )	772.	850.
		42"	2"	AY1-2542M-W( ) ( )	829.	912.
		48"	2"	AY1-2548M-W( ) ( )	889.	978.
		60"	2"	AY1-2560M-W( ) ( )	946.	1,039.
Next up panel on stackable add-up panels 	16"	18"	2"	AY1-1618S-W( ) ( )	472.	513.
		24"	2"	AY1-1624S-W( ) ( )	513.	557.
		30"	2"	AY1-1630S-W( ) ( )	555.	606.
		36"	2"	AY1-1636S-W( ) ( )	599.	655.
		42"	2"	AY1-1642S-W( ) ( )	638.	698.
		48"	2"	AY1-1648S-W( ) ( )	681.	746.
		60"	2"	AY1-1660S-W( ) ( )	740.	806.

Order Code	Specification Information	Application Notes
Example: <b>AY1-1636M-W-C-612</b> <b>AY1</b> Stackable add-up <b>16</b> Height <b>36</b> Width <b>M</b> Mounting kit <b>W</b> Surface type <b>C</b> Glazing finish <b>612</b> Frame finish	<p><i>First suffix indicates application:</i></p> <p>M Morrison panels S Stackable add-up panels</p> <p><i>Second suffix indicates surface type:</i></p> <p>W Glazed</p> <p><i>For glazed panels specify:</i></p> <p>C- Clear tempered glass S- Smoked acrylic T- Translucent acrylic</p> <p>Specify trim caps and connectors separately (see page 85).</p>	<p>Stackable add-up panels provide adaptable privacy on Morrison panels.</p> <p>First up panels include top trim, edge trim in Currents trim grey and bayonet supports that bolt on to top of a Morrison panel.</p> <p>Next up panels include intermediate masts that engage into the sides of first up (or next up) panels of corresponding width. All stackable add-up panels may be removed without tools.</p> <p>Currents for Morrison end connector or end trim (page 77) must be specified when stacking over a Morrison panel in end condition.</p> <p>Top and edge trim are Currents trim grey.</p>

# Stackable add-up panels

*translucent, perforated and marker surface on both sides*

Morrison

description	h	w	d	pattern no.	TC	H	M	
First up panel on Morrison panels 	16"	24"	2"	<b>AY1-1624M-( )</b>	\$779.	\$1,099.	\$549.	
		30"	2"	<b>AY1-1630M-( )</b>	n/a	n/a	590.	
		36"	2"	<b>AY1-1636M-( )</b>	944.	1,398.	639.	
		42"	2"	<b>AY1-1642M-( )</b>	n/a	n/a	692.	
		48"	2"	<b>AY1-1648M-( )</b>	1,131.	1,748.	760.	
		60"	2"	<b>AY1-1660M-( )</b>	1,307.	2,067.	n/a	
	25"	24"	2"	<b>AY1-2524M-( )</b>	813.	1,165.	611.	
		30"	2"	<b>AY1-2530M-( )</b>	n/a	n/a	663.	
		36"	2"	<b>AY1-2536M-( )</b>	982.	1,489.	716.	
		42"	2"	<b>AY1-2542M-( )</b>	n/a	n/a	785.	
		48"	2"	<b>AY1-2548M-( )</b>	1,183.	1,866.	855.	
		60"	2"	<b>AY1-2560M-( )</b>	1,373.	2,209.	n/a	
	Next up panel on stackable add-up panels 	16"	24"	2"	<b>AY1-1624S-( )</b>	779.	1,099.	549.
			30"	2"	<b>AY1-1630S-( )</b>	n/a	n/a	590.
36"			2"	<b>AY1-1636S-( )</b>	944.	1,398.	639.	
42"			2"	<b>AY1-1642S-( )</b>	n/a	n/a	692.	
48"			2"	<b>AY1-1648S-( )</b>	1,131.	1,748.	760.	
60"			2"	<b>AY1-1660S-( )</b>	1,307.	2,067.	n/a	

## Order Code

Example:	<b>AY1-1636-M-TC</b>
<b>AY1</b>	Stackable add-up
<b>16</b>	Height
<b>36</b>	Width
<b>M</b>	Mounting kit
<b>TC</b>	Surface type

## Specification Information

*First suffix indicates application:*  
M Morrison panels  
S Stackable add-up panels

*Second suffix indicates surface type:*  
TC Translucent fibreglass  
H Perforated (light grey only)  
M Marker surface (both sides)

Specify trim caps and connectors separately (see page 85).

## Application Notes

Stackable add-up panels provide adaptable privacy on Morrison panels.

Top and edge trim are Currents trim grey.  
Markerboard surface is non-metallic.

First up panels include top trim, edge trim in Currents trim grey and bayonet supports that bolt on to top of a Morrison panel.






Next up panels include intermediate masts that engage into the sides of first up (or next up) panels of corresponding width. All stackable add-up panels may be removed without tools.

Currents for Morrison end connector or end trim (page 77) must be specified when stacking over a Morrison panel in end condition.

# Stackable add-up connectors and trim caps

## *Morrison applications - first up*

Morrison

description	type	w	d	h	pattern no.	list price
Trim caps 	End cap				<b>AY1-CE</b>	\$5.
	Straight cap	2"	2"	–	<b>AY1 CS</b>	5.
Stackable first up connectors over Morrison panels - Corner 		2"	2"	16"	<b>AY1 ML16-()</b>	224.
		2"	2"	25"	<b>AY1 ML25-()</b>	259.
		2"	2"	32"	<b>AY1 ML32-()</b>	283.
Stackable first up connectors over Morrison panels - T 		2"	2"	16"	<b>AY1 MT16-()</b>	271.
		2"	2"	25"	<b>AY1 MT25-()</b>	331.
		2"	2"	32"	<b>AY1 MT32-()</b>	344.
Stackable first up connectors over Morrison panels - X 		2"	2"	16"	<b>AY1 MX16</b>	319.
		2"	2"	25"	<b>AY1 MX25</b>	404.
		2"	2"	32"	<b>AY1 MX32</b>	410.
Stackable first up connectors over Morrison panels - Straight post 		2"	2"	16"	<b>AY1 MP16-()</b>	224.
		2"	2"	25"	<b>AY1 MP25-()</b>	259.
		2"	2"	32"	<b>AY1 MP32-()</b>	283.


Order Code	Specification Information	Application Notes
Example: <b>AY1 CS</b>	Trim caps are Currents trim grey.	Trim caps are specified by application to fill top corners of stackable add-up panels. Straight cap aligns adjacent add-up panels. End cap finishes the end of the run of add-up panels.
<b>AY1</b> Stackable add-up	Top caps for Stackable connectors over Morrison panels are Currents trim grey.	Stackable connectors join stackable add-up panels over a Morrison connector.
<b>CS</b> Connector type	Specify paint finish for Stackable connector vertical trims.	

# Stackable add-up connectors and trim caps

## *Morrison applications - first up*

Morrison

description	type	w	d	h	pattern no.	list price
Masts for Morrison panel (replacement part)					<b>AY1-MMK</b>	\$49.



### Order Code

Example: **AY1 CS**  
**AY1** Stackable add-up  
**CS** Connector type

### Specification Information

Trim caps are Currents trim grey.  
 Top caps for Stackable connectors over Morrison panels are Currents trim grey.  
 Specify paint finish for Stackable connector vertical trims.

### Application Notes



Trim caps are specified by application to fill top corners of stackable add-up panels. Straight cap aligns adjacent add-up panels. End cap finishes the end of the run of add-up panels.  
 Stackable connectors join stackable add-up panels over a Morrison connector.

# Stackable add-up connectors and trim caps

## *Morrison applications - next up*

Morrison

Panel Planning

description	type	w	d	h	pattern no.	list price
Trim caps 	End cap				<b>AY1-CE</b>	\$5.
	Straight cap	2"	2"	–	<b>AY1 CS</b>	5.
Stackable next up connectors 	Corner	2"	2"	16"	<b>AY1 SML16-( )</b>	199.
	Straight post	2"	2"	16"	<b>AY1 SMP16-( )</b>	199.
	T	2"	2"	16"	<b>AY1 SMT16-( )</b>	246.
	X	2"	2"	16"	<b>AY1 SMX16-( )</b>	294.
<i>(X shown)</i>						
High/low adapter kit					<b>AY1-HLA</b>	60.
<i>(X shown)</i>						
Stacking hardware kit (replacement part)					<b>AY1-SMK</b>	35.

### Order Code

Example: <b>AY1 CS</b>
<b>AY1</b> Stackable add-up
<b>CS</b> Connector type

### Specification Information




Trim caps are Currents trim grey.  
 Top caps for Stackable connectors over Morrison panels are Currents trim grey.  
 Specify paint finish for Stackable connector vertical trims.

### Application Notes

Trim caps are specified by application to fill top corners of stackable add-up panels. Straight cap aligns adjacent add-up panels. End cap finishes the end of the run of add-up panels.  
 Stackable connectors join stackable add-up panels over a Morrison connector.  
 Next up connectors correspond to next up panels.

High-low adapter kit includes an end cap and a bayonet with attachment holes to join stackable add-up panels in a straight high-low configuration. The kit also adapts a corner T or X post for high-low configurations.

Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for panels*  
*power rails*

description	type	w	d	h	pattern no.	list price
 Power rail for panel base	24" w	6"	2"	2"	<b>MR3-E24</b>	\$129.
	30" w	12"	2"	2"	<b>MR3-E30</b>	142.
	36" w	18"	2"	2"	<b>MR3-E36</b>	155.
	42" w	24"	2"	2"	<b>MR3-E42</b>	164.
	48" w	30"	2"	2"	<b>MR3-E48</b>	171.
	60" w	42"	2"	2"	<b>MR3-E60</b>	183.
 Multiple outlet power rails	48" w	30"	2"	2"	<b>MR3-E48-4</b>	245.
	60" w	42"	2"	2"	<b>MR3-E60-4</b>	258.
 Power rail for vertical raceway		2"	2"	30"	<b>MR3-EVR</b>	365.

**Order Code**

Example: <b>MR3-E-30</b>	
<b>MR3</b>	Morrison raceway
<b>E</b>	Eight wire 2 + 2
<b>30</b>	For 30" panel

**Specification Information**

Morrison 2 + 2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

**Application Notes**




Power rails are the primary power distribution component of the Morrison 2 + 2 Raceway. Each rail provides outlet mounting positions on both sides, and receptacles for two branching power connectors at each end. Center supports permit lay-in cabling from either side of the raceway, shielded from power conductors and outlets by grounded steel barriers.

Rail for 24" wide panel accepts one duplex outlet or power infeed centered on each side. Rails for 30" and wider panels accept two outlets (or one outlet and one infeed) each side, 12" from either end of the panel. Multiple outlet power rails accept up to four duplex outlets each side.

Power rail for vertical raceway accepts up to four duplex outlets each side, two above and two below standard worksurface height. Power rail for vertical raceway includes power connector from adjacent powered panel base.



Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for panels*  
*connectors and jumpers*

description	type	w	d	h	pattern no.	list price
Power connector 	Straight	18"	2"	2"	<b>MR3-EPC</b>	\$75.
	Post	21"	2"	2"	<b>MR3-EPCP</b>	75.
Jumper 	6" panel	24"	2"	2"	<b>MR3-EJ6</b>	83.
	6" + 6" panel	30"	2"	2"	<b>MR3-EJ12</b>	89.
	18" panel	36"	2"	2"	<b>MR3-EJ18</b>	94.
	24" panel	42"	2"	2"	<b>MR3-EJ24</b>	101.
	30" panel	48"	2"	2"	<b>MR3-EJ30</b>	107.
	36" panel	54"	2"	2"	<b>MR3-EJ36</b>	117.
	42" panel	60"	2"	2"	<b>MR3-EJ42</b>	123.
	48" panel	66"	2"	2"	<b>MR3-EJ48</b>	129.
	54" panel run	75"	2"	2"	<b>MR3-EJ54P</b>	136.
	60" panel	81"	2"	2"	<b>MR3-EJ60P</b>	142.
	66" panel run	87"	2"	2"	<b>MR3-EJ66P</b>	149.
	72" panel run	93"	2"	2"	<b>MR3-EJ72P</b>	155.
	78" panel run	99"	2"	2"	<b>MR3-EJ78P</b>	164.
	84" panel run	105"	2"	2"	<b>MR3-EJ84P</b>	171.
90" panel run	111"	2"	2"	<b>MR3-EJ90P</b>	177.	
96" panel run	117"	2"	2"	<b>MR3-EJ96P</b>	183.	
Extended jumper 	6" + post	27"	2"	2"	<b>MR3-EJ6P</b>	83.
	6" + post + 6" panel	33"	2"	2"	<b>MR3-EJ12P</b>	89.
	18" + post	39"	2"	2"	<b>MR3-EJ18P</b>	94.
	24" + post	45"	2"	2"	<b>MR3-EJ24P</b>	101.
	30" + post	51"	2"	2"	<b>MR3-EJ30P</b>	107.
	36" + post	57"	2"	2"	<b>MR3-EJ36P</b>	117.
	42" + post	63"	2"	2"	<b>MR3-EJ42P</b>	123.
	48" + post	69"	2"	2"	<b>MR3-EJ48P</b>	129.

**Order Code**

Example: <b>MR3-EPC</b>	
<b>MR3</b>	Morrison raceway
<b>E</b>	Eight wire 2 + 2
<b>P</b>	Power infeed
<b>C</b>	Straight

**Specification Information**

Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

Power connectors are enclosed in steel flexible conduit.







**Application Notes**

Jumpers connect rails on either side of a panel or panels without outlets. Extended jumpers for panels less than 60" wide (suffix -P) transmit power through an adjacent L, T or X post connection. Jumpers for wider panel runs accommodate an intermediate post connection.

Also specify extended jumper when connecting between vertical raceway power rail and a panel base power rail on either side of a panel or panels without outlets.

Power connectors transmit power between adjacent powered panels. Specify straight power connector for straight connections, and post power connector for L, T or X post connections.

Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for panels*  
*outlets and infeeds*

description	type	pattern no.	list price
Duplex outlets, black 	Circuit A	<b>MR3-DA</b>	\$34.
	Circuit B	<b>MR3-DB</b>	34.
	Circuit X	<b>MR3-DX</b>	34.
	Circuit Y	<b>MR3-DY</b>	34.
Duplex outlets, orange 	Circuit X	<b>MR3-DXO</b>	39.
	Circuit Y	<b>MR3-DYO</b>	39.
Duplex outlets, black with orange triangle 	Circuit X	<b>MR3-DXT</b>	39.
	Circuit Y	<b>MR3-DYT</b>	39.
Power infeeds - Panel base 	panel base	<b>MR3-ERPI</b>	224.
Power infeeds - Ceiling 	external power pole	<b>MR3-EPIC</b>	258.
	vertical raceway	<b>MR3-EPVR</b>	224.
Power infeeds - hardwire 	NYC - one direction	<b>MR3-EPNY1</b>	189.
	NYC - two directions	<b>MR3-EPNY2</b>	284.

Order Code	Specification Information	Application Notes
Example: <b>MR3-EPVR</b>		
<b>MR3</b> Morrison raceway	Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.  Duplex outlets are preconfigured to access one of the four circuits, A, B, X, Y, and snap into any standard outlet location (12" from either end of panel). Duplexes on circuits X and Y may be specified with orange face or black face with orange triangle to signify protected circuits for electronic equipment.	Power infeeds connect building power supply to a cluster of interconnected power rails. Panel base infeed snaps into any outlet position in rail, 12" from either side of panel, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box.  Ceiling infeeds include 12'-6" pigtail for connection into panel base through Morrison vertical raceway and ceiling infeed panel, or through standard power pole (supplied by others) adjacent to Morrison panel with power rail.
<b>E</b> Eight wire 2 + 2		
<b>P</b> Power infeed		
<b>VR</b> For vertical raceway		
	Hardwire infeed, used in all New York City installations, includes junction box that mounts within non-powered panel base (any width 24" or greater). Electrical contractor supplies conduit from building power supply to panel, punches infeed hole in raceway cover, and trims power connectors to length. MR3-EPNY2 includes two power connectors to power panels on both sides of infeed panel; MR3-EPNY1 includes only one power connector. Template is included to modify standard N-type raceway cover (without outlet openings).	

Power distribution components  
*2+2™ Raceway*  
*four circuit, eight-wire raceway for panels*  
*surge suppressors*

description	type	pattern no.	list price
Surge suppressors	Circuit A	<b>MR3-SP-A</b>	\$164.
	Circuit B	<b>MR3-SP-B</b>	164.
	Circuit X	<b>MR3-SP-X</b>	164.
	Circuit Y	<b>MR3-SP-Y</b>	164.

**Order Code**

Example:	<b>MR3-SP-A</b>
<b>MR3</b>	Morrison raceway
<b>SP</b>	surge suppressor
<b>A</b>	circuit



**Specification Information**

Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

**Application Notes**

Surge suppressors snap into outlet position adjacent to power infeed to protect all outlets on a circuit.

Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for panels*  
*accessories*

description	type	pattern no.	list price
Desktop power module 	From panel base	<b>MR3-NESP</b>	\$325.
	Hardwire	<b>MR3-NESH</b>	258.
Grommet outlet module 	Directly above panel outlet	<b>MR3-EGM</b>	365.
	Duplex outlet, circuit A	<b>MR1-DA</b>	28.
	Duplex outlet, circuit B	<b>MR1-DB</b>	28.
	Hardwire	<b>MR3-EGMH</b>	271.
	Up to 24" away from panel outlet	<b>MR3-EGM48</b>	380.
Contact protectors (set of 10)		<b>MR3-CP</b>	11.
Wire manager clips (10)	Under worksurface	<b>MR1-WC</b>	31.
High capacity wire managers (10)	Panel connector	<b>ML1-HCWM24</b>	189.

**Order Code**

Example:	<b>MR3-NESP</b>
<b>MR3</b>	Morrison raceway
<b>N</b>	Network
<b>E</b>	Eight wire 2 + 2
<b>S</b>	Stanchion outlet
<b>P</b>	Power feed

**Specification Information**

Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

Duplex outlet circuits are designated by white letters on black background.

**Application Notes**

Desktop power module is power component for desktop power monument or overhead support stanchion. Power module includes two duplex outlets and power connector.






Grommet outlet module stands in any Morrison (not Options) worksurface grommet for convenient access. Grommet outlet module accepts only special duplexes (MR1-DA or MR1-DB) on circuits A or B.

Contact protectors enclose open conductors on power rail wherever outlets or power connectors are not planned.

Wire manager clips are included with Morrison worksurfaces with grommets.

High capacity wire manager fastens at any panel connection. Hinged flap contains 1" x 3" data/communications cables.

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for panels*  
*power rails, connectors and outlets*

description	type	w	d	h	pattern no.	list price
 Power rail for panel base	24"w	6"	2"	2"	<b>MR3-T24</b>	\$149.
	30"w	12"	2"	2"	<b>MR3-T30</b>	162.
	36"w	18"	2"	2"	<b>MR3-T36</b>	175.
	42"w	24"	2"	2"	<b>MR3-T42</b>	189.
	48"w	30"	2"	2"	<b>MR3-T48</b>	196.
	60"w	42"	2"	2"	<b>MR3-T60</b>	210.
 Multiple outlet power rail	48"w	30"	2"	2"	<b>MR3-T48-4</b>	290.
	60"w	42"	2"	2"	<b>MR3-T60-4</b>	305.
Power rail for vertical raceway		2"	2"	30"	<b>MR3-TRV</b>	433.
 Power connector	Straight	18"	2"	2"	<b>MR3-TPC</b>	94.
	Through post	21"	2"	2"	<b>MR3-TPCP</b>	94.
 Duplex outlets, black	Circuit A				<b>MR3-DA</b>	34.
	Circuit B				<b>MR3-DB</b>	34.
	Circuit C				<b>MR3-DC</b>	34.
	Circuit X				<b>MR3-DX</b>	34.
	Circuit Y				<b>MR3-DY</b>	34.
	Circuit Z				<b>MR3-DZ</b>	34.
 Duplex outlets, orange	Circuit X				<b>MR3-DXO</b>	39.
	Circuit Y				<b>MR3-DYO</b>	39.
	Circuit Z				<b>MR3-DZO</b>	39.

**Order Code**

Example: <b>MR3-T-30</b>	
<b>MR3</b>	Morrison raceway
<b>T</b>	Ten wire 3 + 3
<b>30</b>	For 30" panel

**Specification Information**

Morrison 3 + 3™ Raceway is a six-circuit, ten-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.

A, B, X, Y outlets are identical to eight wire, 2+2 components.

Duplex outlet circuits are designated by white letters on black background.

**Application Notes**


Power rails are the primary power distribution component of the Morrison 3 + 3 Raceway. Each rail provides outlet mounting positions on both sides, and receptacles for branching power connectors at each end. Center supports permit lay-in cabling from either side of the raceway, shielded from power conductors and outlets by grounded steel septums. Rail for 24" wide panel accepts one duplex outlet or power infeed on either side. Rails for 30" and wider panels accept two outlets each side, 12" from either end of the panel. Power rail for Vertical Raceway panel accepts up to four duplex outlets each side, two above and two below standard worksurface height.

Power connectors transmit power between adjacent powered panels. Specify straight power connector for straight connections, and post power connector for L, T or X post connections.

Duplex outlets are preconfigured to access one of the six circuits, A, B, C, X, Y, Z, and snap into any standard outlet location (12" from either end of panel). Duplexes on circuits X, Y, and Z may be specified with an orange face, or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.

Surge suppressors snap into outlet position adjacent to power infeed to protect all outlets on a circuit.

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for panels*  
*power rails, connectors and outlets*

description	type	w	d	h	pattern no.	list price
Duplex outlets, black with orange triangle 	Circuit X				<b>MR3-DXT</b>	\$39.
	Circuit Y				<b>MR3-DYT</b>	39.
	Circuit Z				<b>MR3-DZT</b>	39.
<hr/>						
Surge suppressors	Circuit A				<b>MR3-SP-A</b>	164.
	Circuit B				<b>MR3-SP-B</b>	164.
	Circuit C				<b>MR3-SP-C</b>	164.
	Circuit X				<b>MR3-SP-X</b>	164.
	Circuit Y				<b>MR3-SP-Y</b>	164.
	Circuit Z				<b>MR3-SP-Z</b>	164.

**Order Code**

Example: <b>MR3-T-30</b>
<b>MR3</b> Morrison raceway
<b>T</b> Ten wire 3 + 3
<b>30</b> For 30" panel

**Specification Information**

Morrison 3 + 3™ Raceway is a six-circuit, ten-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.

A, B, X, Y outlets are identical to eight wire, 2+2 components.

Duplex outlet circuits are designated by white letters on black background.

**Application Notes**

Power rails are the primary power distribution component of the Morrison 3 + 3 Raceway. Each rail provides outlet mounting positions on both sides, and receptacles for branching power connectors at each end. Center supports permit lay-in cabling from either side of the raceway, shielded from power conductors and outlets by grounded steel septums. Rail for 24" wide panel accepts one duplex outlet or power infeed on either side. Rails for 30" and wider panels accept two outlets each side, 12" from either end of the panel. Power rail for Vertical Raceway panel accepts up to four duplex outlets each side, two above and two below standard worksurface height.

Power connectors transmit power between adjacent powered panels. Specify straight power connector for straight connections, and post power connector for L, T or X post connections.

Duplex outlets are preconfigured to access one of the six circuits, A, B, C, X, Y, Z, and snap into any standard outlet location (12" from either end of panel). Duplexes on circuits X, Y, and Z may be specified with an orange face, or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.




Surge suppressors snap into outlet position adjacent to power infeed to protect all outlets on a circuit.

# Power distribution components

## 3+3™ Raceway

six circuit, ten-wire raceway for panels  
power infeeds

description	type	w	d	h	pattern no.	list price
Power infeeds - Panel base	Panel base				<b>MR3-TRPI</b>	\$258.
Ceiling infeed	external power pole				<b>MR3-TPIC</b>	313.
	vertical raceway				<b>MR3-TPVR</b>	258.
Harwire infeed	NYC - one direction				<b>MR3-TPNY1</b>	218.
	NYC - two directions				<b>MR3-TPNY2</b>	313.



Order Code	Specification Information	Application Notes
Example: <b>MR3-TPVR</b>		
<b>MR3</b> Morrison raceway	Morrison 3 +3™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.	Power infeeds connect building power supply to a cluster of interconnected power rails. Panel base infeed snaps into any outlet position in rail, 12" from either side of panel, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box. Ceiling infeeds include 12'-6" pigtail for connection into panel base through Morrison vertical raceway and ceiling infeed panel, or through standard power pole (supplied by others) adjacent to Morrison panel with power rail.
<b>T</b> Ten wire 3 + 3		
<b>P</b> Power infeed		
<b>VR</b> For vertical raceway		
		Hardwire infeed, used in all New York City installations, includes junction box that mounts within non-powered panel base (any width 24" or greater). Electrical contractor supplies conduit from building power supply to panel, punches infeed hole in raceway cover, and trims power connectors to length.  MR3-TPNY2 includes two power connectors to power panels on both sides of infeed panel; MR3-TPNY1 includes only one power connector. Template is included to modify standard N-type raceway cover (without outlet openings).

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for panels  
jumpers*

description	type	w	d	h	pattern no.	list price
Jumper	18" panel	36"	2"	2"	<b>MR3-TJ18</b>	\$107.
	24" panel	42"	2"	2"	<b>MR3-TJ24</b>	117.
	30" panel	48"	2"	2"	<b>MR3-TJ30</b>	123.
	36" panel	54"	2"	2"	<b>MR3-TJ36</b>	129.
	42" panel	60"	2"	2"	<b>MR3-TJ42</b>	142.
	48" panel	66"	2"	2"	<b>MR3-TJ48</b>	155.
	54" panel run	75"	2"	2"	<b>MR3-TJ54P</b>	164.
	6" + 6" panel	30"	2"	2"	<b>MR3-TJ12</b>	101.
	60" panel	81"	2"	2"	<b>MR3-TJ60P</b>	171.
	66" desk	87"	2"	2"	<b>MR3-TJ66P</b>	177.
	72" panel run	93"	2"	2"	<b>MR3-TJ72P</b>	183.
	78" desk	99"	2"	2"	<b>MR3-TJ78P</b>	189.
	84" panel run	105"	2"	2"	<b>MR3-TJ84P</b>	205.
	90" panel run	111"	2"	2"	<b>MR3-TJ90P</b>	211.
	96" panel run	117"	2"	2"	<b>MR3-TJ96P</b>	218.
Extended jumper	18" + post	39"	2"	2"	<b>MR3-TJ18P</b>	107.
	24" + post	45"	2"	2"	<b>MR3-TJ24P</b>	117.
	30" + post	51"	2"	2"	<b>MR3-TJ30P</b>	123.
	36" + post	57"	2"	2"	<b>MR3-TJ36P</b>	129.
	42" + post	63"	2"	2"	<b>MR3-TJ42P</b>	142.
	48" + post	69"	2"	2"	<b>MR3-TJ48P</b>	155.
	6" + post	27"	2"	2"	<b>MR3-TJ6P</b>	94.
	6" + post + 6" panel	33"	2"	2"	<b>MR3-TJ12P</b>	101.
Power connector	Crossover	24"	2"	2"	<b>MR3-TJ6</b>	94.

**Order Code**

Example: <b>MR3-TJ30</b>	
<b>MR3</b>	Morrison raceway
<b>T</b>	Ten wire 3 + 3
<b>J</b>	Jumper
<b>30</b>	Type

**Specification Information**

Morrison 3 + 3™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.

**Application Notes**

Jumpers connect rails on either side of a panel or panels without outlets. Extended jumpers for panels less than 60" wide (suffix -P) transmit power through an adjacent L, T or X post connection. Jumpers for wider panel runs accommodate an intermediate post connection.

Also specify extended jumper when connecting between vertical raceway power rail and a panel base power rail on either side of a panel or panels without outlets.



# Power distribution components

## *PDC Components*

Morrison

description	type	pattern no.	list price
PDC module extension kit	Set of 10	<b>MR3-PDC-X</b>	\$119.
PDC blank filler	Set of 10	<b>MN2-OF</b>	35.
Under worksurface PDC mounting bracket		<b>MR3-UW-PDC</b>	75.

Panel Planning

### Order Code

Example:	<b>MR3-UW-PDC</b>
<b>MR3</b>	Morrison raceway
<b>UW</b>	Position
<b>PDC</b>	Application

### Application Notes


PDC module extension kit is 1/2" spacer between module and raceway cover, providing more depth for cables and connections inside raceway.

PDC blank filler is black textured cover for unused outlet openings.

Under worksurface PDC bracket mounts anywhere under a worksurface to support two PDC modules with faceplate.

Power distribution components  
*PDC™ Raceway*  
*Terminator and outlets*

Morrison

description	type	w	d	h	pattern no.	list price
PDC terminator 		4"	2"	3"	<b>MA1-PDC-T</b>	\$44.
Terminator adapter for ATT outlets		4"	2"	3"	<b>MA1-TATT2</b>	25.
		4"	2"	3"	<b>MA1-TATT3</b>	25.

Order Code	Specification Information	Application Notes
Example: <b>MA1-PDC-T</b>	Terminator is textured black plastic.	Terminator is two-part molded plastic housing for data and communications outlets.  Terminator protects outlets and improves access to connections.  Terminator adheres to raceway over PDC outlet opening or subway.
<b>MA1</b> Morrison Access		
<b>PDC</b> Application		
<b>T</b> Terminator		
		Separate outlet components fit only the Terminator, which includes a faceplate with two outlet openings.  Other outlet combinations are available on special request.




# Power distribution components

## Ported panel

### data port, outlets, raceway connectors


Morrison

Panel Planning

description	type	pattern no.	list price
Floating data port kit		<b>MR3-FDP</b>	\$46.
Vertical power port bracket kit		<b>MR3-VPBK</b>	79.
			
Vertical duplex outlet Black	Circuit A	<b>MR3-VDA</b>	34.
	Circuit B	<b>MR3-VDB</b>	34.
	Circuit C	<b>MR3-VDC</b>	34.
	Circuit X	<b>MR3-VDX</b>	34.
	Circuit Y	<b>MR3-VDY</b>	34.
	Circuit Z	<b>MR3-VDZ</b>	34.
			
Vertical duplex outlet Orange	Circuit X	<b>MR3-VDXO</b>	39.
	Circuit Y	<b>MR3-VDYO</b>	39.
	Circuit Z	<b>MR3-VDZO</b>	39.
Vertical duplex outlet Black with Orange triangle	Circuit X	<b>MR3-VDXT</b>	39.
	Circuit Y	<b>MR3-VDYT</b>	39.
	Circuit Z	<b>MR3-VDZT</b>	39.
2 + 2 raceway connectors	Base of adjacent panel to far side of 18",24"W panel	<b>MR3-EV24 PC</b>	123.
	Base of adjacent panel to far side of 30",36"W panel	<b>MR3-EV36 PC</b>	136.
	Base of adjacent panel to far side of 42",48"W panel	<b>MR3-EV48 PC</b>	148.
	Base of same panel, adjacent panel to near side	<b>MR3-EVB PC</b>	112.
	Internal jumper to same circuit outlet	<b>MR3-EVI J</b>	123.
			

Order Code	Specification Information	Application Notes
Example: <b>MR3-VPBK</b>		
<b>MR3</b> Morrison	Ported panel electrical components connect to 2+2, four circuit and 3+3, six-circuit raceway components to deliver worksurface-height outlets within the ported panel frame.	Vertical power port bracket kit includes an outlet mounting bracket, a cover mounting bracket and cover plate. Outlet mounting bracket attaches to vertical rails of panel frame.
<b>VP</b> Application		
<b>BK</b> Bracket kit		
	Floating data port allows data and communication outlets to be mounted at any location on the ported panel face except directly above or below electrical outlets.	Vertical duplex outlets are dedicated for ported panel application and are preconfigured to access the circuit indicated by the letter on the outlet face. All outlets are black with white letters. Outlets for circuits X, Y and Z are available with orange face and black face with orange triangle to signify protected circuits for electronic equipment. Base raceway duplex outlets will not work in vertical port applications.
	Floating data ports include front and back mounting plates.	Vertical duplex outlets are one-sided only and must be ordered separately from the bracket kit.
	PDC modules ( faceplates and outlets ) are specified separately.	
	Vertical power and data ports for ported panel are black finish and require field cutting the panel insert for installation.	
		Ported panel connectors power vertical duplex outlets by joining them to the base raceway of the same or adjacent panel.
		MR3-TVB PC connects a base raceway rail with a vertical duplex outlet in the same panel or mounted on the near side of the adjacent ported panel.
		<b>MR3-TV24, 36, 48 PC</b> connect a base raceway rail with a vertical duplex outlet mounted on the far side of, respectively, 18"-24", 30"-36", or 42"-48" wide ported panels.
		<b>MR3-EVI J</b> connects two vertical duplex outlets of the same circuit inside the ported panel frame.
		Based on connector lengths, the intended location of the centerline of the vertical duplex outlet is 32" from the floor.

Power distribution components  
*Ported panel*  
*data port, outlets, raceway connectors*

description	type	pattern no.	list price
 <p>3 + 3 raceway connectors</p>	Base of adjacent panel to far side of 18",24"W panel	<b>MR3-TV24 PC</b>	\$142.
	Base of adjacent panel to far side of 30",36"W panel	<b>MR3-TV36 PC</b>	164.
	Base of adjacent panel to far side of 42",48"W panel	<b>MR3-TV48 PC</b>	177.
	Base of same panel, adjacent panel to near side	<b>MR3-TVB PC</b>	123.
	Internal jumper to same circuit outlet	<b>MR3-TVI J</b>	136.

Order Code	Specification Information	Application Notes						
<p>Example: <b>MR3-VPBK</b></p> <table border="1"> <tr> <td><b>MR3</b></td> <td>Morrison</td> </tr> <tr> <td><b>VP</b></td> <td>Application</td> </tr> <tr> <td><b>BK</b></td> <td>Bracket kit</td> </tr> </table>	<b>MR3</b>	Morrison	<b>VP</b>	Application	<b>BK</b>	Bracket kit	<p>Ported panel electrical components connect to 2+2, four circuit and 3+3, six-circuit raceway components to deliver worksurface-height outlets within the ported panel frame.</p> <p>Floating data port allows data and communication outlets to be mounted at any location on the ported panel face except directly above or below electrical outlets.</p> <p>Floating data ports include front and back mounting plates.</p> <p>PDC modules ( faceplates and outlets ) are specified separately.</p> <p>Vertical power and data ports for ported panel are black finish and require field cutting the panel insert for installation.</p>	<p>Vertical power port bracket kit includes an outlet mounting bracket, a cover mounting bracket and cover plate. Outlet mounting bracket attaches to vertical rails of panel frame.</p> <p>Vertical duplex outlets are dedicated for ported panel application and are preconfigured to access the circuit indicated by the letter on the outlet face. All outlets are black with white letters. Outlets for circuits X, Y and Z are available with orange face and black face with orange triangle to signify protected circuits for electronic equipment. Base raceway duplex outlets will not work in vertical port applications.</p> <p>Vertical duplex outlets are one-sided only and must be ordered separately from the bracket kit.</p>
<b>MR3</b>	Morrison							
<b>VP</b>	Application							
<b>BK</b>	Bracket kit							
		<p>Ported panel connectors power vertical duplex outlets by joining them to the base raceway of the same or adjacent panel.</p> <p>MR3-TVB PC connects a base raceway rail with a vertical duplex outlet in the same panel or mounted on the near side of the adjacent ported panel.</p> <p><b>MR3-TV24, 36, 48 PC</b> connect a base raceway rail with a vertical duplex outlet mounted on the far side of, respectively, 18"-24", 30"-36", or 42"-48" wide ported panels.</p> <p><b>MR3-EVI J</b> connects two vertical duplex outlets of the same circuit inside the ported panel frame.</p> <p>Based on connector lengths, the intended location of the centerline of the vertical duplex outlet is 32" from the floor.</p>						



# Power distribution

## 2+2™ Raceway

### hardwire raceway components

Morrison

Panel Planning



description	type	pattern no.	list price
Power infeed kit 	Hardwire, Chicago	<b>MR2-PICHI</b>	\$282.
Hardwire receptacles kit for panel base 	24"W	<b>MR2-CHI-24</b>	136.
	30"W	<b>MR2-CHI-30</b>	149.
	36"W	<b>MR2-CHI-36</b>	164.
	42"W	<b>MR2-CHI-42</b>	177.
	48"W	<b>MR2-CHI-48</b>	189.
	60"W	<b>MR2-CHI-60</b>	205.
Bridge connector	Straight connections only	<b>MR2-CHI-PT</b>	21.
Hardwire outlet box for stanchion or desktop monument		<b>MR2-NS-CHI</b>	55.
Hardwire receptacles kit for vertical raceway panel, two outlets above and two below worksurface	42"H, 56"H, 64"H, 74"H panel	<b>MR2-RVR42-H4( )</b>	284.
	48"H panel	<b>MR2-RVR48-H4( )</b>	284.
Hardwire receptacles kit for vertical raceway panel, two outlets above worksurface	42"H, 56"H, 64"H, 74"H panel	<b>MR2-RVR42-H2( )</b>	230.
	48"H panel	<b>MR2-RVR48-H2( )</b>	230.

Order Code	Specification Information	Application Notes
Example: <b>MR2-CHI-24</b>	Hardwire raceway components are approved for use in City of Chicago installations.	<p>Hardwire infeed and receptacles kits are field-installed in any Morrison vertical panel base wider than 18".</p> <p>Hardwire infeed consists of code-approved electrical box with mounting bracket.</p> <p>Electrical contractor supplies watertight conduit from building power supply to panel base, punches infeed hole in standard non-powered raceway cover, and supplies flexible conduit for all panel-to-panel power connections.</p> <p>Receptacles kit includes full width cable tray, forming a continuous steel septum between power and data/telecommunications cables.</p> <p>Receptacles kits and hardwire covers accommodate standard Decora-type architectural duplex outlets on one or both sides, 12" from each end of panel.</p>
<b>MR2</b> Power component		
<b>CHI</b> Chicago hardwire		
<b>24</b> Panel width		
		<p>Hardwire outlet openings are in the same position as 2+2 modular raceway outlets. Top cap and raceway cover kits for hardwire raceway include two screws to enclose cable tray as code-approved electrical box.</p> <p>Bridge connector mechanically connects adjacent receptacles kits, eliminating flexible conduit between hardwired panels in a straight connection.</p> <p>Hardwire components do not include wire, outlets, cable conduit, or fittings.</p> <p>Hardwire receptacles kits for vertical raceway panel include face covers.</p>

# Power distribution

## hardwire raceway components

Morrison

description	type	w	d	h	pattern no.	Paint	PV1	PV2	PV3
	With outlet plates	24"		4"	<b>MT6-E24-( )(-)-CHI</b>	\$10.	\$10.	\$10.	\$144.
		30"		4"	<b>MT6-E30-( )(-)-CHI</b>	11.	11.	11.	151.
		36"		4"	<b>MT6-E36-( )(-)-CHI</b>	12.	12.	12.	164.
		42"		4"	<b>MT6-E42-( )(-)-CHI</b>	13.	13.	13.	173.
		48"		4"	<b>MT6-E48-( )(-)-CHI</b>	13.	13.	13.	179.
		60"		4"	<b>MT6-E60-( )(-)-CHI</b>	19.	19.	19.	198.
	PDC raceway cover with hardwire outlet openings	24"		4"	<b>MT6-PDC24-( )(-)-CH</b>	27.			
		30"		4"	<b>MT6-PDC30-( )(-)-CH</b>	30.			
		36"		4"	<b>MT6-PDC36-( )(-)-CH</b>	32.			
		42"		4"	<b>MT6-PDC42-( )(-)-CH</b>	34.			
		48"		4"	<b>MT6-PDC48-( )(-)-CH</b>	36.			
		60"		4"	<b>MT6-PDC60-( )(-)-CH</b>	40.			

### Order Code

Example:	<b>MT6-E24-612-612-CHI</b>
<b>MT6</b>	Top cap/covers
<b>E</b>	Powered
<b>24</b>	Width
<b>612</b>	Top cap finish
<b>612</b>	Raceway finish
<b>CHI</b>	Chicago hardware

### Specification Information

*Specify finish for top cap and raceway cover.*

### Application Notes

For combinations of wood top caps with hardwire raceway covers, insert top cap finish before raceway cover finish.


Hardwire raceway components are approved for use in City of Chicago installations.

Receptacles kits and hardwire covers accommodate standard Decora-type architectural duplex outlets on one or both sides, 12" from each end of panel.

Hardwire outlet openings are in the same position as 2+2 modular raceway outlets. Top cap and raceway cover kits for hardwire raceway include two screws to enclose cable tray as code-approved electrical box.

# Worksurfaces, 1 3/4" 18"D



Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 18"D 	No grommets	30"	17 5/8"	1 3/4"	<b>MW2-S3018-B-( )</b>	\$298.	\$380.	\$441.	\$621.
		36"	17 5/8"	1 3/4"	<b>MW2-S3618-B-( )</b>	326.	427.	472.	667.
		42"	17 5/8"	1 3/4"	<b>MW2-S4218-B-( )</b>	360.	456.	518.	744.
		48"	17 5/8"	1 3/4"	<b>MW2-S4818-B-( )</b>	403.	518.	561.	806.
		54"	17 5/8"	1 3/4"	<b>MW2-S5418-B-( )</b>	432.	549.	609.	867.
		60"	17 5/8"	1 3/4"	<b>MW2-S6018-B-( )</b>	447.	561.	637.	930.
		66"	17 5/8"	1 3/4"	<b>MW2-S6618-B-( )</b>	493.	609.	715.	1,037.
		72"	17 5/8"	1 3/4"	<b>MW2-S7218-B-( )</b>	538.	655.	792.	1,132.

Order Code	Specification Information	Application Notes
Example: <b>MW2-S3618-B-117</b> <b>MW2</b> Worksurface 1 3/4" thick <b>S</b> Worksurface type <b>36</b> Width <b>18</b> Depth <b>B</b> No grommets <b>117</b> Surface finish	B: Worksurface does not include grommets Specify surface finish All worksurfaces are U.L.-listed.	18"D worksurfaces are used interchangeably in desk and panel system applications as shallow main surfaces, extensions, or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports. All worksurfaces have threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations. Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately. 18"D worksurfaces with desk supports or filler panels do not accept pedestals. All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
		Veneer Group 1 worksurfaces are quartered Techgrain®. Veneer Group 2 worksurfaces are rift cut Techgrain®. Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

# Worksurfaces, 1 3/4" 24"D

Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 24"D 	Grommets	24"	23 3/8"	1 3/4"	<b>MW2-S2424-A-()</b>	\$362.	\$458.	\$550.	\$744.
		30"	23 3/8"	1 3/4"	<b>MW2-S3024-A-()</b>	391.	489.	564.	775.
		36"	23 3/8"	1 3/4"	<b>MW2-S3624-A-()</b>	422.	519.	596.	808.
		42"	23 3/8"	1 3/4"	<b>MW2-S4224-A-()</b>	467.	564.	625.	869.
		48"	23 3/8"	1 3/4"	<b>MW2-S4824-A-()</b>	495.	611.	687.	964.
		54"	23 3/8"	1 3/4"	<b>MW2-S5424-A-()</b>	526.	656.	747.	1,040.
		60"	23 3/8"	1 3/4"	<b>MW2-S6024-A-()</b>	570.	701.	795.	1,101.
		66"	23 3/8"	1 3/4"	<b>MW2-S6624-A-()</b>	615.	776.	869.	1,211.
		72"	23 3/8"	1 3/4"	<b>MW2-S7224-A-()</b>	676.	823.	944.	1,336.
		78"	23 3/8"	1 3/4"	<b>MW2-S7824-A-()</b>	735.	900.	1,021.	1,426.
		84"	23 3/8"	1 3/4"	<b>MW2-S8424-A-()</b>	780.	961.	1,096.	1,534.
		90"	23 3/8"	1 3/4"	<b>MW2-S9024-A-()</b>	838.	1,035.	1,189.	1,675.
		96"	23 3/8"	1 3/4"	<b>MW2-S9624-A-()</b>	915.	1,129.	1,310.	1,830.
Straight, 24"D - No grommets 	No grommets	24"	23 3/8"	1 3/4"	<b>MW2-S2424-B-()</b>	298.	395.	486.	682.
		30"	23 3/8"	1 3/4"	<b>MW2-S3024-B-()</b>	326.	427.	501.	714.
		36"	23 3/8"	1 3/4"	<b>MW2-S3624-B-()</b>	360.	456.	532.	744.
		42"	23 3/8"	1 3/4"	<b>MW2-S4224-B-()</b>	403.	501.	561.	806.
		48"	23 3/8"	1 3/4"	<b>MW2-S4824-B-()</b>	432.	549.	624.	900.
		54"	23 3/8"	1 3/4"	<b>MW2-S5424-B-()</b>	464.	593.	684.	977.
		60"	23 3/8"	1 3/4"	<b>MW2-S6024-B-()</b>	506.	636.	733.	1,037.
		66"	23 3/8"	1 3/4"	<b>MW2-S6624-B-()</b>	552.	715.	806.	1,147.
		72"	23 3/8"	1 3/4"	<b>MW2-S7224-B-()</b>	611.	761.	882.	1,272.
		78"	23 3/8"	1 3/4"	<b>MW2-S7824-B-()</b>	671.	836.	958.	1,365.
		84"	23 3/8"	1 3/4"	<b>MW2-S8424-B-()</b>	717.	897.	1,033.	1,472.
		90"	23 3/8"	1 3/4"	<b>MW2-S9024-B-()</b>	774.	972.	1,127.	1,612.
		96"	23 3/8"	1 3/4"	<b>MW2-S9624-B-()</b>	852.	1,064.	1,247.	1,767.

## Order Code

Example:	<b>MW2-S7224-A-117</b>
<b>MW2</b>	Worksurface, 1 3/4" thick
<b>S</b>	Straight worksurface
<b>72</b>	Width
<b>24</b>	Depth
<b>A</b>	Grommets
<b>117</b>	Surface finish

## Specification Information

*Grommets/no grommets:*  
 A- Worksurfaces include 3" grommet in each back corner leading into desk support or wire manager.  
 B- Worksurface does not include grommets.  
 Specify surface finish  
 All worksurfaces are U.L.-listed.

## Application Notes

24"D worksurfaces are used interchangeably as shallow main surfaces, extensions or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports.

All worksurfaces have threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.

Use 18"D pedestals with 24"D worksurfaces for full wire management capability in desk or panel applications.

All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

Plastic laminate worksurfaces are post-formed top and bottom, front and back.

Veneer Group 1 worksurfaces are quartered Techgrain®.

Veneer Group 2 worksurfaces are rift cut Techgrain®.

Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.



Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.

Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.



# Worksurfaces, 1 3/4" 30"D

Morrison



description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 30"D 	Grommets	30"	29 5/8"	1 3/4"	<b>MW2-S3030-A-( )</b>	\$436.	\$534.	\$611.	\$854.
		36"	29 5/8"	1 3/4"	<b>MW2-S3630-A-( )</b>	482.	596.	656.	916.
		42"	29 5/8"	1 3/4"	<b>MW2-S4230-A-( )</b>	511.	625.	702.	977.
		48"	29 5/8"	1 3/4"	<b>MW2-S4830-A-( )</b>	555.	674.	762.	1,054.
		54"	29 5/8"	1 3/4"	<b>MW2-S5430-A-( )</b>	584.	734.	823.	1,113.
		60"	29 5/8"	1 3/4"	<b>MW2-S6030-A-( )</b>	615.	776.	869.	1,211.
		66"	29 5/8"	1 3/4"	<b>MW2-S6630-A-( )</b>	662.	823.	931.	1,318.
		72"	29 5/8"	1 3/4"	<b>MW2-S7230-A-( )</b>	735.	900.	1,021.	1,426.
		78"	29 5/8"	1 3/4"	<b>MW2-S7830-A-( )</b>	795.	973.	1,113.	1,550.
		84"	29 5/8"	1 3/4"	<b>MW2-S8430-A-( )</b>	854.	1,005.	1,204.	1,690.
		90"	29 5/8"	1 3/4"	<b>MW2-S9030-A-( )</b>	930.	1,143.	1,324.	1,876.
		96"	29 5/8"	1 3/4"	<b>MW2-S9630-A-( )</b>	1,017.	1,235.	1,446.	2,061.
Straight 30"D - no grommets 	No grommets	30"	29 5/8"	1 3/4"	<b>MW2-S3030-B-( )</b>	374.	472.	549.	792.
		36"	29 5/8"	1 3/4"	<b>MW2-S3630-B-( )</b>	419.	532.	593.	853.
		42"	29 5/8"	1 3/4"	<b>MW2-S4230-B-( )</b>	447.	561.	637.	915.
		48"	29 5/8"	1 3/4"	<b>MW2-S4830-B-( )</b>	492.	609.	697.	992.
		54"	29 5/8"	1 3/4"	<b>MW2-S5430-B-( )</b>	522.	669.	761.	1,051.
		60"	29 5/8"	1 3/4"	<b>MW2-S6030-B-( )</b>	552.	715.	806.	1,147.
		66"	29 5/8"	1 3/4"	<b>MW2-S6630-B-( )</b>	600.	761.	867.	1,256.
		72"	29 5/8"	1 3/4"	<b>MW2-S7230-B-( )</b>	671.	836.	958.	1,365.
		78"	29 5/8"	1 3/4"	<b>MW2-S7830-B-( )</b>	733.	911.	1,051.	1,487.
		84"	29 5/8"	1 3/4"	<b>MW2-S8430-B-( )</b>	792.	1,005.	1,140.	1,626.
		90"	29 5/8"	1 3/4"	<b>MW2-S9030-B-( )</b>	866.	1,080.	1,261.	1,814.
		96"	29 5/8"	1 3/4"	<b>MW2-S9630-B-( )</b>	953.	1,171.	1,380.	2,000.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MW2-S4230A-117</b> <b>MW2</b> Worksurface, 1 3/4" thick <b>S</b> Straight worksurface <b>42</b> Width <b>30</b> Depth <b>A</b> Grommets <b>117</b> Surface finish	Grommets/no grommets: A- worksurface includes 3" grommet in each back corner leading into desk support or wire manager clips. B- worksurface does not include grommets Specify surface finish.  All worksurfaces are U.L.-listed.	30"D worksurfaces are used interchangeably in desk and panel system applications as main surfaces, extensions or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports.  All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.  Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.  Plastic laminate worksurfaces are post-formed top and bottom, front and back.  Veneer Group 1 worksurfaces are quartered Techgrain®. Veneer Group 2 worksurfaces are rift cut Techgrain®.  Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

# Worksurfaces, 1 3/4" 36"D

Morrison





description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 36"D 	Recessed grommets	66"	35 5/8"	1 3/4"	<b>MW2-S6636-R-( )</b>	\$809.	\$973.	\$1,096.	\$1,504.
		72"	35 5/8"	1 3/4"	<b>MW2-S7236-R-( )</b>	854.	1,052.	1,189.	1,675.
		78"	35 5/8"	1 3/4"	<b>MW2-S7836-R-( )</b>	930.	1,143.	1,295.	1,780.
Straight 36"D - no grommets 	No grommets	66"	35 5/8"	1 3/4"	<b>MW2-S6636-B-( )</b>	745.	911.	1,033.	1,443.
		72"	35 5/8"	1 3/4"	<b>MW2-S7236-B-( )</b>	792.	988.	1,127.	1,612.
		78"	35 5/8"	1 3/4"	<b>MW2-S7836-B-( )</b>	866.	1,080.	1,233.	1,719.

Order Code	Specification Information	Application Notes
Example: <b>MW2-S6636R-117</b>	<i>Grommets/no grommets:</i>	<p>36"D desks may be planned with 6" recessed desk support and 24"D pedestals or end panels, or 29" or 35"W universal end panels with kneehole filler. 36"D worksurfaces do not accept privacy screens.</p> <p>Plastic laminate worksurfaces are post-formed top and bottom, front and back.</p> <p>All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.</p> <p>Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.</p> <p>Veneer Group 1 worksurfaces are quartered Techgrain®.</p> <p>Veneer Group 2 worksurfaces are rift cut Techgrain®.</p> <p>Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.</p>
<b>MW2</b> Worksurface, 1 3/4" thick	B- worksurface does not include grommets	
<b>S</b> Straight worksurface	R- worksurface includes 3" grommets recessed for use with 6" recessed desk support.	
<b>66</b> Width	Specify surface finish.	
<b>36</b> Depth	All worksurfaces are U.L.-listed.	
<b>R</b> Grommets		
<b>117</b> Surface finish		

# Worksurfaces, 1 3/4"

## VDT corners

Morrison





description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Corner 	Corner grommet only	35 5/8"	17 5/8"	1 3/4"	<b>MW2-V3618-A-()</b>	\$767.	\$894.	\$970.	\$1,369.
		35 5/8"	23 5/8"	1 3/4"	<b>MW2-V3624-A-()</b>	798.	909.	984.	1,400.
		41 5/8"	23 5/8"	1 3/4"	<b>MW2-V4224-A-()</b>	825.	953.	1,030.	1,460.
		41 5/8"	29 5/8"	1 3/4"	<b>MW2-V4230-A-()</b>	873.	1,014.	1,089.	1,550.
		47 5/8"	23 5/8"	1 3/4"	<b>MW2-V4824-A-()</b>	975.	1,134.	1,177.	1,719.
		47 5/8"	29 5/8"	1 3/4"	<b>MW2-V4830-A-()</b>	1,021.	1,193.	1,268.	1,810.
Corner - 3 grommets 	3 grommets	35 5/8"	23 5/8"	1 3/4"	<b>MW2-V3624-C-()</b>	861.	972.	1,048.	1,461.
		41 5/8"	23 5/8"	1 3/4"	<b>MW2-V4224-C-()</b>	889.	1,017.	1,092.	1,525.
		41 5/8"	29 5/8"	1 3/4"	<b>MW2-V4230-C-()</b>	935.	1,077.	1,152.	1,614.
		47 5/8"	23 5/8"	1 3/4"	<b>MW2-V4824-C-()</b>	1,037.	1,198.	1,240.	1,780.
		47 5/8"	29 5/8"	1 3/4"	<b>MW2-V4830-C-()</b>	1,085.	1,257.	1,334.	1,873.
		Corner with manual keyboard 	Corner grommet only	35 5/8"	17 5/8"	1 3/4"	<b>MW2-K3618-M-()</b>	1,083.	1,210.
41 5/8"	23 5/8"			1 3/4"	<b>MW2-K4224-M-()</b>	1,141.	1,268.	1,344.	1,772.
47 5/8"	29 5/8"			1 3/4"	<b>MW2-K4830-M-()</b>	1,337.	1,507.	1,583.	2,123.
Corner with pneumatic keyboard 	Corner grommet only			35 5/8"	17 5/8"	1 3/4"	<b>MW2-K3618-P-()</b>	1,474.	1,601.
		41 5/8"	23 5/8"	1 3/4"	<b>MW2-K4224-P-()</b>	1,533.	1,659.	1,736.	2,166.
		47 5/8"	29 5/8"	1 3/4"	<b>MW2-K4830-P-()</b>	1,726.	1,899.	1,974.	2,515.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MW2-V4830-C-117</b>	<i>Grommets/no grommets:</i>	VDT corners may be used interchangeably in desk and panel system applications. They must be supported by VDT support brackets on each back edge or cantilever bridging brackets on each side edge and a cantilever bracket on the back corner.
<b>MW2</b> Worksurface, 1 3/4" thick	A- VDT corner includes 3" grommet in back corner.	Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>V</b> VDT corner	C- VDT corner includes 3" grommet in all three back corners.	Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>48</b> Width	P- VDT corner with integral, pneumatically adjustable keyboard support 24"W x 12"D; includes one grommet.	Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.
<b>30</b> Depth of return	M- VDT corner with integral, mechanically adjustable keyboard support 24"W x 12"D; includes one grommet.	All VDT corner worksurfaces are bored to accept and are shipped with wire manager clips.
<b>C</b> Three grommets		36"W x 18"D VDT corners accept 18"D returns, 36", 42", and 48"W x 24"D VDT corners accept 24"D returns, 42" and 48"W x 30"D VDT corners accept 30"D returns.
<b>117</b> Surface finish		VDT corners are 3/8" less than nominal depth for rear wire clearance or privacy screens.
	Specify surface finish. VDT worksurfaces have threaded metal inserts at all desk support and bracket locations.	Plastic laminate worksurfaces are post-formed on front and back edges. 48" x 24" VDT corners have an inside radius, T-mold front edge that curves into an optimal 45° straight keyboard location.
	All worksurfaces are U.L.-listed.	

# Worksurfaces, 1 3/4" rounded end, 30"D

Morrison

description	w	d	h	pattern no.	paint	lam.	V1	V2	V3
30"D - Recessed grommets 	63"	30"	1 3/4"	<b>MW2-R6330R( ) (L/R)</b>		\$1,195.	\$1,463.	\$1,585.	\$2,249.
	75"	30"	1 3/4"	<b>MW2-R7530R( ) (L/R)</b>		1,242.	1,526.	1,647.	2,311.
	87"	30"	1 3/4"	<b>MW2-R8730R( ) (L/R)</b>		1,330.	1,630.	1,708.	2,421.
30"D - End grommets 	63"	30"	1 3/4"	<b>MW2-R6330E( )</b>		1,195.	1,463.	1,585.	2,249.
	75"	30"	1 3/4"	<b>MW2-R7530E( )</b>		1,242.	1,526.	1,651.	2,311.
	87"	30"	1 3/4"	<b>MW2-R8730E( )</b>		1,330.	1,630.	1,708.	2,421.
30"D - No grommets 	63"	30"	1 3/4"	<b>MW2-R6330B( ) (L/R)</b>		1,131.	1,401.	1,521.	2,186.
	75"	30"	1 3/4"	<b>MW2-R7530B( ) (L/R)</b>		1,177.	1,460.	1,582.	2,247.
	87"	30"	1 3/4"	<b>MW2-R8730B( ) (L/R)</b>		1,264.	1,566.	1,644.	2,356.
Support column 	5"	-	27"	<b>MM2-L26( )</b>		146.			

## Order Code

Example:	<b>MW2-R8730E-117</b>
<b>MW2</b>	Worksurface, 1 3/4" thick
<b>R</b>	Rounded end
<b>87</b>	Width
<b>30</b>	Depth
<b>E</b>	End grommets
<b>117</b>	Surface finish

## Specification Information

### Grommets/no grommets:

- B- worksurface does not include grommets.
- E- rounded end worksurface includes 3" grommet in each straight end corner.
- R- rounded end worksurface includes 3" grommets recessed for use with 6" recessed desk support.

Specify surface finish.  
Rounded end worksurfaces with recessed or no grommets are specified left or right (rounded end when seated at desk). All worksurfaces are U.L.-listed.

Recessed grommets align with desk support recessed 6".

## Application Notes

Rounded end worksurfaces may be used to create fully enclosed desks or open table/desks with support column. For front modesty, use 48"W desk support with 63" rounded end, 60"W desk support with 75" rounded end; 72"W desk support with 87" rounded end.

Use 18"D pedestal or end panel each end with 30"D rounded end with recessed grommets. Rounded end worksurfaces with end grommets are supported by 30"W or 36"W desk support and support column.

Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.





Worksurfaces with end grommets may not be supported by conference end panels.

Plastic laminate worksurfaces have radiused T-mold edge.

Rounded end worksurfaces have threaded metal inserts for desk support, end panel each end, and at all bracket locations. End grommet worksurfaces have no pedestal inserts.

# Worksurfaces, 1 3/4" rounded end, 36"D

Morrison

description	w	d	h	pattern no.	paint	lam.	V1	V2	V3
36"D - Recessed grommets 	66"	36"	1 3/4"	<b>MW2-R6636R( )</b> (L/R)		\$1,330.	\$1,602.	\$1,724.	\$2,390.
	78"	36"	1 3/4"	<b>MW2-R7836R( )</b> (L/R)		1,374.	1,678.	1,768.	2,499.
	90"	36"	1 3/4"	<b>MW2-R9036R( )</b> (L/R)		1,421.	1,737.	1,845.	2,592.
36"D - End grommets 	66"	36"	1 3/4"	<b>MW2-R6636E( )</b>		1,330.	1,602.	1,724.	2,390.
	78"	36"	1 3/4"	<b>MW2-R7836E( )</b>		1,374.	1,678.	1,768.	2,499.
	90"	36"	1 3/4"	<b>MW2-R9036E( )</b>		1,421.	1,737.	1,845.	2,592.
36"D - No grommets 	66"	36"	1 3/4"	<b>MW2-R6636B( )</b> (L/R)		1,264.	1,537.	1,660.	2,325.
	78"	36"	1 3/4"	<b>MW2-R7836B( )</b> (L/R)		1,310.	1,612.	1,704.	2,433.
	90"	36"	1 3/4"	<b>MW2-R9036B( )</b> (L/R)		1,357.	1,673.	1,779.	2,530.
Support column 	5"	-	27"	<b>MM2-L26( )</b>		146.			

Worksurface Planning

## Order Code

Example:	<b>MW2-R7836E-117</b>
<b>MW2</b>	Worksurface, 1 3/4" thick
<b>R</b>	Rounded end
<b>78</b>	Width
<b>36</b>	Depth
<b>E</b>	End grommets
<b>117</b>	Surface finish

## Specification Information

### Grommets/no grommets:

- B- worksurface does not include grommets.
  - E- rounded end worksurface includes 3" grommet in each straight end corner.
  - R- rounded end worksurface includes 3" grommets recessed for use with 6" recessed desk support.
- Specify surface finish.

Rounded end worksurfaces with recessed or no grommets are specified left or right (rounded end when seated at desk). All worksurfaces are U.L.-listed.

Recessed grommets align with desk support recessed 6".

## Application Notes

Rounded end worksurfaces may be used to create fully enclosed desks or open table/desks with support column. For front modesty, use 48"W desk support with 66" rounded end, 60"W desk support with 78" rounded end; 72"W desk support with 90" rounded end.






Use 24"D pedestal or end panel each end with 36"D. Rounded end worksurfaces with end grommets are supported by 30"W or 36"W desk support and support column.

Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.

Worksurfaces with end grommets may not be supported by conference end panels.

Plastic laminate worksurfaces have radiused T-mold edge.


Rounded end worksurfaces have threaded metal inserts for desk support, end panel each end, and at all bracket locations. End grommet worksurfaces have no pedestal inserts.

description	type	w	d	h	pattern no.	paint	lam.	V1	V2	V3
Half round - Standard		30"	48"	1 3/4"	<b>MW2-R3048-B-( )</b>		\$829.	\$991.	\$1,118.	\$1,537.
										
Half round - Extended		42"	48"	1 3/4"	<b>MW2-R4248-B-( )</b>		978.	1,167.	1,320.	1,812.
										
Half round - With vertical panel		30"	50 3/8"	1 3/4"	<b>MW2-R3050-B-( )</b>		914.	1,088.	1,229.	1,692.
										
Teardrop	24" return	42"	24"	1 3/4"	<b>MW2-T4224-B-( )</b>		859.	1,023.	1,158.	1,562.
	30" return	48"	30"	1 3/4"	<b>MW2-T4830-B-( )</b>		1,100.	1,310.	1,481.	2,000.
										
Support column		5"	-	27"	<b>MM2-L26( )</b>		146.			
										

Order Code	Specification Information	Application Notes
Example: <b>MW2-T4224-B-117</b>	Conference worksurfaces do not have grommets.	Conference worksurfaces must be supported by support column and flat bracket or bridging bracket to adjacent desk.
<b>MW2</b> Worksurface, 1 3/4" thick	Specify surface finish.	Half-round and extended half-round is used with back-to-back 24"D straight or VDT corner worksurfaces. Half round with vertical panel attaches to 24"D straight or VDT corner worksurfaces supported by vertical panel.
<b>T</b> Teardrop shape	Worksurfaces have threaded metal inserts at column and all bracket locations.	Teardrop attaches to straight or VDT worksurfaces on either straight edge.
<b>42</b> Diameter	All worksurfaces are U.L.-listed.	Plastic laminate worksurfaces have radiused T-mold edge in same profile as adjacent post-formed worksurfaces.
<b>24</b> Return depth		Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>B</b> No grommets		Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>117</b> Surface finish		Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

# Worksurfaces, 1 1/4" 18"D



Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 18"D 	No grommets	30"	17 5/8"	1 1/4"	<b>MU1-S3018-B-()</b>	\$234.	\$312.	\$369.	\$538.
		36"	17 5/8"	1 1/4"	<b>MU1-S3618-B-()</b>	260.	351.	397.	580.
		42"	17 5/8"	1 1/4"	<b>MU1-S4218-B-()</b>	274.	369.	429.	639.
		48"	17 5/8"	1 1/4"	<b>MU1-S4818-B-()</b>	319.	429.	474.	701.
		54"	17 5/8"	1 1/4"	<b>MU1-S5418-B-()</b>	332.	444.	502.	745.
		60"	17 5/8"	1 1/4"	<b>MU1-S6018-B-()</b>	349.	457.	532.	807.
		66"	17 5/8"	1 1/4"	<b>MU1-S6618-B-()</b>	377.	487.	592.	894.
		72"	17 5/8"	1 1/4"	<b>MU1-S7218-B-()</b>	421.	532.	664.	986.

Order Code	Specification Information	Application Notes
Example: <b>MU1-S4818-B-117</b> <b>MU1</b> Worksurface 1 1/4" thick <b>S</b> Worksurface type <b>48</b> Width <b>18</b> Depth <b>B</b> No grommets <b>117</b> Surface finish	B: Worksurface does not include grommets.  Specify surface finish.  1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.  All worksurfaces are U.L.-listed.	18"D worksurfaces are used interchangeably in desk and panel system applications as shallow main surfaces, extensions, or credenza tops. They may be supported at each end by an 18" end support bracket, 18" cantilever bracket, 18"W conference end panel, 18"D pedestal, or 12"W end panel (MN2-E12) in conjunction with a desk support.  18"D worksurfaces with desk supports do not accept pedestals.  All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.  Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.  Veneer Group 1 worksurfaces are quartered Techgrain®.  Veneer Group 2 worksurfaces are rift cut Techgrain®.  Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.  Suspended pedestals may not be used with 1 1/4" worksurfaces.

# Worksurfaces, 1 1/4" 24"D

Morrison



description	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 24"D - Grommets 	24"	23 3/8"	1 1/4"	<b>MU1-S2424-A-(-)</b>	\$296.	\$389.	\$477.	\$660.
	30"	23 3/8"	1 1/4"	<b>MU1-S3024-A-(-)</b>	323.	415.	492.	689.
	36"	23 3/8"	1 1/4"	<b>MU1-S3624-A-(-)</b>	337.	433.	506.	704.
	42"	23 3/8"	1 1/4"	<b>MU1-S4224-A-(-)</b>	381.	477.	537.	763.
	48"	23 3/8"	1 1/4"	<b>MU1-S4824-A-(-)</b>	395.	506.	579.	854.
	54"	23 3/8"	1 1/4"	<b>MU1-S5424-A-(-)</b>	427.	551.	637.	915.
	60"	23 3/8"	1 1/4"	<b>MU1-S6024-A-(-)</b>	455.	579.	668.	958.
	66"	23 3/8"	1 1/4"	<b>MU1-S6624-A-(-)</b>	497.	655.	743.	1,062.
	72"	23 3/8"	1 1/4"	<b>MU1-S7224-A-(-)</b>	542.	684.	801.	1,169.
	78"	23 3/8"	1 1/4"	<b>MU1-S7824-A-(-)</b>	588.	754.	870.	1,247.
	84"	23 3/8"	1 1/4"	<b>MU1-S8424-A-(-)</b>	628.	808.	932.	1,340.
	90"	23 3/8"	1 1/4"	<b>MU1-S9024-A-(-)</b>	667.	860.	993.	1,427.
96"	23 3/8"	1 1/4"	<b>MU1-S9624-A-(-)</b>	727.	938.	1,085.	1,564.	
Straight, 24"D - No grommets 	24"	23 3/8"	1 1/4"	<b>MU1-S2424-B-(-)</b>	234.	324.	415.	598.
	30"	23 3/8"	1 1/4"	<b>MU1-S3024-B-(-)</b>	260.	351.	429.	627.
	36"	23 3/8"	1 1/4"	<b>MU1-S3624-B-(-)</b>	274.	369.	444.	639.
	42"	23 3/8"	1 1/4"	<b>MU1-S4224-B-(-)</b>	319.	415.	474.	701.
	48"	23 3/8"	1 1/4"	<b>MU1-S4824-B-(-)</b>	332.	444.	517.	792.
	54"	23 3/8"	1 1/4"	<b>MU1-S5424-B-(-)</b>	363.	487.	576.	852.
	60"	23 3/8"	1 1/4"	<b>MU1-S6024-B-(-)</b>	392.	517.	605.	894.
	66"	23 3/8"	1 1/4"	<b>MU1-S6624-B-(-)</b>	434.	592.	681.	1,000.
	72"	23 3/8"	1 1/4"	<b>MU1-S7224-B-(-)</b>	478.	622.	739.	1,105.
	78"	23 3/8"	1 1/4"	<b>MU1-S7824-B-(-)</b>	523.	691.	807.	1,183.
	84"	23 3/8"	1 1/4"	<b>MU1-S8424-B-(-)</b>	564.	744.	869.	1,278.
	90"	23 3/8"	1 1/4"	<b>MU1-S9024-B-(-)</b>	604.	797.	930.	1,366.
96"	23 3/8"	1 1/4"	<b>MU1-S9624-B-(-)</b>	663.	875.	1,021.	1,501.	

Order Code	Specification Information	Application Notes
Example: <b>MU1-S3024-B-117</b>	<i>Grommets/no grommets:</i>	24"D worksurfaces are used interchangeably as shallow main surfaces, extensions or credenza tops. They can be supported at each end by 24" end support bracket, 24" cantilever bracket, 24"W end panel, 18"D pedestal or end panel in conjunction with desk support.
<b>MU1</b> Worksurface, 1 1/4" thick	A- Worksurfaces include 3" grommet in each back corner leading into desk support or wire manager.	Use 18"D pedestals with 24"D worksurfaces for full wire management capability in desk or panel applications.
<b>S</b> Straight worksurface	B- Worksurface does not include grommets.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
<b>30</b> Width	Specify surface finish.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
<b>24</b> Depth	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.	Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>B</b> No grommets	Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.	Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>117</b> Surface finish	All worksurfaces are U.L.-listed.	Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.
		Suspended pedestals may not be used with 1 1/4" worksurfaces.



# Worksurfaces, 1 1/4" 30"D

Morrison





description	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 30"D - Grommets 	30"	29 5/8"	1 1/4"	<b>MU1-S3030-A-( )</b>	\$354.	\$447.	\$520.	\$749.
	36"	29 5/8"	1 1/4"	<b>MU1-S3630-A-( )</b>	381.	492.	551.	795.
	42"	29 5/8"	1 1/4"	<b>MU1-S4230-A-( )</b>	412.	520.	596.	854.
	48"	29 5/8"	1 1/4"	<b>MU1-S4830-A-( )</b>	439.	551.	637.	915.
	54"	29 5/8"	1 1/4"	<b>MU1-S5430-A-( )</b>	469.	610.	696.	988.
	60"	29 5/8"	1 1/4"	<b>MU1-S6030-A-( )</b>	497.	655.	743.	1,062.
	66"	29 5/8"	1 1/4"	<b>MU1-S6630-A-( )</b>	526.	684.	787.	1,152.
	72"	29 5/8"	1 1/4"	<b>MU1-S7230-A-( )</b>	583.	743.	861.	1,240.
	78"	29 5/8"	1 1/4"	<b>MU1-S7830-A-( )</b>	630.	817.	932.	1,367.
	84"	29 5/8"	1 1/4"	<b>MU1-S8430-A-( )</b>	679.	880.	1,005.	1,477.
	90"	29 5/8"	1 1/4"	<b>MU1-S9030-A-( )</b>	720.	938.	1,068.	1,573.
96"	29 5/8"	1 1/4"	<b>MU1-S9630-A-( )</b>	781.	1,018.	1,162.	1,711.	
Straight, 30"D - No grommets 	30"	29 5/8"	1 1/4"	<b>MU1-S3030-B-( )</b>	291.	385.	457.	687.
	36"	29 5/8"	1 1/4"	<b>MU1-S3630-B-( )</b>	319.	429.	487.	733.
	42"	29 5/8"	1 1/4"	<b>MU1-S4230-B-( )</b>	349.	457.	532.	792.
	48"	29 5/8"	1 1/4"	<b>MU1-S4830-B-( )</b>	377.	487.	576.	852.
	54"	29 5/8"	1 1/4"	<b>MU1-S5430-B-( )</b>	405.	548.	634.	926.
	60"	29 5/8"	1 1/4"	<b>MU1-S6030-B-( )</b>	434.	592.	681.	1,000.
	66"	29 5/8"	1 1/4"	<b>MU1-S6630-B-( )</b>	464.	622.	722.	1,089.
	72"	29 5/8"	1 1/4"	<b>MU1-S7230-B-( )</b>	521.	681.	798.	1,177.
	78"	29 5/8"	1 1/4"	<b>MU1-S7830-B-( )</b>	566.	753.	869.	1,302.
	84"	29 5/8"	1 1/4"	<b>MU1-S8430-B-( )</b>	615.	818.	941.	1,411.
	90"	29 5/8"	1 1/4"	<b>MU1-S9030-B-( )</b>	658.	875.	1,007.	1,510.
96"	29 5/8"	1 1/4"	<b>MU1-S9630-B-( )</b>	718.	954.	1,098.	1,648.	

Order Code	Specification Information	Application Notes
Example: <b>MU1-S3030B-117</b>	<i>Grommets/no grommets:</i>	Plastic laminate worksurfaces are post-formed top and bottom, front and back.
<b>MU1</b> Worksurface, 1 1/4" thick	A- worksurface includes 3" grommet in each back corner leading into desk support or wire manager clips.	
<b>S</b> Straight worksurface	B- worksurface does not include grommets	30"D worksurfaces are used interchangeably in desk and panel system applications as main surfaces, extensions or credenza tops. They can be supported at each end by 30" end support bracket, 30" cantilever bracket, 30" flat bracket, 30"W end panel, 24"D pedestal or end panel in conjunction with desk support, or 30"D pedestal.
<b>30</b> Width	Specify surface finish.	
<b>30</b> Depth	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
<b>B</b> No grommets	All worksurfaces are U.L.-listed.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
<b>117</b> Surface finish		Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.
		Suspended pedestals may not be used with 1 1/4" worksurfaces.
		Veneer Group 1 worksurfaces are quartered Techgrain®.
		Veneer Group 2 worksurfaces are rift cut Techgrain®.
		Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

Worksurface Planning

# Worksurfaces, 1 1/4" trapezoidal



Morrison

description	w	d	h	pattern no.	lam.	V1	V2	V3
Right hand - grommet 	48"	30"/24"	1 1/4"	<b>MU1-T48A-R-( )</b>	\$549.	\$686.	\$790.	\$1,104.
	54"	30"/24"	1 1/4"	<b>MU1-T54A-R-( )</b>	659.	823.	948.	1,326.
	60"	30"/24"	1 1/4"	<b>MU1-T60A-R-( )</b>	768.	960.	1,104.	1,547.
	72"	30"/24"	1 1/4"	<b>MU1-T72A-R-( )</b>	878.	1,098.	1,263.	1,767.
Left hand - grommet 	48"	24"/30"	1 1/4"	<b>MU1-T48A-L-( )</b>	549.	686.	790.	1,104.
	54"	24"/30"	1 1/4"	<b>MU1-T54A-L-( )</b>	659.	823.	948.	1,326.
	60"	24"/30"	1 1/4"	<b>MU1-T60A-L-( )</b>	768.	960.	1,104.	1,547.
	72"	24"/30"	1 1/4"	<b>MU1-T72A-L-( )</b>	878.	1,098.	1,263.	1,767.
Right hand - no grommet 	48"	30"/24"	1 1/4"	<b>MU1-T48B-R-( )</b>	494.	618.	711.	995.
	54"	30"/24"	1 1/4"	<b>MU1-T54B-R-( )</b>	604.	756.	869.	1,215.
	60"	30"/24"	1 1/4"	<b>MU1-T60B-R-( )</b>	714.	893.	1,025.	1,435.
	72"	30"/24"	1 1/4"	<b>MU1-T72B-R-( )</b>	823.	1,030.	1,183.	1,656.
Left hand - no grommet 	48"	24"/30"	1 1/4"	<b>MU1-T48B-L-( )</b>	494.	618.	711.	995.
	54"	24"/30"	1 1/4"	<b>MU1-T54B-L-( )</b>	604.	756.	869.	1,215.
	60"	24"/30"	1 1/4"	<b>MU1-T60B-L-( )</b>	714.	893.	1,025.	1,435.
	72"	24"/30"	1 1/4"	<b>MU1-T72B-L-( )</b>	823.	1,030.	1,183.	1,656.

Order Code	Specification Information	Application Notes
Example: <b>MU1-T48B-R-117</b>	<i>Grommets/no grommets:</i>	Plastic laminate worksurfaces are post-formed top and bottom, front and back. All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens. 1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.
<b>MU1</b> Worksurface, 1 1/4" thick	A- worksurface includes 3" grommet in each back corner.	
<b>T</b> Trapezoidal worksurface	B- worksurface does not include grommets	Trapezoidal worksurfaces are used interchangeably in desk and panel system applications. They must be supported at each end by a pedestal, end panel, end support, cantilever or cantilever bridging bracket with a maximum span of 48" between supports. Panel-supported worksurfaces over 48" must be mid-span supported by MB2-C18 brackets, specified separately.
<b>48</b> Width	Specify surface finish.	
<b>A</b> Grommets	Right- and Left- hand are defined by applying trapezoidal tops as returns from rectilinear worksurfaces. R-Right hand 30" D Right, 24" D left edge	Veneer Group 1 worksurfaces are rift cut Techgrain.
<b>R</b> Right hand	L-Left hand 24" D Right, 30" D left edge	
<b>117</b> Surface finish	All worksurfaces are U.L.-listed.	Veneer Group 2 worksurfaces are quartered Techgrain.
		Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

# Worksurfaces, 1 1/4" VDT corners

Morrison

description	w	d	h	pattern no.	lam.	V1	V2	V3
Corner - Corner grommet only 	35 5/8"	17 5/8"	1 1/4"	<b>MU1-V3618-A()</b>	\$603.	\$725.	\$798.	\$1,171.
	35 5/8"	23 3/8"	1 1/4"	<b>MU1-V3624-A()</b>	618.	739.	812.	1,186.
	41 5/8"	23 5/8"	1 1/4"	<b>MU1-V4224-A()</b>	644.	767.	840.	1,245.
	41 5/8"	29 5/8"	1 1/4"	<b>MU1-V4230-A()</b>	677.	812.	885.	1,304.
	47 5/8"	23 5/8"	1 1/4"	<b>MU1-V4824-A()</b>	761.	915.	955.	1,463.
	47 5/8"	29 5/8"	1 1/4"	<b>MU1-V4830-A()</b>	792.	955.	1,030.	1,537.
Corner - 3 grommets 	35 5/8"	23 3/8"	1 1/4"	<b>MU1-V3624-C()</b>	681.	801.	875.	1,249.
	41 5/8"	23 5/8"	1 1/4"	<b>MU1-V4224-C()</b>	708.	829.	903.	1,308.
	41 5/8"	29 5/8"	1 1/4"	<b>MU1-V4230-C()</b>	739.	875.	946.	1,368.
	47 5/8"	23 5/8"	1 1/4"	<b>MU1-V4824-C()</b>	823.	977.	1,020.	1,529.
	47 5/8"	29 5/8"	1 1/4"	<b>MU1-V4830-C()</b>	854.	1,020.	1,092.	1,601.



Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MU1-V4830-C-117</b>	<i>Grommets/no grommets:</i>	VDT corners may be used interchangeably in desk and panel system applications. They may be supported by VDT end support brackets on each back edge; they may be supported by flat bracket or bridging bracket on each side edge.
<b>MU1</b> Worksurface, 1 1/4" thick	A- VDT corner includes 3" grommet in back corner.	VDT corners are 3/8" less than nominal depth for rear wire clearance or privacy screens.
<b>V</b> VDT corner	C- VDT corner includes 3" grommet in all three back corners.	48" x 24" VDT corners have an inside radius, T-mold front edge that curves into an optimal 45° straight keyboard location.
<b>48</b> Width	Specify surface finish.	Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>30</b> Depth of return	1 1/4" VDT corners are solid core construction with threaded metal inserts at desk support and all bracket locations. All worksurfaces are U.L.-listed.	Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>C</b> Three grommets		Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers
<b>117</b> Surface finish		

# Worksurfaces, 1 1/4"

## *split top straight worksurfaces*

Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 30"D 	Grommets	36"	29 5/8"	1 1/4"	<b>MU1-S36DS-A()</b>	\$1,370.	\$1,481.	\$1,539.	\$1,782.
		42"	29 5/8"	1 1/4"	<b>MU1-S42DS-A()</b>	1,401.	1,507.	1,582.	1,843.
		48"	29 5/8"	1 1/4"	<b>MU1-S48DS-A()</b>	1,427.	1,539.	1,626.	1,903.
Straight, 36"D 	Grommets	36"	35 5/8"	1 1/4"	<b>MU1-S36ES-A()</b>	1,402.	1,520.	1,583.	1,846.
		42"	35 5/8"	1 1/4"	<b>MU1-S42ES-A()</b>	1,432.	1,550.	1,629.	1,910.
		48"	35 5/8"	1 1/4"	<b>MU1-S48ES-A()</b>	1,462.	1,583.	1,679.	1,975.

### Order Code

Example:	<b>MU1-S48DS-A-117</b>
<b>MU1</b>	Worksurface, 1 1/4" thick
<b>S</b>	Straight
<b>48</b>	Width
<b>D</b>	Depth
<b>S</b>	Split top
<b>A</b>	Grommet
<b>117</b>	Surface finish

### Specification Information

*Worksurface Depth:*  
 D- 30"D: 18"D monitor platform and 11" keyboard  
 E- 36"D: 24"D monitor platform and 11" keyboard

*Grommets/no grommets:*  
 A- Grommets in back corners of straight tops.  
 Specify surface finish.

1 1/4" worksurfaces are solid core construction with threaded metal inserts at desk support and all bracket locations. All worksurfaces are U.L.-listed.

### Application Notes

Split top worksurfaces include counterbalanced adjustable keyboard/ mouse support with fingertip control.

Front surface adjusts from 5" below back surface to 7" above, and adjusts in tilt from -10° to +10°.

Split top surfaces may be panel supported or desk supported with standard Morrison brackets.

Specify 18"D cantilever brackets with 30"D straight and 24"D cantilever brackets with 36"D straight split tops.



Veneer Group 1 worksurfaces are quartered Techgrain®.

Veneer Group 2 worksurfaces are rift cut Techgrain®.

Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers

# Worksurfaces, 1 1/4" split top VDT corners

Morrison





description	type	w	d	h	pattern no.	lam.	V1	V2	V3
VDT corner 	Corner grommet only	41 5/8"	23 5/8"	1 1/4"	<b>MU1-V42SS-A( )</b>	\$1,632.	\$1,754.	\$1,829.	\$2,233.
		47 5/8"	23 5/8"	1 1/4"	<b>MU1-V48SS-A( )</b>	1,749.	1,903.	1,945.	2,453.
		47 5/8"	29 5/8"	1 1/4"	<b>MU1-V48DS-A( )</b>	1,778.	1,945.	2,018.	2,525.
VDT corner 	3 grommets	41 5/8"	23 5/8"	1 1/4"	<b>MU1-V42SS-C( )</b>	1,695.	1,818.	1,892.	2,297.
		47 5/8"	23 5/8"	1 1/4"	<b>MU1-V48SS-C( )</b>	1,812.	1,967.	2,008.	2,515.
		47 5/8"	29 5/8"	1 1/4"	<b>MU1-V48DS-C( )</b>	1,843.	2,008.	2,082.	2,588.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MU1-V48SS-A-117</b>	<i>VDT Corner Depth:</i>	Split top worksurfaces include counterbalanced adjustable keyboard/ mouse support with fingertip control.
<b>MU1</b> Worksurface, 1 1/4" thick	S- 24"D sides	
<b>V</b> VDT corner	D- 30"D sides	48"W split-top VDT corners must be supported by VDT-end support kits in conjunction with cantilever brackets at side edges.
<b>48</b> Width	<i>Grommets/no grommets:</i>	
<b>S</b> Depth	A- Grommets in back corners of straight tops, one back corner of VDT	Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>S</b> Split top	C- Grommets in all three back corners of VDT	Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>A</b> Grommet	Specify surface finish.	Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.
<b>117</b> Surface finish	1 1/4" VDT corners are solid core construction with threaded metal inserts at desk support and all bracket locations. All worksurfaces are U.L.-listed.	
		Split top surfaces may be panel supported or desk supported with standard Morrison brackets.
		Specify 18"D cantilever brackets with 23 5/8" split corners, and 24"D cantilever or bridging brackets with 29 5/8" D split corners.

# Worksurfaces, 1 1/4" rounded end worksurfaces






Morrison

description	w	d	h	pattern no.	paint	lam.	V1	V2	V3
30"D rounded end - End grommets 	63"	30"	1 1/4"	<b>MU1-R6330E( )</b>		\$941.	\$1,202.	\$1,321.	\$1,945.
	75"	30"	1 1/4"	<b>MU1-R7530E( )</b>		972.	1,246.	1,365.	1,988.
30"D rounded end - Recessed grommets 	62 5/8"	30"	1 1/4"	<b>MU1-R6330R( )(L/R)</b>		941.	1,202.	1,321.	1,945.
	74 5/8"	30"	1 1/4"	<b>MU1-R7530R( )(L/R)</b>		972.	1,246.	1,365.	1,988.
30"D rounded end - No grommets 	62 5/8"	30"	1 1/4"	<b>MU1-R6330B( )(L/R)</b>		877.	1,136.	1,257.	1,881.
	74 5/8"	30"	1 1/4"	<b>MU1-R7530B( )(L/R)</b>		908.	1,181.	1,299.	1,924.
Support column 	5"	-	27"	<b>MM2-L26( )</b>		146.			

Order Code	Specification Information	Application Notes
Example: <b>MU1-R6330E-117</b>	<i>Grommets/no grommets:</i>	Plastic laminate worksurfaces have radiused T mold edge and a flat self-edge in the straight edge.
<b>MU1</b> Worksurface, 1 1/4" thick	E- rounded end worksurface includes 3" grommet in each straight end corner.	
<b>R</b> Rounded end	R- rounded end worksurface includes 3" grommets recessed for use with 6" recessed desk support.	
<b>63</b> Width	B- rounded end worksurface does not include grommets	
<b>30</b> Depth	Specify surface finish.	Rounded end worksurfaces are used interchangeably in desk and panel system applications as main surfaces or extensions. They may be supported by 30" end support brackets, 30" cantilever bracket, 30" flat bracket or 30" conference end panel, and by a support column at the rounded end.  Use 18"D pedestal or end panel with desk support under rounded end worksurfaces with recessed grommets. Use 48"D desk support with 63" rounded end and 60"W desk support with 75" rounded end.  Worksurfaces with end grommets may not be supported by conference end panel.  Suspended pedestals may not be used with 1 1/4" worksurfaces.  Rounded end worksurfaces have threaded metal inserts for desk support, end panel each end, and at all bracket locations. End grommet worksurfaces have no pedestal inserts.
<b>E</b> End grommets	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations..	
<b>117</b> Surface finish	All worksurfaces are U.L.-listed.	
	End grommeted tops have inserts to accept desk support at straight end and no pedestal inserts.	

# Worksurfaces, 1 1/4" conference shapes

Morrison

description	type	w	d	h	pattern no.	paint	lam.	V1	V2	V3
Half round - Standard		30"	48"	1 1/4"	<b>MU1-R3048-B-()</b>		\$642.	\$797.	\$924.	\$1,315.
										
Half round - Extended		42"	48"	1 1/4"	<b>MU1-R4248-B-()</b>		761.	940.	1,090.	1,550.
										
Half round - With vertical panel		30"	50 3/8"	1 1/4"	<b>MU1-R3050-B-()</b>		712.	877.	1,015.	1,448.
										
Teardrop	24" return	42"	24"	1 1/4"	<b>MU1-T4224-B-()</b>		668.	825.	955.	1,363.
	30" return	48"	30"	1 1/4"	<b>MU1-T4830-B-()</b>		855.	1,056.	1,222.	1,742.
										
Support column		5"	-	27"	<b>MM2-L26()</b>		146.			
										

Worksurface Planning

## Order Code

Example:	<b>MU1-R3050B-117</b>
<b>MU1</b>	Worksurface, 1 1/4" thick
<b>R</b>	Rounded end
<b>30</b>	Width
<b>50</b>	Depth
<b>B</b>	No grommet
<b>117</b>	Surface finish

## Specification Information

*Grommets/no grommets:*  
B- worksurface does not include grommets.

Specify surface finish.

1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.

Plastic laminate worksurfaces have radiused T mold edge.

All worksurfaces are U.L.-listed.

## Application Notes




Half-round and extended half-round are used with back-to-back 24"D straight or VDT corner worksurfaces. Half round with vertical panel attaches to 24"D straight or VDT corner worksurfaces supported by vertical panel.

Conference worksurfaces must be supported by support column and flat bracket or bridging bracket to adjacent worksurface.

# Worksurfaces, 1 1/4"

## P-shape curvilinear

Morrison

description	type	w	d	h	pattern no.	paint	lam.	V1	V2	V3
Rounded end left 	24"D return	48"	72"	1 1/4"	<b>MU1-P72SA( )L</b>		\$1,636.	\$1,963.	\$2,122.	\$2,973.
	30"D return	48"	78"	1 1/4"	<b>MU1-P78DA( )L</b>		1,704.	2,046.	2,214.	3,099.
Rounded end right 	24"D return	48"	72"	1 1/4"	<b>MU1-P72SA( )R</b>		1,636.	1,963.	2,122.	2,973.
	30"D return	48"	78"	1 1/4"	<b>MU1-P78DA( )R</b>		1,704.	2,046.	2,214.	3,099.
Rounded end support column 		5"	-	27"	<b>MM2-L26-( )</b>		146.			

### Order Code

Example: <b>MU1-P72SA-117L</b>
<b>MU1</b> Worksurface, 1 1/4"
<b>P</b> P-shape curvilinear
<b>72</b> Overall length
<b>S</b> Depth of return
<b>A</b> Grommets
<b>117</b> Surface finish
<b>L</b> Rounded end left

### Specification Information

S-	24"D side edge
D-	30"D side edge
	Specify surface finish.
	1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support and all bracket locations.
	All worksurfaces are U.L.-listed.
	All P-shape worksurfaces have 2 grommets at 48" end for use with 48" desk and overhead supports.

### Application Notes

P-shape curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by a 48" VDT support bracket kit, or 48" desk support and 6" end panel, in conjunction with rounded end support column. Use flat bracket or bridging bracket to join to adjacent 1 1/4" worksurface.

P-shape laminate surfaces have continuous T-mold edge in profile to match adjacent 1 1/4" worksurfaces.

Veneer Group 1 worksurfaces are quartered Techgrain®.





Veneer Group 2 worksurfaces are rift cut Techgrain®.

Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.



# Worksurfaces, 1 1/4" L-shape curvilinear

Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
24"D returns left and right 	3 grommets	42"	42"	1 1/4"	<b>MU1-C4242SS( )</b>	\$748.	\$900.	\$973.	\$1,364.
		48"	48"	1 1/4"	<b>MU1-C4848SS( )</b>	817.	980.	1,062.	1,483.
		48"	60"	1 1/4"	<b>MU1-C4860SS( )</b>	927.	1,112.	1,204.	1,685.
		48"	72"	1 1/4"	<b>MU1-C4872SS( )</b>	1,065.	1,282.	1,384.	1,942.
		60"	48"	1 1/4"	<b>MU1-C6048SS( )</b>	927.	1,112.	1,204.	1,685.
		72"	48"	1 1/4"	<b>MU1-C7248SS( )</b>	1,065.	1,282.	1,384.	1,942.
24"D return left, 30"D right 	3 grommets	48"	48"	1 1/4"	<b>MU1-C4848SD( )</b>	817.	980.	1,062.	1,483.
		48"	60"	1 1/4"	<b>MU1-C4860SD( )</b>	927.	1,112.	1,204.	1,685.
		48"	72"	1 1/4"	<b>MU1-C4872SD( )</b>	1,065.	1,282.	1,384.	1,942.
		60"	48"	1 1/4"	<b>MU1-C6048SD( )</b>	927.	1,112.	1,204.	1,685.
		72"	48"	1 1/4"	<b>MU1-C7248SD( )</b>	1,065.	1,282.	1,384.	1,942.
30"D return left, 24"D right 	3 grommets	48"	48"	1 1/4"	<b>MU1-C4848DS( )</b>	817.	980.	1,062.	1,483.
		48"	60"	1 1/4"	<b>MU1-C4860DS( )</b>	927.	1,112.	1,204.	1,685.
		48"	72"	1 1/4"	<b>MU1-C4872DS( )</b>	1,065.	1,282.	1,384.	1,942.
		60"	48"	1 1/4"	<b>MU1-C6048DS( )</b>	927.	1,112.	1,204.	1,685.
		72"	48"	1 1/4"	<b>MU1-C7248DS( )</b>	1,065.	1,282.	1,384.	1,942.
30"D returns left and right 	3 grommets	48"	48"	1 1/4"	<b>MU1-C4848DD( )</b>	817.	980.	1,062.	1,483.



Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MU1-C4860SD-117</b> <b>MU1</b> Worksurface, 1 1/4" <b>C</b> L-shape curvilinear <b>48</b> Width left <b>60</b> Width right <b>S</b> Depth of left return <b>D</b> Depth of right return <b>117</b> Surface finish	Width dimension (W) refers to width of left-side back edge; depth dimension (D) indicates width of right-side back edge. S- 24"D side edge D- 30"D side edge  Specify surface finish.  1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support and all bracket locations.  All worksurfaces are U.L.-listed.  All L-shape curvilinear worksurfaces have three grommets.	Veneer Group 1 worksurfaces are quartered Techgrain®.  Veneer Group 2 worksurfaces are rift cut Techgrain®.  Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.  L-shape curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by corner desk supports or by VDT end support bracket kit. Use cantilever bridging brackets or flat brackets to join to adjacent worksurfaces.  L-shape surfaces may also be supported by MN1- end panel in conjunction with desk support, or cantilever bracket in panel planning.  L-shape surfaces are veneer or post-formed plastic laminate on both back edges, matching profile T-mold on curvilinear front, and self-edge on sides.  Curvilinear worksurfaces are available only in 1 1/4" thickness.  L-shape surfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.  If specifying privacy screens on both back edges, one or both must be 48" back-of-VDT type.

# Worksurfaces, 1 1/4"

## J-shape surfaces

Morrison



description	w	d	h	pattern no.	paint	lam.
J-shape - Rounded left 	30"	23 5/8"	1 1/4"	<b>MU1-J30A( )L</b>		\$584.
	36"	23 5/8"	1 1/4"	<b>MU1-J36A( )L</b>		628.
	42"	23 5/8"	1 1/4"	<b>MU1-J42A( )L</b>		668.
	48"	23 5/8"	1 1/4"	<b>MU1-J48A( )L</b>		709.
J-shape - Rounded right 	30"	23 5/8"	1 1/4"	<b>MU1-J30A( )R</b>		584.
	36"	23 5/8"	1 1/4"	<b>MU1-J36A( )R</b>		628.
	42"	23 5/8"	1 1/4"	<b>MU1-J42A( )R</b>		668.
	48"	23 5/8"	1 1/4"	<b>MU1-J48A( )R</b>		709.

Order Code	Specification Information	Application Notes
Example: <b>MU1-J48A177-L</b>		
<b>MU1</b> Worksurface, 1 1/4"	1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support and all bracket locations and pilot holes at pedestal locations.	J-shape curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by straight desk support or cantilever brackets. J-shapes also require 9" Network end panel in desk or panel planning.
<b>J</b> J-shape	Specify surface finish.	
<b>48</b> Width	All worksurfaces are U.L.-listed.	
<b>A</b> With grommets	J-shape worksurfaces have 2 grommets for use with freestanding desk and overhead supports.	Use flat bracket or bridging bracket to join to adjacent 1 1/4" worksurface. Also specify VDT end support bracket kit for optimal stability of vertical panel behind J-shape worksurface.
<b>117</b> Surface finish		J-shape surfaces are post-formed on back edge, matching profile T-mold on curvilinear front, and self-edge on sides.
<b>L</b> Left		J-shapes are available only in plastic laminate, 1 1/4" thickness.
		J-shape surfaces are 3/8" less than nominal depth for wire clearance or privacy screens.

# Worksurfaces, 1 1/4"

## Wave-end surfaces

Morrison

description	w	d	h	pattern no.	lam.
Left wave-end 	36"	29 5/8"	1 1/4"	<b>MU1-W36A( )L</b>	\$709.
	42"	29 5/8"	1 1/4"	<b>MU1-W42A( )L</b>	748.
	48"	29 5/8"	1 1/4"	<b>MU1-W48A( )L</b>	792.
Right wave-end 	36"	29 5/8"	1 1/4"	<b>MU1-W36A( )R</b>	709.
	42"	29 5/8"	1 1/4"	<b>MU1-W42A( )R</b>	748.
	48"	29 5/8"	1 1/4"	<b>MU1-W48A( )R</b>	792.





Order Code	Specification Information	Application Notes
Example: <b>MU1-W48A117-L</b> <b>MU1</b> Worksurface, 1 1/4" <b>W</b> Wave-end curvilinear <b>48</b> Width <b>A</b> With grommets <b>117</b> Surface finish <b>L</b> Left	1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support, and all bracket locations and pilot holes at pedestal locations.  Specify surface finish.  All worksurfaces are U.L.-listed.  Wave-end worksurfaces have 2 grommets for use with freestanding desk and overhead supports.	Wave-end curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by straight desk support or cantilever brackets.  Use flat bracket or bridging bracket to join to adjacent 1 1/4" worksurface.  Wave-end surfaces are post-formed on back edge, matching profile T-mold on curvilinear front, and self-edge on sides.  Wave-end surfaces are available only in plastic laminate, 1 1/4" thickness.  Wave-end surfaces are nominal 30"D at left or right, and align with 24"D surface at the other end. Inserts for 24"D pedestal are standard at the wave end.  Wave-end surfaces are 3/8" less than nominal depth for wire clearance or privacy screens.

# Worksurfaces, 1 1/4"

Morrison

## 120° corners

### 90° return

description	w	return	h	pattern no.	lam.	V1	V2	V3
90° return Right hand - grommet 	36"	24"	1 1/4"	<b>MU1-Y36S-AR-( )()</b>	\$563.	\$787.	\$797.	\$969.
	42"	24"	1 1/4"	<b>MU1-Y42S-AR-( )()</b>	594.	954.	964.	1,274.
	48"	24"	1 1/4"	<b>MU1-Y48S-AR-( )()</b>	660.	1,051.	1,061.	1,594.
	60"	24"	1 1/4"	<b>MU1-Y60S-AR-( )()</b>	802.	n/a	n/a	n/a
90° return Left hand - grommet 	36"	24"	1 1/4"	<b>MU1-Y36S-AL-( )()</b>	563.	787.	797.	969.
	42"	24"	1 1/4"	<b>MU1-Y42S-AL-( )()</b>	594.	954.	964.	1,274.
	48"	24"	1 1/4"	<b>MU1-Y48S-AL-( )()</b>	660.	1,051.	1,061.	1,594.
	60"	24"	1 1/4"	<b>MU1-Y60S-AL-( )()</b>	802.	n/a	n/a	n/a
90° return - no grommet 	36"	24"	1 1/4"	<b>MU1-Y36S-B-( )()</b>	543.	766.	776.	949.
	42"	24"	1 1/4"	<b>MU1-Y42S-B-( )()</b>	573.	934.	944.	1,254.
	48"	24"	1 1/4"	<b>MU1-Y48S-B-( )()</b>	639.	1,030.	1,040.	1,573.
	60"	24"	1 1/4"	<b>MU1-Y60S-B-( )()</b>	782.	n/a	n/a	n/a
Transitional 	24"		1 1/4"	<b>MU1-YTS-( )()</b>	447.	581.	592.	769.

#### Order Code

Example: <b>MU1-Y48S-A-R-L-117</b>
<b>MU1</b> Worksurface, 1 1/4" thick
<b>Y</b> 120° corner, 90° returns
<b>48</b> Width
<b>S</b> 24"D return
<b>A</b> Grommets
<b>R</b> Right hand
<b>L</b> Laminate
<b>117</b> Surface finish

#### Specification Information

Width dimension (w) refers to width of both back edges.

Specify surface finish.

1 1/4" worksurfaces are solid core construction with threaded metal inserts at desk supports and all standard bracket locations.

Grommets/no grommets:

A- worksurface includes 2 grommets in 2 back corners, creating Left- and Right-hand applications (see illustration).

B- worksurface does not include grommets. Worksurfaces with no grommets are not handed.

#### Application Notes

Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

120° worksurfaces with 90° returns are used mainly in panel system applications. They can be supported at each end with 24" end support brackets, 24" cantilever bracket, 24"W end panel, 18"D and 24"D pedestal or end panel in conjunction with desk supports.

120° corner is supported by a standard (90°) 24"D cantilever bracket.

Use cantilever bridging brackets to join to adjacent worksurface or to transitional 120° worksurface.

Transitional worksurfaces connect two 120° corner tops with 90° returns.





Veneer Group 1 worksurfaces are quartered Techgrain®.

Veneer Group 2 worksurfaces are rift cut Techgrain®.

Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

120° corners



Meeting corners

description	w	return	h	pattern no.	lam.	V1	V2	V3
Meeting corner Right hand - grommet	48"	24"	1 1/4"	<b>MU1-M48S-AR-( ) ( )</b>	\$680.	n/a	n/a	n/a
								
Meeting corner Left hand - grommet	48"	24"	1 1/4"	<b>MU1-M48S-AL-( ) ( )</b>	680.	n/a	n/a	n/a
								
Meeting corner Right hand - no grommet	48"	24"	1 1/4"	<b>MU1-M48S-BR-( ) ( )</b>	660.	n/a	n/a	n/a
								
Meeting corner Left hand - no grommet	48"	24"	1 1/4"	<b>MU1-M48S-BL-( ) ( )</b>	660.	n/a	n/a	n/a
								

Order Code	Specification Information	Application Notes
Example: <b>MU1-M48S-A-L-L-117</b>		
<b>MU1</b> Worksurface, 1 1/4" thick	Width dimension (w) refers to width of smaller back edge. Total width of back edge with rounded meeting area is 62 1/2".	Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
<b>M</b> Meeting corner		120° meeting worksurfaces are used mainly in panel system applications. Support at the rounded meeting end with a Morrison support column, specified separately. They can be supported at the other end by 24" end support brackets, 24" cantilever bracket, 24"W end panel, 18"D and 24"D pedestal or end panel in conjunction with desk supports. Morrison Network straight desk support may be used under the 48W back edge.
<b>48</b> Width	Specify surface finish.	120° corner is supported by 24"D cantilever bracket.
<b>S</b> 24"D return		Use 24"D cantilever bridging brackets to join to adjacent worksurfaces.
<b>A</b> Grommets	1 1/4" worksurfaces are solid core construction with threaded metal inserts at desk supports and all standard bracket locations.	Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>L</b> Left hand		Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>L</b> Laminate	Grommets/no grommets:	Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.
<b>117</b> Surface finish	A- worksurface includes 2 grommets in 2 back corners. B- worksurface does not include grommets.	

# Morrison Options worksurfaces, 1 1/4" 18"D



Morrison

description	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 18"D - Grommet 	30"	17 3/8"	1 1/4"	LU1-S3018-A-( )	\$192.	\$266.	\$322.	\$481.
	36"	17 3/8"	1 1/4"	LU1-S3618-A-( )	203.	287.	335.	509.
	42"	17 3/8"	1 1/4"	LU1-S4218-A-( )	227.	319.	375.	577.
	48"	17 3/8"	1 1/4"	LU1-S4818-A-( )	252.	355.	397.	615.
	54"	17 3/8"	1 1/4"	LU1-S5418-A-( )	275.	381.	437.	668.
	60"	17 3/8"	1 1/4"	LU1-S6018-A-( )	300.	406.	475.	737.
	66"	17 3/8"	1 1/4"	LU1-S6618-A-( )	323.	429.	526.	817.
	72"	17 3/8"	1 1/4"	LU1-S7218-A-( )	347.	454.	579.	885.
	78"	17 3/8"	1 1/4"	LU1-S7818-A-( )	371.	482.	609.	931.
	84"	17 3/8"	1 1/4"	LU1-S8418-A-( )	395.	509.	638.	979.
	90"	17 3/8"	1 1/4"	LU1-S9018-A-( )	420.	538.	681.	1,043.
	96"	17 3/8"	1 1/4"	LU1-S9618-A-( )	444.	563.	719.	1,102.
	108"	17 3/8"	1 1/4"	LU1-S10818-A-( )	479.	602.	769.	1,179.
120"	17 3/8"	1 1/4"	LU1-S12018-A-( )	526.	653.	830.	1,278.	
Straight, 18"D - No grommet 	30"	17 3/8"	1 1/4"	LU1-S3018-B-( )	167.	242.	298.	458.
	36"	17 3/8"	1 1/4"	LU1-S3618-B-( )	181.	265.	311.	484.
	42"	17 3/8"	1 1/4"	LU1-S4218-B-( )	203.	295.	350.	552.
	48"	17 3/8"	1 1/4"	LU1-S4818-B-( )	228.	333.	375.	592.
	54"	17 3/8"	1 1/4"	LU1-S5418-B-( )	252.	358.	415.	646.
	60"	17 3/8"	1 1/4"	LU1-S6018-B-( )	276.	384.	452.	713.
	66"	17 3/8"	1 1/4"	LU1-S6618-B-( )	300.	405.	503.	793.
	72"	17 3/8"	1 1/4"	LU1-S7218-B-( )	323.	429.	554.	861.
	78"	17 3/8"	1 1/4"	LU1-S7818-B-( )	348.	459.	586.	906.
	84"	17 3/8"	1 1/4"	LU1-S8418-B-( )	371.	484.	616.	955.
	90"	17 3/8"	1 1/4"	LU1-S9018-B-( )	396.	514.	658.	1,019.
	96"	17 3/8"	1 1/4"	LU1-S9618-B-( )	420.	540.	695.	1,079.
	108"	17 3/8"	1 1/4"	LU1-S10818-B-( )	457.	579.	745.	1,155.
120"	17 3/8"	1 1/4"	LU1-S12018-B-( )	503.	628.	808.	1,255.	

Order Code	Specification Information	Application Notes
Example: <b>LU1-S4818-B-117</b>	<i>Grommet/no grommet:</i>	18"D worksurfaces are used in panel system applications as shallow main surfaces, extensions or credenza tops. They may be supported at each end by an 18" end support bracket, 18" cantilever bracket, 18"W desk end panel or 18"D pedestal.
<b>LU1</b> Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	
<b>S</b> Straight worksurface	B- worksurface does not include grommet	Options worksurfaces cannot be used in conjunction with Network desk supports.
<b>48</b> Width		
<b>18</b> Depth	Specify surface finish.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
<b>B</b> No grommet	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	
<b>117</b> Surface finish	Edge grommets are centered at rear of worksurface.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
		Panel-supported 1 1/4" worksurfaces over 96" must be pedestal or MB2-C24 cantilever bracket supported every 48".
		Suspended pedestals may not be used with 1 1/4" worksurfaces.

# Morrison Options worksurfaces, 1 1/4" 24"D

Morrison



description	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 24"D - Grommet 	24"	23 3/8"	1 1/4"	LU1-S2424-A-( )	\$215.	\$305.	\$388.	\$561.
	30"	23 3/8"	1 1/4"	LU1-S3024-A-( )	227.	313.	401.	576.
	36"	23 3/8"	1 1/4"	LU1-S3624-A-( )	240.	331.	417.	588.
	42"	23 3/8"	1 1/4"	LU1-S4224-A-( )	264.	353.	430.	627.
	48"	23 3/8"	1 1/4"	LU1-S4824-A-( )	286.	393.	463.	711.
	54"	23 3/8"	1 1/4"	LU1-S5424-A-( )	312.	430.	514.	775.
	60"	23 3/8"	1 1/4"	LU1-S6024-A-( )	336.	455.	539.	815.
	66"	23 3/8"	1 1/4"	LU1-S6624-A-( )	360.	509.	595.	897.
	72"	23 3/8"	1 1/4"	LU1-S7224-A-( )	384.	520.	631.	980.
	78"	23 3/8"	1 1/4"	LU1-S7824-A-( )	406.	553.	651.	1,022.
	84"	23 3/8"	1 1/4"	LU1-S8424-A-( )	431.	606.	707.	1,076.
	90"	23 3/8"	1 1/4"	LU1-S9024-A-( )	456.	640.	753.	1,144.
	96"	23 3/8"	1 1/4"	LU1-S9624-A-( )	479.	679.	796.	1,210.
	108"	23 3/8"	1 1/4"	LU1-S10824-A-( )	526.	719.	845.	1,294.
120"	23 3/8"	1 1/4"	LU1-S12024-A-( )	576.	787.	923.	1,403.	
Straight, 24"D - No grommet 	24"	23 3/8"	1 1/4"	LU1-S2424-B-( )	192.	280.	363.	539.
	30"	23 3/8"	1 1/4"	LU1-S3024-B-( )	203.	289.	378.	551.
	36"	23 3/8"	1 1/4"	LU1-S3624-B-( )	217.	308.	393.	564.
	42"	23 3/8"	1 1/4"	LU1-S4224-B-( )	240.	331.	406.	603.
	48"	23 3/8"	1 1/4"	LU1-S4824-B-( )	264.	368.	438.	687.
	54"	23 3/8"	1 1/4"	LU1-S5424-B-( )	287.	406.	491.	751.
	60"	23 3/8"	1 1/4"	LU1-S6024-B-( )	312.	430.	516.	791.
	66"	23 3/8"	1 1/4"	LU1-S6624-B-( )	337.	484.	571.	874.
	72"	23 3/8"	1 1/4"	LU1-S7224-B-( )	360.	496.	608.	957.
	78"	23 3/8"	1 1/4"	LU1-S7824-B-( )	384.	531.	626.	998.
	84"	23 3/8"	1 1/4"	LU1-S8424-B-( )	407.	583.	683.	1,053.
	90"	23 3/8"	1 1/4"	LU1-S9024-B-( )	431.	619.	732.	1,121.
	96"	23 3/8"	1 1/4"	LU1-S9624-B-( )	457.	656.	772.	1,187.
	108"	23 3/8"	1 1/4"	LU1-S10824-B-( )	503.	695.	821.	1,271.
120"	23 3/8"	1 1/4"	LU1-S12024-B-( )	551.	762.	898.	1,378.	

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>LU1-S3024-B-117</b>	<i>Grommet/no grommet:</i>	24"D worksurfaces are used interchangeably as shallow main surfaces, extensions or credenza tops.
<b>LU1</b> Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	Options worksurfaces cannot be used in conjunction with Network desk supports.
<b>S</b> Straight worksurface	B- worksurface does not include grommet	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
<b>30</b> Width	Specify surface finish.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
<b>24</b> Depth	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	Panel-supported 1 1/4" worksurfaces over 96" must be pedestal or MB2-C24 cantilever bracket supported every 48".
<b>B</b> No grommet	Edge grommets are centered at rear of worksurface.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
<b>117</b> Surface finish		

# Morrison Options worksurfaces, 1 1/4" 30"D

Morrison





description	w	d	h	pattern no.	lam.	V1	V2	V3
Straight, 30"D - Grommets 	30"	29 5/8"	1 1/4"	<b>LU1-S3030-A-()</b>	\$252.	\$340.	\$408.	\$628.
	36"	29 5/8"	1 1/4"	<b>LU1-S3630-A-()</b>	275.	380.	436.	667.
	42"	29 5/8"	1 1/4"	<b>LU1-S4230-A-()</b>	300.	403.	475.	720.
	48"	29 5/8"	1 1/4"	<b>LU1-S4830-A-()</b>	323.	429.	513.	774.
	54"	29 5/8"	1 1/4"	<b>LU1-S5430-A-()</b>	347.	482.	565.	841.
	60"	29 5/8"	1 1/4"	<b>LU1-S6030-A-()</b>	371.	520.	605.	908.
	66"	29 5/8"	1 1/4"	<b>LU1-S6630-A-()</b>	395.	546.	640.	991.
	72"	29 5/8"	1 1/4"	<b>LU1-S7230-A-()</b>	431.	582.	693.	1,055.
	78"	29 5/8"	1 1/4"	<b>LU1-S7830-A-()</b>	456.	619.	725.	1,109.
	84"	29 5/8"	1 1/4"	<b>LU1-S8430-A-()</b>	479.	653.	765.	1,170.
	90"	29 5/8"	1 1/4"	<b>LU1-S9030-A-()</b>	503.	685.	804.	1,220.
	96"	29 5/8"	1 1/4"	<b>LU1-S9630-A-()</b>	526.	719.	845.	1,284.
Straight, 30"D - No grommets 	30"	29 5/8"	1 1/4"	<b>LU1-S3030-B-()</b>	228.	317.	387.	604.
	36"	29 5/8"	1 1/4"	<b>LU1-S3630-B-()</b>	252.	355.	413.	644.
	42"	29 5/8"	1 1/4"	<b>LU1-S4230-B-()</b>	276.	380.	452.	696.
	48"	29 5/8"	1 1/4"	<b>LU1-S4830-B-()</b>	300.	405.	489.	750.
	54"	29 5/8"	1 1/4"	<b>LU1-S5430-B-()</b>	323.	459.	543.	819.
	60"	29 5/8"	1 1/4"	<b>LU1-S6030-B-()</b>	348.	496.	582.	886.
	66"	29 5/8"	1 1/4"	<b>LU1-S6630-B-()</b>	371.	522.	619.	967.
	72"	29 5/8"	1 1/4"	<b>LU1-S7230-B-()</b>	407.	558.	669.	1,031.
	78"	29 5/8"	1 1/4"	<b>LU1-S7830-B-()</b>	431.	596.	703.	1,087.
	84"	29 5/8"	1 1/4"	<b>LU1-S8430-B-()</b>	457.	628.	741.	1,146.
	90"	29 5/8"	1 1/4"	<b>LU1-S9030-B-()</b>	479.	662.	781.	1,198.
	96"	29 5/8"	1 1/4"	<b>LU1-S9630-B-()</b>	503.	695.	821.	1,260.

Order Code	Specification Information	Application Notes
Example: <b>LU1-S3030B-117</b>	<i>Grommets/no grommets:</i>	30"D worksurfaces are used in panel system applications as main surfaces, extensions or credenza tops. They can be supported at each end by 30" end support bracket, 30" cantilever bracket or 30"W end panel.
<b>LU1</b> Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	
<b>S</b> Straight worksurface	B- worksurface does not include grommets	Options worksurfaces cannot be used in conjunction with Network desk supports. All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
<b>30</b> Width	Specify surface finish.	
<b>30</b> Depth	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C24 bracket, specified separately. Suspended pedestals may not be used with 1 1/4" worksurfaces.
<b>B</b> No grommets	Edge grommets are centered at rear of worksurface.	
<b>117</b> Surface finish		



# Morrison Options worksurfaces, 1 1/4" trapezoidal

Morrison

description	w	d	h	pattern no.	lam.	V1	V2	V3
Right hand - grommet 	48"	30"/24"	1 1/4"	<b>LU1-T48A-R-( )</b>	\$406.	\$509.	\$584.	\$818.
	54"	30"/24"	1 1/4"	<b>LU1-T54A-R-( )</b>	517.	646.	742.	1,038.
	60"	30"/24"	1 1/4"	<b>LU1-T60A-R-( )</b>	626.	784.	899.	1,260.
	72"	30"/24"	1 1/4"	<b>LU1-T72A-R-( )</b>	736.	921.	1,058.	1,480.
Left hand - grommet 	48"	24"/30"	1 1/4"	<b>LU1-T48A-L-( )</b>	406.	509.	584.	818.
	54"	24"/30"	1 1/4"	<b>LU1-T54A-L-( )</b>	517.	646.	742.	1,038.
	60"	24"/30"	1 1/4"	<b>LU1-T60A-L-( )</b>	626.	784.	899.	1,260.
	72"	24"/30"	1 1/4"	<b>LU1-T72A-L-( )</b>	736.	921.	1,058.	1,480.
Right hand - no grommet 	48"	30"/24"	1 1/4"	<b>LU1-T48B-R-( )</b>	385.	481.	552.	772.
	54"	30"/24"	1 1/4"	<b>LU1-T54B-R-( )</b>	494.	618.	711.	995.
	60"	30"/24"	1 1/4"	<b>LU1-T60B-R-( )</b>	604.	756.	869.	1,215.
	72"	30"/24"	1 1/4"	<b>LU1-T72B-R-( )</b>	714.	893.	1,025.	1,435.
Left hand - no grommet 	48"	24"/30"	1 1/4"	<b>LU1-T48B-L-( )</b>	385.	481.	552.	772.
	54"	24"/30"	1 1/4"	<b>LU1-T54B-L-( )</b>	494.	618.	711.	995.
	60"	24"/30"	1 1/4"	<b>LU1-T60B-L-( )</b>	604.	756.	869.	1,215.
	72"	24"/30"	1 1/4"	<b>LU1-T72B-L-( )</b>	714.	893.	1,025.	1,435.

## Order Code

Example: <b>LU1-T48B-R-117</b>
<b>LU1</b> Worksurface, 1 1/4" thick
<b>T</b> Trapezoidal
<b>48</b> Width
<b>B</b> No grommets
<b>R</b> Right hand
<b>117</b> Surface finish

## Specification Information

*Grommets/ no grommets*  
 A- worksurface includes one edge grommet  
 B- worksurface does not include grommets

Specify surface finish.

Edge grommets are centered at rear of worksurface. Right-and-Left and are defined by applying trapezoidal tops as returns from rectilinear worksurfaces.  
 R- Right hand  
 30" D Right, 24" D Left edge  
 L- Left hand  
 24" D Right, 30" D Left edge

## Application Notes

Veneer Group 1 worksurfaces are rift cut Techgrain.  
 Veneer Group 2 worksurfaces are quartered Techgrain.  
 Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

1 1/4" Options worksurfaces are 3-ply solid core construction with pilot holes at all pedestal, end panel and bracket locations.

Trapezoidal worksurfaces must be supported at each end by a pedestal, cantilever or cantilever bridging bracket with a maximum span of 48" between supports. Panel-supported worksurfaces over 48" must be mid-span supported by MB2-C18 brackets, specified separately.




Options worksurfaces cannot be used in conjunction with Network desk supports.

All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

# Morrison Options worksurfaces, 1 1/4"

## VDT corners and split-top surfaces

Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Corner 	Corner grommet only	36"	17 5/8"	1 1/4"	<b>LU1-V3618-A( )</b>	\$457.	\$573.	\$640.	\$997.
		36"	23 5/8"	1 1/4"	<b>LU1-V3624-A( )</b>	468.	583.	654.	1,009.
		42"	23 5/8"	1 1/4"	<b>LU1-V4224-A( )</b>	492.	608.	678.	1,063.
		42"	29 5/8"	1 1/4"	<b>LU1-V4230-A( )</b>	517.	646.	715.	1,114.
		48"	23 5/8"	1 1/4"	<b>LU1-V4824-A( )</b>	577.	720.	762.	1,245.
		48"	29 5/8"	1 1/4"	<b>LU1-V4830-A( )</b>	600.	762.	827.	1,311.
Split top corner 	Corner grommet only	42"	23 5/8"	1 1/4"	<b>LU1-V42SS-A( )</b>	1,423.	1,537.	1,605.	1,982.
		48"	23 5/8"	1 1/4"	<b>LU1-V48SS-A( )</b>	1,505.	1,647.	1,687.	2,162.
		48"	29 5/8"	1 1/4"	<b>LU1-V48DS-A( )</b>	1,530.	1,684.	1,752.	2,226.
Split top straight 	Center grommet	36"	29 5/8"	1 1/4"	<b>LU1-S36DS-A( )</b>	1,211.	1,314.	1,369.	1,596.
		42"	29 5/8"	1 1/4"	<b>LU1-S42DS-A( )</b>	1,235.	1,338.	1,406.	1,647.
		48"	29 5/8"	1 1/4"	<b>LU1-S48DS-A( )</b>	1,259.	1,363.	1,445.	1,700.

### Order Code

Example:	<b>LU1-V4830-A-117</b>
<b>LU1</b>	Worksurface, 1 1/4" thick
<b>V</b>	VDT corner
<b>48</b>	Width
<b>30</b>	Depth of return
<b>A</b>	Corner grommet
<b>117</b>	Specify finish

### Specification Information

*Grommet/no grommet:*  
 A- VDT corner includes one edge grommet in back corner. Straight split top has one center back edge grommet.  
 Specify surface finish.  
 1 1/4" Options worksurfaces are solid core construction with pilot holes at all bracket locations.

### Application Notes

VDT corners and split top straight surfaces are used in panel system applications. Options VDT corners may be supported by left or right hand 24" cantilever brackets at the rear corner, and cantilever bridging bracket on each side edge (see page 157).

Options straight split top should be supported by 18"D cantilever bracket.

48"W split-top corners must be supported by VDT- end support brackets kits in conjunction with cantilever brackets at side edges.

Options worksurfaces cannot be used in conjunction with Morrison Network desk supports.

36"W x 18"D VDT corners accept 18"D returns, 36", 42", and 48"W x 24"D VDT corners accept 24"D returns, 42" and 48"W x 30"D VDT corners accept 30"D returns.





VDT corners are 3/8" less than nominal depth for rear wire clearance.

Split top corners have counterbalanced adjustable keyboard/mouse surface with fingertip control. Front surface adjusts from 5" below to 7" above back surface, and adjusts in tilt from -10° to +10°.

# Morrison Options worksurfaces, 1 1/4"

## L-shape curvilinear

Morrison





description	type	w	d	h	pattern no.	lam.	V1	V2	V3	
24"D returns left and right 	2 grommets	48"	60"	1 1/4"	<b>LU1-C4860SS( )</b>	\$706.	\$882.	\$969.	\$1,427.	
		48"	72"	1 1/4"	<b>LU1-C4872SS( )</b>	812.	1,015.	1,115.	1,644.	
		60"	48"	1 1/4"	<b>LU1-C6048SS( )</b>	706.	882.	969.	1,427.	
		72"	48"	1 1/4"	<b>LU1-C7248SS( )</b>	812.	1,015.	1,115.	1,644.	
	Corner grommet	42"	42"	1 1/4"	<b>LU1-C4242SS( )</b>	571.	714.	785.	1,154.	
		48"	48"	1 1/4"	<b>LU1-C4848SS( )</b>	623.	777.	856.	1,257.	
	24"D return left, 30"D right 	2 grommets	48"	60"	1 1/4"	<b>LU1-C4860SD( )</b>	706.	882.	969.	1,427.
			48"	72"	1 1/4"	<b>LU1-C4872SD( )</b>	812.	1,015.	1,115.	1,644.
60"			48"	1 1/4"	<b>LU1-C6048SD( )</b>	706.	882.	969.	1,427.	
72"			48"	1 1/4"	<b>LU1-C7248SD( )</b>	812.	1,015.	1,115.	1,644.	
Corner grommet		48"	48"	1 1/4"	<b>LU1-C4848SD( )</b>	623.	777.	856.	1,257.	
30"D return left, 24"D right 		2 grommets	48"	60"	1 1/4"	<b>LU1-C4860DS( )</b>	706.	882.	969.	1,427.
			48"	72"	1 1/4"	<b>LU1-C4872DS( )</b>	812.	1,015.	1,115.	1,644.
			60"	48"	1 1/4"	<b>LU1-C6048DS( )</b>	706.	882.	969.	1,427.
	72"		48"	1 1/4"	<b>LU1-C7248DS( )</b>	812.	1,015.	1,115.	1,644.	
	Corner grommet	48"	48"	1 1/4"	<b>LU1-C4848DS( )</b>	623.	777.	856.	1,257.	
	30"D returns left and right	Corner grommet	48"	48"	1 1/4"	<b>LU1-C4848DD( )</b>	623.	777.	856.	1,257.
										

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>LU1-C4860SD-117</b>		
<b>LU1</b> Options worksurface, 1 1/4"	Width dimension (W) refers to width of left-side back edge; depth dimension (D) indicates width of right-side back edge.	Options L-shaped curvilinear worksurfaces may be supported by left- or right-hand cantilever brackets at the rear corner and cantilever bridging bracket on each side edge. Use mid-span support whenever Options worksurfaces span more than 48".
<b>C</b> L-shape curvilinear	S- 24"D side edge	
<b>48</b> Width left	D- 30"D side edge	
<b>60</b> Width right	Specify surface finish.	
<b>S</b> Depth of left return	1 1/4" curvilinear surfaces are solid core construction with pilot holes at all bracket locations.	
<b>D</b> Depth of right return		
<b>117</b> Surface finish		L-shape surfaces are veneer or post-formed plastic laminate on both back edges, matching profile T-mold on curvilinear front, and self-edge on sides.
		Curvilinear worksurfaces are available only in 1 1/4" thickness.
		L-shape surfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

# Morrison Options worksurfaces, 1 1/4" rounded end and conference shapes

Morrison

description	type	w	d	h	pattern no.	paint	lam.	V1	V2	V3
30"D rounded end 	No grommets	62 3/8"	30"	1 1/4"	<b>LU1-R6330B( ) (L/R)</b>		\$667.	\$915.	\$1,028.	\$1,632.
	No grommets	74 3/8"	30"	1 1/4"	<b>LU1-R7530B( ) (L/R)</b>		691.	952.	1,064.	1,659.
Half round 	With vertical panel	30"	50 3/8"	1 1/4"	<b>LU1-R3050-B( )</b>		491.	635.	756.	1,130.
Teardrop 	24" return	42"	24"	1 1/4"	<b>LU1-T4224-B( )</b>		510.	660.	784.	1,172.
	30" return	48"	30"	1 1/4"	<b>LU1-T4830-B( )</b>		653.	844.	1,001.	1,497.
Support column 		5"	-	27"	<b>MM2-L26( )</b>		146.			

## Order Code

Example:	<b>LU1-R6330B-117-L</b>
<b>LU1</b>	Options worksurface, 1 1/4" thick
<b>R</b>	Rounded end
<b>63</b>	Width
<b>30</b>	Depth
<b>B</b>	No grommets
<b>117</b>	Surface finish
<b>L</b>	Left hand

## Specification Information

*Grommets/no grommets:*  
 B- worksurface does not include grommets.  
 Specify surface finish.  
 1 1/4" worksurfaces are 3-ply, solid core construction. Plastic laminate worksurfaces have radiused T mold edge.  
 Rounded end worksurfaces have a flat self-edge in the straight end.





## Application Notes

Rounded end worksurfaces may be supported by 30" end support brackets, 30" flat bracket or 30" conference end panel, and by a support column at the rounded end.  
 Suspended pedestals may not be used with 1 1/4" worksurfaces.  
 Conference worksurfaces must be supported by support column and flat bracket or bridging bracket to adjacent desk.  
 Half round with vertical panel attaches to 24"D straight or VDT corner worksurfaces supported by vertical panel.

# Morrison Options worksurfaces, 1 1/4"

## Wave-end surfaces

Morrison




description	w	d	h	pattern no.	lam
Left wave-end - Grommet 	36"	29 3/8"	1 1/4"	<b>LU1-W36AL()</b>	\$586.
	42"	29 3/8"	1 1/4"	<b>LU1-W42AL()</b>	623.
	48"	29 3/8"	1 1/4"	<b>LU1-W48AL()</b>	659.
Left wave-end - No grommet 	36"	29 3/8"	1 1/4"	<b>LU1-W36BL()</b>	576.
	42"	29 3/8"	1 1/4"	<b>LU1-W42BL()</b>	611.
	48"	29 3/8"	1 1/4"	<b>LU1-W48BL()</b>	649.
Right wave-end - Grommet 	36"	29 3/8"	1 1/4"	<b>LU1-W36AR()</b>	586.
	42"	29 3/8"	1 1/4"	<b>LU1-W42AR()</b>	623.
	48"	29 3/8"	1 1/4"	<b>LU1-W48AR()</b>	659.
Right wave-end - No grommet 	36"	29 3/8"	1 1/4"	<b>LU1-W36BR()</b>	576.
	42"	29 3/8"	1 1/4"	<b>LU1-W42BR()</b>	611.
	48"	29 3/8"	1 1/4"	<b>LU1-W48BR()</b>	649.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>LU1-W48AL-117</b>	1 1/4" curvilinear surfaces are solid core construction with pilot holes at bracket and pedestal locations.	Options wave-end curvilinear worksurfaces are for panel planning only and cannot be used in conjunction with Network desk supports.
<b>LU1</b>		
<b>W</b>	Options worksurface, 1 1/4"	
<b>48</b>	Wave-end curvilinear	
<b>A</b>	Width	Use cantilever bridging bracket to join to adjacent 1 1/4" worksurface.
<b>L</b>	With grommets	Wave-end surfaces are post-formed on back edge, matching profile T-mold on curvilinear front, and self-edge on sides.
<b>117</b>	Left	Wave-end surfaces are available only in plastic laminate, 1 1/4" thickness.
	Surface finish	Wave-end surfaces are nominal 30"D at left or right, and align with 24"D surface at the other end.
	Specify surface finish.	
	Edge grommets are centered at rear of worksurface.	
	<i>Grommets/no grommets:</i>	
	A- Worksurface includes one edge grommet	
	B- Worksurface does not include grommets	

## 120° corners

## 90° returns and Diamond

description	type	w	return	h	pattern no.	lam.	V1	V2	V3
90° return 	no grommet	36"	24"	1 1/4"	<b>LU1-Y36S-B( ) ( )</b>	\$528.	\$741.	\$751.	\$914.
		42"	24"	1 1/4"	<b>LU1-Y42S-B( ) ( )</b>	558.	898.	908.	1,203.
		48"	24"	1 1/4"	<b>LU1-Y48S-B( ) ( )</b>	619.	990.	1,000.	1,507.
		60"	24"	1 1/4"	<b>LU1-Y60S-B( ) ( )</b>	756.	n/a	n/a	n/a
Diamond 	no grommet	36"	24"	1 1/4"	<b>LU1-D36S-B( ) ( )</b>	523.	756.	761.	939.
		42"	24"	1 1/4"	<b>LU1-D42S-B( ) ( )</b>	589.	924.	929.	1,254.
		48"	24"	1 1/4"	<b>LU1-D48S-B( ) ( )</b>	634.	1,035.	1,040.	1,578.
Transitional 		24"		1 1/4"	<b>LU1-YTS-( ) ( )</b>	406.	528.	538.	699.

## Order Code

Example:	<b>LU1-Y48S-B-L-L-117</b>
<b>LU1</b>	Options worksurface, 1 1/4" thick
<b>Y</b>	120° corner, 90° returns
<b>48</b>	Width
<b>S</b>	24"D return
<b>B</b>	No Grommets
<b>L</b>	Left hand
<b>L</b>	Laminate
<b>117</b>	Surface finish

## Specification Information

Width dimensions (w) refers to width of both back edges.

Specify surface finish.

1 1/4" Options worksurfaces are solid core construction with pilot holes at standard support locations.

120° Options worksurfaces are available without grommets only.

## Application Notes

Worksurfaces are 3/8" less than nominal depth for rear wire clearance.

120° Morrison Options worksurfaces with 90° returns are used in panel system applications only. They can be supported at each end by 24" end support brackets, 24" cantilever bracket or 18"D and 24"D pedestals. 120° corner is supported by a standard (90°) 24"D cantilever bracket.

Use cantilever bridging brackets to join to adjacent worksurfaces or to transitional 120° worksurfaces. Use mid-span support whenever Options worksurfaces span more than 48".

Transitional worksurfaces connect two 120° corner tops with 90° returns.

120° Morrison Options worksurfaces with 120° returns are used in panel system applications only. They can be supported at each return end by 24" end support brackets, 24" cantilever bracket or 18"D and 24"D pedestals. 120° corner is supported by standard (90°) 24"D cantilever bracket.

Order brackets with wood screws for Morrison Options worksurfaces.

Veneer Group 1 worksurfaces are quartered Techgrain®.


Veneer Group 2 worksurfaces are rift cut Techgrain®.

Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.

120° corners

Meeting corner

description	w	return	h	pattern no.	lam.	V1	V2	V3
Meeting corner Right hand - no grommet	48"	24"	1 1/4"	<b>LU1-M48S-BRL()</b>	\$639.	n/a	n/a	n/a



Meeting corner Left hand - no grommet	48"	24"	1 1/4"	<b>LU1-M48S-BLL()</b>	639.	n/a	n/a	n/a
--	-----	-----	--------	-----------------------	------	-----	-----	-----




Order Code	Specification Information	Application Notes
Example: <b>LU1-M48S-B-L-L-117</b>		
<b>LU1</b> Options worksurface, 1 1/4" thick	Width dimension (w) refers to width of smaller back edge. Total width of back edge with rounded meeting area is 62 1/2".	Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
<b>M</b> Meeting corner	Specify surface finish.	Morrison Options 120° meeting worksurfaces are used in panel system application only. They are supported at the rounded meeting end by a Morrison support column, specified separately. They can be supported at the other end by 24" end support brackets, 24" cantilever bracket or 18"D and 24"D pedestals.
<b>48</b> Width	1 1/4" worksurfaces are solid core construction with pilot holes at all support locations.	120° corner is supported by 24"D cantilever bracket.
<b>S</b> 24"D return		Use 24"D cantilever bridging brackets to join to adjacent worksurfaces.
<b>B</b> No Grommets		Veneer Group 1 worksurfaces are quartered Techgrain®.
<b>L</b> Left hand		Veneer Group 2 worksurfaces are rift cut Techgrain®.
<b>L</b> Laminate	120° Options worksurfaces are available without grommets only.	Veneer Group 3 worksurfaces are narrow heart, flat cut natural veneers.
<b>117</b> Surface finish		


# Morrison Options worksurfaces, 1 1/4" Arc

Morrison

description	w	return	h	pattern no.	lam.	V1	V2	V3
Arc Right hand	48"	24"	1 1/4"	<b>LU1-A48S-ARL( )</b>	\$853.	n/a	n/a	n/a



Arc Left hand	48"	24"	1 1/4"	<b>LU1-A48S-ALL( )</b>	853.	n/a	n/a	n/a
------------------	-----	-----	--------	------------------------	------	-----	-----	-----





Order Code	Specification Information	Application Notes
Example: <b>LU1-A48S-A-L-L-117</b>		
<b>LU1</b> Options worksurface, 1 1/4" thick	Width dimension (w) refers to width of the three back edges.	Worksurfaces are 3/8" less than nominal depth for rear wire clearance.
<b>A</b> Arc	Specify surface finish. Available in laminate only.	120° Arc worksurfaces are used in panel system applications. They must be supported by cantilever brackets at each connector/post location.
<b>48</b> Width		
<b>S</b> 24"D return	Morrison Options Arc worksurfaces are solid core construction with 0.8 mm flat pvc edge on all sides.	
<b>A</b> Grommets		
<b>L</b> Left hand		
<b>L</b> Laminate	Arc worksurfaces always come with scalloped grommet openings on all 48" edges.	
<b>117</b> Surface finish		



Currents worksurfaces for Morrison  
*straight, flat front*  
*3/8" wire drop and grommet*

Morrison


description	w	d	h	pattern no.	lam.	V2	V3
24"D - Straight worksurface, flat front 	24"	23 5/8"	1"	<b>AWM2 F2424</b> ( ) ( )	\$243.	\$364.	\$487.
	30"	23 5/8"	1"	<b>AWM2 F3024</b> ( ) ( )	268.	401.	536.
	36"	23 5/8"	1"	<b>AWM2 F3624</b> ( ) ( )	291.	439.	584.
	42"	23 5/8"	1"	<b>AWM2 F4224</b> ( ) ( )	317.	475.	633.
	48"	23 5/8"	1"	<b>AWM2 F4824</b> ( ) ( )	341.	511.	681.
	54"	23 5/8"	1"	<b>AWM2 F5424</b> ( ) ( )	364.	549.	730.
	60"	23 5/8"	1"	<b>AWM2 F6024</b> ( ) ( )	389.	584.	780.
	66"	23 5/8"	1"	<b>AWM2 F6624</b> ( ) ( )	414.	620.	827.
	72"	23 5/8"	1"	<b>AWM2 F7224</b> ( ) ( )	439.	656.	876.
	78"	23 5/8"	1"	<b>AWM2 F7824</b> ( ) ( )	462.	695.	925.
	84"	23 5/8"	1"	<b>AWM2 F8424</b> ( ) ( )	487.	730.	973.
	90"	23 5/8"	1"	<b>AWM2 F9024</b> ( ) ( )	510.	764.	1,021.
96"	23 5/8"	1"	<b>AWM2 F9624</b> ( ) ( )	536.	803.	1,071.	
30"D - Straight worksurface, flat front 	30"	29 5/8"	1"	<b>AWM2 F3030</b> ( ) ( )	304.	456.	607.
	36"	29 5/8"	1"	<b>AWM2 F3630</b> ( ) ( )	329.	493.	656.
	42"	29 5/8"	1"	<b>AWM2 F4230</b> ( ) ( )	354.	529.	706.
	48"	29 5/8"	1"	<b>AWM2 F4830</b> ( ) ( )	376.	566.	755.
	54"	29 5/8"	1"	<b>AWM2 F5430</b> ( ) ( )	407.	612.	815.
	60"	29 5/8"	1"	<b>AWM2 F6030</b> ( ) ( )	439.	656.	876.
	66"	29 5/8"	1"	<b>AWM2 F6630</b> ( ) ( )	475.	711.	950.
	72"	29 5/8"	1"	<b>AWM2 F7230</b> ( ) ( )	511.	765.	1,022.
	78"	29 5/8"	1"	<b>AWM2 F7830</b> ( ) ( )	547.	820.	1,093.
	90"	29 5/8"	1"	<b>AWM2 F9030</b> ( ) ( )	620.	930.	1,241.
	96"	29 5/8"	1"	<b>AWM2 F9630</b> ( ) ( )	656.	985.	1,315.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>AWM2 F4830-119-119</b>	<p><i>Specify top finish first, followed by trim finish.</i></p> <p>Please refer to the Currents price list for finishes.</p>	<p>Worksurfaces are sized for Morrison panel-based applications and may be supported by Morrison panel planning brackets or end-supported from Currents wall. 24"D straight tops may also be cantilevered from Currents service wall. Underside of worksurfaces is drilled to accept all Morrison panel-planning brackets, Morrison and Currents pedestals, and worksurface stiffeners. 24"D straight tops are also drilled to accept Currents wall cantilever brackets.</p> <p>When using Morrison end support brackets, order MB3-EC18, 24 or 30.</p> <p>Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately (page 142).</p> <p>Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.</p>
<b>AWM2</b> Worksurface		
<b>F</b> Flat		
<b>48</b> Width		
<b>30</b> Depth		
<b>119</b> Top finish		
<b>119</b> Trim finish		
	<p>Flat front allows two straight worksurfaces to meet at right angles.</p> <p>Actual worksurface depth is 3/8" less than nominal 24" and 30" for cable clearance.</p> <p>All worksurfaces include one edge grommet, centered at rear of worksurface, with maximum clearance of 1 3/8".</p> <p>Currents for Morrison worksurfaces feature crisp, 90-degree corners eliminating the corner kick detail typical of Currents universal worksurfaces. This facilitates the use of brackets, pedestals and end panels at the side edge of worksurfaces.</p>	





corner

3/8" wire drop and grommet

description	type	w	d	h	pattern no.	lam.	V2	V3
Corner worksurfaces 	24"D both sides	42"	42"	1"	<b>AWM2 C4242 S ( )()</b>	\$543.	\$813.	\$1,085.
		48"	48"	1"	<b>AWM2 C4848 S ( )()</b>	602.	904.	1,205.
		60"	60"	1"	<b>AWM2 C6060 S ( )()</b>	843.	n/a	n/a
	30"D both sides	42"	42"	1"	<b>AWM2 C4242 D ( )()</b>	543.	813.	1,085.
		48"	48"	1"	<b>AWM2 C4848 D ( )()</b>	602.	904.	1,205.
		60"	60"	1"	<b>AWM2 C6060 D ( )()</b>	843.	n/a	n/a
	30"D left/24"D right	42"	42"	1"	<b>AWM2 C4242 L ( )()</b>	543.	813.	1,085.
		48"	48"	1"	<b>AWM2 C4848 L ( )()</b>	602.	904.	1,205.
		60"	60"	1"	<b>AWM2 C6060 L ( )()</b>	843.	n/a	n/a
	24"D left/30"D right	42"	42"	1"	<b>AWM2 C4242 R ( )()</b>	543.	813.	1,085.
		48"	48"	1"	<b>AWM2 C4848 R ( )()</b>	602.	904.	1,205.
		60"	60"	1"	<b>AWM2 C6060 R ( )()</b>	843.	n/a	n/a

Order Code	Specification Information	Application Notes
Example: <b>AWM2 C4848S-119-119</b> <b>AWM2</b> Worksurface <b>C</b> Corner <b>48</b> Width left <b>48</b> Width right <b>S</b> Depth left and right <b>119</b> Top finish <b>119</b> Trim finish	Dimensions shown in "w" column are nominal width of left back edge. Dimensions shown in "d" column are nominal width of right back edge.  <i>Worksurface depths:</i> S 24"D both sides L 30"D left/24"D right R 24"D left/30"D right  Specify top finish first, followed by trim finish.  Please refer to the Currents price list for finishes.	Wood grain laminate is not available on 60"W x 60"D corner worksurfaces.  Worksurfaces are sized for Morrison panel-based applications and may be supported by Morrison panel-planning brackets or end-supported and cantilevered from Currents wall. Underside of worksurfaces is drilled to accept all Morrison panel-planning brackets, Morrison and Currents pedestals, and worksurface stiffeners. 24"D worksurfaces are also drilled to accept Currents wall cantilever brackets.  When using Morrison end support brackets, order MB3-EC18, 24 or 30.  Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately (page 142).  Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.  Actual worksurface depth is 3/8" less than nominal 24" and 30" for cable clearance.  All worksurfaces include two edge grommets, centered on back edges of worksurface, with maximum clearance of 1 5/8".

*extended corner  
3/8" wire drop and grommet  
extended left*





description	w	d	h	pattern no.	lam.	V2	V3
24"D both sides - Corner worksurfaces, extended left 	60"	36"	1"	<b>AWM2 C6036 S ( ) ( )</b>	\$602.	\$904.	\$1,205.
	60"	42"	1"	<b>AWM2 C6042 S ( ) ( )</b>	664.	993.	1,324.
	60"	48"	1"	<b>AWM2 C6048 S ( ) ( )</b>	724.	1,085.	1,445.
	72"	36"	1"	<b>AWM2 C7236 S ( ) ( )</b>	724.	1,085.	1,445.
	72"	42"	1"	<b>AWM2 C7242 S ( ) ( )</b>	783.	1,174.	1,566.
	72"	48"	1"	<b>AWM2 C7248 S ( ) ( )</b>	843.	1,266.	1,687.
30"D both sides - Corner worksurfaces, extended left 	60"	48"	1"	<b>AWM2 C6048 D ( ) ( )</b>	784.	1,174.	1,567.
	72"	48"	1"	<b>AWM2 C7248 D ( ) ( )</b>	904.	1,355.	1,808.
	84"	48"	1"	<b>AWM2 C8448 D ( ) ( )</b>	1,024.	1,538.	2,050.
24"D left/30"D right - Corner worksurfaces, extended left 	60"	42"	1"	<b>AWM2 C6042 R ( ) ( )</b>	724.	1,085.	1,445.
	60"	48"	1"	<b>AWM2 C6048 R ( ) ( )</b>	784.	1,174.	1,567.
	72"	42"	1"	<b>AWM2 C7242 R ( ) ( )</b>	843.	1,265.	1,687.
	72"	48"	1"	<b>AWM2 C7248 R ( ) ( )</b>	904.	1,355.	1,808.
	84"	48"	1"	<b>AWM2 C8448 R ( ) ( )</b>	1,024.	1,538.	2,050.
30"D left/24"D right - Corner worksurfaces, extended left 	60"	42"	1"	<b>AWM2 C6042 L ( ) ( )</b>	724.	1,085.	1,445.
	60"	48"	1"	<b>AWM2 C6048 L ( ) ( )</b>	784.	1,174.	1,567.
	72"	42"	1"	<b>AWM2 C7242 L ( ) ( )</b>	843.	1,265.	1,687.
	72"	48"	1"	<b>AWM2 C7248 L ( ) ( )</b>	904.	1,355.	1,808.
	84"	48"	1"	<b>AWM2 C8448 L ( ) ( )</b>	1,024.	1,538.	2,050.

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>AWM2 C6036S119-119</b>	Dimensions shown in "w" column are nominal width of left back edge.	<p>Worksurfaces are sized for Morrison panel-based applications and may be supported by Morrison panel-planning brackets or end-supported and cantilevered from Currents wall. Extended side may also be supported with Currents C-legs. Underside of worksurface is drilled to accept all Morrison panel-planning brackets, Morrison and Currents pedestals, worksurface stiffeners and Currents C-leg on the extended side.</p> <p>When using Morrison end support brackets, order MB3-EC18, 24 or 30.</p> <p>Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately (page 142).</p> <p>Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.</p> <p>Actual worksurface is 3/8" less than nominal 24" and 30" for cable clearance.</p> <p>All worksurfaces include two edge grommets, centered on back edges of worksurface, with maximum clearance of 1 5/8."</p>
<b>AWM2</b> Worksurface	Dimensions shown in "d" column are nominal width of right back edge.	
<b>C</b> Corner		
<b>60</b> Width left		
<b>36</b> Width right		
<b>S</b> Depth left and right	<i>Worksurface depths:</i>	
<b>119</b> Top finish	S 24"D both sides	
<b>119</b> Trim finish	L 30"D left/24"D right	
	R 24"D left/30"D right	
	Specify top finish first, followed by trim finish.	
	Please refer to the Currents price list for finishes.	



Currents worksurfaces for Morrison  
*extended corner*  
*3/8" wire drop and grommet*  
*extended right*

Morrison

description	w	d	h	pattern no.	lam.	V2	V3
24"D both sides - Corner worksurfaces extended right 	36"	60"	1"	<b>AWM2 C3660 S ( ) ( )</b>	\$602.	\$904.	\$1,205.
	36"	72"	1"	<b>AWM2 C3672 S ( ) ( )</b>	724.	1,085.	1,445.
	42"	60"	1"	<b>AWM2 C4260 S ( ) ( )</b>	664.	993.	1,324.
	42"	72"	1"	<b>AWM2 C4272 S ( ) ( )</b>	783.	1,174.	1,566.
	48"	60"	1"	<b>AWM2 C4860 S ( ) ( )</b>	724.	1,085.	1,445.
	48"	72"	1"	<b>AWM2 C4872 S ( ) ( )</b>	843.	1,266.	1,687.
	48"	84"	1"	<b>AWM2 C4884 S ( ) ( )</b>	964.	1,445.	1,928.
30"D both sides - Corner worksurfaces extended right 	48"	60"	1"	<b>AWM2 C4860 D ( ) ( )</b>	784.	1,174.	1,567.
	48"	72"	1"	<b>AWM2 C4872 D ( ) ( )</b>	904.	1,355.	1,808.
	48"	84"	1"	<b>AWM2 C4884 D ( ) ( )</b>	1,024.	1,538.	2,050.
24"D left/30"D right - Corner worksurfaces extended right 	42"	60"	1"	<b>AWM2 C4260 R ( ) ( )</b>	724.	1,085.	1,445.
	42"	72"	1"	<b>AWM2 C4272 R ( ) ( )</b>	843.	1,265.	1,687.
	48"	60"	1"	<b>AWM2 C4860 R ( ) ( )</b>	784.	1,174.	1,567.
	48"	72"	1"	<b>AWM2 C4872 R ( ) ( )</b>	904.	1,355.	1,808.
	48"	84"	1"	<b>AWM2 C4884 R ( ) ( )</b>	1,024.	1,538.	2,050.
30"D left/24"D right - Corner worksurfaces extended right 	42"	60"	1"	<b>AWM2 C4260 L ( ) ( )</b>	724.	1,085.	1,445.
	42"	72"	1"	<b>AWM2 C4272 L ( ) ( )</b>	843.	1,265.	1,687.
	48"	60"	1"	<b>AWM2 C4860 L ( ) ( )</b>	784.	1,174.	1,567.
	48"	72"	1"	<b>AWM2 C4872 L ( ) ( )</b>	904.	1,355.	1,808.
	48"	84"	1"	<b>AWM2 C4884 L ( ) ( )</b>	1,024.	1,538.	2,050.

Order Code	Specification Information	Application Notes														
<p>Example: <b>AWM2 C3660S-119-119</b></p> <table border="1"> <tr> <td><b>AWM2</b></td> <td>Worksurface</td> </tr> <tr> <td><b>C</b></td> <td>Corner</td> </tr> <tr> <td><b>36</b></td> <td>Width left</td> </tr> <tr> <td><b>60</b></td> <td>Width right</td> </tr> <tr> <td><b>S</b></td> <td>Depth left and right</td> </tr> <tr> <td><b>119</b></td> <td>Top finish</td> </tr> <tr> <td><b>119</b></td> <td>Trim finish</td> </tr> </table>	<b>AWM2</b>	Worksurface	<b>C</b>	Corner	<b>36</b>	Width left	<b>60</b>	Width right	<b>S</b>	Depth left and right	<b>119</b>	Top finish	<b>119</b>	Trim finish	<p>Dimensions shown in "w" column are nominal width of left back edge. Dimensions shown in "d" column are nominal width of right back edge.</p> <p><i>Worksurface depths:</i></p> <p>S 24"D both sides  L 30"D left/24"D right  R 24"D left/30"D right</p> <p>Specify top finish first, followed by trim finish.</p> <p>Please refer to the Currents price list for finishes.</p>	<p>Worksurfaces are sized for Morrison panel-based applications and may be supported by Morrison panel-planning brackets or end-supported and cantilevered from Currents wall. Extended side may also be supported with Currents C-legs. Underside of worksurface is drilled to accept all Morrison panel-planning brackets, Morrison and Currents pedestals, worksurface stiffeners and Currents C-leg on the extended side.</p> <p>When using Morrison end support brackets, order MB3-EC18, 24 or 30.</p> <p>Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately (page 142).</p> <p>Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.</p> <p>Actual worksurface is 3/8" less than nominal 24" and 30" for cable clearance.</p> <p>All worksurfaces include two edge grommets, centered on back edges of worksurface, with maximum clearance of 1 5/8."</p>
<b>AWM2</b>	Worksurface															
<b>C</b>	Corner															
<b>36</b>	Width left															
<b>60</b>	Width right															
<b>S</b>	Depth left and right															
<b>119</b>	Top finish															
<b>119</b>	Trim finish															


*P-shape*  
*3/8" wire drop and grommet*

description	w	d	h	pattern no.	lam.	V2	V3
P-shape surfaces, extended left 	75"	48"	1"	<b>AWM2 P7548 S ( ) ( )</b>	\$964.	\$1,445.	\$1,928.
	87"	48"	1"	<b>AWM2 P8748 S ( ) ( )</b>	1,085.	1,628.	2,168.
P-shape surfaces, extended right 	48"	78"	1"	<b>AWM2 P4875 S ( ) ( )</b>	964.	1,445.	1,928.
	48"	87"	1"	<b>AWM2 P4887 S ( ) ( )</b>	1,085.	1,628.	2,168.

Order Code	Specification Information	Application Notes
Example: <b>AWM2 P7548 S-119-119</b>	Specify top finish first, followed by trim finish.	<p>Worksurfaces are sized for Morrison panel-based applications and may be supported by Morrison panel-planning brackets.</p> <p>P-shaped worksurfaces may be supported with Morrison brackets or cantilevered from Currents service wall along 48" edge, and supported by a 24"D Currents C-leg at conference end. Specify supports separately.</p> <p>All P-shaped worksurfaces correspond to a 24"D adjacent straight or corner worksurface.</p> <p>Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately (page 142).</p> <p>When using Morrison end support brackets, order MB3-EC18, 24 or 30.</p> <p>Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.</p>
<b>AWM2</b> Worksurface	Please refer to the Currents price list for finishes.	
<b>P</b> P-shape		
<b>75</b> Width left		
<b>48</b> Width right		
<b>S</b> Depth of return		
<b>119</b> Top finish		
<b>119</b> Trim finish		<p>Actual worksurface depth is 3/8" less than nominal for cable clearance.</p> <p>All worksurfaces include one edge grommet, centered at rear of worksurface, with maximum clearance of 1 5/8".</p> <p>For 90" application span, use two AWB-S42 stiffeners.</p> <p>For 96" application span, use two AWB-S48 stiffeners.</p>

# Currents worksurfaces for Morrison stiffeners

Morrison

description	type	w	d	h	pattern no.	list
	36"	20"	1 1/2"	2"	<b>AWM1 S36</b>	\$47.
	42"	26"	1 1/2"	2"	<b>AWM1 S42</b>	49.
	48"	32"	1 1/2"	2"	<b>AWM1 S48</b>	51.
	60"	44"	1 1/2"	2"	<b>AWM1 S60</b>	53.
	66"	50"	1 1/2"	2"	<b>AWM1 S66</b>	55.
	72"	56"	1 1/2"	2"	<b>AWM1 S72</b>	57.
	78"	62"	1 1/2"	2"	<b>AWM1 S78</b>	60.
	84"	68"	1 1/2"	2"	<b>AWM1 S84</b>	62.

## Order Code

*Example:* **AWM1 S48**

**AWM1** Worksurface

**S** Stiffener

**48** Type

## Application Notes

Currents worksurfaces for Morrison require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately.

When using Morrison end support brackets, order MB3-EC18, 24 or 30.

Currents worksurfaces for Morrison cannot be used in conjunction with Morrison Network desk supports.

For 90" application span, use two AWM1-S42 stiffeners.

For 96" application span, use two AWM1-S48 stiffeners.



Stiffener mounts 18" from front edge of worksurface and will interfere with mobile or floorstanding pedestals greater than 18" deep.

To accommodate a floorstanding pedestal greater than 18" deep at one end of worksurface, specify stiffener for 12" narrower worksurface. To accommodate two floorstanding pedestals or double-wide at one end of worksurface, specify stiffener for 24" narrower worksurface.

# Cascade edge worksurfaces

## Rectangular

Morrison

description	w	d	h	pattern no.	Solid	woodgrain
24"D Rectangular 	24"	24"	1 1/8"	<b>MCE1R2424N</b>	\$171.	\$197.
	30"	24"	1 1/8"	<b>MCE1R3024N</b>	197.	227.
	36"	24"	1 1/8"	<b>MCE1R3624N</b>	218.	251.
	42"	24"	1 1/8"	<b>MCE1R4224N</b>	251.	289.
	48"	24"	1 1/8"	<b>MCE1R4824N</b>	282.	324.
	54"	24"	1 1/8"	<b>MCE1R5424N</b>	303.	348.
	60"	24"	1 1/8"	<b>MCE1R6024N</b>	329.	378.
	66"	24"	1 1/8"	<b>MCE1R6624N</b>	355.	409.
	72"	24"	1 1/8"	<b>MCE1R7224N</b>	371.	426.
	78"	24"	1 1/8"	<b>MCE1R7824N</b>	398.	457.
	84"	24"	1 1/8"	<b>MCE1R8424N</b>	421.	484.
	90"	24"	1 1/8"	<b>MCE1R9024N</b>	475.	546.
96"	24"	1 1/8"	<b>MCE1R9624N</b>	518.	595.	
30"D Rectangular 	24"	30"	1 1/8"	<b>MCE1R2430N</b>	219.	252.
	30"	30"	1 1/8"	<b>MCE1R3030N</b>	245.	282.
	36"	30"	1 1/8"	<b>MCE1R3630N</b>	272.	313.
	42"	30"	1 1/8"	<b>MCE1R4230N</b>	296.	340.
	48"	30"	1 1/8"	<b>MCE1R4830N</b>	329.	378.
	54"	30"	1 1/8"	<b>MCE1R5430N</b>	372.	427.
	60"	30"	1 1/8"	<b>MCE1R6030N</b>	409.	471.
	66"	30"	1 1/8"	<b>MCE1R6630N</b>	456.	524.
	72"	30"	1 1/8"	<b>MCE1R7230N</b>	475.	546.
	78"	30"	1 1/8"	<b>MCE1R7830N</b>	507.	583.
	84"	30"	1 1/8"	<b>MCE1R8430N</b>	538.	618.
	90"	30"	1 1/8"	<b>MCE1R9030N</b>	579.	665.
96"	30"	1 1/8"	<b>MCE1R9630N</b>	619.	712.	

Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MCE1R4824N, 118</b> <b>MCE1</b> Cascade edge worksurface <b>R</b> Rectangular <b>48</b> Width <b>24</b> Depth <b>N</b> No grommets <b>118</b> Surface finish	Specify: Grommet / No grommet. Replace the "N" suffix from the pattern number with "G". Add \$20.  Finish:  <b>Solid:</b> 114 Folkstone Grey 117 Soft Grey 118 Bright White 119 Pumice  <b>Woodgrain:</b> 124 Medium Cherry 125 Natural Maple 126 Natural Cherry 127 Walnut	Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.  Cascade Edge are not drilled for wire management clips, pedestals or brackets.  Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.

Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.

Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"

Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.

Worksurfaces may be supported at each end by pedestals or end support "EC" brackets and cantilever brackets matching the worksurface depth.


Panel supported worksurfaces over 48" must be mid-span supported by cantilever brackets, specified separately.

Order Morrison brackets with wood screws (suffix-W).

# Cascade edge worksurfaces

## Blended "D"

Morrison

description	A	B	C	h	pattern no.	solid	woodgrain
 <p>right hand shown</p>	66"	48"	24"	1 1/8"	<b>MCE1BD6648S(L/R)</b>	\$695.	\$799.
	66"	48"	30"	1 1/8"	<b>MCE1BD6648D(L/R)</b>	731.	841.
	72"	48"	24"	1 1/8"	<b>MCE1BD7248S(L/R)</b>	711.	818.
	72"	48"	30"	1 1/8"	<b>MCE1BD7248D(L/R)</b>	758.	872.
	78"	48"	24"	1 1/8"	<b>MCE1BD7848S(L/R)</b>	821.	944.
	78"	48"	30"	1 1/8"	<b>MCE1BD7848D(L/R)</b>	848.	975.
	84"	48"	24"	1 1/8"	<b>MCE1BD8448S(L/R)</b>	843.	969.
	84"	48"	30"	1 1/8"	<b>MCE1BD8448D(L/R)</b>	896.	1,030.


Order Code	Specification Information	Application Notes
Example: <b>MCE1BD7248SL-118</b>	<i>Finish:</i>	<p>Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.</p> <p>Cascade Edge are not drilled for wire management clips, pedestals or brackets.</p> <p>Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.</p>
<b>MCE1</b> Cascade edge worksurface	<i>Solid:</i>	
<b>BD</b> Blended "D"	114 Folkstone Grey	
<b>72</b> Width	117 Soft Grey	
<b>48</b> Depth	118 Bright White	
<b>S</b> 24"d return	119 Pumice	
<b>L</b> Extended left	<i>Woodgrain:</i>	
<b>118</b> Surface finish	124 Medium Cherry	
	125 Natural Maple	
	126 Natural Cherry	
	127 Walnut	
		<p>Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.</p> <p>Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"</p> <p>Worksurfaces require support every 48" in width. All support hardware is ordered separately.</p> <p>Blended-D worksurfaces are supported by a 48" VDT support bracket kit in conjunction with a rounded end support column. Use flat bracket or bridging bracket to join to adjacent worksurface.</p> <p>Order Morrison brackets with wood screws (suffix -W).</p>



# Cascade edge worksurfaces

## Curvilinear Corner

Morrison

description	A	B	C	h	pattern no	solid	woodgrain
	36"	24"	24"	1 1/8"	<b>MCE1L3636SSN</b>	\$430.	\$495.
	42"	24"	24"	1 1/8"	<b>MCE1L4242SSN</b>	518.	596.
	42"	24"	30"	1 1/8"	<b>MCE1L4242SDN</b>	616.	708.
	42"	30"	24"	1 1/8"	<b>MCE1L4242DSN</b>	616.	708.
	48"	24"	24"	1 1/8"	<b>MCE1L4848SSN</b>	583.	670.
	48"	24"	30"	1 1/8"	<b>MCE1L4848SDN</b>	697.	802.
	48"	30"	24"	1 1/8"	<b>MCE1L4848DSN</b>	697.	802.
	48"	30"	30"	1 1/8"	<b>MCE1L4848DDN</b>	626.	720.

### Order Code

Example:	<b>MCE1L4848SSG-114</b>
<b>MCE1</b>	Cascade edge worksurface
<b>L</b>	Curvilinear "L" top
<b>48</b>	Width
<b>48</b>	Depth
<b>S</b>	24"d, left side
<b>S</b>	24"d, right side
<b>G</b>	Grommet
<b>114</b>	Surface finish

### Specification Information

*Specify:*  
Grommet / no grommet.  
Replace the "N" suffix from the pattern number with "G". Add \$40.  
*Finish:*

#### *Solid:*

114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice

#### *Woodgrain:*

124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

### Application Notes

Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.

Cascade Edge worksurfaces are not drilled for wire management clips, pedestals or brackets.

Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.

Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.

Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"

Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.

Worksurfaces may be supported by left or right hand 18" cantilever brackets at the rear corner, and cantilever bridging brackets on each side edge.


Panel supported worksurfaces over 48" must be mid-span supported by cantilever brackets, specified separately.

Order Morrison brackets with wood screws (suffix -W).

# Cascade edge worksurfaces

## Blended "L"

Morrison

description	B	C	A	D	h	pattern no.	solid	woodgrain
	42"	60"	24"	24"	1 1/8"	<b>MCE1L4260SSN</b>	\$712.	\$819.
	42"	66"	24"	24"	1 1/8"	<b>MCE1L4266SSN</b>	731.	841.
	42"	72"	24"	24"	1 1/8"	<b>MCE1L4272SSN</b>	759.	873.
	42"	78"	24"	24"	1 1/8"	<b>MCE1L4278SSN</b>	767.	882.
	48"	60"	24"	24"	1 1/8"	<b>MCE1L4860SSN</b>	721.	829.
	48"	60"	24"	30"	1 1/8"	<b>MCE1L4860SDN</b>	708.	814.
	48"	60"	30"	24"	1 1/8"	<b>MCE1L4860DSN</b>	708.	814.
	48"	66"	24"	24"	1 1/8"	<b>MCE1L4866SSN</b>	747.	859.
	48"	66"	24"	30"	1 1/8"	<b>MCE1L4866SDN</b>	744.	856.
	48"	66"	30"	24"	1 1/8"	<b>MCE1L4866DSN</b>	744.	856.
	48"	72"	24"	24"	1 1/8"	<b>MCE1L4872SSN</b>	774.	890.
	48"	72"	24"	30"	1 1/8"	<b>MCE1L4872SDN</b>	779.	896.
	48"	72"	30"	24"	1 1/8"	<b>MCE1L4872DSN</b>	779.	896.
	48"	78"	24"	24"	1 1/8"	<b>MCE1L4878SSN</b>	854.	982.
	48"	84"	24"	24"	1 1/8"	<b>MCE1L4884SSN</b>	960.	1,104.
	60"	42"	24"	24"	1 1/8"	<b>MCE1L6042SSN</b>	712.	819.
	60"	48"	24"	24"	1 1/8"	<b>MCE1L6048SSN</b>	721.	829.
	60"	48"	24"	30"	1 1/8"	<b>MCE1L6048SDN</b>	708.	814.
	60"	48"	30"	24"	1 1/8"	<b>MCE1L6048DSN</b>	708.	814.
	66"	42"	24"	24"	1 1/8"	<b>MCE1L6642SSN</b>	731.	841.
66"	48"	24"	24"	1 1/8"	<b>MCE1L6648SSN</b>	747.	859.	
66"	48"	24"	30"	1 1/8"	<b>MCE1L6648SDN</b>	744.	856.	
66"	48"	30"	24"	1 1/8"	<b>MCE1L6648DSN</b>	744.	856.	
72"	42"	24"	24"	1 1/8"	<b>MCE1L7242SSN</b>	759.	873.	
72"	48"	24"	24"	1 1/8"	<b>MCE1L7248SSN</b>	774.	890.	
72"	48"	24"	30"	1 1/8"	<b>MCE1L7248SDN</b>	779.	896.	
72"	48"	30"	24"	1 1/8"	<b>MCE1L7248DSN</b>	779.	896.	


Order Code	Specification Information	Application Notes
Example: <b>MCE1L4872SDG-114</b>	<i>Specify:</i> Grommet / no grommet. Replace the "N" suffix from the pattern number with "G". Add \$40.	Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.
<b>MCE1</b> Cascade edge worksurface	<i>Finish:</i>	
<b>L</b> Blended "L" top	<i>Solid:</i>	Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance. Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"
<b>48</b> Depth	114 Folkstone Grey	
<b>72</b> Width	117 Soft Grey	Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.
<b>S</b> 24"d return left	118 Bright White	
<b>D</b> 30"d return right	119 Pumice	Worksurfaces may be supported by left or right hand 18" cantilever brackets at the rear corner, and cantilever bridging brackets on each side edge.
<b>G</b> Grommet	<i>Woodgrain:</i>	
<b>114</b> Surface finish	124 Medium Cherry	Panel supported worksurfaces over 48" must be mid-span supported by cantilever brackets, specified separately. Order Morrison brackets with wood screws (suffix -W).
	125 Natural Maple	
	126 Natural Cherry	
	127 Walnut	
		Cascade Edge worksurfaces are not drilled for wire management clips, pedestals or brackets. Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.

# Cascade edge worksurfaces

## Blended "L"

Morrison

description	B	C	A	D	h	pattern no.	solid	woodgrain
Blended "L"	78"	42"	24"	24"	1 1/8"	<b>MCE1L7842SSN</b>	\$767.	\$882.
	78"	48"	24"	24"	1 1/8"	<b>MCE1L7848SSN</b>	854.	982.
	84"	48"	24"	24"	1 1/8"	<b>MCE1L8448SSN</b>	960.	1,104.



Order Code	Specification Information	Application Notes
Example: <b>MCE1L4872SDG-114</b>	<i>Specify:</i> Grommet / no grommet. Replace the "N" suffix from the pattern number with "G". Add \$40.	<p>Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care.</p> <p>Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.</p> <p>Cascade Edge worksurfaces are not drilled for wire management clips, pedestals or brackets.</p> <p>Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.</p>
<b>MCE1</b> Cascade edge worksurface		
<b>L</b> Blended "L" top	<i>Finish:</i>	
<b>48</b> Depth	<i>Solid:</i>	
<b>72</b> Width	114 Folkstone Grey	
<b>S</b> 24"d return left	117 Soft Grey	
<b>D</b> 30"d return right	118 Bright White	
<b>G</b> Grommet	119 Pumice	
<b>114</b> Surface finish	<i>Woodgrain:</i>	
	124 Medium Cherry 125 Natural Maple 126 Natural Cherry 127 Walnut	

Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.

Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"

Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.

Worksurfaces may be supported by left or right hand 18" cantilever brackets at the rear corner, and cantilever bridging brackets on each side edge.






Panel supported worksurfaces over 48" must be mid-span supported by cantilever brackets, specified separately.

Order Morrison brackets with wood screws (suffix -W).

# Cascade edge worksurfaces

## Half round and Corner round

Morrison



description	w	d	h	pattern no.	solid	woodgrain
 Half Round	50 1/4" notched for panel	18"	1 1/8"	<b>MCE1H4818P</b>	\$371.	\$427.
	60 1/4" notched for panel	24"	1 1/8"	<b>MCE1H6024P</b>	511.	588.
	48"	18"	1 1/8"	<b>MCE1H4818</b>	371.	427.
	60"	24"	1 1/8"	<b>MCE1H6024</b>	511.	588.
24"D- RH Corner Round	24"	24"	1 1/8"	<b>MCE1CR24R</b>	197.	227.
						
24"D- LH Corner Round	24"	24"	1 1/8"	<b>MCE1CR24L</b>	197.	227.
						
24"D - Notched Corner Round	24" notched	24"	1 1/8"	<b>MCE1CR24N</b>	197.	227.
						
Sample	12"	12"	1 1/8"	<b>MCE1R1212G</b>	107.	123.
						

Order Code	Specification Information	Application Notes
Example: <b>MCE1H4818P-117</b>	<i>Specify:</i>	<p>Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.</p> <p>Cascade Edge worksurfaces are not drilled for wire management clips, pedestals or brackets.</p> <p>Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.</p>
<b>MCE1</b> Cascade edge worksurface	<i>Finish:</i>	
<b>H</b> Half round	Solid:	
<b>48</b> Width	114 Folkstone Grey	
<b>18</b> Depth	117 Soft Grey	
<b>P</b> Notched for panel	118 Bright White	
<b>117</b> Surface finish	119 Pumice	
	<i>Woodgrain:</i>	
	124 Medium Cherry	
	125 Natural Maple	
	126 Natural Cherry	
	127 Walnut	
	<p>Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.</p> <p>Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.</p> <p><i>Half Round:</i> Half round worksurfaces may be supported by cantilever bridging brackets in conjunction with a rounded end support column.</p> <p><i>Corner Round:</i> Notched corner round worksurfaces are supported by cantilever bridging brackets on both side edges.</p> <p>End run Left- and Right-handed corner round worksurfaces are supported by a combination of an end bracket along the panel edge and a cantilever bridging bracket to the adjacent worksurface side edge.</p> <p>Order Morrison brackets with wood screws ( suffix -W ).</p>	

# Cascade edge worksurfaces

## Wave End

Morrison

description	1	2	3	A	B	h	pattern no.	solid	woodgrain
Wave End, RH 	36"	30"	24"	3"	15"	1 1/8"	<b>MCE1W362430N</b>	\$462.	\$531.
	42"	30"	24"	9"	15"	1 1/8"	<b>MCE1W422430N</b>	485.	558.
	48"	30"	24"	15"	15"	1 1/8"	<b>MCE1W482430N</b>	519.	597.
	72"	30"	24"	30 1/2"	23 1/2"	1 1/8"	<b>MCE1W722430N</b>	661.	760.
Wave End, LH 	36"	24"	30"	15"	3"	1 1/8"	<b>MCE1W363024N</b>	462.	531.
	42"	24"	30"	15"	9"	1 1/8"	<b>MCE1W423024N</b>	485.	558.
	48"	24"	30"	15"	15"	1 1/8"	<b>MCE1W483024N</b>	519.	597.
	78"	24"	30"	23 1/2"	30 1/2"	1 1/8"	<b>MCE1W723024N</b>	661.	760.

Worksurface Planning

### Order Code

Example:	<b>MCE1W483024N-118</b>
<b>MCE1</b>	Cascade edge worksurface
<b>W</b>	Wave end
<b>48</b>	Width
<b>30</b>	Depth left
<b>24</b>	Depth right
<b>N</b>	No Grommet
<b>118</b>	Surface finish

### Specification Information

*Specify:*  
Grommet / no grommet.  
Replace the "N" suffix from the pattern number with "G". Add \$20.

#### *Finish:*

*Solid:*  
114 Folkstone Grey  
117 Soft Grey  
118 Bright White  
119 Pumice

#### *Woodgrain:*

124 Medium Cherry  
125 Natural Maple  
126 Natural Cherry  
127 Walnut

### Application Notes

Cascade Edge worksurfaces are wrapped with a vinyl sheet heated and pressed around an MDF substrate. They are more susceptible to denting, impact, tearing and marring than conventional high pressure laminate and should be handled with care. Do not drag worksurfaces across any flooring surface during installation. Treat Cascade Edge worksurfaces like veneer worksurfaces and they will perform well under normal conditions. Cascade Edge worksurfaces have a 5 year warranty on defects in workmanship and materials. This warranty does not cover damage occurring during or after installation.

Cascade Edge worksurfaces are not drilled for wire management clips, pedestals or brackets.

Cascade Edge worksurfaces are for panel-based planning only and cannot be used in conjunction with Network desk supports.

Worksurfaces are 1/16" less than nominal width and 3/8" less than nominal depth for rear wire clearance.

Edge grommets are centered at rear edge of worksurface for maximum clearance of 1 3/8"

Worksurfaces require support every 48" in width. All supporting hardware is ordered separately.

Worksurfaces may be supported at each end by pedestals or end support "EC" brackets and cantilever brackets matching the worksurface depth. Use cantilever bridging bracket to join to adjacent worksurface.



Panel supported worksurfaces over 48" must be mid-span supported by cantilever brackets, specified separately.

Order Morrison brackets with wood screws ( suffix -W ).

# Universal and conference desk end panels

## *Morrison desks and panel-based planning*

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
	Desk height	17"	1 1/4"	26"	<b>MK4-U2618-P/V-( )</b>	\$279.	\$300.	\$348.	\$494.
		23"	1 1/4"	26"	<b>MK4-U2624-P/V-( )</b>	296.	348.	409.	590.
		29"	1 1/4"	26"	<b>MK4-U2630-P/V-( )</b>	313.	409.	472.	669.
		35"	1 1/4"	26"	<b>MK4-U2636-P/V-( )</b>	347.	472.	536.	764.
	Desk Height (Right hand shown)	17"	1 1/4"	26"	<b>MK4-C2618-P/V-( )-(L/R)</b>	347.	362.	409.	590.
		23"	1 1/4"	26"	<b>MK4-C2624-P/V-( )-(L/R)</b>	361.	409.	472.	684.
		29"	1 1/4"	26"	<b>MK4-C2630-P/V-( )-(L/R)</b>	376.	472.	536.	764.
		35"	1 1/4"	26"	<b>MK4-C2636-P/V-( )-(L/R)</b>	395.	536.	600.	860.

### Order Code

Example:	<b>MK4-U2624-P-612</b>
<b>MK4</b>	Desk panel
<b>U</b>	Desk panel type
<b>26</b>	Height
<b>24</b>	Width
<b>P</b>	Surface type
<b>612</b>	Finish

### Specification Information

*Surface type:*  
P- Painted  
V- Veneer

Specify L/R left or right hand application for conference end panels. Desk height end panels support worksurface at 28 1/4" or 28 3/4". 7"W end panels are used to support 18"D worksurfaces.

23"W end panels are used to support 24"D or 30"D worksurfaces with recessed grommets.

29"W end panels are used to support 30"D or 36"D worksurfaces.

35"W end panels are used to support 36"D worksurfaces.

### Application Notes

Veneer Group 1 end panels are quartered Techgrain®.

Veneer Group 2 end panels are figured Techgrain®.

Veneer Group 3 end panels are narrow heart, flat cut natural veneers.

Universal end panels may be used as end support for a worksurface, in conjunction with vertical panels (specify MB1-N separately) or kneehole filler panels.

Universal panels are predrilled to accept brackets or filler panels either direction.

**A universal end panel includes bracket MB1-T desk end panel/worksurface.**

Conference end panels are used for table desks and similar applications where neither pedestals nor filler panels are used.

Conference end panels cannot be mounted under rounded end surfaces with end grommets.

**A conference end panel includes brackets MB1-T, desk end panel/worksurface and MB1-D, conference end panel/worksurface.**


Universal and conference end panels are not used in conjunction with desk supports (see page 161).

# VDT corner and transitional end panels


## *Morrison desks and panel-based planning*

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
VDT corner panels (shipped in pairs)	Desk height	34"	1 1/4"	26"	<b>MK4-V2636-P/V-( )</b>	\$834.	\$977.	\$1,104.	\$1,544.
		40"	1 1/4"	26"	<b>MK4-V2642-P/V-( )</b>	918.	1,040.	1,182.	1,672.



description	type	w	d	h	pattern no.	Paint	V1	V2	V3
VDT transitional end panel	Desk height	35"	1 1/8"	26"	<b>MK4-X2636-P/V-( )-(L/R)</b>	408.	488.	568.	798.
		41"	1 1/8"	26"	<b>MK4-X2642-P/V-( )-(L/R)</b>	442.	536.	600.	828.



Worksurface Planning

### Order Code

Example:	<b>MK4-V2636-P-612</b>
<b>MK4</b>	Desk panel
<b>V</b>	Desk panel type
<b>26</b>	Height
<b>36</b>	Width
<b>P</b>	Surface type
<b>612</b>	Finish

### Specification Information

*Surface type:*  
P- Painted  
V- Veneer

### Application Notes

*VDT corner end panel widths:*      *Corresponding worksurface widths:*  
34"                              36"  
40"                              42"  
35"                              36"  
41"                              42"

VDT corner panels are wood desk panels ordered and shipped in pairs: one left and one right.

34"W VDT corner end panels support both sides of 36" VDT corner worksurfaces.

40"W VDT corner end panels support both sides of 42" VDT corner worksurfaces.

**VDT corner end panels include 2 MB1-T brackets, VDT corner end panels/worksurface and bracket MB1-L1, filler/desk end panel.**

VDT transitional end panels are used when one back edge of a VDT surface is supported by a vertical panel.

**A VDT transitional end panel includes bracket MB1-T, desk end panel/ worksurface. Specify bracket MB1-W 18 or 20(L or R) separately.**

Veneer Group 1 end panels are quartered Techgrain®.

Veneer Group 2 end panels are figured Techgrain®.


Veneer Group 3 end panels are narrow heart, flat cut natural veneers.

# Kneehole filler and transitional filler panels


## Morrison desks

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
Kneehole filler	Desk height	57"	1 1/8"	26"	<b>MK4-K6026-P/V-( )</b>	\$395.	\$520.	\$583.	\$828.
		63"	1 1/8"	26"	<b>MK4-K6626-P/V-( )</b>	442.	568.	632.	891.
		69"	1 1/8"	26"	<b>MK4-K7226-P/V-( )</b>	492.	600.	679.	956.
		75"	1 1/8"	26"	<b>MK4-K7826-P/V-( )</b>	558.	644.	723.	1,035.



Transitional filler	Desk height	58 1/2"	1 1/8"	26"	<b>MK4-T6026-P/V-( )</b>	395.	520.	583.	828.
		64 1/2"	1 1/8"	26"	<b>MK4-T6626-P/V-( )</b>	442.	568.	632.	891.
		70 1/2"	1 1/8"	26"	<b>MK4-T7226-P/V-( )</b>	492.	600.	679.	956.
		76 1/2"	1 1/8"	26"	<b>MK4-T7826-P/V-( )</b>	558.	644.	723.	1,035.





Order Code	Specification Information	Application Notes
Example: <b>MK4-T6026-P-612</b>	<i>Surface type:</i>	<i>Kneehole filler panel widths:</i>
<b>MK4</b> Desk panel	P- Painted	<i>Corresponding straight work surface widths:</i>
<b>T</b> Desk panel type	V- Veneer	<i>Corresponding rounded work surface widths:</i>
<b>60</b> Width		57" 60" 66" 72" 78"
<b>26</b> Height		60" 60" 66" 72" 78"
<b>P</b> Surface type		74 5/8" 77 3/8" - 86 3/8" 89 3/8" -
<b>612</b> Finish		
		Transitional filler panels are used between a universal desk end panel and a vertical panel.
		<b>A transitional filler panel includes bracket MB1-L1, filler panel/desk end panel. Specify bracket MB1-W 18 or 20(L or R) separately.</b>
		A transitional filler panel over 70"W is shipped with a center stabilizing bracket, MB1-AUX-D.
		Veneer Group 1 end panels are quartered Techgrain®.
		Veneer Group 2 end panels are figured Techgrain®.
		Veneer Group 3 end panels are narrow heart, flat cut natural veneers.
		Kneehole filler panels span use between two universal desk end panels to construct a freestanding wood desk.
		<b>A kneehole panel includes 2 brackets MB1-L1, filler panel/desk end panel.</b>
		All 69"W and 75"W kneehole filler panels are shipped with a center stabilizing bracket, MB1-AUX-D.



# Return and bridge filler panels

## Morrison desks

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
Return filler 	Desk height	32 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R3026-(P/V)-( )-(L/R)</b>	\$313.	\$379.	\$424.	\$605.
		38 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R3626-(P/V)-( )-(L/R)</b>	326.	409.	459.	654.
		44 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R4226-(P/V)-( )-(L/R)</b>	347.	442.	503.	700.
		50 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R4826-(P/V)-( )-(L/R)</b>	376.	472.	568.	780.
		62 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R6026-(P/V)-( )-(L/R)</b>	426.	552.	649.	891.
		68 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R6626-(P/V)-( )-(L/R)</b>	477.	600.	697.	956.
		74 <sup>3</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-R7226-(P/V)-( )-(L/R)</b>	541.	644.	742.	1,052.
Bridge filler 	Desk height	38 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B3026-(P/V)-( )</b>	313.	394.	442.	621.
		44 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B3626-(P/V)-( )</b>	326.	424.	469.	669.
		50 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B4226-(P/V)-( )</b>	347.	459.	520.	730.
		56 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B4826-(P/V)-( )</b>	376.	503.	568.	811.
		68 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B6026-(P/V)-( )</b>	442.	583.	662.	940.
		74 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B6626-(P/V)-( )</b>	492.	632.	723.	1,035.
		80 <sup>1</sup> / <sub>2</sub> "	1 <sup>1</sup> / <sub>8</sub> "	26"	<b>MK4-B7226-(P/V)-( )</b>	558.	662.	774.	1,099.

Worksurface Planning



Order Code	Specification Information	Application Notes	
Example: <b>MK4-R3026-P-612-L</b>	<i>Return filler</i>	Return filler panels provide enclosure between a universal desk end panel and the end panel of a return.	
<b>MK4</b> Desk panel	<i>Corresponding</i>		
<b>R</b> Desk panel type	<i>panel widths:</i>	Return filler panels may also be connected to a vertical panel to provide enclosure for a desk or machine height return off a panel supported workstation. Specify MB1-FV brackets separately.	
<b>30</b> Width	30"		
<b>26</b> Height	36"		
<b>P</b> Surface type	38 <sup>3</sup> / <sub>4</sub> "		
<b>612</b> Paint	44 <sup>3</sup> / <sub>4</sub> "		
<b>L</b> Left	42"		
	48"		
	60"		
	66"	All 69"W and 75"W return filler panels are shipped with a center stabilizing bracket, MB1-AUX-D.	
	72"		
	<i>Bridge filler</i>		
	<i>Corresponding</i>		
	<i>panel widths:</i>		
	30"		
	36"		
	42"		
	48"		
	60"	<b>A return filler panel includes bracket MB1-L1, filler panel/desk end panel and all connecting hardware.</b>	
	66"		
	72"		
	<i>Surface type:</i>		
	P- Painted		
	V- Veneer		
			Bridge filler panels are used between two universal end panels under a bridge worksurface. Bridge filler panels may also be specified for desk enclosure between two vertical panels (specify brackets MB1-FV separately.)
		All 69"W, 75"W and 81"W bridge filler panels are shipped with a center stabilizing bracket, MB1-AUX-D.	

# Brackets

## panel planning

### end support and VDT brackets

Morrison

description		type	w	d	h	pattern no.	paint	
 End support brackets-E with machine screws	End support	18"D straight worksurface	-	18"	1 1/4"	<b>MB3-E18M-()</b>	\$35.	
		24"D straight worksurface	-	24"	1 1/4"	<b>MB3-E24M-()</b>	37.	
		30"D straight worksurface	-	30"	1 1/4"	<b>MB3-E30M-()</b>	41.	
		36"D straight worksurface	-	36"	1 1/4"	<b>MB3-E36M-()</b>	47.	
	End support for 30" high panel	18"D straight worksurface	-	18"	1 1/4"	<b>MB3-EC18M-()*</b>	35.	
		24"D straight worksurface	-	24"	1 1/4"	<b>MB3-EC24M-()*</b>	37.	
		30"D straight worksurface	-	30"	1 1/4"	<b>MB3-EC30M-()*</b>	41.	
	VDT support	36"D VDT worksurface	36"	3/8"	1 1/4"	<b>MB3-EV36M-()</b>	47.	
		42"D VDT worksurface	42"	3/8"	1 1/4"	<b>MB3-EV42M-()</b>	49.	
		48"D VDT worksurface	48"	3/8"	1 1/4"	<b>MB3-EV48M-()</b>	52.	
	 End support brackets-E with wood screws	End support	18"D straight worksurface	-	18"	1 1/4"	<b>MB3-E18W-()</b>	35.
			24"D straight worksurface	-	24"	1 1/4"	<b>MB3-E24W-()</b>	37.
			30"D straight worksurface	-	30"	1 1/4"	<b>MB3-E30W-()</b>	41.
36"D straight worksurface			-	36"	1 1/4"	<b>MB3-E36W-()</b>	47.	
End support for 30" high panel		18"D straight worksurface	-	18"	1 1/4"	<b>MB3-EC18W-()*</b>	35.	
		24"D straight worksurface	-	24"	1 1/4"	<b>MB3-EC24W-()*</b>	37.	
		30"D straight worksurface	-	30"	1 1/4"	<b>MB3-EC30W-()*</b>	41.	
VDT support		36"D VDT worksurface	36"	3/8"	1 1/4"	<b>MB3-EV36W-()</b>	47.	
		42"D VDT worksurface	42"	3/8"	1 1/4"	<b>MB3-EV42W-()</b>	49.	
		48"D VDT worksurface	48"	3/8"	1 1/4"	<b>MB3-EV48W-()</b>	52.	
VDT end support bracket kits-V with machine screws (includes 2 VDT end brackets and 1 stabilizer bracket)			36"D VDT worksurface	36"	3/8"	1 1/4"	<b>MB3-V36M-()</b>	111.
			42"D VDT worksurface	42"	3/8"	1 1/4"	<b>MB3-V42M-()</b>	117.
			48"D VDT worksurface	48"	3/8"	1 1/4"	<b>MB3-V48M-()</b>	129.


Order Code	Specification Information	Application Notes
Example: <b>MB3-E30-M-612</b>	<i>Bracket type:</i>	E-type end support brackets support 1 1/4" or 1 3/4" worksurface from connector tracks at both back and front.
<b>MB3</b> Bracket	E- End support	Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.
<b>E</b> Bracket type	V- VDT corner end support	Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.
<b>30</b> Bracket depth	C- Cantilever	EV- bracket supports one back edge of VDT or curvilinear corner surface when other side is desk-supported.
<b>M</b> Machine screws	<i>Specify paint finish.</i>	V-type end support bracket kits support both back edges of 90° VDT corner worksurfaces.
<b>612</b> Paint finish		V-kits include two end support and one AUX-V.
		*MB3-EC18-(), MB3-EC24-(), and MB3-EC30-() end support brackets should be specified when supporting worksurfaces from 30" high panels or for supporting Currents work-surfaces for Morrison from all panel heights.

# Brackets

## panel planning

### end support and VDT brackets

description	type	w	d	h	pattern no.	paint
VDT end support bracket kits-V with wood screws (includes 2 VDT end brackets and 1 stabilizer bracket)	36"D VDT worksurface	36"	3/8"	1 1/4"	<b>MB3-V36W-()</b>	\$111.
	42"D VDT worksurface	42"	3/8"	1 1/4"	<b>MB3-V42W-()</b>	117.
	48"D VDT worksurface	48"	3/8"	1 1/4"	<b>MB3-V48W-()</b>	129.







Order Code	Specification Information	Application Notes
Example: <b>MB3-E30-M-612</b>	<i>Bracket type:</i>	E-type end support brackets support 1 1/4" or 1 3/4" worksurface from connector tracks at both back and front.
<b>MB3</b> Bracket	E- End support	Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.
<b>E</b> Bracket type	V- VDT corner end support	
<b>30</b> Bracket depth	C- Cantilever	
<b>M</b> Machine screws	<i>Specify paint finish.</i>	EV- bracket supports one back edge of VDT or curvilinear corner surface when other side is desk-supported.
<b>612</b> Paint finish		V-type end support bracket kits support both back edges of 90° VDT corner worksurfaces.
		V-kits include two end support and one AUX-V.
		Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.
		*MB3-EC18-(), MB3-EC24-(), and MB3-EC30-() end support brackets should be specified when supporting worksurfaces from 30" high panels or for supporting Currents work-surfaces for Morrison from all panel heights.

# Brackets

## panel planning

### cantilever brackets

Morrison

description	type	w	d	h	pattern no.	list price
 Cantilever brackets-C with machine screws	18"D worksurface	1/2"	15"	8 1/2"	<b>MB2-C18M-(L/R)-()</b>	\$45.
	24"D worksurface	1/2"	21"	11 1/2"	<b>MB2-C24M-(L/R)-()</b>	53.
	30"D worksurface	1/2"	24"	13 1/2"	<b>MB2-C30M-(L/R)-()</b>	62.
 Cantilever brackets-C with wood screws	18"D worksurface	1/2"	15"	8 1/2"	<b>MB2-C18W-(L/R)-()</b>	45.
	24"D worksurface	1/2"	21"	11 1/2"	<b>MB2-C24W-(L/R)-()</b>	53.
	30"D worksurface	1/2"	24"	13 1/2"	<b>MB2-C30W-(L/R)-()</b>	62.
Cantilever tie-clips-AUX-C (10)		-	-	-	<b>MB1-AUX-C</b>	12.
 Worksurface/vertical panel spacer-Y with machine screws		1/16"	15"	8 1/2"	<b>MB2-YM-(L/R)-()</b>	38.
 Worksurface/vertical panel spacer-Y with wood screws		1/16"	15"	8 1/2"	<b>MB2-YW-(L/R)-()</b>	38.







Order Code	Specification Information	Application Notes
Example: <b>MB2-C24W-R-612</b>	<i>Bracket type:</i>	C-type cantilever brackets support worksurfaces from connector track at the back. Specify left or right.
<b>MB2</b> Bracket	E- End support	Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.
<b>C</b> Bracket type	V- VDT corner end support	
<b>24</b> Bracket depth	C- Cantilever	AUX-C cantilever tie-clips tie together two adjacent cantilever brackets for added stability.
<b>W</b> Wood screws	Y- Worksurface/vertical panel spacer	Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.
<b>R</b> Left or right		
<b>612</b> Paint finish	<i>Specify paint finish.</i>	Y-type spacer brackets secure the end of pedestal-supported worksurfaces to a connector track. Y brackets maintain the 3/8" wire drop and allow pedestal fronts to align with the end of the worksurface.

# Brackets

## panel planning

### flat brackets, cantilever brackets

Morrison

description	type	w	d	h	pattern no.	list price
 Flat brackets with machine screws	18" surface	3 1/2"	8"	–	<b>MB3-F18M</b>	\$27.
	24" surface	3 1/2"	14"	–	<b>MB3-F24M</b>	30.
	30"/36" surfaces	3 1/2"	20"	–	<b>MB3-F30M</b>	33.
 Flat brackets with wood screws	18" surface	3 1/2"	8"	–	<b>MB3-F18W</b>	27.
	24" surface	3 1/2"	14"	–	<b>MB3-F24W</b>	30.
	30"/36" surfaces	3 1/2"	20"	–	<b>MB3-F30W</b>	33.
 Cantilever bridging with machine screws	18"D surfaces support brackets				<b>MB1-CB18M</b>	65.
	24"D surfaces				<b>MB1-CB24M</b>	77.
	30"D surfaces				<b>MB1-CB30M</b>	87.
 Cantilever bridging with wood screws	18"D surfaces support brackets				<b>MB1-CB18W</b>	65.
	24"D surfaces				<b>MB1-CB24W</b>	77.
	30"D surfaces				<b>MB1-CB30W</b>	87.
 VDT support panel kit-VP with machine screws		1"	12"	24"	<b>MB1-VP-1224M</b>	227.
		1"	12"	26"	<b>MB1-VP-1226M</b>	234.
 VDT support panel kit-VP with wood screws		1"	12"	24"	<b>MB1-VP-1224W</b>	227.
		1"	12"	26"	<b>MB1-VP-1226W</b>	234.

Worksurface Planning





Order Code	Specification Information	Application Notes
Example: <b>MB3-F24M</b>	<i>Bracket type:</i>	Flat bridging brackets attach two worksurfaces at the same height in 90° "L", VDT or end-to-end applications (in conjunction with floorstanding pedestal support).
<b>MB3</b> Bracket	F- Flat	VP-type brackets attach anywhere under worksurface to provide additional support in large freestanding desks or in vertical panel applications.
<b>F</b> Bracket type	CB- Cantilever bridging	Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.
<b>24</b> Bracket depth	VP- VDT support panel kit	Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.
<b>M</b> Machine screws		Flat bridging brackets are universal for freestanding or panel based planning.
		Cantilever bridging brackets provide cantilever support for curvilinear and VDT corner surfaces and returns at the same height. Cantilever bridging brackets may be used in conjunction with VDT end support brackets.

# Brackets

## panel planning

### desk end panel, pedestal extender, filler panel

Morrison

description		type	w	d	h	pattern no.	list price
Desk end panel/vertical panel-N 		with machine screws	–	–	–	<b>MB1-NM-(L/R)-()</b>	\$64.
		with wood screws	–	–	–	<b>MB1-NW-(L/R)-()</b>	64.
Pedestal extender-R 	shallow	24", desk ht.	1"	6"	26"	<b>MB2-RS2426-(L/R)-()</b>	133.
		30", desk ht.	1"	12"	26"	<b>MB2-RS3026-(L/R)-()</b>	157.
	deep	30", desk ht.	1"	6"	26"	<b>MB2-RD3026-(L/R)-()</b>	133.
		36", desk ht.	1"	12"	26"	<b>MB2-RD3626-(L/R)-()</b>	157.
Filler panel/vertical panel-FV 		Desk height				<b>MB1-FV26-(L/R)-()</b>	54.
Transitional filler panel/worksurface-W 		Desk height with machine screws				<b>MB1-W20M-(L/R)-()</b>	64.
		Desk height with wood screws				<b>MB1-W20W-(L/R)-()</b>	64.






Order Code	Specification Information	Application Notes
Example: <b>MB2-RS2426-R-612</b>	Specify left or right end of return or bridge worksurface.	N-type desk end panel/vertical panel brackets ensure alignment and rigidity between worksurface, universal end panel or pedestal extender, and back panel.
<b>MB2</b> Bracket	<i>Bracket type:</i>	R-type pedestal extender brackets close the gap between a pedestal and a vertical panel. Pedestal extender brackets can receive an MB1-N bracket to secure to a vertical panel, or a kneehole filler panel. Description indicates application by worksurface depth/pedestal depth/pedestal height.
<b>R</b> Pedestal extender	N- Desk end panel/vertical panel	FV-type filler panel/vertical panel brackets are used when a return or bridge filler panel is adjacent to a vertical panel end connector.
<b>S</b> Pedestal depth	RS- 18"D pedestal extender	Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.
<b>24</b> Worksurface depth	RD- 24"D pedestal extender	Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.
<b>26</b> Bracket height	FV- Filler panel/vertical panel	
<b>R</b> Right-hand	W- Transitional filler/worksurface	
<b>612</b> Paint finish	<i>Specify paint finish.</i>	W-type filler panel/worksurface brackets are used at the end of a transitional filler panel nearest to the vertical panel. The same bracket MB1-W20()- (L/R) is used for both machine and desk height.

# Brackets

## *panel planning*

### *end panel and filler panel*

Morrison

description	type	w	d	h	pattern no.	list price
Desk end panel/worksurface-T with machine screws 	18" surfaces				<b>MB1-T18M</b>	\$27.
	24"-36" surfaces				<b>MB1-T24M</b>	30.
Desk end panel/worksurface-T with wood screws 	18" surfaces				<b>MB1-T18W</b>	27.
	24"-36" surfaces				<b>MB1-T24W</b>	30.
Conference end panel/worksurface D 					<b>MB1-D</b>	56.
Desk panel mid span bracket - AUX-D 	with machine screws	-	-		<b>MB1-AUX-DM</b>	24.
	with wood screws	-	-		<b>MB1-AUX-DW</b>	24.
Filler panel/desk end panel- L1 					<b>MB1-L1</b>	24.




Worksurface Planning

Order Code	Specification Information	Application Notes
Example: <b>MB1-T18W</b>	<i>Bracket type:</i>	
<b>MB1</b> Bracket	T- Desk end panel/worksurface	Brackets on this page are replacement parts for Morrison desk panels.
<b>T</b> Bracket type	D- Conference end panel/worksurface	T-type bracket joins desk end panel to worksurface (included in all end panels).
<b>18</b> Bracket height	AUX-D- Filler panel/worksurface	D-type bracket provides additional stability for conference end panels (included in all conference end panels.)
<b>W</b> Wood screws	L1- Filler panel/desk end panel	L-bracket joins end panel to kneehole or return filler (included with all filler panels.) AUX-D bracket is included in all filler panels greater than 60" wide.
		Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces. Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.

# Morrison Network Desk System

## desk supports

Morrison

description	type	w	d	h	pattern no.	list price
 Straight desk supports	24"	24"	6"	26"	<b>MN2-D2400( )</b>	\$389.
	30"	30"	6"	26"	<b>MN2-D3000( )</b>	393.
	36"	36"	6"	26"	<b>MN2-D3600( )</b>	401.
	42"	42"	6"	26"	<b>MN2-D4200( )</b>	411.
	48"	48"	6"	26"	<b>MN2-D4800( )</b>	417.
	54"	54"	6"	26"	<b>MN2-D5400( )</b>	424.
	60"	60"	6"	26"	<b>MN2-D6000( )</b>	435.
	66"	66"	6"	26"	<b>MN2-D6600( )</b>	442.
	72"	72"	6"	26"	<b>MN2-D7200( )</b>	460.
	78"	78"	6"	26"	<b>MN2-D7800( )</b>	474.
 90° corner supports	36" x 36"	36"	36"	26"	<b>MN2-D3636( )</b>	641.
	42" x 42"	42"	42"	26"	<b>MN2-D4242( )</b>	654.
	48" x 48"	48"	48"	26"	<b>MN2-D4848( )</b>	672.
	60" x 60"	60"	60"	26"	<b>MN2-D6060( )</b>	705.
	72" x 72"	72"	72"	26"	<b>MN2-D7272( )</b>	750.
 Return supports	24"	18"	6"	26"	<b>MN2-D0024( )</b>	226.
	30"	24"	6"	26"	<b>MN2-D0030( )</b>	229.
	36"	30"	6"	26"	<b>MN2-D0036( )</b>	237.
	42"	36"	6"	26"	<b>MN2-D0042( )</b>	246.
	48"	42"	6"	26"	<b>MN2-D0048( )</b>	254.
	54"	48"	6"	26"	<b>MN2-D0054( )</b>	263.
	60"	54"	6"	26"	<b>MN2-D0060( )</b>	269.
	66"	60"	6"	26"	<b>MN2-D0066( )</b>	276.
	72"	66"	6"	26"	<b>MN2-D0072( )</b>	294.
	78"	72"	6"	26"	<b>MN2-D0078( )</b>	309.

### Order Code

Example:	<b>MN2-D4848-612</b>
<b>MN2</b>	Network component
<b>D</b>	Desk support
<b>48</b>	Width of desk
<b>48</b>	Width of return
<b>612</b>	Paint finish

### Specification Information

Specify desk support the width of the worksurface to be supported.

Corner desk support is used under any combination of worksurfaces up to 72". Specify flat brackets separately.

Return support may be connected to straight desk support to form other 90° corner support combinations. Specify return support the sum of the width of the return and the depth of the desk (or width of VDT).

Desk spans wider than 60" require pedestal support at one end of the worksurface.

*Specify painted finish.*

### Application Notes

Corner legs include two grommets (3" x 2 1/2") in back and side, for cable and power distribution to adjacent desk supports. All grommets have caps, 3 1/4" x 3 1/4". Two grommet sleeves to protect cables are also provided.

Desk supports enclose the back 6" of freestanding Morrison System desks, enabling full horizontal and vertical wire management, and giving the structural support necessary for desk mounted overhead storage.

Straight desk supports are specified the same width as the desk (or VDT + return). Return supports continue the wireway for L-shape desks, supporting the end of the desk and width of the return. 90° corner supports may be used to support desk-and-return or VDT-with-extensions.

Desk supports consist of nominal 6" x 6" corner legs and horizontal modesty/wireway channel 8"H x 1 1/2"D.

Straight desk supports include 2 legs and 1 channel; 90° corner supports include 3 legs and 2 channels. Return supports include 1 leg and 1 channel and connect to straight desk support to form 90° corner. All components are interchangeable and non-handed.

Worksurfaces are supported by desk supports in conjunction with end panels, pedestals or brackets linking to adjacent desks.

MN2- desk support corner legs and wireway channels are interchangeable with original MN1- desk supports.





Hardware kits for beam and leg components include metal inserts. Tops will be drilled for field installation.



# Morrison Network Desk System

## desk end and filler panels

Morrison

description	type	w	d	h	pattern no.	list price
		6"	1 1/4"	26"	<b>MN2-E06-( )</b>	\$226.
		7 1/2"	1 1/4"	26"	<b>MN2-E09-( )</b>	240.
	18"d	10 1/2"	1 1/4"	26"	<b>MN2-E12-( )</b>	254.
	24"d	16 1/2"	1 1/4"	26"	<b>MN2-E18-( )</b>	296.
	30"d	22 1/2"	1 1/4"	26"	<b>MN2-E24-( )</b>	326.
	Support panel	6"	1"	26"	<b>MN2-RDR( )</b>	229.
	Stanchion adapter kit	-	-	-	<b>MN2-RSAK</b>	13.
	Return support adapter	6"	1 1/4"	26"	<b>MN2-RER-( )</b>	127.
	18"d	18"	1 1/2"	8"	<b>MN2-EW18-( )</b>	127.
	24"d	24"	1 1/2"	8"	<b>MN2-EW24-( )</b>	141.

Worksurface Planning

### Order Code

Example: <b>MN2-E24-612</b>
<b>MN2</b> Morrison Network
<b>E</b> End panel
<b>24</b> Depth
<b>612</b> Finish

### Specification Information

Specify desk end and filler panels to correspond with desk depth and width. End panels are nominally 6" less deep than desk to accommodate desk support. Actual filler panels are 12" less wide than desk, to fit between desk support corner legs.

Return support adapter attaches to front edge of end panel. Specify return support in same nominal width as return worksurface.

*Specify painted finishes for end panels, filler panels and accessories.*

### Application Notes

Desk end panels are used to support an end of a freestanding desk without pedestal support. Integral brackets permit application on left or right end of desk.

For desk planning applications with full end panel and desk support:

Use MN2-E12 with 18"D worksurface

Use MN2-E18 with 24"D worksurface

Use MN2-E24 with 30"D worksurface

For 24"D VDT desks with extensions, specify MN2-E06 end panel and single bridging bracket. For 30"D VDT, specify MN2-E12 end panel and single bridging bracket.

For support of one end of 24"D return with desk support adjacent to freestanding Interaction corner table, specify MN2-E09.

Desk end panels do not permit adjacent pedestal attachment.

Transitional support panel secures a return desk support to Morrison vertical panel connector track in integrated desk and panel planning.

Transitional panel also acts as a leg or pedestal extender to stabilize vertical panels supporting overhead storage.

Use MN2-RDR to stabilize each side of vertical panel at half-round conference worksurface.

Transitional panel includes one grommet.


Return support adapter is specified when adding a return worksurface to a desk with end panel. Adapter extends from end panel to return support. End panel wireway attaches to inside of end panel to link desk support wireway to return support.

Filler panels provide full enclosure for desk supports, filling the knee-hole space between corner legs. They are specified in addition to corresponding desk supports.

# Morrison Network Desk System

## *desk end and filler panels*

Morrison

description	type	w	d	h	pattern no.	list price
Filler panel for desk support 	24"w	12"	1/2"	18"	<b>MN2-F24( )</b>	\$183.
	30"w	18"	1/2"	18"	<b>MN2-F30( )</b>	197.
	36"w	24"	1/2"	18"	<b>MN2-F36( )</b>	211.
	42"w	30"	1/2"	18"	<b>MN2-F42( )</b>	226.
	48"w	36"	1/2"	18"	<b>MN2-F48( )</b>	254.
	54"w	42"	1/2"	18"	<b>MN2-F54( )</b>	282.
	60"w	48"	1/2"	18"	<b>MN2-F60( )</b>	326.
	66"w	54"	1/2"	18"	<b>MN2-F66( )</b>	353.
	72"w	60"	1/2"	18"	<b>MN2-F72( )</b>	394.
78"w	66"	1/2"	18"	<b>MN2-F78( )</b>	437.	

### Order Code

Example: <b>MN2-E24-612</b>
<b>MN2</b> Morrison Network
<b>E</b> End panel
<b>24</b> Depth
<b>612</b> Finish

### Specification Information

Specify desk end and filler panels to correspond with desk depth and width. End panels are nominally 6" less deep than desk to accommodate desk support. Actual filler panels are 12" less wide than desk, to fit between desk support corner legs.

Return support adapter attaches to front edge of end panel. Specify return support in same nominal width as return worksurface.

*Specify painted finishes for end panels, filler panels and accessories.*

### Application Notes

Desk end panels are used to support an end of a freestanding desk without pedestal support. Integral brackets permit application on left or right end of desk.

For desk planning applications with full end panel and desk support:

Use MN2-E12 with 18"D worksurface

Use MN2-E18 with 24"D worksurface

Use MN2-E24 with 30"D worksurface

For 24"D VDT desks with extensions, specify MN2-E06 end panel and single bridging bracket. For 30"D VDT, specify MN2-E12 end panel and single bridging bracket.

For support of one end of 24"D return with desk support adjacent to freestanding Interaction corner table, specify MN2-E09.

Desk end panels do not permit adjacent pedestal attachment.

Transitional support panel secures a return desk support to Morrison vertical panel connector track in integrated desk and panel planning.

Transitional panel also acts as a leg or pedestal extender to stabilize vertical panels supporting overhead storage.

Use MN2-RDR to stabilize each side of vertical panel at half-round conference worksurface.

Transitional panel includes one grommet.


Return support adapter is specified when adding a return worksurface to a desk with end panel. Adapter extends from end panel to return support. End panel wireway attaches to inside of end panel to link desk support wireway to return support.

Filler panels provide full enclosure for desk supports, filling the knee-hole space between corner legs. They are specified in addition to corresponding desk supports.

# Morrison Network Desk System

## brackets

Morrison


description	type	w	d	h	pattern no.	paint
Desk support light seal					<b>MN2-DD( )</b>	\$85.
						
Desk support to pedestal					<b>MN1-DP</b>	13.
Flat brackets with machine screws	18"D worksurface	3 1/2"	8"	–	<b>MB3-F18M</b>	27.
	24"D worksurface	3 1/2"	14"	–	<b>MB3-F24M</b>	30.
	30"/36"D worksurface	3 1/2"	20"	–	<b>MB3-F30M</b>	33.
Single bridging bracket	18"D worksurface	3 1/2"	10"	5 1/4"	<b>MB1-SB18(L/R)</b>	64.
	24"D worksurface	3 1/2"	13 1/2"	5 1/4"	<b>MB1-SB24(L/R)</b>	76.
	30"D worksurface	3 1/2"	19 1/2"	5 1/2"	<b>MB1-SB30(L/R)</b>	82.
Dual bridging bracket	24"D worksurfaces	3 3/4"	13 1/2"	4"	<b>MB1-DB24</b>	130.
	30"D worksurfaces	3 3/4"	19 1/2"	5 1/2"	<b>MB1-DB30</b>	145.
Transitional support panel	Support panel	6"	1"	26"	<b>MN2-RDR( )</b>	229.
	Stanchion adapter kit	–	–	–	<b>MN2-RSAK</b>	13.
Worksurface stiffener	54" worksurface	43"	2 1/2"	1"	<b>MB1-WS54</b>	87.
	60" worksurface	49"	2 1/2"	1"	<b>MB1-WS60</b>	87.
	66" worksurface	55"	2 1/2"	1"	<b>MB1-WS66</b>	87.
	72" worksurface	61"	2 1/2"	1"	<b>MB1-WS72</b>	87.

Worksurface Planning


Order Code	Specification Information	Application Notes
Example: <b>MB1-SB24-L</b>	Specify paint finish for transitional support panel and light seal.	F-type flat brackets join worksurfaces at the same height, in desk or panel system application.
<b>MB1</b> Bracket	All other brackets are black.	For pedestal or end panel supported worksurface to half-round or teardrop, use flat brackets and support column.
<b>SB</b> Type	Specify single bridging bracket left or right handed (left for conference top on left when seated at worksurface).	For clear access kneespace at half-round with vertical panel, use transitional support panel, single bridging bracket, and support column.
<b>24</b> Worksurface size		Desk support light seal wraps around corner legs of adjacent desk supports, and provides additional lay-in cable.
<b>L</b> Left		Worksurface stiffeners may be used to span distances over 48" without pedestal support. (Use one size smaller than worksurface width when supporting one end with a pedestal.) Specify the pattern number which corresponds to the width to be spanned, e.g. MB1-WS54 enables a 3-ply MU1 or LU1 worksurface to span 54".
		SB bridging brackets are used to join desk supported worksurface to 1/2 round or teardrop, when worksurface is not pedestal supported. SB brackets may also be used with transitional support panel to join worksurface to teardrop or 1/2 round with vertical panel.
		MB1-SB18(L/R) single bridging bracket supports freestanding split VDT with 24" returns; it should be used on each side in combination with 9" end panels MNZE09( ).
		DB bridging bracket is used to join adjacent desk supports and worksurfaces.

*desk mounted overhead storage, counter, and power monument*

description	type	w	d	h	pattern no.	paint
Stanchions for desk mounted Reuter overhead storage, pair	1 3/4" worksurface	5"	5"	20"	<b>RO2-NS20( )</b>	\$387.
	1 1/4" worksurface	5"	5"	20 1/2"	<b>RO2-NS21( )</b>	387.




Stanchions for desk mount counter, pair	1 1/4" worksurface	5"	5"	13 1/2"	<b>MN2-NS14( )</b>	394.
---	--------------------	----	----	---------	--------------------	------




Reinforcement channel for desk mount counters	60" counter	48"	2"	1/2"	<b>MS2-URC60-N</b>	81.
	66" counter	54"	2"	1/2"	<b>MS2-URC66-N</b>	81.
	72" counter	60"	2"	1/2"	<b>MS2-URC72-N</b>	81.
	78" counter	66"	2"	1/2"	<b>MS2-URC78-N</b>	81.
	84" counter	72"	2"	1/2"	<b>MS2-URC84-N</b>	81.
	90" counter	78"	2"	1/2"	<b>MS2-URC90-N</b>	81.

Desktop power monument	1 3/4" worksurfaces	5"	5"	13"	<b>MN2-PMW( )</b>	197.
	1 1/4" worksurfaces	5"	5"	13 1/2"	<b>MN2-PMU( )</b>	197.




Order Code	Specification Information	Application Notes
Example: <b>MN2-PMU-612</b>	<i>Specify paint finish for overhead supports, monuments, and covers:</i>	<p>Stanchions and overhead supports are bolted to desk supported worksurfaces with grommets. Overheads may span over end of worksurface and width of return worksurface if grommets and desk support legs align with stanchions.</p> <p>Reuter stanchions support any width Reuter overhead cabinet, or shelf, and include cover plates and mounting hardware.</p> <p>Stanchions for desk mounted counter may be specified with MS2-shelves on page . Stanchions support shelf underside at 42"H, positioned above 15"H privacy screen.</p> <p>Specify reinforcement channel for counters wider than 60".</p>
<b>MN2</b> Network		
<b>PM</b> Power monument		
<b>U</b> 1 1/4" worksurface		
<b>612</b> Paint finish		
	<p>All stanchions include internal and surface concealment channels for task light cords.</p> <p>Desktop power monument attaches to grommet in freestanding or panel-supported worksurfaces. Monument includes top cap to align with 42"H panels, and front cover with four outlet openings.</p> <p>Specify stanchion outlets cover when planning PDC modules and/or power module in Reuter stanchions. Stanchion outlets cover has four openings; specify blank outlet fillers for unused openings.</p> <p>Specify desktop power module for desktop outlets in power monument or stanchions (see page 169).</p>	


*desk mounted overhead storage, counter, and power monument*

description	type	w	d	h	pattern no.	paint
Stanchion outlets cover 	1 3/4" worksurfaces	7"	1/2"	15"	<b>MN2-SO20( )</b>	\$35.
	1 1/4" worksurfaces	7"	1/2"	15 1/2"	<b>MN2-SO21( )</b>	35.
Blank outlet filler (10)					<b>MN2-OF</b>	35.

Order Code	Specification Information	Application Notes
Example: <b>MN2-PMU-612</b>	<i>Specify paint finish for overhead supports, monuments, and covers:</i>	<p>Stanchions and overhead supports are bolted to desk supported worksurfaces with grommets. Overheads may span over end of worksurface and width of return worksurface if grommets and desk support legs align with stanchions.</p> <p>Reuter stanchions support any width Reuter overhead cabinet, or shelf, and include cover plates and mounting hardware.</p> <p>Stanchions for desk mounted counter may be specified with MS2-shelves on page . Stanchions support shelf underside at 42"H, positioned above 15"H privacy screen.</p> <p>Specify reinforcement channel for counters wider than 60".</p>
<b>MN2</b> Network		
<b>PM</b> Power monument		
<b>U</b> 1 1/4" worksurface		
<b>612</b> Paint finish		
	<p>All stanchions include internal and surface concealment channels for task light cords.</p> <p>Desktop power monument attaches to grommet in freestanding or panel-supported worksurfaces. Monument includes top cap to align with 42"H panels, and front cover with four outlet openings.</p> <p>Specify stanchion outlets cover when planning PDC modules and/or power module in Reuter stanchions. Stanchion outlets cover has four openings; specify blank outlet fillers for unused openings.</p> <p>Specify desktop power module for desktop outlets in power monument or stanchions (see page 169).</p>	

Power distribution components  
 2+2™ Raceway  
 four circuit, eight-wire raceway for desk supports  
 power rails

description	type	w	d	h	pattern no.	list price
	30"w	12"	2"	2"	<b>MR3-NE30</b>	\$155.
	36"w	18"	2"	2"	<b>MR3-NE36</b>	171.
	42"w	24"	2"	2"	<b>MR3-NE42</b>	177.
	48"w	30"	2"	2"	<b>MR3-NE48</b>	183.
	54"w	30"	2"	2"	<b>MR3-NE54</b>	189.
	60"w	42"	2"	2"	<b>MR3-NE60</b>	196.
	66"w	48"	2"	2"	<b>MR3-NE66</b>	205.
	72"w	54"	2"	2"	<b>MR3-NE72</b>	211.
78"w	60"	2"	2"	<b>MR3-NE78</b>	218.	

	48"	30"	2"	2"	<b>MR3-NE48-4</b>	258.
	60"	42"	2"	2"	<b>MR3-NE60-4</b>	271.
	66"	48"	2"	2"	<b>MR3-NE66-4</b>	284.
	72"	54"	2"	2"	<b>MR3-NE72-4</b>	300.
	78"	60"	2"	2"	<b>MR3-NE78-4</b>	313.

Order Code	Specification Information
Example: <b>MR3-NE30</b>	
<b>MR3</b>	Morrison raceway
<b>N</b>	For Network desks
<b>E</b>	Eight wire 2 + 2
<b>30</b>	for 30" panel






Morrison 2 + 2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

**Application Notes**

Power rails are the primary power distribution component of the Morrison 2 + 2 Raceway. Each rail provides outlet mounting positions and receptacles for branching power connectors at each end. End brackets permit lay-in cabling in the desk support trough.

Rails accept two outlets, 12" from either end of the desk. Multiple outlet rails for 48" - 78" desks accept 4 duplex outlets, 12" and 18" from either end of desk.

Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for desk supports*  
*outlets, connectors, jumpers, infeeds*

description	type	w	d	h	pattern no.	list price
Duplex outlets, black 	Circuit A				<b>MR3-DA</b>	\$34.
	Circuit B				<b>MR3-DB</b>	34.
	Circuit X				<b>MR3-DX</b>	34.
	Circuit Y				<b>MR3-DY</b>	34.
Duplex outlets, orange 	Circuit X				<b>MR3-DXO</b>	39.
	Circuit Y				<b>MR3-DYO</b>	39.
Duplex outlets, black with orange triangle 	Circuit X				<b>MR3-DXT</b>	39.
	Circuit Y				<b>MR3-DYT</b>	39.
Power connector 	Straight/L	18"	2"	2"	<b>MR3-EPC</b>	75.
	Crossover	24"	2"	2"	<b>MR3-EJ6</b>	83.
	Panel/desk	36"	2"	3"	<b>MR3-NEPD</b>	271.
Jumper 	12" end panel	30"	2"	2"	<b>MR3-EJ12</b>	89.
	18" end panel	36"	2"	2"	<b>MR3-EJ18</b>	94.
	24" end panel	42"	2"	2"	<b>MR3-EJ24</b>	101.
	24" desk	42"	2"	2"	<b>MR3-EJ24</b>	101.
	30" desk	48"	2"	2"	<b>MR3-EJ30</b>	107.
	36" desk	54"	2"	2"	<b>MR3-EJ36</b>	117.
	42" desk	60"	2"	2"	<b>MR3-EJ42</b>	123.
	48" desk	66"	2"	2"	<b>MR3-EJ48</b>	129.
	54" desk	75"	2"	2"	<b>MR3-EJ54P</b>	136.
	60" desk	81"	2"	2"	<b>MR3-EJ60P</b>	142.
	66" desk	87"	2"	2"	<b>MR3-EJ66P</b>	149.
	72" desk	93"	2"	2"	<b>MR3-EJ72P</b>	155.
78" desk	99"	2"	2"	<b>MR3-EJ78P</b>	164.	

**Order Code**

Example: <b>MR3-NEPD</b>	
<b>MR3</b>	Morrison raceway
<b>N</b>	For Network desks
<b>E</b>	Eight wire 2 + 2
<b>PD</b>	Panel/desk

**Specification Information**

Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

**Application Notes**

Power infeeds connect building power supply to a cluster of interconnected power rails. Desk support infeed snaps into the end of any desk power rail, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box. Panel/desk connector transmits power between the end of a desk support rail and any panel base power rail outlet position.

Hardwire infeed, used in all New York City installations, includes junction box that mounts to the inside of a desk support corner leg. Electrical contractor supplies conduit from building power supply to box and trims power connector to length. Hardwire kit includes painted finish cover panel.


Duplex outlets are preconfigured to access one of the four circuits, A, B, X, Y, and snap into any standard outlet location (12" from either end of desk). Duplexes on circuits X and Y may be specified with orange face or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.

Power connectors transmit power between adjacent powered desks. Crossover transmits power "diagonally" between non-adjacent desks in a cluster of 3 or 4 desk supports.

Jumpers connect rails on either side of a desk end panel or desk support without outlets.

Power distribution components  
*2+2™ Raceway*  
*four circuit, eight-wire raceway for desk supports*  
*outlets, connectors, jumpers, infeeds*

description	type	w	d	h	pattern no.	list price
Power infeeds	Panel/desk connector				<b>MR3-NEPD</b>	\$271.
	Desk support infeed				<b>MR3-NEPI</b>	205.
	Hardwire infeed (NYC)				<b>MR3-NEPNY( )</b>	271.



**Order Code**

Example: <b>MR3-NEPD</b>
<b>MR3</b> Morrison raceway
<b>N</b> For Network desks
<b>E</b> Eight wire 2 + 2
<b>PD</b> Panel/desk

**Specification Information**

Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.

**Application Notes**

Power infeeds connect building power supply to a cluster of interconnected power rails. Desk support infeed snaps into the end of any desk power rail, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box. Panel/desk connector transmits power between the end of a desk support rail and any panel base power rail outlet position.

Hardwire infeed, used in all New York City installations, includes junction box that mounts to the inside of a desk support corner leg. Electrical contractor supplies conduit from building power supply to box and trims power connector to length. Hardwire kit includes painted finish cover panel.



Duplex outlets are preconfigured to access one of the four circuits, A, B, X, Y, and snap into any standard outlet location (12" from either end of desk). Duplexes on circuits X and Y may be specified with orange face or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.

Power connectors transmit power between adjacent powered desks. Crossover transmits power "diagonally" between non-adjacent desks in a cluster of 3 or 4 desk supports.

Jumpers connect rails on either side of a desk end panel or desk support without outlets.






Power distribution components  
**2+2™ Raceway**  
*four circuit, eight-wire raceway for desk supports*  
*accessories*

description	type	pattern no.	list price
 Desktop power module	From desk support power rail	<b>MR3-NESD</b>	\$205.
	From panel	<b>MR3-NESP</b>	325.
	Hardwire	<b>MR3-NESH</b>	258.
 Grommet outlet module	Directly above panel outlet	<b>MR3-EGM</b>	365.
	Duplex outlet, circuit A	<b>MR1-DA</b>	28.
	Duplex outlet, circuit B	<b>MR1-DB</b>	28.
	From desk support	<b>MR3-NEGM</b>	300.
	Hardwire	<b>MR3-EGMH</b>	271.
	Up to 24" away from panel outlet	<b>MR3-EGM48</b>	380.
Contact protectors (set of 10)		<b>MR3-CP</b>	11.
Wire manager clips (10)	Under worksurface	<b>MR1-WC</b>	31.
High capacity wire managers (10)	Panel connector	<b>ML1-HCWM24</b>	189.
Desk to desk cable sleeves (10)		<b>MN2-CS</b>	36.
Surge suppressors	Circuit A	<b>MR3-SP-A</b>	164.
	Circuit B	<b>MR3-SP-B</b>	164.
	Circuit X	<b>MR3-SP-X</b>	164.
	Circuit Y	<b>MR3-SP-Y</b>	164.

Order Code	Specification Information	Application Notes
Example: <b>MR3-NESD</b>		
<b>MR3</b> Morrison raceway		
<b>N</b> Network		
<b>E</b> Eight wire 2 + 2		
<b>S</b> Power infeed		
<b>D</b> Desk feed		
	<p>Morrison 2 +2™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 2 + 2™ Raceway components distribute two 20-amp convenience circuits (A and B), with neutral and ground, and two protected 20-amp circuits (X and Y) with separate neutral and ground.</p> <p>Duplex outlet circuits are designated by white letters on black background.</p>	<p>Desktop power module is power component for desktop power monument or overhead support stanchion. Power module includes two duplex outlets and power connector.</p> <p>Grommet outlet module stands in any Morrison (not Options) worksurface grommet for convenient access. Grommet outlet module accepts only special duplexes (MR1-DA or MR1-DB) on circuits A or B.</p> <p>Contact protectors enclose open conductors on power rail wherever outlets or power connectors are not planned.</p> <p>Cable sleeves contain and protect power and data cables passing between desk supports.</p> <p>Surge suppressors snap into outlet position adjacent to power infeed to protect all outlets on a circuit.</p>

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for desk supports*  
*power rail and module*

description	type	w	d	h	pattern no.	list price
 Power rail for desk support	30" w	12"	2"	2"	<b>MR3-NT30</b>	\$177.
	36" w	18"	2"	2"	<b>MR3-NT36</b>	189.
	42" w	24"	2"	2"	<b>MR3-NT42</b>	196.
	48" w	30"	2"	2"	<b>MR3-NT48</b>	205.
	54" w	42"	2"	2"	<b>MR3-NT54</b>	211.
	60" w	48"	2"	2"	<b>MR3-NT60</b>	218.
	66" w	54"	2"	2"	<b>MR3-NT66</b>	230.
	72" w	60"	2"	2"	<b>MR3-NT72</b>	236.
	78" w	66"	2"	2"	<b>MR3-NT78</b>	245.
 Multiple outlet power rail for desk	48" w	30"	2"	2"	<b>MR3-NT48-4</b>	313.
	60" w	42"	2"	2"	<b>MR3-NT60-4</b>	325.
	66" w	48"	2"	2"	<b>MR3-NT66-4</b>	341.
	72" w	54"	2"	2"	<b>MR3-NT72-4</b>	352.
	78" w	60"	2"	2"	<b>MR3-NT78-4</b>	365.
 Desktop power module	From desk support power rail				<b>MR3-NESD</b>	205.
	From panel				<b>MR3-NESP</b>	325.
	Hardwire				<b>MR3-NESH</b>	258.
Surge suppressors	Circuit A				<b>MR3-SP-A</b>	164.
	Circuit B				<b>MR3-SP-B</b>	164.
	Circuit C				<b>MR3-SP-C</b>	164.
	Circuit X				<b>MR3-SP-X</b>	164.
	Circuit Y				<b>MR3-SP-Y</b>	164.
	Circuit Z				<b>MR3-SP-Z</b>	164.

**Order Code**

Example:	<b>MR3-NT-30</b>
<b>MR3</b>	Morrison raceway
<b>NT</b>	Ten wire 3 + 3
<b>30</b>	For 30" panel

**Specification Information**

Morrison 3 + 3™ Raceway is a six-circuit, ten-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.

**Application Notes**



Power rails are the primary power distribution component of the Morrison 3 + 3 Raceway. Each rail provides outlet mounting positions and receptacles for branching power connectors at each end.

Rails accept two outlets, 12" from either end of desk. Multiple outlet rails for 48" - 78" desks accept four duplex outlets, 12" and 18" from either end of desk.

Desktop power module is power component for Desktop Power Monument or overhead support stanchion. Power module includes two duplex outlets, and power connector. First duplex outlet is wired to circuits A and B. Second duplex outlet to circuits X and Y.

Surge suppressors snap into outlet position adjacent to power infeed to protect all outlets on a circuit.

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for desk supports  
 connectors and jumpers*

description	type	w	d	h	pattern no.	list price
 Power connector	Straight/L	18"	2"	2"	<b>MR3-TPC</b>	\$94.
	Crossover	24"	2"	2"	<b>MR3-TJ6</b>	94.
	Panel/desk	36"	2"	3"	<b>MR3-NTPD</b>	313.
 Jumper	12" end panel	30"	2"	2"	<b>MR3-TJ12</b>	101.
	18" end panel	36"	2"	2"	<b>MR3-TJ18</b>	107.
	24" desk	42"	2"	2"	<b>MR3-TJ24</b>	117.
	24" end panel	42"	2"	2"	<b>MR3-TJ24</b>	117.
	30" desk	48"	2"	2"	<b>MR3-TJ30</b>	123.
	36" desk	54"	2"	2"	<b>MR3-TJ36</b>	129.
	42" desk	60"	2"	2"	<b>MR3-TJ42</b>	142.
	48" desk	66"	2"	2"	<b>MR3-TJ48</b>	155.
	54" desk	75"	2"	2"	<b>MR3-TJ54P</b>	164.
	60" desk	81"	2"	2"	<b>MR3-TJ60P</b>	171.
	66" desk	87"	2"	2"	<b>MR3-TJ66P</b>	177.
	72" desk	93"	2"	2"	<b>MR3-TJ72P</b>	183.
	78" desk	99"	2"	2"	<b>MR3-TJ78P</b>	189.

**Order Code**

Example: <b>MR3-TJ12</b>
<b>MR3</b> Morrison raceway
<b>T</b> Ten wire 3 + 3 jumper
<b>J</b> Jumper
<b>12</b> For 12" end panel

**Specification Information**

Morrison 3 + 3™ Raceway is a six-circuit, ten-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.





**Application Notes**

Power connectors transmit power between adjacent powered desks. Crossover transmits power "diagonally" between non-adjacent desks in a cluster of 3 or 4 desk supports.

Jumpers connect rails on either side of a desk end panel or desk support without outlets.

Power connectors and jumpers are enclosed in steel flexible conduit.

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for desk supports*  
*infeeds, outlets and cable sleeves*

description	type	pattern no.	list price
 Power infeeds	Desk support infeed	<b>MR3-NTPI</b>	\$230.
	Hardwire infeed (NYC)	<b>MR3-NTPNY()</b>	313.
	Panel/desk connector	<b>MR3-NTPD</b>	313.
 Duplex outlets, black	Circuit A	<b>MR3-DA</b>	34.
	Circuit B	<b>MR3-DB</b>	34.
	Circuit C	<b>MR3-DC</b>	34.
	Circuit X	<b>MR3-DX</b>	34.
	Circuit Y	<b>MR3-DY</b>	34.
	Circuit Z	<b>MR3-DZ</b>	34.
 Duplex outlets, orange	Circuit X	<b>MR3-DXO</b>	39.
	Circuit Y	<b>MR3-DYO</b>	39.
	Circuit Z	<b>MR3-DZO</b>	39.
 Duplex outlets, black with orange triangle	Circuit X	<b>MR3-DXT</b>	39.
	Circuit Y	<b>MR3-DYT</b>	39.
	Circuit Z	<b>MR3-DZT</b>	39.

**Order Code**

Example: <b>MR3-NTPI</b>
<b>MR3</b> Morrison raceway
<b>N</b> Network desk support
<b>T</b> Ten wire 3 + 3
<b>PI</b> Power infeed

**Specification Information**

Morrison 3 + 3™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.

Duplex outlet circuits are designated by white letters on black background, or black letters on orange background.

*Specify paint finishes for hardwire infeed kit.*

**Application Notes**

Power infeeds connect building power supply to a cluster of interconnected power rails. Desk support infeed snaps into the end of any desk power rail, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box. Panel/desk connector transmits power between the end of a desk support rail and any panel base power rail outlet position.

Hardwire infeed, used in all New York City installations, includes junction box that mounts to the inside of a desk support corner leg. Electrical contractor supplies conduit from building power supply to box and trims power connector to length. Hardwire kit includes painted finish cover panel.


Duplex outlets are preconfigured to access one of the six circuits, A, B, C, X, Y, Z, and snap into any standard outlet location. Duplexes on circuits X, Y, Z may be specified with orange face or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.

Grommet outlet module stands in any Morrison (not Options) worksurface grommet for convenient access. Grommet outlet module accepts only special duplexes (MR1-DA or MR1-DB) on circuits A or B.

Contact protectors enclose open conductors on power rail wherever outlets or power connectors are not planned.

Cable sleeves contain and protect power and data cables passing between desk supports.

Power distribution components  
**3+3™ Raceway**  
*six circuit, ten-wire raceway for desk supports*  
*infeeds, outlets and cable sleeves*



description	type	pattern no.	list price
 Grommet outlet module	Duplex outlet, circuit A	<b>MR1-DA</b>	\$28.
	Duplex outlet, circuit B	<b>MR1-DB</b>	28.
	From desk support	<b>MR3-NEGM</b>	300.
	Hardwire	<b>MR3-EGMH</b>	271.
Contact protectors (set of 10)		<b>MR3-CP</b>	11.
Desk to desk cable sleeves (10)		<b>MN2-CS</b>	36.

Order Code	Specification Information	Application Notes
Example: <b>MR3-NTPI</b> <b>MR3</b> Morrison raceway <b>N</b> Network desk support <b>T</b> Ten wire 3 + 3 <b>PI</b> Power infeed	<p>Morrison 3 + 3™ Raceway is a four-circuit, eight-wire modular power distribution system, for use in Morrison panels and Network desk supports. 3 + 3™ Raceway components distribute three 20-amp convenience circuits (A, B, C), with neutral and ground, and three protected 20-amp circuits (X, Y, Z) with separate neutral and ground.</p> <p>Duplex outlet circuits are designated by white letters on black background, or black letters on orange background.</p> <p><i>Specify paint finishes for hardwire infeed kit.</i></p>	<p>Power infeeds connect building power supply to a cluster of interconnected power rails. Desk support infeed snaps into the end of any desk power rail, and includes 6 foot liquid-tight conduit and pigtail for connection to floor or wall electrical box. Panel/desk connector transmits power between the end of a desk support rail and any panel base power rail outlet position.</p> <p>Hardwire infeed, used in all New York City installations, includes junction box that mounts to the inside of a desk support corner leg. Electrical contractor supplies conduit from building power supply to box and trims power connector to length. Hardwire kit includes painted finish cover panel.</p> <p>Duplex outlets are preconfigured to access one of the six circuits, A, B, C, X, Y, Z, and snap into any standard outlet location. Duplexes on circuits X, Y, Z may be specified with orange face or black face with orange triangle to signify protected circuits for electronic equipment; all other duplexes are black.</p> <p>Grommet outlet module stands in any Morrison (not Options) worksurface grommet for convenient access. Grommet outlet module accepts only special duplexes (MR1-DA or MR1-DB) on circuits A or B.</p> <p>Contact protectors enclose open conductors on power rail wherever outlets or power connectors are not planned.</p> <p>Cable sleeves contain and protect power and data cables passing between desk supports.</p>

# Floorstanding pedestals

## 18"D, 24"D, and 30"D

Morrison

description	type	w	d	h	pattern no.	P1	P2	P3	V1	V2	V3
	Desk height	14 <sup>7</sup> / <sub>8</sub> "	18"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-S2B1F(-)(-)</b>	\$821.	\$821.	\$862.	\$969.	\$1,052.	\$1,193.
		14 <sup>7</sup> / <sub>8</sub> "	24"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-D2B1F(-)(-)</b>	922.	922.	967.	1,052.	1,164.	1,276.
		14 <sup>7</sup> / <sub>8</sub> "	30"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-E2B1F(-)(-)</b>	1,024.	1,024.	1,076.	1,151.	1,247.	1,373.
	Desk height	14 <sup>7</sup> / <sub>8</sub> "	18"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-S0B2F(-)(-)</b>	729.	729.	764.	861.	919.	1,020.
		14 <sup>7</sup> / <sub>8</sub> "	24"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-D0B2F(-)(-)</b>	827.	827.	868.	955.	1,012.	1,116.
		14 <sup>7</sup> / <sub>8</sub> "	30"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-E0B2F(-)(-)</b>	926.	926.	972.	1,048.	1,107.	1,208.

### Order Code

Example:	<b>MD6-D2B1F-612-612</b>
<b>MD6</b>	Pedestal
<b>D</b>	Deep
<b>2B1F</b>	Configuration
<b>612</b>	Paint finish for case
<b>612</b>	Veneer/paint finish for drawer fronts

### Specification Information

Specify finishes for case and front.

All drawer pulls are matte black.

All pedestals are equipped with locks. Order pedestal locks with a KnollKey order form.

Veneer Group 1 drawerfronts are quartered Techgrain®.

Veneer Group 2 drawerfronts are figured Techgrain®.

Veneer Group 3 drawerfronts are narrow heart, flat cut natural veneers.

### Application Notes

18"D pedestals may be used under any Morrison worksurface. 24"D pedestals can be used under 30" and 36"D worksurfaces, without obstructing wire management through worksurface grommets.

24"D pedestals may also be installed under 24"D surfaces without grommets; 30"D pedestals may be used only under 30"D surfaces without grommets.

Pedestals are bolted into either end of any worksurface over 30"W. Insert locations and case construction permit use of pedestals as worksurface support, with or without universal desk end panels.

One box drawer divider is included with each 2 box, 1 file and 1 box, 1 file pedestal. Drawers accept up to 7 dividers, or 6 stationery insert trays.




All file drawers accommodate letter width filing front-to-back. 18"D file drawers accommodate legal files side-to-side. 24" and 30"D file drawer pedestals include one file support for legal filing, side-to-side.

Order file supports separately to equip other drawer in 24" or 30" deep 2 file.

# Double-width floorstanding pedestals and cabinets

## Network Double Wide

Morrison

description	type	w	d	h	pattern no.	P1	P2	P3	V1	V2	V3
Double-wide, 2 file 	30"W	29 <sup>3</sup> / <sub>4</sub> "	18"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-W0B2F-(-)(-)</b>	\$1,253.	\$1,253.	\$1,321.	\$1,458.	\$1,590.	\$1,820.
	36"W	35 <sup>3</sup> / <sub>4</sub> "	18"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD6-X0B2F-(-)(-)</b>	1,579.	1,579.	1,659.	1,883.	2,017.	2,263.
Double door cabinet 	30"W	29 <sup>3</sup> / <sub>4</sub> "	18"	26 <sup>5</sup> / <sub>8</sub> "	<b>MD4-WDD30-(-)(-)</b>	1,098.	1,098.	1,152.	1,333.	1,455.	1,695.
Letter filing kits	30"W	27"	-	9"	<b>MD6-WDK</b>		275.				
	36"W	33"	-	9"	<b>MD6-XDK</b>		275.				
Vertical dividers 	Set of 10				<b>MD6-VP</b>		106.				


Order Code	Specification Information	Application Notes
Example: <b>MD6-W0B2F-612-612</b>	<i>Specify finishes for case and front.</i>	
<b>MD6</b> Pedestal	All drawer pulls are matte black.	Double-wide pedestals can be used under 18", 24", 30" and 36"D worksurfaces.
<b>W</b> 2 file, double width	All pedestals are equipped with locks. Order pedestal locks with a KnollKey order form.	2-file pedestals allow legal filing side-to-side or front-to-back. Double door cabinet includes one adjustable shelf.
<b>0B2F</b> Configuration		
<b>612</b> Paint finish for case		
<b>612</b> Veneer/paint finish for fronts	Veneer Group 1 drawerfronts are quartered Techgrain®. Veneer Group 2 drawerfronts are figured Techgrain®. Veneer Group 3 drawerfronts are narrow heart, flat cut natural veneers.	Weight distribution limitations preclude using only double-width pedestals and worksurfaces to create freestanding credenzas. Letter filing partition kits include 2 vertical dividers and 2 movable backs, to allow side-to-side letter width filing. 30"W pedestals are bolted into either end of any worksurface, 30"W or more. Insert locations and case construction permit use of pedestals as worksurface support, with or without universal desk end panels.

# Double-width floorstanding pedestals and cabinets


## Options Double Wide

Morrison

description	type	w	d	h	pattern no.	P1	P2	P3	V1	V2	V3
Double-wide, 2 file	30"W	30"	19"	26 <sup>7</sup> / <sub>8</sub> "	<b>MD7 DW30C( )( )</b>	\$1,099.	\$1,099.	\$1,153.	\$1,268.	\$1,382.	\$1,584.
	36"W	36"	19"	26 <sup>7</sup> / <sub>8</sub> "	<b>MD7 DW36C( )( )</b>	1,394.	1,394.	1,462.	1,639.	1,753.	1,969.



Double door cabinet	30"W	30"	19"	26 <sup>7</sup> / <sub>8</sub> "	<b>MD7 DC30C( )( )</b>	955.	955.	1,003.	1,132.	1,228.	1,432.
---------------------	------	-----	-----	----------------------------------	------------------------	------	------	--------	--------	--------	--------



### Order Code

Example:	<b>MD7-DW30C-612-612</b>
<b>MD7</b>	Pedestal
<b>DW</b>	2 file, double width
<b>30C</b>	Configuration
<b>612</b>	Paint finish for case
<b>612</b>	Veneer/paint finish for fronts

### Specification Information

Specify finishes for case and front.  
All pedestals are equipped with locks. Order pedestal locks with a KnollKey order form.

Veneer Group 1 drawerfronts are quartered Techgrain®.

Veneer Group 2 drawerfronts are figured Techgrain®.

Veneer Group 3 drawerfronts are narrow heart, flat cut natural veneers.

### Application Notes

Options double-wide pedestals can be used under 18", 24", 30" and 36"D worksurfaces in panel planning applications only.





2-file pedestals allow legal filing side-to-side or front-to-back. Double door cabinet includes one adjustable shelf.

Weight distribution limitations preclude using only double-width pedestals and worksurfaces to create freestanding credenzas.



# Mobile pedestals 18"D

Morrison

description	type	w	d	h	pattern no.	P1	P2	P3	V1	V2	V3
1 box, 1 file	Machine or desk height	14 <sup>7</sup> / <sub>8</sub> "	18"	23 <sup>3</sup> / <sub>8</sub> "	<b>MD6-M1B1F-(-)(-)</b>	\$1,127.	\$1,127.	\$1,182.	\$1,242.	\$1,299.	\$1,387.
											
2 box, 1 file	Freestanding	14 <sup>7</sup> / <sub>8</sub> "	18"	29 <sup>3</sup> / <sub>8</sub> "	<b>MD6-M2B1F-(-)(-)</b>	1,377.	1,377.	1,445.	1,522.	1,600.	1,735.
											
2 file	Freestanding	14 <sup>7</sup> / <sub>8</sub> "	18"	29 <sup>3</sup> / <sub>8</sub> "	<b>MD6-M0B2F-(-)(-)</b>	1,180.	1,180.	1,239.	1,303.	1,367.	1,456.
											
Pencil tray		13 <sup>1</sup> / <sub>8</sub> "	6 <sup>1</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>4</sub> "	<b>MD6-PT</b>	32.					
											






Order Code	Specification Information	Application Notes
Example: <b>MD6-M1B1F-612-612</b>	<i>Specify finishes for case and front.</i>	Mobile pedestals include top with finger grip, locking casters, and counter weight. One box, one file mobile pedestal will fit under any Morrison worksurface at desk or machine height.
<b>MD6</b> Pedestal	All drawer pulls are matte black.	2 box/file or 2 file mobile pedestals are higher than standard desk height worksurfaces.
<b>M</b> Mobile	All pedestals are equipped with locks.	One box drawer divider is included with each 2 box, 1 file and 1 box, 1 file pedestal. Drawers accept up to 7 dividers or 5 stationery insert trays.
<b>1B1F</b> Configuration	Order locks with a KnollKey order form.	Mobile pedestal handle attaches to either height mobile pedestal top for easier movement around a facility. Handle stores on top of pedestal and unfolds for use.
<b>612</b> Painted finish for case		
<b>612</b> Veneer/paint finish for fronts		

Storage

# Pedestal accessories

## *Morrison Pedestals*

Morrison

description	type	w	d	h	pattern no.	list price
Pencil tray 		12 1/4"	6 1/4"	1 1/4"	<b>MD6-PT</b>	\$32.
Stationery inserts, set of four trays 		—	—	—	<b>MD6-ST</b>	130.
Drawer divider 	Box				<b>MD6-BD</b>	28.
	File				<b>MD6-FD</b>	28.
File support (set of 2) 					<b>MD6-FS</b>	11.
Mobile pedestal handle 					<b>MD6-PULL-( )</b>	126.

### Order Code

Example: **MD6-PT**

**MD6** Pedestal

**PT** Pencil tray

### Application Notes

Pencil tray rests on any box drawer.

Stationery inserts are sloped trays for 18"D box drawer.

Specify two sets of inserts for 24" or 30"D box drawers.

Drawer dividers are sloped U-shape inserts for box or file drawers.





Specify file support for side-to-side filling in 24" or 30" file drawers.

Mobile pedestal handle attaches to either height mobile pedestal top for easier movement around a facility. Handle stores on top of pedestal and unfolds for use.

# Intermediate shelves

*Designed by John Rizzi*

Morrison

description	type	w	d	h	pattern no.	Paint
Full width 	60"	60"	10"	3/4"	<b>MM3-IS60F( )</b>	\$306.
	66"	66"	10"	3/4"	<b>MM3-IS66F( )</b>	346.
	72"	72"	10"	3/4"	<b>MM3-IS72F( )</b>	385.
	78"	78"	10"	3/4"	<b>MM3-IS78F( )</b>	442.
Returns 	60"	60"	10"	3/4"	<b>MM3-IS60R( )</b>	270.
	66"	66"	10"	3/4"	<b>MM3-IS66R( )</b>	306.
	72"	72"	10"	3/4"	<b>MM3-IS72R( )</b>	346.
	78"	78"	10"	3/4"	<b>MM3-IS78R( )</b>	385.
Half round endpiece		11"	22"	3/4"	<b>MM3-ISE( )</b>	134.
						
Quarter round endpiece		10"	10"	3/4"	<b>MM3-ISX( )</b>	79.
						

## Order Code

Example:	<b>MM3-IS72R-612</b>
<b>MM3</b>	Accessory
<b>IS</b>	Intermediate shelves
<b>72</b>	Width
<b>R</b>	Return
<b>612</b>	Paint finish

## Specification Information

*Specify paint finish.*

Specify return shelves by number that corresponds to total return dimension (depth of desk and width of return).

## Application Notes

Intermediate shelves provide an additional level of storage between the worksurface and standard overhead storage.


Intermediate shelves include brackets for cantilever support from vertical panel connector tracks.

Intermediate shelves may be mounted on 1" increments of height up to 1" from top of panel. Recommended position is 6" - 7" above the worksurface.

Use full width shelves with back panels of the same total width. Add returns to form a continuous "L". Half-round endpiece joins back-to-back shelves over a half-round conference worksurface. Quarter round terminates an intermediate shelf at a straight panel connection.

Intermediate shelves cannot be mounted to freestanding desks or overhead supports.

Use full width intermediate shelves that correspond with actual workstation width.

description	w	d	h	pattern no.	list
Aluminum shelf with panel brackets 	24"	8"	1"	<b>MM3-AS24-( )</b>	\$345.
	30"	8"	1"	<b>MM3-AS30-( )</b>	367.
	36"	8"	1"	<b>MM3-AS36-( )</b>	389.
	42"	8"	1"	<b>MM3-AS42-( )</b>	409.
	48"	8"	1"	<b>MM3-AS48-( )</b>	427.
	60"	8"	1"	<b>MM3-AS60-( )</b>	467.
	72"	8"	1"	<b>MM3-AS72-( )</b>	504.

### Order Code

Example: <b>MM3-AS48-613</b>
<b>MM3</b> Accessory
<b>AS</b> Aluminum Shelf
<b>48</b> Width
<b>613</b> Bracket finish

### Specification Information

Specify shelf width and paint finish for brackets.

Shelf is extruded aluminum with an anodized finish. Shelf end caps are painted silver.

### Application Notes

Aluminum display shelves provide an additional level of storage between the worksurface and standard overhead storage.




Aluminum display shelves include brackets for support from vertical panel connector tracks.

Shelves may be mounted on any combination of vertical panels of the same total width.

Shelves may extend 12" past the mounting bracket on either side.


Shelves and flush counter surfaces, 1 3/4"  
panel or wall mounted  
steel bookshelves

Morrison

description	type	w	d	h	pattern no.	paint
		24"	13"	1 3/4"	<b>MS1-S2413-()</b>	\$217.
		30"	13"	1 3/4"	<b>MS1-S3013-()</b>	232.
		36"	13"	1 3/4"	<b>MS1-S3613-()</b>	251.
		42"	13"	1 3/4"	<b>MS1-S4213-()</b>	285.
		48"	13"	1 3/4"	<b>MS1-S4813-()</b>	360.
		60"	13"	1 3/4"	<b>MS1-S6013-()</b>	410.
	Bookend (pair)	-	13"	6"	<b>MB1-B13-()</b>	67.
	Shelf auxiliary support	-	-	-	<b>MB2-AUX-S-()</b>	33.
	Tie clip, adjacent	-	-	-	<b>MB1-TC-()</b>	8.
	Undershelf (pair)	-	13"	8"	<b>MB1-C13-()</b>	67.
Shelf organizers, black (10)		-	-	-	<b>MS1-SO</b>	33.
	Transaction shelf brackets (set of four)	1"	4"	6"	<b>MB2-TS-()</b>	76.

Order Code	Specification Information	Application Notes	
Example: <b>MS1-S2413-612</b>	<i>Specify paint finish for brackets and steel shelves.</i>	<p>All steel bookshelves have holes for shelf organizers (do not add -H).</p> <p>13"D shelves hold binders, books and other reference material. Order brackets and shelf organizers, if applicable, separately.</p> <p>13"D steel bookshelves come with holes for shelf organizers. Only bookend-style brackets are approved for use with steel shelves.</p>	
<b>MS1W</b> Shelf			<p>Standard 13" deep shelves double as flush counter surfaces. Specify undershelf or transaction shelf brackets for this application. Each set supports a maximum span of 48". Shelves over 60"W require MB2-AUX-S auxiliary support brackets.</p> <p>All shelf brackets accept task light fixtures with the exception of the transaction shelf brackets MB2-TS-(). Adjacent bookend-style shelf brackets require MB1-TC tie clip to secure full-width task light.</p> <p>For wall mounting shelves see page 188.</p> <p>Desk mounted counter surfaces do not accept task lights.</p>
<b>24</b> Width			
<b>13</b> Depth			
<b>612</b> Surface finish			

Shelves and flush counter surfaces, 1 3/4"  
panel or wall mounted  
laminated and veneer shelves

description	w	d	h	pattern no.	with holes (suffix-H)			without holes				
					lam	V1	V2	V3	lam	V1	V2	V3
Panel mounted shelves and flush counter surfaces 	24"	13"	1 3/4"	<b>MS2-W2413-( )</b>	\$225.	\$313.	\$345.	\$486.	\$212.	\$298.	\$332.	\$472.
	30"	13"	1 3/4"	<b>MS2-W3013-( )</b>	245.	345.	379.	537.	233.	332.	368.	524.
	36"	13"	1 3/4"	<b>MS2-W3613-( )</b>	276.	396.	443.	621.	263.	383.	431.	609.
	42"	13"	1 3/4"	<b>MS2-W4213-( )</b>	309.	443.	511.	723.	296.	431.	498.	709.
	48"	13"	1 3/4"	<b>MS2-W4813-( )</b>	343.	511.	564.	824.	330.	498.	551.	812.
	60"	13"	1 3/4"	<b>MS2-W6013-( )</b>	375.	580.	661.	941.	363.	567.	648.	929.
	66"	13"	1 3/4"	<b>MS2-W6613-( )</b>	409.	644.	727.	1,028.	396.	630.	712.	1,015.
	72"	13"	1 3/4"	<b>MS2-W7213-( )</b>	440.	694.	777.	1,093.	427.	679.	762.	1,081.
	78"	13"	1 3/4"	<b>MS2-W7813-( )</b>	472.	758.	841.	1,194.	460.	745.	828.	1,181.
	84"	13"	1 3/4"	<b>MS2-W8413-( )</b>	506.	809.	909.	1,295.	494.	795.	896.	1,283.
	90"	13"	1 3/4"	<b>MS2-W9013-( )</b>	539.	876.	974.	1,379.	526.	862.	962.	1,369.

**Order Code**

Example: <b>MS2-W4213-612-H</b>
<b>MS2W</b> Shelf
<b>42</b> Width
<b>13</b> Depth
<b>612</b> Surface finish
<b>H</b> With holes

**Specification Information**

*Specify finish for shelves.*

**Application Notes**

*Note:*  
Add H to pattern number for shelf holes that accept shelf organizers.

Veneer Group 1 shelves are quartered Techgrain®.

Veneer Group 2 shelves are rift cut Techgrain®.

Veneer Group 3 shelves are narrow heart, flat cut natural veneers.

13"D shelves hold binders, books and other reference material. Order brackets and shelf organizers, if applicable, separately.

13"D steel bookshelves come with holes for shelf organizers. Only bookend-style brackets are approved for use with steel shelves.

Standard 13" deep shelves double as flush counter surfaces. Specify undershelf or transaction shelf brackets for this application. Each set supports a maximum span of 48". Shelves over 60"W require MB1-AUX-S auxiliary support brackets.



All shelf brackets accept task light fixtures with the exception of the transaction shelf brackets MB2-TS-( ). Adjacent bookend-style shelf brackets require MB1-TC tie clip to secure full-width task light.

For wall mounting shelves see page 188.

Desk mounted counter surfaces do not accept task lights.

Shelves and flush counter surfaces, 1 1/4"  
 panel or wall mounted  
 laminate and veneer shelves

Morrison

description	type	w	d	h	pattern no.	lam.	V1	V2	V3
Shelves without holes 		24"	13"	1 1/4"	<b>MS2-U2413( )</b>	\$152.	\$245.	\$274.	\$400.
		30"	13"	1 1/4"	<b>MS2-U3013( )</b>	178.	274.	292.	444.
		36"	13"	1 1/4"	<b>MS2-U3613( )</b>	210.	305.	367.	523.
		42"	13"	1 1/4"	<b>MS2-U4213( )</b>	227.	349.	411.	601.
		48"	13"	1 1/4"	<b>MS2-U4813( )</b>	258.	411.	471.	693.
		60"	13"	1 1/4"	<b>MS2-U6013( )</b>	305.	470.	540.	790.
		66"	13"	1 1/4"	<b>MS2-U6613( )</b>	329.	506.	582.	849.
		72"	13"	1 1/4"	<b>MS2-U7213( )</b>	354.	544.	625.	912.
		78"	13"	1 1/4"	<b>MS2-U7813( )</b>	375.	579.	668.	973.
		84"	13"	1 1/4"	<b>MS2-U8413( )</b>	400.	616.	708.	1,034.
	90"	13"	1 1/4"	<b>MS2-U9013( )</b>	423.	651.	752.	1,094.	
Shelves with holes 		24"	13"	1 1/4"	<b>MS2-U2413( )H</b>	164.	258.	287.	413.
		30"	13"	1 1/4"	<b>MS2-U3013( )H</b>	193.	287.	305.	458.
		36"	13"	1 1/4"	<b>MS2-U3613( )H</b>	224.	318.	378.	536.
		42"	13"	1 1/4"	<b>MS2-U4213( )H</b>	241.	363.	423.	614.
		48"	13"	1 1/4"	<b>MS2-U4813( )H</b>	271.	423.	485.	705.
		60"	13"	1 1/4"	<b>MS2-U6013( )H</b>	318.	484.	553.	803.
		66"	13"	1 1/4"	<b>MS2-U6613( )H</b>	341.	519.	594.	861.
		72"	13"	1 1/4"	<b>MS2-U7213( )H</b>	367.	556.	639.	926.
		78"	13"	1 1/4"	<b>MS2-U7813( )H</b>	388.	592.	678.	986.
		84"	13"	1 1/4"	<b>MS2-U8413( )H</b>	413.	629.	722.	1,047.
	90"	13"	1 1/4"	<b>MS2-U9013( )H</b>	437.	667.	762.	1,109.	

**Order Code**

Example: <b>MS2-U-4213-612-H</b>
<b>MS2</b> Shelf
<b>U</b> 1 1/4" thick
<b>42</b> Width
<b>13</b> Depth
<b>612</b> Surface finish
<b>H</b> With holes

**Specification Information**

*Specify finish.*  
 Specify suffix H for shelf holes that accept shelf organizers.  
 Veneer Group 1 shelves are quartered Techgrain®.  
 Veneer Group 2 shelves are rift cut Techgrain®.  
 Veneer Group 3 shelves are narrow heart, flat cut natural veneer.


**Application Notes**


Panel mounted shelves are cantilevered from vertical panel connector tracks with bookend or undershelf brackets. 1 1/4" shelves must be midspan supported every 48".  
 13"D shelves hold binders, books and other reference material. Order brackets and shelf organizers, if applicable, separately.  
 Bookend-style brackets keep material upright when vertical panels are not used at the ends of shelves (brackets are shipped in pairs.)

Standard 13" deep shelves double as flush counter surfaces. Specify undershelf brackets or desk-mount stanchions for this application.  
 For wall mounted shelves see page 188.  
 All shelves accept task lights. Adjacent bookend-style shelves require MB1-TC tie clip to secure full width task light.  
 Transaction shelf brackets support panel-mounted shelves without holes. Each set supports a maximum span of 48".

Shelves and flush counter surfaces, 1 1/4"  
panel or wall mounted  
shelf brackets

Morrison

description	type	w	d	h	pattern no.	paint
	1 1/4" shelf auxiliary support	-	-	-	<b>MB1-UAUXS-( )</b>	\$33.
	Bookend (pair)	-	13"	6"	<b>MB1-B13-( )</b>	67.
	Tie clip, adjacent shelves	-	-	-	<b>MB1-TC( )</b>	8.
	Undershelf (pair), 1 1/4"	-	13"	8"	<b>MB1-UC13-( )</b>	67.
Shelf organizers, black (10)		-	-	-	<b>MS1-SO</b>	33.
Transaction shelf brackets (set of four)		1"	4"	6"	<b>MB2-TS-( )</b>	76.



**Order Code**

Example: <b>MB1-UAUXS-611</b>	
<b>MB1-</b>	Shelf bracket
<b>UAUXS</b>	
<b>611</b>	Finish

**Application Notes**

Panel mounted shelves are canti-levered from vertical panel connector tracks with bookend or undershelf brackets. 1 1/4" shelves must be midspan supported every 48".

13"D shelves hold binders, books and other reference material. Order brackets and shelf organizers, if applicable, separately.

Bookend-style brackets keep material upright when vertical panels are not used at the ends of shelves (brackets are shipped in pairs.)

Standard 13" deep shelves double as flush counter surfaces. Specify undershelf brackets or desk-mount stanchions for this application.

For wall mounted shelves see page 188.

All shelves accept task lights. Adjacent bookend-style shelves require MB1-TC tie clip to secure full width task light.



Transaction shelf brackets support panel-mounted shelves without holes. Each set supports a maximum span of 48".



# Morrison overhead cabinets

## panel mounted

Morrison

description	w	d	h	pattern no.	Paint	V1	V2	V3
 Painted or veneer front, panel mounted - lock	30"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-30-( )-( )-N-L</b>	\$671.	\$745.	\$795.	\$892.
	36"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-36-( )-( )-N-L</b>	774.	858.	910.	1,007.
	42"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-42-( )-( )-N-L</b>	895.	975.	1,037.	1,141.
	48"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-48-( )-( )-N-L</b>	996.	1,087.	1,155.	1,271.
	60"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-60-( )-( )-N-L</b>	1,199.	1,314.	1,395.	1,555.
 Painted or veneer front, panel mounted - No lock	30"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-30-( )-( )-N-N</b>	610.	686.	737.	832.
	36"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-36-( )-( )-N-N</b>	713.	798.	850.	949.
	42"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-42-( )-( )-N-N</b>	831.	914.	978.	1,082.
	48"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-48-( )-( )-N-N</b>	933.	1,027.	1,094.	1,214.
	60"	14"	17 <sup>3</sup> / <sub>4</sub> "	<b>MO8-60-( )-( )-N-N</b>	1,137.	1,256.	1,337.	1,498.
Vertical dividers (10)	-	-	-	<b>MO7-VD-( )</b>	115.			

### Order Code

Example:	<b>MO8-60-612-612-N-N</b>
<b>MO8</b>	Overhead cabinet
<b>60</b>	Width
<b>612</b>	Paint finish for case
<b>612</b>	Surface finish for door
<b>N</b>	Black pulls
<b>N</b>	No lock

### Specification Information

*Specify finishes for case and front.*

Overhead cabinet door pulls are matte black.

Order overhead cabinet locks with a KnollKey order form.

Veneer Group 1 cabinet doors are quartered Techgrain®.

Veneer Group 2 cabinet doors are figured Techgrain®.

Veneer Group 3 cabinet doors are narrow heart, flat cut natural veneer.

### Application Notes

Overhead cabinets are hung from vertical panels with removable brackets. Cabinet door recedes within cabinet to allow use of top of overhead for storage or lighting.



Interior shelves have slots for vertical dividers.

Order vertical dividers separately.

# Task lights for panel or wall mounted storage

## *Morrison shelves and overheads*

Morrison


description	w	d	h	pattern no.	list price	light	with dimmer	with electronic ballast
High efficiency task 	30"	12 1/2"	2 1/4"	<b>ML3-T30(-)</b>		\$386.	\$444.	\$423.
	36"	12 1/2"	2 1/4"	<b>ML3-T36(-)</b>		401.	458.	440.
	42"	12 1/2"	2 1/4"	<b>ML3-T42(-)</b>		416.	474.	453.
	48"	12 1/2"	2 1/4"	<b>ML3-T48(-)</b>		430.	488.	468.
	60"	12 1/2"	2 1/4"	<b>ML3-T60(-)</b>		476.	535.	514.
	66"	12 1/2"	2 1/4"	<b>ML3-T66(-)</b>		519.	577.	558.
	72"	12 1/2"	2 1/4"	<b>ML3-T72(-)</b>		549.	607.	587.
	78"	12 1/2"	2 1/4"	<b>ML3-T78(-)</b>		579.	638.	617.
	84"	12 1/2"	2 1/4"	<b>ML3-T84(-)</b>		610.	n/a	646.
	90"	12 1/2"	2 1/4"	<b>ML3-T90(-)</b>		682.	n/a	722.
Task 	30"	12 1/2"	2 1/4"	<b>ML4-F30(-)</b>		208.	265.	
	36"	12 1/2"	2 1/4"	<b>ML4-F36(-)</b>		238.	296.	
	42"	12 1/2"	2 1/4"	<b>ML4-F42(-)</b>		266.	326.	
	48"	12 1/2"	2 1/4"	<b>ML4-F48(-)</b>		312.	370.	
	60"	12 1/2"	2 1/4"	<b>ML4-F60(-)</b>		341.	400.	
	66"	12 1/2"	2 1/4"	<b>ML4-F66(-)</b>		372.	430.	
	72"	12 1/2"	2 1/4"	<b>ML4-F72(-)</b>		401.	458.	
Wire managers (set of 10)	-	-	-	<b>ML2-WM</b>	96.			

Order Code	Specification Information	Application Notes
Example: <b>ML3-TD48-612</b>		
<b>ML3</b> Lighting	Insert suffix "D" for dimmer switch after the T or F in pattern number. Insert suffix "E" for electronic ballast after the fixture width in pattern number - e.g. ML3T36E( ).	High efficiency lights include Octron lamp, 9' grounded cordset, batwing lens, rocker switch, and integral mounting brackets. Lens is tinted to distribute an average 60 foot candles over entire worksurface without glare.
<b>T</b> Fixture type	No dimmer on fluorescent lamps with electronic ballasts.	Cordsets on 30"-72" lights exit at center of fixture. Cordsets on 78"-90" task lights and all ambient lights exit the right side of the fixture, and may be changed to the left side in the field.
<b>D</b> With dimmer	For Chicago task lights, add CH to pattern number and \$45 list.	Task lights include standard fluorescent cool white lamp, 9' grounded cordset, prismatic lens, rocker switch, and integral mounting brackets.
<b>48</b> Width	For New York task lights, add NY to pattern number.	Task and high efficiency task lights may be mounted to any equal-width combination of shelves or overheads; not for use with Morrison Options.
<b>612</b> Paint finish		Lights with dimmer include 3-position rocker switch.
		Reuter overhead cabinets do not accept ML1-, ML2- or ML3- task or ambient lights.
		Morrison Network lighting is UL listed. UL File E 102458/E 102459. Can be hardwired where required.

# Morrison Network overhead storage

## desk mounted Morrison overheads

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
	Lock	30"	14"	17 3/4"	<b>MO8-N30( ) ( )NL</b>	\$671.	\$745.	\$795.	\$892.
		36"	14"	17 3/4"	<b>MO8-N36( ) ( )NL</b>	774.	858.	910.	1,007.
		42"	14"	17 3/4"	<b>MO8-N42( ) ( )NL</b>	895.	975.	1,037.	1,141.
		48"	14"	17 3/4"	<b>MO8-N48( ) ( )NL</b>	996.	1,087.	1,155.	1,271.
		60"	14"	17 3/4"	<b>MO8-N60( ) ( )NL</b>	1,199.	1,314.	1,395.	1,555.
	No lock	30"	14"	17 3/4"	<b>MO8-N30( ) ( )NN</b>	610.	686.	737.	832.
		36"	14"	17 3/4"	<b>MO8-N36( ) ( )NN</b>	713.	798.	850.	949.
		42"	14"	17 3/4"	<b>MO8-N42( ) ( )NN</b>	831.	914.	978.	1,082.
		48"	14"	17 3/4"	<b>MO8-N48( ) ( )NN</b>	933.	1,027.	1,094.	1,214.
		60"	14"	17 3/4"	<b>MO8-N60( ) ( )NN</b>	1,137.	1,256.	1,337.	1,498.
Back for stanchion mounted overheads		30"	3/8"	17 3/4"	<b>MO7-NB30( )</b>	215.			
		36"	3/8"	17 3/4"	<b>MO7-NB36( )</b>	229.			
		42"	3/8"	17 3/4"	<b>MO7-NB42( )</b>	247.			
		48"	3/8"	17 3/4"	<b>MO7-NB48( )</b>	261.			
		60"	3/8"	17 3/4"	<b>MO7-NB60( )</b>	292.			

### Order Code

Example:	<b>MO8-N60-612-612-N-N</b>
<b>MO8</b>	Overhead cabinet
<b>N</b>	Network mounted
<b>60</b>	Width
<b>612</b>	Paint finish for case
<b>612</b>	Surface finish for door
<b>N</b>	Black pulls
<b>N</b>	No lock

### Specification Information

*Specify finish for case and front.*

Order overhead cabinet locks with a KnollKey order form.

Veneer Group 1 cabinet doors are quartered Techgrain®.

Veneer Group 2 cabinet doors are figured Techgrain®.

Veneer Group 3 cabinet doors are narrow heart, flat cut natural veneer.

Interior shelves have slots for vertical dividers. Order vertical dividers separately.

Desk mounted MO8 overheads align with 64"H panel and vertical storage.

Overhead cabinet door pulls are matte black.

### Application Notes

Stanchion mounted overhead cabinets attach to overhead supports. Specify overhead backs separately for finished appearance in back-to-back or exposed applications.

Specify conversion kit MO7-SMB only if converting panel hung overheads to stanchion mounted.

Wall-mounting Morrison overhead cabinets: Use MO8-WMR to mount up to 120" of MO8 overheads. Specify one MO8-WMB for each overhead.

For Options overheads or Morrison or Options shelves, use MO6-WMSK to wall mount up to 9' of shelves or overheads. Kit includes wall mount rail and one vertical standard. Specify one additional MO6 WMSB for each shelf or overhead. Morrison shelves also require MB1-B13 shelf brackets.

Wall mount rails may be trimmed to length.

Specify conversion kit MO7-PMB only if converting stanchion mounted overheads to panel hung.

Wall mount wire manager is two-part wire concealment kit, 22"H.

Storage

Morrison Network overhead storage  
*desk or wall mounted Morrison overheads, shelf and overhead  
 wall-mount kits*

Morrison



description	type	w	d	h	pattern no.	paint
Conversion kit, mounting brackets for overhead supports					<b>MO7-SMB</b>	\$39.
Vertical dividers (set of 10)					<b>MO7-VD( )</b>	115.
Morrison, Network overhead wall mount rail		120"	1"	3 1/2"	<b>MO8-WMR-( )</b>	259.
Morrison, Network overhead wall mount brackets (2)		-	-	-	<b>MO8-WMB-( )</b>	99.
Wall mounting kit for shelves and Options overheads		111"	1"	2"	<b>MO6-WMSK-( )</b>	259.
Wall mounting vertical standard for shelves and Options overheads		3/4"	1"	18"	<b>MO6-WMSB-( )</b>	68.
Conversion kits, panel mount - brackets for overheads		-	-	-	<b>MO7-PMB-( )</b>	39.
Wall mount wire managers, set of 10					<b>MWM-J</b>	129.

Order Code	Specification Information	Application Notes
Example: <b>MO8-N60-612-612-N-N</b>	<i>Specify paint finish for brackets.</i>	Stanchion mounted overhead cabinets attach to overhead supports. Specify overhead backs separately for finished appearance in back-to-back or exposed applications.
<b>MO8</b> Overhead cabinet		Specify conversion kit MO7-SMB only if converting panel hung overheads to stanchion mounted.
<b>N</b> Network mounted		Wall-mounting Morrison overhead cabinets: Use MO8-WMR to mount up to 120" of MO8 overheads. Specify one MO8-WMB for each overhead.
<b>60</b> Width		For Options overheads or Morrison or Options shelves, use MO6-WMSK to wall mount up to 9' of shelves or overheads. Kit includes wall mount rail and one vertical standard. Specify one additional MO6 WMSB for each shelf or overhead. Morrison shelves also require MB1-B13 shelf brackets.
<b>612</b> Paint finish for case		Wall mount rails may be trimmed to length.
<b>612</b> Surface finish for door		Specify conversion kit MO7-PMB only if converting stanchion mounted overheads to panel hung.
<b>N</b> Surface finish for pulls		Wall mount wire manager is two-part wire concealment kit, 22"H.
<b>N</b> No lock		

# Morrison Network overhead storage

## *Morrison overhead supports*

Morrison

description	type	w	d	h	pattern no.	paint	
	Overhead support for 1 3/4" worksurfaces	30"	29"	13"	17"	<b>MN2-S3017()</b>	\$527.
		36"	35"	13"	17"	<b>MN2-S3617()</b>	544.
		42"	41"	13"	17"	<b>MN2-S4217()</b>	557.
		48"	47"	13"	17"	<b>MN2-S4817()</b>	577.
		54"	53"	13"	17"	<b>MN2-S5417()</b>	588.
		60"	59"	13"	17"	<b>MN2-S6017()</b>	607.
		66"	65"	13"	17"	<b>MN2-S6617()</b>	625.
		72"	71"	13"	17"	<b>MN2-S7217()</b>	639.
	78"	77"	13"	17"	<b>MN2-S7817()</b>	669.	
	Overhead support for 1 1/4" worksurfaces	30"	29"	13"	17 1/2"	<b>MN2-S3018()</b>	527.
		36"	35"	13"	17 1/2"	<b>MN2-S3618()</b>	544.
		42"	41"	13"	17 1/2"	<b>MN2-S4218()</b>	557.
		48"	47"	13"	17 1/2"	<b>MN2-S4818()</b>	577.
		54"	53"	13"	17 1/2"	<b>MN2-S5418()</b>	588.
		60"	59"	13"	17 1/2"	<b>MN2-S6018()</b>	607.
		66"	65"	13"	17 1/2"	<b>MN2-S6618()</b>	625.
		72"	71"	13"	17 1/2"	<b>MN2-S7218()</b>	639.
		78"	77"	13"	17 1/2"	<b>MN2-S7818()</b>	669.

### Order Code

Example: <b>MN2-S7217-612</b>
<b>MN2</b> Network
<b>S</b> Overhead support
<b>72</b> Width
<b>17</b> Height
<b>612</b> Paint finish

### Specification Information

*Specify paint finish.*

### Application Notes

Overhead supports are bolted to desk supported worksurfaces with grommets. Overheads may span over end of worksurface and width of return worksurface if grommets and desk support legs align with stanchions.

Overhead supports include 2 stanchions with cover plates, mounting hardware, and full platform for overheads.

Overhead supports are pre-configured for the following combinations of overhead storage units:

<i>Support Overhead</i>	
<i>width</i>	<i>storage</i>
30"	one 30"
36"	one 36"
42"	one 42"
48"	one 48"
54"	one 54"
60"	one 60" or two 30"
66"	one 30" and one 36"
72"	two 36"
78"	one 36" and one 42"

Stanchions may be equipped with desktop power module (page 169) and stanchion outlets cover (page 164).

Overhead supports are used only with Morrison overhead cabinets. For desk-mounted Reuter overheads, specify stanchions (page 200).


Storage

# Overhead Storage

## T5 Task Light for Morrison Network

Morrison



description	type	w	d	h	pattern no.	standard	advanced
Task Light	Use with 24" and wider overhead	18"	4"	1 1/2"	<b>MN2T5E19 ( )</b>	\$186.	n/a
	Use with 30" and wider overhead	25"	4"	1 1/2"	<b>MN2T5E25 ( )</b>	199.	360.
	Use with 42" and wider overhead	37"	4"	1 1/2"	<b>MN2T5E37 ( )</b>	229.	379.
	Use with 60" and wider overhead	49"	4"	1 1/2"	<b>MN2T5E49 ( )</b>	289.	394.



Order Code	Specification Information	Application Notes
Example: MN2T5E19S	<i>Specify:</i>	Task lights mount into the recess in the underside of overhead cabinets and shelves at least 6" wider than task light width.
MN2 Task Light	Width - Task Lights mount in cabinets and shelves at least 6" wider than light width.	Morrison Network task lights are mounted inside the horizontal beam of the overhead support.
T5 T5 lamp	Type:	Task light cord may be managed in either stanchion to desk support wireway.
E Electronic ballast	S Standard	Task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9' grounded corset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware.
19 Width	A Advanced	Task light cordset is center exit. On smaller units cord exit is off-center, but still not handed.
S Standard	Specify suffix -CH and add \$45 list for City of Chicago installations. Example: MN2T5E19S-CH	Task lights are TCLP compliant and meet requirements of California Title 24.
	All housings are black.	Advanced task lights are fitted with ballast and lamp compliant with LEED requirements.

# Morrison Options overhead cabinets and shelves panel or wall mounted

Morrison

description	type	w	d	h	pattern no.	Paint	V1	V2	V3
 Overhead cabinet	Lock	24"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-24-()</b> ( )-L	\$445.	\$511.	\$537.	\$601.
		30"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-30-()</b> ( )-L	498.	561.	601.	662.
		36"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-36-()</b> ( )-L	549.	624.	662.	724.
		42"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-42-()</b> ( )-L	603.	673.	724.	800.
		48"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-48-()</b> ( )-L	657.	738.	785.	872.
		60"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-60-()</b> ( )-L	734.	834.	898.	1,011.
	No lock	24"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-24-()</b> ( )-N	395.	462.	488.	551.
		30"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-30-()</b> ( )-N	446.	514.	551.	612.
		36"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-36-()</b> ( )-N	498.	576.	612.	674.
		42"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-42-()</b> ( )-N	551.	625.	674.	749.
		48"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-48-()</b> ( )-N	605.	688.	739.	825.
		60"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>LO2-60-()</b> ( )-N	684.	785.	849.	961.
Vertical dividers (6)		-	-	-	<b>LO2-VD-()</b>	139.			
 Steel bookshelves		24"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S2413-()</b>	150.			
		30"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S3013-()</b>	163.			
		36"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S3613-()</b>	174.			
		42"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S4213-()</b>	189.			
		48"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S4813-()</b>	199.			
		60"	13"	7 <sup>3</sup> / <sub>4</sub> "	<b>LS1-S6013-()</b>	226.			
Wall mounting kit for shelves and Options overheads		111"	1"	2"	<b>MO6-WMSK-()</b>	259.			
Wall mounting vertical standard for shelves and Options overheads		<sup>3</sup> / <sub>4</sub> "	1"	18"	<b>MO6-WMSB-()</b>	68.			

Order Code	Specification Information	Application Notes
Example: <b>LO2-60-612-612-N</b>	Order overhead cabinet locks with a KnollKey order form.	Overhead cabinets are hung from vertical panels with integral brackets. Cabinet door opens over the top of the cabinet. Overhead cabinets cannot be used in Network freestanding applications.  Order vertical dividers separately.  13"D shelves hold binders, books and other reference material.  Bookshelves consist of two steel side panels with integral brackets.
<b>LO2</b> Overhead cabinet		
<b>60</b> Width		
<b>612</b> Paint finish for case		
<b>612</b> Surface finish for door		
<b>N</b> No lock		All shelves accept task light fixtures.  For Options overheads or shelves, use MO6-WMSK to wall mount up to 9' of shelves or overheads. Kit includes wall mount rail and one vertical standard. Specify one additional MO6 WMSB for each shelf or overhead.  Wall mount rails may be trimmed to length.

# Morrison Options

## T5 Task Light

Morrison

description	type	w	d	h	pattern no.	Standard List	Advanced List
Task Light	Use with 24" and wider overhead	19"	4"	1 1/2"	<b>LL2T5E19 ( )</b>	\$148.	n/a
	Use with 30" and wider overhead	25"	4"	1 1/2"	<b>LL2T5E25 ( )</b>	187.	360.
	Use with 42" and wider overhead	37"	4"	1 1/2"	<b>LL2T5E37 ( )</b>	210.	379.
	Use with 60" and wider overhead	37"	4"	1 1/2"	<b>LL2T5E49 ( )</b>	249.	394.




Order Code	Specification Information	Application Notes
Example: LL2T5E19S	<i>Specify:</i>	Task lights mount into the recess in the underside of overhead cabinets and shelves at least 6" wider than task light width.
LL2 Task Light	Width - Task Lights mount in cabinets and shelves at least 6" wider than light width.	Task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9' grounded corset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware.
T5 T5 lamp	Type:	Task light cordset is center exit. On smaller units cord exit is off-center, but still not handed.
E Electronic ballast	S Standard	Task lights are TCLP compliant and meet requirements of California Title 24.
19 Width	A Advanced	Advanced task lights are fitted with ballast and lamp compliant with LEED requirements.
S Standard	Specify suffix -CH and add \$45 list for City of Chicago installations. Example: LL2T5E19S-CH	
	All housings are black.	



# Morrison Options overhead brackets

Morrison

description	w	d	h	pattern no.	paint
Morrison Options overhead downmount brackets and back panel (for Currents 64"H wall only)	24"			AA1-LO24 DN( )	\$216.
	30"			AA1-LO30 DN( )	224.
	36"			AA1-LO36 DN( )	229.
	42"			AA1-LO42 DN( )	235.
	48"			AA1-LO48 DN( )	241.






Storage

Order Code	Specification Information	Application Notes
Example: <b>AA1-LO36 DN-612</b>	<i>Specify paint finish for overhead downmount kit.</i>	Morrison Options overhead downmount bracket kits include back panel and brackets to suspend Options overhead cabinets from 64"H Currents service wall crown.
<b>AA1</b> Currents accessory		
<b>LO</b> Overhead cabinet		
<b>36</b> Case width		
<b>DN</b> Downmount		
<b>612</b> Paint finish		

# Reuter open shelf

*Designed by Robert Reuter*

Morrison

description	type	w	d	h	pattern no.	black	P1	P2	P3
 Open shelf Morrison panel brackets		24"	13"	8"	<b>RS1-M24( )</b>		\$268.	\$268.	\$281.
		30"	13"	8"	<b>RS1-M30( )</b>		293.	293.	309.
		36"	13"	8"	<b>RS1-M36( )</b>		332.	332.	348.
		42"	13"	8"	<b>RS1-M42( )</b>		358.	358.	375.
		48"	13"	8"	<b>RS1-M48( )</b>		384.	384.	402.
		60"	13"	8"	<b>RS1-M60( )</b>		448.	448.	470.
 Open shelf no mounting hardware		24"	13"	8"	<b>RS1-N24( )</b>		255.	255.	268.
		30"	13"	8"	<b>RS1-N30( )</b>		282.	282.	296.
		36"	13"	8"	<b>RS1-N36( )</b>		320.	320.	337.
		42"	13"	8"	<b>RS1-N42( )</b>		345.	345.	362.
		48"	13"	8"	<b>RS1-N48( )</b>		371.	371.	389.
		60"	13"	8"	<b>RS1-N60( )</b>		435.	435.	458.
 Interior partitions	Vertical, set of 5	–	12"	6"	<b>RS1-VP</b>	70.			
	Horizontal, set of 10	6"	12"	–	<b>RO1-HP6</b>	115.			
		9"	12"	–	<b>RO1-HP9</b>	146.			
		12"	12"	–	<b>RO1-HP12</b>	173.			
		15"	12"	–	<b>RO1-HP15</b>	202.			

## Order Code

Example:	<b>RS1-M48-612</b>
<b>RS1</b>	Reuter shelf
<b>M</b>	Morrison panel mounted
<b>48</b>	Width
<b>612</b>	Finish

## Specification Information

*Specify paint finishes for shelf.*

## Application Notes

Interior partitions are black painted steel finish.

Reuter storage is a universal product applicable on Morrison or other Knoll systems.




Open shelves may be mounted on any combination of vertical panels the same width. Reuter open shelves may be Morrison Network desk-mounted, mounted on other Knoll systems, cantilevered above panels, or wall-mounted. Specify Reuter shelves with no mounting hardware, and brackets separately.

Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting three horizontal partitions at 2" increments on either or both sides. Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than shelf width. Available in sets of 10; 6", 9", 12", 15" widths.

# Reuter open overhead

*Designed by Robert Reuter*

Morrison

description	type	w	d	h	pattern no.	black	P1	P2	P3	V2
 Open overhead Morrison panel brackets		30"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM30( )</b>		\$435.	\$435.	\$458.	
		36"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM36( )</b>		498.	498.	523.	
		42"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM42( )</b>		563.	563.	591.	
		48"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM48( )</b>		626.	626.	658.	
		60"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM60( )</b>		729.	729.	764.	
		72"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-OM72( )</b>		856.	856.	900.	
 Open overhead no mounting hardware		30"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON30( )</b>		422.	422.	443.	
		36"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON36( )</b>		486.	486.	510.	
		42"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON42( )</b>		550.	550.	578.	
		48"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON48( )</b>		614.	614.	644.	
		60"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON60( )</b>		714.	714.	753.	
		72"	13"	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-ON72( )</b>		843.	843.	885.	
 Interior partitions	Vertical, set of 5	–	11"	12"	<b>RO3-VP</b>	75.				
	Horizontal, set of 10	6"	11"	–	<b>RO1-HP6</b>	115.				
		9"	11"	–	<b>RO1-HP9</b>	146.				
		12"	11"	–	<b>RO1-HP12</b>	173.				
		15"	11"	–	<b>RO1-HP15</b>	202.				
Door retrofit kit, with lock	For open overhead	30"			<b>RO3-RD30( )L</b>	296.	296.	312.	571.	
		36"			<b>RO3-RD36( )L</b>	320.	320.	337.	620.	
		42"			<b>RO3-RD42( )L</b>	373.	373.	391.	673.	
		48"			<b>RO3-RD48( )L</b>	409.	409.	428.	722.	
		60"			<b>RO3-RD60( )L</b>	625.	625.	656.	1,161.	
		72"			<b>RO3-RD72( )L</b>	702.	702.	736.	1,263.	
Door retrofit kit, no lock	For open overhead	30"			<b>RO3-RD30( )N</b>	226.	226.	237.	n/a	
		36"			<b>RO3-RD36( )N</b>	262.	262.	275.	n/a	
		42"			<b>RO3-RD42( )N</b>	316.	316.	332.	n/a	
		48"			<b>RO3-RD48( )N</b>	349.	349.	368.	n/a	
		60"			<b>RO3-RD60( )N</b>	509.	509.	535.	n/a	
		72"			<b>RO3-RD72( )N</b>	587.	587.	616.	n/a	

## Order Code

Example:	<b>RO3-OM24-612</b>
<b>RO1-O</b>	Reuter open overhead
<b>M</b>	Morrison panel mounted
<b>24</b>	Width
<b>612</b>	Finish

## Specification Information

*Specify finish for case and door.*

## Application Notes

Interior partitions are black painted steel finish.

Door retrofit kits convert an open overhead to an enclosed cabinet and include Reuter overhead door, left and right arm mechanisms, and lock or lock plug.

Reuter storage is a universal product applicable on Morrison or other Knoll systems. Open overheads may be mounted on any combination of vertical panels the same width or up to 12" less than shelf width.


Reuter open overheads may be desk-mounted, mounted on other Knoll systems, cantilevered above panels, or wall-mounted. Specify open overhead with no mounting hardware and brackets separately.

Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting three horizontal partitions at 2" increments on either or both sides. Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than shelf width. Available in sets of 10; 6", 9", 12", 15" widths.


Reuter overhead cabinet  
*Morrison panel mounted*  
*Designed by Robert Reuter*

Morrison


description	type	w	d	h	pattern no.	black	P1	P2	P3	V2
Enclosed cabinet, with lock (Morrison panel brackets) - One door		24"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M24( )( )L</b>		\$603.	\$603.	\$634.	\$905.
		30"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M30( )( )L</b>		674.	674.	707.	974.
		36"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M36( )( )L</b>		778.	778.	816.	1,091.
		42"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M42( )( )L</b>		898.	898.	943.	1,212.
		48"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M48( )( )L</b>		999.	999.	1,049.	1,327.



Enclosed cabinet, with lock (Morrison panel brackets) - Two doors		60"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M60( )( )L</b>		1,266.	1,266.	1,328.	1,824.
		66"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M66( )( )L</b>		1,379.	1,379.	1,450.	1,955.
		72"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M72( )( )L</b>		1,476.	1,476.	1,550.	2,062.



Enclosed cabinet, no lock (Morrison panel brackets) - One door		24"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M24( )( )N</b>		545.	545.	572.	n/a
		30"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M30( )( )N</b>		616.	616.	647.	n/a
		36"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M36( )( )N</b>		720.	720.	755.	n/a
		42"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M42( )( )N</b>		839.	839.	881.	n/a
		48"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-M48( )( )N</b>		940.	940.	989.	n/a





Order Code	Specification Information	Application Notes
Example: <b>RO3-M48-612-M-L</b>		
<b>RO1</b> Reuter overhead cabinet	First suffix is for case, second is door finish.	Reuter storage is a universal product applicable on Morrison or other Knoll systems. Overhead cabinets may be mounted on any combination of vertical panels the same width or up to 12" less than cabinet width. Cabinet door rotates above cabinet on side pivots, counterbalanced by two pneumatic cylinders. Two door cabinets have center divider and four pneumatic cylinders.
<b>M</b> Morrison panel mounted	<i>Specify finish for case and door:</i> Interior partitions are black painted steel finish.	
<b>48</b> Width		Ganging bracket (page 201) joins adjacent overheads or shelves for additional stiffness and alignment.
<b>612</b> Case finish		Order locks for overheads with a KnollKey order form. Please note that Reuter overhead cabinets 60"W or wider require two lock cores.
<b>M</b> Front finish		Reuter overhead doors without locks include black, Knoll-logo insert, in the same position.
<b>L</b> With lock		Insert may be removed to retrofit a lock later.
		Reuter overheads may be mounted on other Knoll systems, cantilevered above 42" or 56" Morrison panels, or wall-mounted. Specify Reuter overheads on the next page and mounting options on page .
		Vertical interior partitions may be positioned on 1 <sup>1</sup> / <sub>2</sub> " increments of width anywhere across shelf, 1 <sup>1</sup> / <sub>2</sub> " in from each side. Vertical partitions contain cutouts for mounting five horizontal partitions at 2" increments on either or both sides. Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than cabinet width. Available in sets of 10; 6", 9", 12", 15" widths.

Reuter overhead cabinet  
*Morrison panel mounted*  
*Designed by Robert Reuter*

Morrison

description	type	w	d	h	pattern no.	black	P1	P2	P3	V2
Enclosed cabinet, no lock (Morrison panel brackets) - Two doors		60"	14 1/4"	14 3/4"	<b>RO3-M60( )(JN)</b>		\$1,147.	\$1,147.	\$1,205.	n/a
		66"	14 1/4"	14 3/4"	<b>RO3-M66( )(JN)</b>		1,263.	1,263.	1,325.	n/a
		72"	14 1/4"	14 3/4"	<b>RO3-M72( )(JN)</b>		1,357.	1,357.	1,427.	n/a



Interior partitions	type	w	d	h	pattern no.	black
	Horizontal, set of 10	6"	11"	-	<b>RO1-HP6</b>	115.
	Horizontal, set of 10	9"	11"	-	<b>RO1-HP9</b>	146.
	Horizontal, set of 10	12"	11"	-	<b>RO1-HP12</b>	173.
	Horizontal, set of 10	15"	11"	-	<b>RO1-HP15</b>	202.
	Vertical, set of 5	-	11"	12"	<b>RO3-VP</b>	75.

Order Code	Specification Information	Application Notes												
<p>Example: <b>RO3-M48-612-M-L</b></p> <table border="1"> <tr> <td><b>RO1</b></td> <td>Reuter overhead cabinet</td> </tr> <tr> <td><b>M</b></td> <td>Morrison panel mounted</td> </tr> <tr> <td><b>48</b></td> <td>Width</td> </tr> <tr> <td><b>612</b></td> <td>Case finish</td> </tr> <tr> <td><b>M</b></td> <td>Front finish</td> </tr> <tr> <td><b>L</b></td> <td>With lock</td> </tr> </table>	<b>RO1</b>	Reuter overhead cabinet	<b>M</b>	Morrison panel mounted	<b>48</b>	Width	<b>612</b>	Case finish	<b>M</b>	Front finish	<b>L</b>	With lock	<p>First suffix is for case, second is door finish.</p> <p><i>Specify finish for case and door:</i>            Interior partitions are black painted steel finish.</p>	<p>Reuter storage is a universal product applicable on Morrison or other Knoll systems. Overhead cabinets may be mounted on any combination of vertical panels the same width or up to 12" less than cabinet width. Cabinet door rotates above cabinet on side pivots, counterbalanced by two pneumatic cylinders. Two door cabinets have center divider and four pneumatic cylinders.</p> <p>Reuter overheads may be mounted on other Knoll systems, cantilevered above 42" or 56" Morrison panels, or wall-mounted. Specify Reuter overheads on the next page and mounting options on page .</p> <p>Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting five horizontal partitions at 2" increments on either or both sides. Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than cabinet width. Available in sets of 10; 6", 9", 12", 15" widths.</p>
<b>RO1</b>	Reuter overhead cabinet													
<b>M</b>	Morrison panel mounted													
<b>48</b>	Width													
<b>612</b>	Case finish													
<b>M</b>	Front finish													
<b>L</b>	With lock													

Ganging bracket (page 201) joins adjacent overheads or shelves for additional stiffness and alignment.

Order locks for overheads with a KnollKey order form. Please note that Reuter overhead cabinets 60"W or wider require two lock cores.

Reuter overhead doors without locks include black, Knoll-logo insert, in the same position.


Insert may be removed to retrofit a lock later.

Storage


Reuter overhead cabinet  
*desk, wall, or other Knoll system mounted*  
*Designed by Robert Reuter*

Morrison


description	type	w	d	h	pattern no.	black	P1	P2	P3	V2
Enclosed cabinet, with lock (no mounting hardware) - One door		24"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N24( ) (J)L</b>		\$591.	\$591.	\$620.	\$891.
		30"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N30( ) (J)L</b>		659.	659.	694.	962.
		36"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N36( ) (J)L</b>		762.	762.	801.	1,078.
		42"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N42( ) (J)L</b>		884.	884.	929.	1,199.
		48"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N48( ) (J)L</b>		988.	988.	1,036.	1,316.




Enclosed cabinet, with lock (no mounting hardware) - Two doors		60"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N60( ) (J)L</b>		1,250.	1,250.	1,314.	1,813.
		66"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N66( ) (J)L</b>		1,368.	1,368.	1,434.	1,942.
		72"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N72( ) (J)L</b>		1,461.	1,461.	1,534.	2,051.



Enclosed cabinet, no lock (no mounting hardware) - One door		24"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N24( ) (J)N</b>		531.	531.	558.	n/a
		30"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N30( ) (J)N</b>		602.	602.	633.	n/a
		36"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N36( ) (J)N</b>		705.	705.	739.	n/a
		42"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N42( ) (J)N</b>		827.	827.	868.	n/a
		48"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N48( ) (J)N</b>		928.	928.	974.	n/a



Enclosed cabinet, no lock (no mounting hardware) - Two doors		60"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N60( ) (J)N</b>		1,134.	1,134.	1,190.	n/a
		66"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N66( ) (J)N</b>		1,249.	1,249.	1,312.	n/a
		72"	14 <sup>1</sup> / <sub>4</sub> "	14 <sup>3</sup> / <sub>4</sub> "	<b>RO3-N72( ) (J)N</b>		1,347.	1,347.	1,413.	n/a




Order Code	
Example:	<b>RO3-N48-P-L-613-P-613</b>
<b>RO3</b>	Reuter overhead cabinet
<b>N</b>	No brackets
<b>48</b>	Width
<b>P</b>	With pull
<b>L</b>	With lock
<b>613</b>	Case finish
<b>P</b>	Front finish type
<b>613</b>	Front finish

Specification Information	
<i>Specify finish for case and door.</i>	
<i>Finish types for front:</i>	
P	Painted
V	Veneer

Application Notes	
Reuter storage is a universal product applicable on Knoll systems.	Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than cabinet width. Available in sets of 10; 6", 9", 12", 15" widths.
Cabinet door rotates above cabinet on side pivots, counterbalanced by two pneumatic cylinders. Two-door cabinets have center divider and four pneumatic cylinders. Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting up to five horizontal partitions at 2" increments on either or both sides.	Order locks for overheads with a KnollKey order form. Please note that Reuter overhead cabinets 60"W or wider require two lock cores.
	Reuter overhead doors without locks include black, Knoll-logo insert, in the same position. Insert may be removed to retrofit a lock later.

Reuter overhead cabinet  
*desk, wall, or other Knoll system mounted*  
*Designed by Robert Reuter*

Morrison

description	type	w	d	h	pattern no.	black	P1	P2	P3	V2
Interior partitions 	Vertical, set of 5	–	11"	12"	<b>RO3-VP</b>	\$75.				
	Horizontal, set of 10	6"	11"	–	<b>RO1-HP6</b>	115.				
	Horizontal, set of 10	9"	11"	–	<b>RO1-HP9</b>	146.				
	Horizontal, set of 10	12"	11"	–	<b>RO1-HP12</b>	173.				
	Horizontal, set of 10	15"	11"	–	<b>RO1-HP15</b>	202.				

**Order Code**

Example:	<b>RO3-N48-P-L-613-P-613</b>
<b>RO3</b>	Reuter overhead cabinet
<b>N</b>	No brackets
<b>48</b>	Width
<b>P</b>	With pull
<b>L</b>	With lock
<b>613</b>	Case finish
<b>P</b>	Front finish type
<b>613</b>	Front finish

**Specification Information**

*Specify finish for case and door.*

*Finish types for front:*

P Painted  
 V Veneer

**Application Notes**

Reuter storage is a universal product applicable on Knoll systems.

Cabinet door rotates above cabinet on side pivots, counterbalanced by two pneumatic cylinders. Two-door cabinets have center divider and four pneumatic cylinders. Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting up to five horizontal partitions at 2" increments on either or both sides.

Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than cabinet width. Available in sets of 10; 6", 9", 12", 15" widths.

Order locks for overheads with a KnollKey order form. Please note that Reuter overhead cabinets 60"W or wider require two lock cores.

Reuter overhead doors without locks include black, Knoll-logo insert, in the same position. Insert may be removed to retrofit a lock later.

Reuter overhead storage  
*desk and panel mounting options*  
*Designed by Robert Reuter*

Morrison

description	type	w	d	h	pattern no.	black	paint
Stanchions for Network desk mount, pair	1 1/4" worksurface	5"	5"	20 1/2"	<b>RO2-NS21( )</b>		\$387.
	1 3/4" worksurface	5"	5"	20"	<b>RO2-NS20( )</b>		387.
Stanchion outlets cover	1 1/4" worksurface	7"	1/2"	15 1/2"	<b>MN2SO21( )</b>	35.	
	1 3/4" worksurface	7"	1/2"	15"	<b>MN2SO20( )</b>	35.	
Panel mount brackets, pair, overhead cabinet	For Dividends panels				<b>RO1-DPB</b>		47.
	For Equity panels				<b>RO1-EPB</b>		38.
	For Morrison panels				<b>RO1-MPB</b>		38.
	For Reff System panels				<b>RO1-RPB</b>		38.
Panel mount brackets, pair, open shelf	For Dividends panels				<b>RS1-DPB</b>		47.
	For Equity panels				<b>RS1-EPB</b>		32.
	For Morrison panels				<b>RS1-MPB</b>		32.
	For Reff System panels				<b>RS1-RPB</b>		32.
Upmount brackets	For Equity panels				<b>RO1-ECB( )</b>		84.
	For Morrison panels	1/2"	10"	10"	<b>RO1-CB( )</b>		84.
	For Reff panels				<b>RO1-RCB( )</b>		84.




Order Code	Specification Information	Application Notes
Example: <b>RO2-NS21-612</b>	<i>Specify paint finish for stanchions and upmount brackets.</i>	Reuter overhead cabinets and shelves may be mounted on Network desks or other Knoll systems, upmounted, or wall-mounted. Use bracket kits on this page with Reuter storage without mounting hardware.
<b>RO2</b> Reuter overhead	Panel mount brackets are painted black finish.	Specify stanchion outlets cover when planning PDC modules and/or power module in overhead support. See page for information on desktop power module.
<b>NS</b> Network stanchions		Upmount brackets support bottom of Reuter storage 1" or 2" above, or flush with top of corresponding width Morrison, Equity or Reff panel.
<b>21</b> Height		Overhead storage may be centered on, or mount to either side of Equity post. Note that full 6" modular width Reuter storage is wider than Equity centerline-width panel surrounds.
<b>612</b> Paint finish		Specify 22"H privacy screens (to 49"H) to enclose space between overhead and desk.



# Reuter overhead storage wall-mounting options and ADA pull ←


Designed by Robert Reuter

description	type	w	d	h	pattern no.	black
Wall mount frames, overhead cabinet	24" or 30"W overheads	23"	1/2"	13"	<b>RO1-WMF2</b>	\$73.
	36" or 42"W overheads	35"	1/2"	13"	<b>RO1-WMF3</b>	79.
	48" or 60"W overheads	47"	1/2"	13"	<b>RO1-WMF4</b>	84.




<del>Wall mount frames, shelf</del>	<del>24"W shelf</del>	<del>23"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF24</b></del>	<del>73.</del>
	<del>30"W shelf</del>	<del>29"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF30</b></del>	<del>77.</del>
	<del>36"W shelf</del>	<del>35"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF36</b></del>	<del>79.</del>
	<del>42"W shelf</del>	<del>41"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF42</b></del>	<del>82.</del>
	<del>48"W shelf</del>	<del>47"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF48</b></del>	<del>84.</del>
	<del>60"W shelf</del>	<del>59"</del>	<del>1 1/2"</del>	<del>6"</del>	<del><b>RS1-WMF60</b></del>	<del>88.</del>

Wall mount wire manager, set of 10					<b>MWM-J</b>	129.
------------------------------------	--	--	--	--	--------------	------



Ganging bracket					<b>RO1-GB</b>	12.
ADA pull					<b>RO1-PULL</b>	42.




Order Code	Specification Information	Application Notes
Example: <b>RO1-GB</b>	Wall mount frames are painted black finish.	Wall mount frames secure Reuter overhead cabinet or shelf to wall (frame/wall mounting hardware is not included). Frame is concealed behind storage. Use two RO1-WMF2 to wall-mount 66" - and 72"-wide Reuter overheads.
<b>RO1</b> Reuter overhead	ADA pull is stainless steel.	Reuter open shelves 66" and 72"W are for stanchion support only.
<b>GB</b> Ganging bracket		Wall mount wire manager is two-part wire concealment kit, 22"H (medium grey only).
		Ganging bracket joins adjacent Reuter overheads or shelves for additional stiffness and alignment when storage is planned on only one side of a panel run.
		ADA pull mounts to Reuter painted front overhead door to allow seated users to close door easily. Specify one for each cabinet 24" - 48", two for cabinets 60" - 72".
		ADA pull cannot be mounted on wood front Reuter doors.


Reuter flat front overhead cabinet  
*flat front*  
*Designed by Robert Reuter*

Morrison

description	w	d	h	pattern no.	P3	L	V1	V2	V3
Enclosed cabinet (no mounting hardware) - One door, no pull, no lock	30"	14 1/4"	14 3/4"	<b>RO3-A30NN ( ) ( )</b>	\$818.	\$876.	\$954.	\$995.	\$1,204.
	36"	14 1/4"	14 3/4"	<b>RO3-A36NN ( ) ( )</b>	922.	994.	1,106.	1,164.	1,484.
	42"	14 1/4"	14 3/4"	<b>RO3-A42NN ( ) ( )</b>	1,031.	1,130.	1,282.	1,368.	1,834.
	48"	14 1/4"	14 3/4"	<b>RO3-A48NN ( ) ( )</b>	1,208.	1,274.	1,387.	1,490.	2,127.
Enclosed cabinet (no mounting hardware) - Two doors, no pull, no lock	60"	14 1/4"	14 3/4"	<b>RO3-A60NN ( ) ( )</b>	1,569.	1,698.	1,772.	1,865.	2,311.
	72"	14 1/4"	14 3/4"	<b>RO3-A72NN ( ) ( )</b>	1,789.	1,918.	2,058.	2,183.	2,863.
Enclosed cabinet (no mounting hardware) - One door, no pull, with lock	30"	14 1/4"	14 3/4"	<b>RO3-A30NL ( ) ( )</b>	875.	932.	1,010.	1,051.	1,260.
	36"	14 1/4"	14 3/4"	<b>RO3-A36NL ( ) ( )</b>	979.	1,050.	1,162.	1,220.	1,540.
	42"	14 1/4"	14 3/4"	<b>RO3-A42NL ( ) ( )</b>	1,087.	1,187.	1,340.	1,424.	1,890.
	48"	14 1/4"	14 3/4"	<b>RO3-A48NL ( ) ( )</b>	1,265.	1,330.	1,444.	1,546.	2,183.
Enclosed cabinet (no mounting hardware) - Two doors, no pull, with lock	60"	14 1/4"	14 3/4"	<b>RO3-A60NL ( ) ( )</b>	1,682.	1,811.	1,884.	1,977.	2,424.
	72"	14 1/4"	14 3/4"	<b>RO3-A72NL ( ) ( )</b>	1,901.	2,030.	2,170.	2,295.	2,975.
Enclosed cabinet (no mounting hardware) - One door, with pull, no lock	30"	14 1/4"	14 3/4"	<b>RO3-A30PN ( ) ( )</b>	981.	1,038.	1,116.	1,158.	1,367.
	36"	14 1/4"	14 3/4"	<b>RO3-A36PN ( ) ( )</b>	1,087.	1,159.	1,270.	1,328.	1,648.
	42"	14 1/4"	14 3/4"	<b>RO3-A42PN ( ) ( )</b>	1,197.	1,297.	1,450.	1,534.	2,000.
	48"	14 1/4"	14 3/4"	<b>RO3-A48PN ( ) ( )</b>	1,379.	1,445.	1,559.	1,661.	2,297.
Enclosed cabinet (no mounting hardware) - Two doors, with pull, no lock	60"	14 1/4"	14 3/4"	<b>RO3-A60PN ( ) ( )</b>	1,893.	2,023.	2,097.	2,189.	2,635.
	72"	14 1/4"	14 3/4"	<b>RO3-A72PN ( ) ( )</b>	2,115.	2,245.	2,386.	2,510.	3,190.
Enclosed cabinet (no mounting hardware) - One door, with pull, with lock	30"	14 1/4"	14 3/4"	<b>RO3-A30PL ( ) ( )</b>	1,037.	1,094.	1,172.	1,214.	1,423.
	36"	14 1/4"	14 3/4"	<b>RO3-A36PL ( ) ( )</b>	1,143.	1,215.	1,326.	1,384.	1,705.
	42"	14 1/4"	14 3/4"	<b>RO3-A42PL ( ) ( )</b>	1,253.	1,353.	1,506.	1,590.	2,056.
	48"	14 1/4"	14 3/4"	<b>RO3-A48PL ( ) ( )</b>	1,435.	1,502.	1,615.	1,718.	2,354.
Enclosed cabinet (no mounting hardware) - Two doors, with pull, with lock	60"	14 1/4"	14 3/4"	<b>RO3-A60PL ( ) ( )</b>	2,005.	2,135.	2,209.	2,302.	2,749.
	60"	14 1/4"	14 3/4"	<b>RO3-A72PL ( ) ( )</b>	2,228.	2,358.	2,498.	2,622.	3,302.



Order Code	Specification Information	Application Notes
<b>Example: RO3-A30PL-117-L-117</b>	Specify mounting hardware separately.	Reuter storage is a universal product applicable Knoll systems.
<b>RO3</b> Reuter overhead	Optional anodized aluminum front pull trims the entire width of cabinet door.	Cabinet door rotates above cabinet on side pivots, counterbalanced by two pneumatic cylinders. Two-door cabinets have center divider and four pneumatic cylinders. Vertical interior partitions may be positioned on 1 1/2" increments of width anywhere across shelf, 1 1/2" in from each side. Vertical partitions contain cutouts for mounting up to five horizontal partitions at 2" increments on either or both sides.
<b>A</b> flat front	<i>Specify paint finishes for case.</i>	Horizontals are suspended between two verticals, and may be positioned end-to-end in any combination up to 3" less than cabinet width. Available in sets of 10; 6", 9", 12", 15" widths.
<b>30</b> width	<i>Finish types for front:</i>	Order locks for overheads with a KnollKey order form. Please note that Reuter overhead cabinets 60"W or wider require two lock cores.
<b>P</b> with pull	L laminate	
<b>L</b> with lock	P paint	
<b>117</b> case finish	V veneer or techwood	
<b>L</b> front finish type		
<b>117</b> front color		




description	type	w	d	h	pattern no.	Standard List	Advanced List
Task Light 	Use with 24" and wider overhead	19"	4"	1 1/2"	<b>RTAT5E19 ( )</b>	\$194.	n/a
	Use with 30" and wider overhead	25"	4"	1 1/2"	<b>RTAT5E25 ( )</b>	209.	360.
	Use with 42" and wider overhead	37"	4"	1 1/2"	<b>RTAT5E37 ( )</b>	225.	379.
	Use with 60" and wider overhead	49"	4"	1 1/2"	<b>RTAT5E49 ( )</b>	244.	394.
	Use with 66" and wider overhead	61"	4"	1 1/2"	<b>RTAT5E61 ( )</b>	260.	410.

Order Code	Specification Information	Application Notes
Example: RTAT5E19S <hr/> RTA Task Light <hr/> T5 T5 lamp <hr/> E Electronic ballast <hr/> 19 Width <hr/> S Standard	<p><i>Specify:</i></p> <p>Width - Task Lights mount in cabinets and shelves at least 5" wider than light width.</p> <p>Type:</p> <p>S Standard A Advanced</p> <p>Specify suffix -CH and add \$45 list for City of Chicago installations. Example: RTAT5E19S-CH</p> <p>All housings are black.</p>	<p>Task lights mount into the recess in the underside of overhead cabinets and shelves at least 5" wider than task light width.</p> <p>Task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9' grounded corset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware.</p> <p>Task light cordset is center exit. On smaller units cort exit is off-center, but still not handed.</p> <p>Task lights are TCLP compliant and meet requirements of California Title 24.</p> <p>Advanced task lights are fitted with ballast and lamp compliant with LEED requirements.</p>

# Morrison Network privacy screens

## back screens

Morrison


description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
 Back of worksurface screens to 42"H		30"	3/4"	15"	<b>MZ1-B3015-()</b>	\$172.	\$194.	\$199.	\$218.	\$230.	\$245.	\$272.
		36"	3/4"	15"	<b>MZ1-B3615-()</b>	207.	224.	230.	253.	265.	278.	300.
		42"	3/4"	15"	<b>MZ1-B4215-()</b>	253.	265.	274.	301.	319.	327.	350.
		48"	3/4"	15"	<b>MZ1-B4815-()</b>	284.	295.	304.	334.	352.	374.	399.
		54"	3/4"	15"	<b>MZ1-B5415-()</b>	331.	342.	351.	388.	408.	424.	450.
		60"	3/4"	15"	<b>MZ1-B6015-()</b>	365.	372.	385.	422.	444.	472.	500.
		66"	3/4"	15"	<b>MZ1-B6615-()</b>	398.	401.	n/a	n/a	480.	n/a	n/a
		72"	3/4"	15"	<b>MZ1-B7215-()</b>	428.	444.	n/a	n/a	528.	n/a	n/a
	78"	3/4"	15"	<b>MZ1-B7815-()</b>	473.	488.	n/a	n/a	580.	n/a	n/a	
 Back of worksurface screens to overhead support height, 46"H		30"	3/4"	19"	<b>MZ1-B3019-()</b>	219.	237.	245.	268.	282.	293.	320.
		36"	3/4"	19"	<b>MZ1-B3619-()</b>	270.	283.	291.	321.	334.	343.	364.
		42"	3/4"	19"	<b>MZ1-B4219-()</b>	319.	326.	333.	370.	388.	408.	431.
		48"	3/4"	19"	<b>MZ1-B4819-()</b>	363.	371.	380.	419.	442.	484.	492.
		54"	3/4"	19"	<b>MZ1-B5419-()</b>	412.	415.	429.	473.	496.	507.	538.
		60"	3/4"	19"	<b>MZ1-B6019-()</b>	444.	458.	472.	520.	547.	553.	589.
		66"	3/4"	19"	<b>MZ1-B6619-()</b>	490.	501.	n/a	n/a	597.	n/a	n/a
		72"	3/4"	19"	<b>MZ1-B7219-()</b>	538.	548.	n/a	n/a	651.	n/a	n/a
	78"	3/4"	19"	<b>MZ1-B7819-()</b>	587.	594.	n/a	n/a	707.	n/a	n/a	
 Back of worksurface screens, to Reuter overhead support height, 49"H		30"	3/4"	22"	<b>MZ1-B3022-()</b>	268.	281.	289.	320.	333.	343.	365.
		36"	3/4"	22"	<b>MZ1-B3622-()</b>	330.	342.	351.	387.	407.	414.	429.
		42"	3/4"	22"	<b>MZ1-B4222-()</b>	380.	387.	399.	440.	460.	488.	511.
		48"	3/4"	22"	<b>MZ1-B4822-()</b>	444.	445.	459.	508.	533.	542.	590.
		54"	3/4"	22"	<b>MZ1-B5422-()</b>	489.	490.	508.	562.	590.	598.	630.
		60"	3/4"	22"	<b>MZ1-B6022-()</b>	520.	545.	562.	620.	651.	657.	680.
		66"	3/4"	22"	<b>MZ1-B6622-()</b>	582.	606.	n/a	n/a	718.	n/a	n/a
		72"	3/4"	22"	<b>MZ1-B7222-()</b>	649.	650.	n/a	n/a	772.	n/a	n/a
	78"	3/4"	22"	<b>MZ1-B7822-()</b>	697.	700.	n/a	n/a	832.	n/a	n/a	

Order Code	Specification Information	Application Notes
Example: <b>MZ1-B6619-15-W210/2</b> <b>MZ1</b> Morrison Network privacy screen <b>B</b> Back of worksurface <b>66</b> Width <b>19</b> Height <b>15</b> Surface type and group no. <b>W210/2</b> Upholstery	<i>Surface type:</i> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  * Morrison Network screens may be used with Plannable Upstart tables. Refer to front of Upstart price book for planning information.	Back of worksurface screens provide visual barrier and tackable surface from underside of worksurface to a height of 42", 46" or 49".  Screen widths should correspond to straight worksurface width, or sum of VDT corner and return widths.  Use back of worksurface screen for VDT applications where one side is backed by a vertical panel.  VDT worksurfaces will accept back screens on only one back edge.  Back screens may not be used at the end of a straight worksurface; use end screens in this application.  Privacy screens are not available in a combination of fabrics.  Back of worksurface screens are full dimension: two smaller screens may be substituted for a larger one. For example, if using fabric grades 20-70, specify two 36" screens for a 72" surface.
		Between back-to-back straight or VDT worksurfaces specify a single 3/4" back screen. This allows back-to-back 23 5/8"D or 29 5/8"D worksurfaces to plan on a precise 6" module.  15" high screens are used for a 42" horizon.  19"H screens are used to fill in space between worksurface and Morrison overhead.  22"H screens fill the space between worksurface and Reuter overhead.  All but shared end screens start at the bottom of the worksurface.  Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit, and stiffener clip.  For replacement screen stiffeners see Accessories page.  Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Morrison Network privacy screens

## VDT screens

Morrison



description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
Back of VDT screens 	To 42"H	35 <sup>5</sup> / <sub>8</sub> "	3/4"	15"	<b>MZ1-V3615-()</b>	\$207.	\$224.	\$230.	\$245.	\$253.	\$272.	\$300.
		41 <sup>5</sup> / <sub>8</sub> "	3/4"	15"	<b>MZ1-V4215-()</b>	253.	265.	274.	293.	300.	320.	350.
		47 <sup>5</sup> / <sub>8</sub> "	3/4"	15"	<b>MZ1-V4815-()</b>	284.	295.	304.	327.	342.	364.	399.
		59 <sup>5</sup> / <sub>8</sub> "	3/4"	15"	<b>MZ1-V6015-()</b>	361.	374.	387.	413.	429.	457.	495.
		71 <sup>5</sup> / <sub>8</sub> "	3/4"	15"	<b>MZ1-V7215-()</b>	437.	451.	n/a	n/a	517.	n/a	n/a
	To 46"H	35 <sup>5</sup> / <sub>8</sub> "	3/4"	19"	<b>MZ1-V3619-()</b>	273.	282.	291.	309.	319.	332.	364.
		41 <sup>5</sup> / <sub>8</sub> "	3/4"	19"	<b>MZ1-V4219-()</b>	319.	326.	333.	357.	372.	399.	431.
		47 <sup>5</sup> / <sub>8</sub> "	3/4"	19"	<b>MZ1-V4819-()</b>	363.	372.	385.	409.	415.	445.	492.
		59 <sup>5</sup> / <sub>8</sub> "	3/4"	19"	<b>MZ1-V6019-()</b>	454.	471.	487.	528.	550.	585.	634.
		71 <sup>5</sup> / <sub>8</sub> "	3/4"	19"	<b>MZ1-V7219-()</b>	545.	568.	n/a	n/a	661.	n/a	n/a
	To 49"H	35 <sup>5</sup> / <sub>8</sub> "	3/4"	22"	<b>MZ1-V3622-()</b>	330.	342.	351.	375.	379.	399.	429.
		41 <sup>5</sup> / <sub>8</sub> "	3/4"	22"	<b>MZ1-V4222-()</b>	380.	387.	399.	419.	443.	478.	511.
		47 <sup>5</sup> / <sub>8</sub> "	3/4"	22"	<b>MZ1-V4822-()</b>	444.	447.	461.	490.	491.	492.	590.
		59 <sup>5</sup> / <sub>8</sub> "	3/4"	22"	<b>MZ1-V6022-()</b>	527.	547.	564.	613.	640.	678.	736.
		71 <sup>5</sup> / <sub>8</sub> "	3/4"	22"	<b>MZ1-V7222-()</b>	630.	657.	n/a	n/a	769.	n/a	n/a

Order Code	Specification Information	Application Notes
Example: <b>MZ1-V4822-15-W210/2</b> <b>MZ1</b> Morrison Network privacy screen <b>V</b> VDT <b>48</b> Width <b>22</b> Height <b>15</b> Surface type and group no. <b>W210/2</b> Upholstery	<p><i>Surface type:</i></p> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45	Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit and stiffener clip.  15" high screens are used for a 42" horizon.  19"H screens are used to fill in space between worksurface and desk mounted Morrison Network overheads.  22"H screens fill the space between worksurface and desk mounted Reuter overheads.  Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.
	VDT worksurfaces will not accept back screens on both back edges. Use VDT screens on at least one back edge.  VDT screens are not in pairs; specify one for each back edge or one VDT screen and one back screen.	* Morrison Network screens may be used with Plannable Upstart tables. Refer to front of Upstart price book for planning information.

Storage

# Morrison Network privacy screens end screens




Morrison

description	type	w	d	h	pattern no.	10	15	20	30	35	40	45
 End screens for outside application	To 42"H	24"	3/4"	15"	<b>MZ1-E2415-W/U-( )</b>	\$164.	\$188.	\$193.	\$202.	\$214.	\$233.	\$265.
		30"	3/4"	15"	<b>MZ1-E3015-W/U-( )</b>	182.	200.	207.	222.	233.	248.	282.
	To 46"H	24"	3/4"	19"	<b>MZ1-E2419-W/U-( )</b>	198.	215.	219.	239.	247.	265.	296.
		30"	3/4"	19"	<b>MZ1-E3019-W/U-( )</b>	228.	247.	253.	272.	281.	296.	330.
	To 49"H	24"	3/4"	22"	<b>MZ1-E2422-W/U-( )</b>	233.	246.	251.	270.	281.	298.	329.
		30"	3/4"	22"	<b>MZ1-E3022-W/U-( )</b>	278.	293.	299.	321.	328.	348.	379.
 End screens for shared application	To 42"H	24"	3/4"	13"	<b>MZ1-S2415-W/U-( )</b>	158.	179.	186.	195.	206.	224.	254.
		30"	3/4"	13"	<b>MZ1-S3015-W/U-( )</b>	172.	194.	199.	213.	224.	238.	272.
	To 46"H	24"	3/4"	17"	<b>MZ1-S2419-W/U-( )</b>	190.	207.	213.	227.	238.	254.	287.
		30"	3/4"	17"	<b>MZ1-S3019-W/U-( )</b>	219.	237.	245.	261.	270.	287.	320.
	To 49"H	24"	3/4"	20"	<b>MZ1-S2422-W/U-( )</b>	222.	236.	241.	259.	270.	288.	319.
		30"	3/4"	20"	<b>MZ1-S3022-W/U-( )</b>	268.	281.	289.	309.	319.	332.	365.

Order Code	Specification Information	Application Notes
Example: <b>MZ1-S3019W15-W210/2</b> <b>MZ1</b> Morrison Network privacy screen <b>S</b> Shared <b>30</b> Width <b>19</b> Height <b>W</b> For 1 3/4" worksurface <b>15</b> Surface type and group no. <b>W210/2</b> Upholstery	<i>Surface type:</i> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 35- Fabric group 35 40- Fabric group 40 45- Fabric group 45  <i>End screens specify:</i> W- For use with 1 3/4" thick worksurfaces U- For use with 1 1/4" thick worksurfaces  * Morrison Network screens may be used with Plannable Upstart tables. Refer to front of Upstart price book for planning information.	End screens must be used at the end of straight or rounded end worksurfaces.  End screens for outside application cover the end of the worksurface and align with adjacent back screens.  End screens for shared application begin above the worksurface to allow modular planning when straight worksurfaces are end-to-end.  When specifying end screens under 64"H panel mounted Morrison Network overheads with task lights, only screens to 42"H will fit.  With 64"H panel-mounted Reuter overheads any screen up to 49"H may be planned perpendicular to storage.
		Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit and stiffener clip.  15" high screens are used for a 42" horizon.  19"H screens are used to fill in space between worksurface and desk mounted Morrison Network overheads.  22"H screens fill the space between worksurface and desk mounted Reuter overheads.  All but shared end screens start at the bottom of the worksurface.  Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.

# Kiosk vertical storage freestanding

Morrison

description	type	w	d	h	pattern no.	Black	Paint
Options Kiosk	4 files/coats	24"	24"	64"	<b>LV3-S64(L/R)-()</b>		\$3,195.
	Cupola	24"	24"	4 1/2"	<b>MV2-STC()</b>		478.
	Extended depth cupola	24"	26 1/4"	4 1/2"	<b>MV1-STCX()</b>		478.
	Extended depth flat top cap	24"	26 1/4"	1"	<b>MV1-SFCX()</b>		205.
	Flat top cap	24"	24"	1"	<b>MV1-SFC()</b>		205.
Standard 24"W x 24"D 	4 files/coats (front access)	24"	24"	56"	<b>MV3-S56F-(L/R)-()</b>		5,180.
	4 files/coats (front access)	24"	24"	64"	<b>MV3-S64F-(L/R)-()</b>		5,467.
	Cupola	24"	24"	4 1/2"	<b>MV2-STC()</b>		478.
	Extended depth cupola	24"	26 1/4"	4 1/2"	<b>MV1-STCX()</b>		478.
	Extended depth flat top cap	24"	26 1/4"	1"	<b>MV1-SFCX()</b>		205.
	Flat top cap	24"	24"	1"	<b>MV1-SFC()</b>		205.
	Top cabinet (side access)	24"	24"	18"	<b>MV2-S18S-(L/R)-()</b>		1,296.
	Deep 24"W x 30"D 	4 files/coats (front access)	24"	30"	56"	<b>MV3-D56F-(L/R)-()</b>	
4 files/coats (front access)		24"	30"	64"	<b>MV3-D64F-(L/R)-()</b>		5,608.
Cupola		24"	30"	4 1/2"	<b>MV1-DTC()</b>		549.
Extended depth cupola		24"	32 1/4"	4 1/2"	<b>MV1-DTCX()</b>		549.
Extended depth flat top cap		24"	32 1/4"	1"	<b>MV1-DFCX()</b>		274.
Flat top cap		24"	30"	1"	<b>MV1-DFC()</b>		274.
Top cabinet (side access)		24"	30"	18"	<b>MV2-D18S-(L/R)-()</b>		1,328.
Back panel for Kiosk			24"	2"	56"	<b>MV1-BP5624()</b>	
		24"	2"	64"	<b>MV1-BP6424()</b>		918.
Adjustable shelf kit (3 shelves)	Deep	9"	24"	1"	<b>MV1-DAS</b>		383.
	Standard	9"	18"	1"	<b>MV1-SAS</b>		383.
File support (set of 2) 					<b>MD6-FS</b>		11.

## Order Code

Example:	<b>MV3-D64F-RV</b>
<b>MV3</b>	Vertical storage
<b>D</b>	30" deep
<b>64</b>	Height
<b>F</b>	Front access
<b>R</b>	Right door hinge
<b>V</b>	Case and front finish

## Specification Information

Specify Melamine finishes for sides, top, and back of Options Kiosk.

Options Kiosk fronts may be specified in any standard Morrison painted finish. Sides, top and back are available in melamine only.

### Melamine finishes:

128	Fog
119	Pumice
114	Folkstone Grey

Kiosk storage is available in full painted finishes only.

S-	24"W x 24"D
D-	24"W x 30"D
L-	Hinged door for coats (shelves) on left
R-	Hinged door for coats (shelves) on right

All kiosks have KnollKey lock for door, and internal sliding lock switch for files.

## Application Notes

Options Kiosks are freestanding wood construction vertical storage with four Morrison file drawers, hinged door cabinet, and coat storage with door. Options Kiosks have painted fronts and melamine sides, back and interior. The melamine top is finished, with lock cams and a few pilot holes visible.

Kiosks are identical to Options kiosks but painted on all surfaces.

64"H Kiosks include cabinet with hinged door over the file drawers.

18"H top cabinet attaches to 56"H Kiosk to create 74"H storage unit. Top cabinet includes front access hinged door storage over the coat storage and open shelves accessible from the sides.

File supports for kiosk drawers must be ordered separately.

Flat top caps may be specified separately to coordinate with Morrison panel top caps; vault-shaped cupolas may also be used to prevent storage above kiosk.

Kiosk back panels and extended depth top caps or cupolas are used with adjacent vertical panels.

Back panel is notched to connect to panel with brackets and trim included.

Specify straight connector track same height as vertical panel, and hi/low top cap for post configurations, in width of adjacent panel.

description	type	w	d	h	pattern no.	list price	V1		
							L	V2	V3
Pencil drawer		14 1/2"	15"	1 1/4"	<b>MM1-PD-( )</b>	\$195.			
Coathooks (10)		-	-	-	<b>MM2-CH</b>	59.			
Pencil tray		12 1/4"	6 1/4"	1 1/4"	<b>MD6-PT</b>	32.			
Stationery inserts		-	-	-	<b>MD6-ST</b>	130.			
Stabilizer foot		2"	13"	14"	<b>MM1-SF-( )</b>	226.			
Carpet grips (10)	Panel	-	-	-	<b>MM2-CG</b>	17.			
	Pedestal or desk support	-	-	-	<b>MM2-NCG</b>	17.			
Worksurface insert package	Package of 10				<b>MM1-IN10</b>	3.			
	Package of 100				<b>MM1-IN100</b>	29.			
Replacement grommets (10)	Thin surface	3"	3"	1 1/4"	<b>MM1UG</b>	81.			
	Thick surface	3"	3"	1 3/4"	<b>MM1WG</b>	81.			
Privacy screen alignment clips, set of 10	Corner				<b>MZ1-LS</b>	28.			
	Straight				<b>MZ1-SS</b>	28.			
Desk-to-desk cable sleeves	(10)				<b>MN2-CS</b>	36.			
Wire managers (set of 10)		-	-	-	<b>ML2-WM</b>	96.			
Sample Worksurface	Currents for Morrison	16"	16"	1"	<b>AWMSAMP1616</b>	75.	95.	200.	
	Morrison	16"	16"	1 1/4"	<b>MSAMP1616</b>	75.	95.	200.	

**Order Code**

Example:	<b>MM1-PD-612</b>
<b>MM1</b>	Accessory
<b>PD</b>	Height
<b>612</b>	Medium grey

Products indicated with are available on KnollNow.

**Specification Information**

*Specify paint finishes.*

Coathooks engage below the top cap at any point on the vertical panel.

Pencil drawer secures underneath a worksurface.

Stabilizer foot attaches to connector track to stabilize panel runs.

Carpet grips snap under panel glides to prevent panel runs from sliding. Glide rotates in carpet grip to permit leveling.



<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
AA1 39E	77	AWM2 C4884 S	140	AY1 MT16	85	AY1-2542M	84
AA1 48E	77	AWM2 C6036 S	139	AY1 MT25	85	AY1-2542M-A	82
AA1 64E	77	AWM2 C6042 L	139	AY1 MT32	85	AY1-2542M-W	83
AA1 RE	77	AWM2 C6042 R	139	AY1 MX16	85	AY1-2548M	84
AA1 T06	77	AWM2 C6042 S	139	AY1 MX25	85	AY1-2548M-A	82
AA1 T18	77	AWM2 C6048 D	139	AY1 MX32	85	AY1-2548M-W	83
AA1 T24	77	AWM2 C6048 L	139	AY1 SML16	87	AY1-2560M	84
AA1 T30	77	AWM2 C6048 R	139	AY1 SMP16	87	AY1-2560M-A	82
AA1 T36	77	AWM2 C6048 S	139	AY1 SMT16	87	AY1-2560M-W	83
AA1 T42	77	AWM2 C6060 D	138	AY1 SMX16	87	AY1-CE	85, 87
AA1 T48	77	AWM2 C6060 L	138	AY1-1618M-A	82	AY1-HLA	87
AA1 T60	77	AWM2 C6060 R	138	AY1-1618M-W	83	AY1-MMK	86
AA1 T72	77	AWM2 C6060 S	138	AY1-1618S-A	82	AY1-SMK	87
AA1 TML2	77	AWM2 C7236 S	139	AY1-1618S-W	83	AY1-DMK	40, 41
AA1 TMP1	77	AWM2 C7242 L	139	AY1-1624M	84	LL2T5E19	192
AA1 TMS2	77	AWM2 C7242 R	139	AY1-1624M-A	82	LL2T5E25	192
AA1 TMT3	77	AWM2 C7242 S	139	AY1-1624M-W	83	LL2T5E37	192
AA1 TMX4	77	AWM2 C7248 D	139	AY1-1624S	84	LL2T5E49	192
AA1-LO24 DN	193	AWM2 C7248 L	139	AY1-1624S-A	82	LO2-24	191
AA1-LO30 DN	193	AWM2 C7248 R	139	AY1-1624S-W	83	LO2-30	191
AA1-LO36 DN	193	AWM2 C7248 S	139	AY1-1630M	84	LO2-36	191
AA1-LO42 DN	193	AWM2 C8448 D	139	AY1-1630M-A	82	LO2-42	191
AA1-LO48 DN	193	AWM2 C8448 L	139	AY1-1630M-W	83	LO2-48	191
AC1-39E1	77	AWM2 C8448 R	139	AY1-1630S	84	LO2-60	191
AC1-48E1	77	AWM2 C8448 S	139	AY1-1630S-A	82	LO2-VD	191
AC1-64E1	77	AWM2 F2424	137	AY1-1630S-W	83	LS1-S2413	191
AWM1 S36	142	AWM2 F3024	137	AY1-1636M	84	LS1-S3013	191
AWM1 S42	142	AWM2 F3030	137	AY1-1636M-A	82	LS1-S3613	191
AWM1 S48	142	AWM2 F3624	137	AY1-1636M-W	83	LS1-S4213	191
AWM1 S60	142	AWM2 F3630	137	AY1-1636S	84	LS1-S4813	191
AWM1 S66	142	AWM2 F4224	137	AY1-1636S-A	82	LS1-S6013	191
AWM1 S72	142	AWM2 F4230	137	AY1-1636S-W	83	LU1-A48S-ALL	136
AWM1 S78	142	AWM2 F4824	137	AY1-1642M	84	LU1-A48S-ARL	136
AWM1 S84	142	AWM2 F4830	137	AY1-1642M-A	82	LU1-C4242SS	131
AWM2 C3660 S	140	AWM2 F5424	137	AY1-1642M-W	83	LU1-C4848DD	131
AWM2 C3672 S	140	AWM2 F5430	137	AY1-1642S	84	LU1-C4848DS	131
AWM2 C4242 D	138	AWM2 F6024	137	AY1-1642S-A	82	LU1-C4848SD	131
AWM2 C4242 L	138	AWM2 F6030	137	AY1-1642S-W	83	LU1-C4848SS	131
AWM2 C4242 R	138	AWM2 F6624	137	AY1-1648M	84	LU1-C4860DS	131
AWM2 C4242 S	138	AWM2 F6630	137	AY1-1648M-A	82	LU1-C4860SD	131
AWM2 C4260 L	140	AWM2 F7224	137	AY1-1648M-W	83	LU1-C4860SS	131
AWM2 C4260 R	140	AWM2 F7230	137	AY1-1648S	84	LU1-C4872DS	131
AWM2 C4260 S	140	AWM2 F7824	137	AY1-1648S-A	82	LU1-C4872SD	131
AWM2 C4272 L	140	AWM2 F7830	137	AY1-1648S-W	83	LU1-C4872SS	131
AWM2 C4272 R	140	AWM2 F8424	137	AY1-1660M	84	LU1-C6048DS	131
AWM2 C4272 S	140	AWM2 F9024	137	AY1-1660M-A	82	LU1-C6048SD	131
AWM2 C4848 D	138	AWM2 F9030	137	AY1-1660M-W	83	LU1-C6048SS	131
AWM2 C4848 L	138	AWM2 F9624	137	AY1-1660S	84	LU1-C7248DS	131
AWM2 C4848 R	138	AWM2 F9630	137	AY1-1660S-A	82	LU1-C7248SD	131
AWM2 C4848 S	138	AWM2 P4875 S	141	AY1-1660S-W	83	LU1-C7248SS	131
AWM2 C4860 D	140	AWM2 P4887 S	141	AY1-2518M-A	82	LU1-D36S-B	134
AWM2 C4860 L	140	AWM2 P7548 S	141	AY1-2518M-W	83	LU1-D42S-B	134
AWM2 C4860 R	140	AWM2 P8748 S	141	AY1-2524M	84	LU1-D48S-B	134
AWM2 C4860 S	140	AWMSAMP1616	208	AY1-2524M-A	82	LU1-M48S-BLL	135
AWM2 C4872 D	140	AY1 CS	85, 87	AY1-2524M-W	83	LU1-M48S-BRL	135
AWM2 C4872 L	140	AY1 ML16	85	AY1-2530M	84	LU1-R3050-B	132
AWM2 C4872 R	140	AY1 ML25	85	AY1-2530M-A	82	LU1-R6330B	132
AWM2 C4872 S	140	AY1 ML32	85	AY1-2530M-W	83	LU1-R7530B	132
AWM2 C4884 D	140	AY1 MP16	85	AY1-2536M	84	LU1-S10818-A	126
AWM2 C4884 L	140	AY1 MP25	85	AY1-2536M-A	82	LU1-S10818-B	126
AWM2 C4884 R	140	AY1 MP32	85	AY1-2536M-W	83	LU1-S10824-A	127

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
LU1-S10824-B	127	LU1-S8418-B	126	M2-1**0	64	M2-8300	61, 62
LU1-S12018-A	126	LU1-S8424-A	127	M2-1*0*	64	M2-8400	61, 62
LU1-S12018-B	126	LU1-S8424-B	127	M2-1060	59, 60	M2-8*8*	65
LU1-S12024-A	127	LU1-S8430-A	128	M2-1080	59, 60	M2-88**	65
LU1-S12024-B	127	LU1-S8430-B	128	M2-1*1*	65	M2-8*8*	66
LU1-S2424-A	127	LU1-S9018-A	126	M2-11**	65	M2-88**	66
LU1-S2424-B	127	LU1-S9018-B	126	M2-1*1*	66	M2-8*80	63
LU1-S3018-A	126	LU1-S9024-A	127	M2-11**	66	M2-88*0	63
LU1-S3018-B	126	LU1-S9024-B	127	M2-1*10	63	M2-8*80	64
LU1-S3024-A	127	LU1-S9030-A	128	M2-11*0	63	M2-88*0	64
LU1-S3024-B	127	LU1-S9030-B	128	M2-1*10	64	M2-888*	65, 66
LU1-S3030-A	128	LU1-S9618-A	126	M2-11*0	64	M2-8900	61, 62
LU1-S3030-B	128	LU1-S9618-B	126	M2-111*	65, 66	M2-9030	59, 60
LU1-S3618-A	126	LU1-S9624-A	127	M2-1600	61, 62	M2-9300	61, 62
LU1-S3618-B	126	LU1-S9624-B	127	M2-1800	61, 62	M2-9303	63, 64
LU1-S3624-A	127	LU1-S9630-A	128	M2-5***	65, 66	M2-9330	63, 64
LU1-S3624-B	127	LU1-S9630-B	128	M2-5**0	63	M2-9333	65, 66
LU1-S3630-A	128	LU1-T4224-B	132	M2-5*0*	63	M2-9390	63, 64
LU1-S3630-B	128	LU1-T4830-B	132	M2-5**0	64	M2-9393	65, 66
LU1-S36DS-A	130	LU1-T48A-L	129	M2-5*0*	64	M2-9930	63, 64
LU1-S4218-A	126	LU1-T48A-R	129	M2-5030	59, 60	M2-9933	65, 66
LU1-S4218-B	126	LU1-T48B-L	129	M2-5040	59, 60	M2-9993	65, 66
LU1-S4224-A	127	LU1-T48B-R	129	M2-5080	59, 60	MA1-CE	74
LU1-S4224-B	127	LU1-T54A-L	129	M2-5300	61, 62	MA1-CI48	73
LU1-S4230-A	128	LU1-T54A-R	129	M2-5400	61, 62	MA1-CI60	73
LU1-S4230-B	128	LU1-T54B-L	129	M2-5*5*	65	MA1-CI72	73
LU1-S42DS-A	130	LU1-T54B-R	129	M2-55**	65	MA1-CL	74
LU1-S4818-A	126	LU1-T60A-L	129	M2-5*5*	66	MA1-CP	74
LU1-S4818-B	126	LU1-T60A-R	129	M2-55**	66	MA1-CS	74
LU1-S4824-A	127	LU1-T60B-L	129	M2-5*50	63	MA1-CT	74
LU1-S4824-B	127	LU1-T60B-R	129	M2-55*0	63	MA1-CX	74
LU1-S4830-A	128	LU1-T72A-L	129	M2-5*50	64	MA1-F14C	72
LU1-S4830-B	128	LU1-T72A-R	129	M2-55*0	64	MA1-F22C	72
LU1-S48DS-A	130	LU1-T72B-L	129	M2-555*	65, 66	MA1-F32C	72
LU1-S5418-A	126	LU1-T72B-R	129	M2-5800	61, 62	MA1-F38C	72
LU1-S5418-B	126	LU1-V3618-A	130	M2-6***	65, 66	MA1-F4200	71
LU1-S5424-A	127	LU1-V3624-A	130	M2-6**0	63	MA1-F4240	71
LU1-S5424-B	127	LU1-V4224-A	130	M2-6*0*	63	MA1-F4244	71
LU1-S5430-A	128	LU1-V4230-A	130	M2-6**0	64	MA1-F4288	71
LU1-S5430-B	128	LU1-V42SS-A	130	M2-6*0*	64	MA1-F42C	72
LU1-S6018-A	126	LU1-V4824-A	130	M2-6030	59, 60	MA1-F42F	72
LU1-S6018-B	126	LU1-V4830-A	130	M2-6040	59, 60	MA1-F4800	71
LU1-S6024-A	127	LU1-V48DS-A	130	M2-6050	59, 60	MA1-F4840	71
LU1-S6024-B	127	LU1-V48SS-A	130	M2-6080	59, 60	MA1-F4844	71
LU1-S6030-A	128	LU1-W36AL	133	M2-6300	61, 62	MA1-F4888	71
LU1-S6030-B	128	LU1-W36AR()	133	M2-6400	61, 62	MA1-F48C	72
LU1-S6618-A	126	LU1-W36BL	133	M2-6500	61, 62	MA1-F48F	72
LU1-S6618-B	126	LU1-W36BR	133	M2-6*6*	65	MA1-F5600	71
LU1-S6624-A	127	LU1-W42AL()	133	M2-66**	65	MA1-F5640	71
LU1-S6624-B	127	LU1-W42AR()	133	M2-6*6*	66	MA1-F5644	71
LU1-S6630-A	128	LU1-W42BL	133	M2-66**	66	MA1-F5688	71
LU1-S6630-B	128	LU1-W42BR	133	M2-6*60	63	MA1-F56C	72
LU1-S7218-A	126	LU1-W48AL()	133	M2-66*0	63	MA1-F56F	72
LU1-S7218-B	126	LU1-W48AR	133	M2-6*60	64	MA1-F6400	71
LU1-S7224-A	127	LU1-W48BL	133	M2-66*0	64	MA1-F6440	71
LU1-S7224-B	127	LU1-W48BR	133	M2-666*	65, 66	MA1-F6444	71
LU1-S7230-A	128	LU1-Y36S-B	134	M2-6800	61, 62	MA1-F6488	71
LU1-S7230-B	128	LU1-Y42S-B	134	M2-8***	65, 66	MA1-F64C	72
LU1-S7818-A	126	LU1-Y48S-B	134	M2-8**0	63	MA1-F64F	72
LU1-S7818-B	126	LU1-Y60S-B	134	M2-8*0*	63	MA1-F8000	71
LU1-S7824-A	127	LU1-YTS	134	M2-8**0	64	MA1-F8040	71
LU1-S7824-B	127	LV3-S64(L/R)	207	M2-8*0*	64	MA1-F8044	71
LU1-S7830-A	128	M2-1***	65, 66	M2-8030	59, 60	MA1-F8088	71
LU1-S7830-B	128	M2-1**0	63	M2-8040	59, 60	MA1-F80C	72
LU1-S8418-A	126	M2-1*0*	63	M2-8090	59, 60	MA1-F80F	72

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MA1-H18	74	MB1-DB24	163	MB3-F30W	157	MC1-A16L2	49, 51
MA1-H24	74	MB1-DB30	163	MB3-V36M	154	MC1-A16P1	49, 51
MA1-H30	74	MB1-FV26-(L/R)	158	MB3-V36W	155	MC1-A16S1	49, 51
MA1-H36	74	MB1-L1	159	MB3-V42M	154	MC1-A16S2	50, 52
MA1-H42	74	MB1-NM-(L/R)	158	MB3-V42W	155	MC1-A16T3	49, 51
MA1-H48	74	MB1-NW-(L/R)	158	MB3-V48M	154	MC1-A16X4	49, 51
MA1-H6	74	MB1-SB18(L/R)	163	MB3-V48W	155	MC1-A18E1	49, 51
MA1-H60	74	MB1-SB24(L/R)	163	MC1-30E1	53, 54	MC1-A18L2	49, 51
MA1-HCS10	75	MB1-SB30(L/R)	163	MC1-30L2	53, 54	MC1-A18P1	49, 51
MA1-HCS14	75	MB1-T18M	159	MC1-30S1	53, 54	MC1-A18S1	49, 51
MA1-HCS16	75	MB1-T18W	159	MC1-30T3	53, 54	MC1-A18S2	50, 52
MA1-HCS18	75	MB1-T24M	159	MC1-30V2	55, 56	MC1-A18T3	49, 51
MA1-HCS22	75	MB1-T24W	159	MC1-30X4	53, 54	MC1-A18X4	49, 51
MA1-HCS26	75	MB1-TC	181, 184	MC1-30Y3	56	MC1-A22E1	49, 51
MA1-HCS32	75	MB1-UAUXS	184	MC1-39E1	53, 54	MC1-A22L2	49, 51
MA1-HCS6	75	MB1-UC13	184	MC1-39L2	53, 54	MC1-A22P1	49, 51
MA1-HCS8	75	MB1-VP-1224M	157	MC1-39S1	53, 54	MC1-A22S1	49, 51
MA1-HCS9	75	MB1-VP-1224W	157	MC1-39T3	53, 54	MC1-A22S2	50, 52
MA1-HHL18	74	MB1-VP-1226M	157	MC1-39V2	55, 56	MC1-A22T3	49, 51
MA1-HHL24	74	MB1-VP-1226W	157	MC1-39X4	53, 54	MC1-A22X4	49, 51
MA1-HHL30	74	MB1-W20M-(L/R)	158	MC1-39Y3	56	MC1-A32E1	49, 51
MA1-HHL36	74	MB1-W20W-(L/R)	158	MC1-42E1	53, 54	MC1-A32L2	49, 51
MA1-HHL42	74	MB1-WS54	163	MC1-42L2	53, 54	MC1-A32P1	49, 51
MA1-HHL48	74	MB1-WS60	163	MC1-42S1	53, 54	MC1-A32S1	49, 51
MA1-HHL6	74	MB1-WS66	163	MC1-42T3	53, 54	MC1-A32S2	50, 52
MA1-HHL60	74	MB1-WS72	163	MC1-42V2	55, 56	MC1-A32T3	49, 51
MA1-PDC-T	98	MB2-AUX-S	181	MC1-42X4	53, 54	MC1-A32X4	49, 51
MA1-TATT2	98	MB2-C18M-(L/R)	156	MC1-42Y3	56	MCE1BD6648D(L/R)	144
MA1-TATT3	98	MB2-C18W-(L/R)	156	MC1-48E1	53, 54	MCE1BD6648S(L/R)	144
MA1-TC18	76	MB2-C24M-(L/R)	156	MC1-48L2	53, 54	MCE1BD7248D(L/R)	144
MA1-TC24	76	MB2-C24W-(L/R)	156	MC1-48S1	53, 54	MCE1BD7248S(L/R)	144
MA1-TC30	76	MB2-C30M-(L/R)	156	MC1-48T3	53, 54	MCE1BD7848D(L/R)	144
MA1-TC36	76	MB2-C30W-(L/R)	156	MC1-48V2	55, 56	MCE1BD7848S(L/R)	144
MA1-TC42	76	MB2-RD3026-(L/R)	158	MC1-48X4	53, 54	MCE1BD8448D(L/R)	144
MA1-TC48	76	MB2-RD3626-(L/R)	158	MC1-48Y3	56	MCE1BD8448S(L/R)	144
MA1-TC6	76	MB2-RS2426-(L/R)	158	MC1-56E1	53, 54	MCE1CR24L	148
MA1-TC60	76	MB2-RS3026-(L/R)	158	MC1-56L2	53, 54	MCE1CR24N	148
MA1-TCE	76	MB2-TS	181, 184	MC1-56S1	53, 54	MCE1CR24R	148
MA1-TCL	76	MB2-YM-(L/R)	156	MC1-56T3	53, 54	MCE1H4818	148
MA1-TCP	76	MB2-YW-(L/R)	156	MC1-56V2	55, 56	MCE1H4818P	148
MA1-TCS	76	MB3-E18M	154	MC1-56X4	53, 54	MCE1H6024	148
MA1-TCT	76	MB3-E18W	154	MC1-56Y3	56	MCE1H6024P	148
MA1-V4206	71	MB3-E24M	154	MC1-64E1	53, 54	MCE1L3636SSN	145
MA1-V4806	71	MB3-E24W	154	MC1-64H1	57, 58	MCE1L4242DSN	145
MA1-V5606	71	MB3-E30M	154	MC1-64L2	53, 54	MCE1L4242SDN	145
MA1-V6406	71	MB3-E30W	154	MC1-64S1	53, 54	MCE1L4242SSN	145
MA1-V8006	71	MB3-E36M	154	MC1-64T3	53, 54	MCE1L4260SSN	146
MA1-VWM39	75	MB3-E36W	154	MC1-64V2	55, 56	MCE1L4266SSN	146
MA1-VWM42	75	MB3-EC18M	154	MC1-64X4	53, 54	MCE1L4272SSN	146
MA1-VWM48	75	MB3-EC18W	154	MC1-64Y3	56	MCE1L4278SSN	146
MA1-VWM56	75	MB3-EC24M	154	MC1-80E1	53, 54	MCE1L4848DDN	145
MA1-VWM64	75	MB3-EC24W	154	MC1-80L2	53, 54	MCE1L4848DSN	145
MA1-VWM80	75	MB3-EC30M	154	MC1-80S1	53, 54	MCE1L4848SDN	145
MB1-AUX-C	156	MB3-EC30W	154	MC1-80T3	53, 54	MCE1L4848SSN	145
MB1-AUX-DM	159	MB3-EV36M	154	MC1-80V2	55, 56	MCE1L4860DSN	146
MB1-AUX-DW	159	MB3-EV36W	154	MC1-80X4	53, 54	MCE1L4860SDN	146
MB1-B13	181, 184	MB3-EV42M	154	MC1-80Y3	56	MCE1L4860SSN	146
MB1-C13	181	MB3-EV42W	154	MC1-A09E1	49, 51	MCE1L4866DSN	146
MB1-CB18M	157	MB3-EV48M	154	MC1-A09L2	49, 51	MCE1L4866SDN	146
MB1-CB18W	157	MB3-EV48W	154	MC1-A09P1	49, 51	MCE1L4866SSN	146
MB1-CB24M	157	MB3-F18M	157, 163	MC1-A09S1	49, 51	MCE1L4872DSN	146
MB1-CB24W	157	MB3-F18W	157	MC1-A09S2	50, 52	MCE1L4872SDN	146
MB1-CB30M	157	MB3-F24M	157, 163	MC1-A09T3	49, 51	MCE1L4872SSN	146
MB1-CB30W	157	MB3-F24W	157	MC1-A09X4	49, 51	MCE1L4878SSN	146
MB1-D	159	MB3-F30M	157, 163	MC1-A16E1	49, 51	MCE1L4884SSN	146

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MCE1L6042SSN	146	MD6-ST	178, 208	MM1-DSP1	40, 41	MN2-DD	163
MCE1L6048DSN	146	MD6-VP	175	MM1-DSS1	40, 41	MN2-E06	161
MCE1L6048SDN	146	MD6-W0B2F	175	MM1-IN10	208	MN2-E09	161
MCE1L6048SSN	146	MD6-WDK	175	MM1-IN100	208	MN2-E12	161
MCE1L6642SSN	146	MD6-X0B2F	175	MM1-PD	208	MN2-E18	161
MCE1L6648DSN	146	MD6-XDK	175	MM1-PSL2	68	MN2-E24	161
MCE1L6648SDN	146	MD7 DC30C	176	MM1-PSS1	68	MN2-EW18	161
MCE1L6648SSN	146	MD7 DW30C	176	MM1-SF	68, 208	MN2-EW24	161
MCE1L7242SSN	146	MD7 DW36C	176	MM1UG	208	MN2-F24	162
MCE1L7248DSN	146	MHD-8036-(L/R)-(P/L/V)	41	MM1WG	208	MN2-F30	162
MCE1L7248SDN	146	MHD-8042-(L/R)-(P/L/V)	41	MM1-WS30	67	MN2-F36	162
MCE1L7248SSN	146	MK4-B3026-(P/V)	153	MM1-WS39	67	MN2-F42	162
MCE1L7842SSN	147	MK4-B3626-(P/V)	153	MM1-WS42	67	MN2-F48	162
MCE1L7848SSN	147	MK4-B4226-(P/V)	153	MM1-WS48	67	MN2-F54	162
MCE1L8448SSN	147	MK4-B4826-(P/V)	153	MM1-WS56	67	MN2-F60	162
MCE1R1212C	148	MK4-B6026-(P/V)	153	MM1-WS64	67	MN2-F66	162
MCE1R2424N	143	MK4-B6626-(P/V)	153	MM1-WS80	67	MN2-F72	162
MCE1R2430N	143	MK4-B7226-(P/V)	153	MM2-CG	68, 208	MN2-F78	162
MCE1R3024N	143	MK4-C2618-P/V	150	MM2-CH	208	MN2-NS14	164
MCE1R3030N	143	MK4-C2624-P/V	150	MM2-L26	108, 109, 110, 118, 119, 120, 132	MN2-OF	97, 165
MCE1R3624N	143	MK4-C2630-P/V	150	MM2-NCC	208	MN2-PMU	164
MCE1R3630N	143	MK4-C2636-P/V	150	MM3-AS24	180	MN2-PMW	164
MCE1R4224N	143	MK4-K6026-P/V	152	MM3-AS30	180	MN2-RDR	161, 163
MCE1R4230N	143	MK4-K6626-P/V	152	MM3-AS36	180	MN2-RER	161
MCE1R4824N	143	MK4-K7226-P/V	152	MM3-AS42	180	MN2-RSAK	161, 163
MCE1R4830N	143	MK4-K7826-P/V	152	MM3-AS48	180	MN2-S3017	189
MCE1R5424N	143	MK4-R3026-(P/V)	153	MM3-AS60	180	MN2-S3018	189
MCE1R5430N	143	MK4-R3626-(P/V)	153	MM3-AS72	180	MN2-S3617	189
MCE1R6024N	143	MK4-R4226-(P/V)	153	MM3-IS60F	179	MN2-S3618	189
MCE1R6030N	143	MK4-R4826-(P/V)	153	MM3-IS60R	179	MN2-S4217	189
MCE1R6624N	143	MK4-R6026-(P/V)	153	MM3-IS66F	179	MN2-S4218	189
MCE1R6630N	143	MK4-R6626-(P/V)	153	MM3-IS66R	179	MN2-S4817	189
MCE1R7224N	143	MK4-R7226-(P/V)	153	MM3-IS72F	179	MN2-S4818	189
MCE1R7230N	143	MK4-T6026-P/V	152	MM3-IS72R	179	MN2-S5417	189
MCE1R7824N	143	MK4-T6626-P/V	152	MM3-IS78F	179	MN2-S5418	189
MCE1R7830N	143	MK4-T7226-P/V	152	MM3-IS78R	179	MN2-S6017	189
MCE1R8424N	143	MK4-T7826-P/V	152	MM3-ISE	179	MN2-S6018	189
MCE1R8430N	143	MK4-U2618-P/V	150	MM3-ISX	179	MN2-S6617	189
MCE1R9024N	143	MK4-U2624-P/V	150	MN1-DP	163	MN2-S6618	189
MCE1R9030N	143	MK4-U2630-P/V	150	MN2-CS	169, 173, 208	MN2-S7217	189
MCE1R9624N	143	MK4-U2636-P/V	150	MN2-D0024	160	MN2-S7218	189
MCE1R9630N	143	MK4-V2636-P/V	151	MN2-D0030	160	MN2-S7817	189
MCE1W362430N	149	MK4-V2642-P/V	151	MN2-D0036	160	MN2-S7818	189
MCE1W363024N	149	MK4-X2636-P/V	151	MN2-D0042	160	MN2-SO20	165
MCE1W422430N	149	MK4-X2642-P/V	151	MN2-D0048	160	MN2SO20	200
MCE1W423024N	149	ML1-HCWM24	92, 169	MN2-D0054	160	MN2-SO21	165
MCE1W482430N	149	ML2-WM	186, 208	MN2-D0060	160	MN2SO21	200
MCE1W483024N	149	ML3-T30	186	MN2-D0066	160	MN2T5E19	190
MCE1W722430N	149	ML3-T36	186	MN2-D0072	160	MN2T5E25	190
MCE1W723024N	149	ML3-T42	186	MN2-D0078	160	MN2T5E37	190
MD4-WDD30	175	ML3-T48	186	MN2-D2400	160	MN2T5E49	190
MD6-BD	178	ML3-T60	186	MN2-D3000	160	MO6-WMSB	188, 191
MD6-DOB2F()	174	ML3-T66	186	MN2-D3600	160	MO6-WMSK	188, 191
MD6-D2B1F()	174	ML3-T72	186	MN2-D3636	160	MO7-NB30	187
MD6-E0B2F()	174	ML3-T78	186	MN2-D4200	160	MO7-NB36	187
MD6-E2B1F()	174	ML3-T84	186	MN2-D4242	160	MO7-NB42	187
MD6-FD	178	ML3-T90	186	MN2-D4800	160	MO7-NB48	187
MD6-FS	178, 207	ML4-F30	186	MN2-D4848	160	MO7-NB60	187
MD6-M0B2F	177	ML4-F36	186	MN2-D5400	160	MO7-PMB	188
MD6-M1B1F	177	ML4-F42	186	MN2-D6000	160	MO7-SMB	188
MD6-M2B1F	177	ML4-F48	186	MN2-D6060	160	MO7-VD	185, 188
MD6-PT	177, 178, 208	ML4-F60	186	MN2-D6600	160	MO8-30	185
MD6-PULL	178	ML4-F66	186	MN2-D7200	160	MO8-36	185
MD6-S0B2F()	174	ML4-F72	186	MN2-D7272	160	MO8-42	185
MD6-S2B1F()	174	MM1-DSL2	40, 41	MN2-D7800	160	MO8-48	185

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MO8-60	185	MP2-3960-N	12	MP2-4848N	20	MP2-6442	28, 30
MO8-N30	187	MP2-4218	16, 18	MP2-4848-P	36	MP2-6442-C/T/F	29
MO8-N36	187	MP2-4218-C/T	17	MP2-4848-V	23	MP2-6442-M	38, 39
MO8-N42	187	MP2-4218-N	16	MP2-4860	20	MP2-6442N	28
MO8-N48	187	MP2-4218-P	36	MP2-4860N	20	MP2-6442-P	37
MO8-N60	187	MP2-4218-V	19	MP2-5618	24, 26	MP2-6442-V	31
MO8-WMB	188	MP2-4224	16, 18	MP2-5618-C/T	25	MP2-6448	28, 30
MO8-WMR	188	MP2-4224-C/T	17	MP2-5618N	24	MP2-6448-C/T/F	29
MP2-3018	8, 10	MP2-4224-N	16	MP2-5618-P	37	MP2-6448-M	38, 39
MP2-3018-C/T	9	MP2-4224-P	36	MP2-5618-V	27	MP2-6448N	28
MP2-3018-N	8	MP2-4224-V	19	MP2-5624	24, 26	MP2-6448-P	37
MP2-3018-V	11	MP2-4230	16, 18	MP2-5624-C/T	25	MP2-6448-V	31
MP2-3024	8, 10	MP2-4230-C/T	17	MP2-5624-M	38, 39	MP2-6460	28
MP2-3024-C/T	9	MP2-4230-N	16	MP2-5624N	24	MP2-6460N	28
MP2-3024-N	8	MP2-4230-P	36	MP2-5624-P	37	MP2-8018	32, 34
MP2-3024-V	11	MP2-4230-V	19	MP2-5624-V	27	MP2-8018-C/T	33
MP2-3030	8, 10	MP2-4236	16, 18	MP2-5630	24, 26	MP2-8018-N	32
MP2-3030-C/T	9	MP2-4236-C/T	17	MP2-5630-C/T	25	MP2-8018-P	37
MP2-3030-N	8	MP2-4236-N	16	MP2-5630-M	38, 39	MP2-8018-V	35
MP2-3030-V	11	MP2-4236-P	36	MP2-5630N	24	MP2-8024	32, 34
MP2-3036	8, 10	MP2-4236-V	19	MP2-5630-P	37	MP2-8024-C/T	33
MP2-3036-C/T	9	MP2-4242	16, 18	MP2-5630-V	27	MP2-8024-M	38, 39
MP2-3036-N	8	MP2-4242-C/T	17	MP2-5636	24, 26	MP2-8024-N	32
MP2-3036-V	11	MP2-4242-N	16	MP2-5636-C/T	25	MP2-8024-P	37
MP2-3042	8, 10	MP2-4242-P	36	MP2-5636-M	38, 39	MP2-8024-V	35
MP2-3042-C/T	9	MP2-4242-V	19	MP2-5636N	24	MP2-8030	32, 34
MP2-3042-N	8	MP2-4248	16, 18	MP2-5636-P	37	MP2-8030-C/T	33
MP2-3042-V	11	MP2-4248-C/T	17	MP2-5636-V	27	MP2-8030-M	38, 39
MP2-3048	8, 10	MP2-4248-N	16	MP2-5642	24, 26	MP2-8030-N	32
MP2-3048-C/T	9	MP2-4248-P	36	MP2-5642-C/T	25	MP2-8030-P	37
MP2-3048-N	8	MP2-4248-V	19	MP2-5642-M	38, 39	MP2-8030-V	35
MP2-3048-V	11	MP2-4260	16	MP2-5642N	24	MP2-8036	32, 34
MP2-3060	8	MP2-4260-N	16	MP2-5642-P	37	MP2-8036-C/T	33
MP2-3060-N	8	MP2-4818	20, 22	MP2-5642-V	27	MP2-8036-M	38, 39
MP2-3918	12, 14	MP2-4818-C/T/F	21	MP2-5648	24, 26	MP2-8036-N	32
MP2-3918-C/T/F	13	MP2-4818N	20	MP2-5648-C/T	25	MP2-8036-P	37
MP2-3918-N	12	MP2-4818-P	36	MP2-5648-M	38, 39	MP2-8036-V	35
MP2-3918-P	36	MP2-4818-V	23	MP2-5648N	24	MP2-8042	32, 34
MP2-3918-V	15	MP2-4824	20, 22	MP2-5648-P	37	MP2-8042-C/T	33
MP2-3924	12, 14	MP2-4824-C/T/F	21	MP2-5648-V	27	MP2-8042-M	38, 39
MP2-3924-C/T/F	13	MP2-4824-M	38, 39	MP2-5660	24	MP2-8042-N	32
MP2-3924-N	12	MP2-4824N	20	MP2-5660N	24	MP2-8042-P	37
MP2-3924-P	36	MP2-4824-P	36	MP2-6418	28, 30	MP2-8042-V	35
MP2-3924-V	15	MP2-4824-V	23	MP2-6418-C/T/F	29	MP2-8048	32, 34
MP2-3930	12, 14	MP2-4830	20, 22	MP2-6418N	28	MP2-8048-C/T	33
MP2-3930-C/T/F	13	MP2-4830-C/T/F	21	MP2-6418-P	37	MP2-8048-M	38, 39
MP2-3930-N	12	MP2-4830-M	38, 39	MP2-6418-V	31	MP2-8048-N	32
MP2-3930-P	36	MP2-4830N	20	MP2-6424	28, 30	MP2-8048-V	35
MP2-3930-V	15	MP2-4830-P	36	MP2-6424-C/T/F	29	MP3-A1618	45, 47, 48
MP2-3936	12, 14	MP2-4830-V	23	MP2-6424-M	38, 39	MP3-A1618N	46
MP2-3936-C/T/F	13	MP2-4836	20, 22	MP2-6424N	28	MP3-A1624	45, 47, 48
MP2-3936-N	12	MP2-4836-C/T/F	21	MP2-6424-P	37	MP3-A1624-M	44
MP2-3936-P	36	MP2-4836-M	38, 39	MP2-6424-V	31	MP3-A1624N	46
MP2-3936-V	15	MP2-4836N	20	MP2-6430	28, 30	MP3-A1630	45, 47, 48
MP2-3942	12, 14	MP2-4836-P	36	MP2-6430-C/T/F	29	MP3-A1630-M	44
MP2-3942-C/T/F	13	MP2-4836-V	23	MP2-6430-M	38, 39	MP3-A1630N	46
MP2-3942-N	12	MP2-4842	20, 22	MP2-6430N	28	MP3-A1636	45, 47, 48
MP2-3942-P	36	MP2-4842-C/T/F	21	MP2-6430-P	37	MP3-A1636-M	44
MP2-3942-V	15	MP2-4842-M	38, 39	MP2-6430-V	31	MP3-A1636N	46
MP2-3948	12, 14	MP2-4842N	20	MP2-6436	28, 30	MP3-A1642	45, 47, 48
MP2-3948-C/T/F	13	MP2-4842-P	36	MP2-6436-C/T/F	29	MP3-A1642-M	44
MP2-3948-N	12	MP2-4842-V	23	MP2-6436-M	38, 39	MP3-A1642N	46
MP2-3948-P	36	MP2-4848	20, 22	MP2-6436N	28	MP3-A1648	45, 47, 48
MP2-3948-V	15	MP2-4848-C/T/F	21	MP2-6436-P	37	MP3-A1648-M	44
MP2-3960	12	MP2-4848-M	38, 39	MP2-6436-V	31	MP3-A1648N	46

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MP3-A1660	45	MP3-W0960-C/T	42	MR3-E60-4	88	MR3-NT42	170
MP3-A1660N	46	MP3-W1618-C/T/F	42	MR3-EGM	92, 169	MR3-NT48	170
MP3-A1818	45, 47, 48	MP3-W1624-C/T/F	42	MR3-EGM48	92, 169	MR3-NT48-4	170
MP3-A1818N	46	MP3-W1630-C/T/F	42	MR3-EGMH	92, 169, 173	MR3-NT54	170
MP3-A1824	45, 47, 48	MP3-W1636-C/T/F	42	MR3-EJ12	89, 167	MR3-NT60	170
MP3-A1824-M	44	MP3-W1642-C/T/F	42	MR3-EJ12P	89	MR3-NT60-4	170
MP3-A1824N	46	MP3-W1648-C/T/F	42	MR3-EJ18	89, 167	MR3-NT66	170
MP3-A1830	45, 47, 48	MP3-W1660-C/T/F	42	MR3-EJ18P	89	MR3-NT66-4	170
MP3-A1830-M	44	MP3-W1818-C/T	42	MR3-EJ24	89, 167	MR3-NT72	170
MP3-A1830N	46	MP3-W1824-C/T	42	MR3-EJ24P	89	MR3-NT72-4	170
MP3-A1836	45, 47, 48	MP3-W1830-C/T	42	MR3-EJ30	89, 167	MR3-NT78	170
MP3-A1836-M	44	MP3-W1836-C/T	42	MR3-EJ30P	89	MR3-NT78-4	170
MP3-A1836N	46	MP3-W1842-C/T	42	MR3-EJ36	89, 167	MR3-NTPD	171, 172
MP3-A1842	45, 47, 48	MP3-W1848-C/T	42	MR3-EJ36P	89	MR3-NTPI	172
MP3-A1842-M	44	MP3-W1860-C/T	42	MR3-EJ42	89, 167	MR3-NTPNY	172
MP3-A1842N	46	MP3-W2218-C/T/F	42	MR3-EJ42P	89	MR3-PDC-X	97
MP3-A1848	45, 47, 48	MP3-W2224-C/T/F	42	MR3-EJ48	89, 167	MR3-SP-A	91, 94, 169, 170
MP3-A1848-M	44	MP3-W2230-C/T/F	42	MR3-EJ48P	89	MR3-SP-B	91, 94, 169, 170
MP3-A1848N	46	MP3-W2236-C/T/F	42	MR3-EJ54P	89, 167	MR3-SP-C	94, 170
MP3-A1860	45	MP3-W2242-C/T/F	42	MR3-EJ6	89, 167	MR3-SP-X	91, 94, 169, 170
MP3-A1860N	46	MP3-W2248-C/T/F	42	MR3-EJ60P	89, 167	MR3-SP-Y	91, 94, 169, 170
MP3-A2218	45, 47, 48	MP3-W2260-C/T/F	42	MR3-EJ66P	89, 167	MR3-SP-Z	94, 170
MP3-A2218N	46	MP3-W3218-C/T	43	MR3-EJ6P	89	MR3-T24	93
MP3-A2224	45, 47, 48	MP3-W3224-C/T	43	MR3-EJ72P	89, 167	MR3-T30	93
MP3-A2224-M	44	MP3-W3230-C/T	43	MR3-EJ78P	89, 167	MR3-T36	93
MP3-A2224N	46	MP3-W3236-C/T	43	MR3-EJ84P	89	MR3-T42	93
MP3-A2230	45, 47, 48	MP3-W3242-C/T	43	MR3-EJ90P	89	MR3-T48	93
MP3-A2230-M	44	MP3-W3248-C/T	43	MR3-EJ96P	89	MR3-T48-4	93
MP3-A2230N	46	MP3-W3260-C/T	43	MR3-EPC	89, 167	MR3-T60	93
MP3-A2236	45, 47, 48	MR1-DA	92, 169, 173	MR3-EPCP	89	MR3-T60-4	93
MP3-A2236-M	44	MR1-DB	92, 169, 173	MR3-EPIC	90	MR3-TJ12	96, 171
MP3-A2236N	46	MR1-WC	92, 169	MR3-EPNY1	90	MR3-TJ12P	96
MP3-A2242	45, 47, 48	MR2-CHI-24	101	MR3-EPNY2	90	MR3-TJ18	96, 171
MP3-A2242-M	44	MR2-CHI-30	101	MR3-EPVR	90	MR3-TJ18P	96
MP3-A2242N	46	MR2-CHI-36	101	MR3-ERPI	90	MR3-TJ24	96, 171
MP3-A2248	45, 47, 48	MR2-CHI-42	101	MR3-EV24 PC	99	MR3-TJ24P	96
MP3-A2248-M	44	MR2-CHI-48	101	MR3-EV36 PC	99	MR3-TJ30	96, 171
MP3-A2248N	46	MR2-CHI-60	101	MR3-EV48 PC	99	MR3-TJ30P	96
MP3-A2260	45	MR2-CHI-PT	101	MR3-EVB PC	99	MR3-TJ36	96, 171
MP3-A2260N	46	MR2-NS-CHI	101	MR3-EVI J	99	MR3-TJ36P	96
MP3-A3218	45, 47, 48	MR2-PICHI	101	MR3-EVR	88	MR3-TJ42	96, 171
MP3-A3218N	46	MR2-RVR42-H2	101	MR3-FDP	99	MR3-TJ42P	96
MP3-A3224	45, 47, 48	MR2-RVR42-H4	101	MR3-NE30	166	MR3-TJ48	96, 171
MP3-A3224-M	44	MR2-RVR48-H2	101	MR3-NE36	166	MR3-TJ48P	96
MP3-A3224N	46	MR2-RVR48-H4	101	MR3-NE42	166	MR3-TJ54P	96, 171
MP3-A3230	45, 47, 48	MR3-CP	92, 169, 173	MR3-NE48	166	MR3-TJ6	96, 171
MP3-A3230-M	44	MR3-DA	90, 93, 167, 172	MR3-NE48-4	166	MR3-TJ60P	96, 171
MP3-A3230N	46	MR3-DB	90, 93, 167, 172	MR3-NE54	166	MR3-TJ66P	96, 171
MP3-A3236	45, 47, 48	MR3-DC	93, 172	MR3-NE60	166	MR3-TJ6P	96
MP3-A3236-M	44	MR3-DX	90, 93, 167, 172	MR3-NE60-4	166	MR3-TJ72P	96, 171
MP3-A3236N	46	MR3-DXO	90, 93, 167, 172	MR3-NE66	166	MR3-TJ78P	96, 171
MP3-A3242	45, 47, 48	MR3-DXT	90, 94, 167, 172	MR3-NE66-4	166	MR3-TJ84P	96
MP3-A3242-M	44	MR3-DY	90, 93, 167, 172	MR3-NE72	166	MR3-TJ90P	96
MP3-A3242N	46	MR3-DYO	90, 93, 167, 172	MR3-NE72-4	166	MR3-TJ96P	96
MP3-A3248	45, 47, 48	MR3-DYT	90, 94, 167, 172	MR3-NE78	166	MR3-TPC	93, 171
MP3-A3248-M	44	MR3-DZ	93, 172	MR3-NE78-4	166	MR3-TPCP	93
MP3-A3248N	46	MR3-DZO	93, 172	MR3-NEGM	169, 173	MR3-TPIC	95
MP3-A3260	45	MR3-DZT	94, 172	MR3-NEPD	167, 168	MR3-TPNY1	95
MP3-A3260N	46	MR3-E24	88	MR3-NEPI	168	MR3-TPNY2	95
MP3-W0918-C/T	42	MR3-E30	88	MR3-NEPNY	168	MR3-TPVR	95
MP3-W0924-C/T	42	MR3-E36	88	MR3-NESH	169, 170	MR3-TRPI	95
MP3-W0930-C/T	42	MR3-E42	88	MR3-NESH	92, 169, 170	MR3-TV24 PC	100
MP3-W0936-C/T	42	MR3-E48	88	MR3-NESP	92, 169, 170	MR3-TV36 PC	100
MP3-W0942-C/T	42	MR3-E48-4	88	MR3-NT30	170	MR3-TV48 PC	100
MP3-W0948-C/T	42	MR3-E60	88	MR3-NT36	170	MR3-TVB PC	100

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MR3-TVI J	100	MT1-16L2	69, 70	MT5-HLS48	80	MU1-S2424-B	112
MR3-TVR	93	MT1-16T3	69, 70	MT5-HLS60	80	MU1-S3018-B	111
MR3-UW-PDC	97	MT1-18E1	69, 70	MT5-N18	78, 79	MU1-S3024-A	112
MR3-VDA	99	MT1-18L2	69, 70	MT5-N24	78, 79	MU1-S3024-B	112
MR3-VDB	99	MT1-18T3	69, 70	MT5-N30	78, 79	MU1-S3030-A	113
MR3-VDC	99	MT1-22E1	69, 70	MT5-N36	78, 79	MU1-S3030-B	113
MR3-VDX	99	MT1-22L2	69, 70	MT5-N42	78, 79	MU1-S3618-B	111
MR3-VDXO	99	MT1-22T3	69, 70	MT5-N48	78, 79	MU1-S3624-A	112
MR3-VDXT	99	MT1-30E1	69, 70	MT5-N6	78, 79	MU1-S3624-B	112
MR3-VDY	99	MT1-30L2	69, 70	MT5-N60	78, 79	MU1-S3630-A	113
MR3-VDYO	99	MT1-30T3	69, 70	MT5-PDC-24	81	MU1-S3630-B	113
MR3-VDYT	99	MT1-32E1	69, 70	MT5-PDC-30	81	MU1-S36DS-A	116
MR3-VDZ	99	MT1-32L2	69, 70	MT5-PDC-36	81	MU1-S36ES-A	116
MR3-VDZO	99	MT1-32T3	69, 70	MT5-PDC-42	81	MU1-S4218-B	111
MR3-VDZT	99	MT1-39E1	69, 70	MT5-PDC-48	81	MU1-S4224-A	112
MR3-VPBK	99	MT1-39L2	69, 70	MT5-PDC-60	81	MU1-S4224-B	112
MRD-6436-(L/R)	40	MT1-39T3	69, 70	MT6-E24	102	MU1-S4230-A	113
MRD-6442-(L/R)	40	MT1-42E1	69, 70	MT6-E30	102	MU1-S4230-B	113
MRD-6448-(L/R)	40	MT1-42L2	69, 70	MT6-E36	102	MU1-S42DS-A	116
MRD-8036-(L/R)	40	MT1-42T3	69, 70	MT6-E42	102	MU1-S42ES-A	116
MRD-8042-(L/R)	40	MT1-48E1	69, 70	MT6-E48	102	MU1-S4818-B	111
MRD-8048-(L/R)	40	MT1-48L2	69, 70	MT6-E60	102	MU1-S4824-A	112
MRD-FT36	40	MT1-48T3	69, 70	MT6-PDC24	102	MU1-S4824-B	112
MRD-FT42	40	MT1-56E1	69, 70	MT6-PDC30	102	MU1-S4830-A	113
MRD-FT48	40	MT1-56L2	69, 70	MT6-PDC36	102	MU1-S4830-B	113
MS1-S2413	181	MT1-56T3	69, 70	MT6-PDC42	102	MU1-S48DS-A	116
MS1-S3013	181	MT1-64E1	69, 70	MT6-PDC48	102	MU1-S48ES-A	116
MS1-S3613	181	MT1-64L2	69, 70	MT6-PDC60	102	MU1-S5418-B	111
MS1-S4213	181	MT1-64T3	69, 70	MU1-C4242SS	121	MU1-S5424-A	112
MS1-S4813	181	MT1-64XL2	40	MU1-C4848DD	121	MU1-S5424-B	112
MS1-S6013	181	MT1-64XT3	40	MU1-C4848DS	121	MU1-S5430-A	113
MS1-SO	181, 184	MT1-80E1	69, 70	MU1-C4848SD	121	MU1-S5430-B	113
MS2-U2413	183	MT1-80L2	69, 70	MU1-C4848SS	121	MU1-S6018-B	111
MS2-U3013	183	MT1-80T3	69, 70	MU1-C4860DS	121	MU1-S6024-A	112
MS2-U3613	183	MT1-80XL2	40, 41	MU1-C4860SD	121	MU1-S6024-B	112
MS2-U4213	183	MT1-80XT3	40, 41	MU1-C4860SS	121	MU1-S6030-A	113
MS2-U4813	183	MT5-CE1	78, 79	MU1-C4872DS	121	MU1-S6030-B	113
MS2-U6013	183	MT5-CH1	78, 79	MU1-C4872SD	121	MU1-S6618-B	111
MS2-U6613	183	MT5-CL2	78, 79	MU1-C4872SS	121	MU1-S6624-A	112
MS2-U7213	183	MT5-CP1	78, 79	MU1-C6048DS	121	MU1-S6624-B	112
MS2-U7813	183	MT5-CS2	78, 79	MU1-C6048SD	121	MU1-S6630-A	113
MS2-U8413	183	MT5-CT3	78, 79	MU1-C6048SS	121	MU1-S6630-B	113
MS2-U9013	183	MT5-CV2	55, 56	MU1-C7248DS	121	MU1-S7218-B	111
MS2-URC60-N	164	MT5-CX4	78, 79	MU1-C7248SD	121	MU1-S7224-A	112
MS2-URC66-N	164	MT5-CY3	55, 56	MU1-C7248SS	121	MU1-S7224-B	112
MS2-URC72-N	164	MT5-E24	78, 79	MU1-J30A	122	MU1-S7230-A	113
MS2-URC78-N	164	MT5-E30	78, 79	MU1-J36A	122	MU1-S7230-B	113
MS2-URC84-N	164	MT5-E36	78, 79	MU1-J42A	122	MU1-S7824-A	112
MS2-URC90-N	164	MT5-E42	78, 79	MU1-J48A	122	MU1-S7824-B	112
MS2-W2413	182	MT5-E48	78, 79	MU1-M48S-AL	125	MU1-S7830-A	113
MS2-W3013	182	MT5-E60	78, 79	MU1-M48S-AR	125	MU1-S7830-B	113
MS2-W3613	182	MT5-EX48	81	MU1-M48S-BL	125	MU1-S8424-A	112
MS2-W4213	182	MT5-EX60	81	MU1-M48S-BR	125	MU1-S8424-B	112
MS2-W4813	182	MT5-HLC18	80	MU1-P72SA	120	MU1-S8430-A	113
MS2-W6013	182	MT5-HLC24	80	MU1-P78DA	120	MU1-S8430-B	113
MS2-W6613	182	MT5-HLC30	80	MU1-R3048-B	119	MU1-S9024-A	112
MS2-W7213	182	MT5-HLC36	80	MU1-R3050-B	119	MU1-S9024-B	112
MS2-W7813	182	MT5-HLC42	80	MU1-R4248-B	119	MU1-S9030-A	113
MS2-W8413	182	MT5-HLC48	80	MU1-R6330B	118	MU1-S9030-B	113
MS2-W9013	182	MT5-HLC60	80	MU1-R6330E	118	MU1-S9624-A	112
MSAMP1616	208	MT5-HLS18	80	MU1-R6330R	118	MU1-S9624-B	112
MT1-09E1	69, 70	MT5-HLS24	80	MU1-R7530B	118	MU1-S9630-A	113
MT1-09L2	69, 70	MT5-HLS30	80	MU1-R7530E	118	MU1-S9630-B	113
MT1-09T3	69, 70	MT5-HLS36	80	MU1-R7530R	118	MU1-T4224-B	119
MT1-16E1	69, 70	MT5-HLS42	80	MU1-S2424-A	112	MU1-T4830-B	119



<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MU1-T48A-L	114	MV3-S56F-(L/R)	207	MW2-S6630-B	105	MZ1-B7222	204
MU1-T48A-R	114	MV3-S64F-(L/R)	207	MW2-S6636-B	106	MZ1-B7815	204
MU1-T48B-L	114	MW2-K3618-M	107	MW2-S6636-R	106	MZ1-B7819	204
MU1-T48B-R	114	MW2-K3618-P	107	MW2-S7218-B	103	MZ1-B7822	204
MU1-T54A-L	114	MW2-K4224-M	107	MW2-S7224-A	104	MZ1-E2415-W/U	206
MU1-T54A-R	114	MW2-K4224-P	107	MW2-S7224-B	104	MZ1-E2419-W/U	206
MU1-T54B-L	114	MW2-K4830-M	107	MW2-S7230-A	105	MZ1-E2422-W/U	206
MU1-T54B-R	114	MW2-K4830-P	107	MW2-S7230-B	105	MZ1-E3015-W/U	206
MU1-T60A-L	114	MW2-R3048-B	110	MW2-S7236-B	106	MZ1-E3019-W/U	206
MU1-T60A-R	114	MW2-R3050-B	110	MW2-S7236-R	106	MZ1-E3022-W/U	206
MU1-T60B-L	114	MW2-R4248-B	110	MW2-S7824-A	104	MZ1-LS	208
MU1-T60B-R	114	MW2-R6330B	108	MW2-S7824-B	104	MZ1-S2415-W/U	206
MU1-T72A-L	114	MW2-R6330E	108	MW2-S7830-A	105	MZ1-S2419-W/U	206
MU1-T72A-R	114	MW2-R6330R	108	MW2-S7830-B	105	MZ1-S2422-W/U	206
MU1-T72B-L	114	MW2-R6636B	109	MW2-S7836-B	106	MZ1-S3015-W/U	206
MU1-T72B-R	114	MW2-R6636E	109	MW2-S7836-R	106	MZ1-S3019-W/U	206
MU1-V3618-A	115	MW2-R6636R	109	MW2-S8424-A	104	MZ1-S3022-W/U	206
MU1-V3624-A	115	MW2-R7530B	108	MW2-S8424-B	104	MZ1-SS	208
MU1-V3624-C	115	MW2-R7530E	108	MW2-S8430-A	105	MZ1-V3615	205
MU1-V4224-A	115	MW2-R7530R	108	MW2-S8430-B	105	MZ1-V3619	205
MU1-V4224-C	115	MW2-R7836B	109	MW2-S9024-A	104	MZ1-V3622	205
MU1-V4230-A	115	MW2-R7836E	109	MW2-S9024-B	104	MZ1-V4215	205
MU1-V4230-C	115	MW2-R7836R	109	MW2-S9030-A	105	MZ1-V4219	205
MU1-V42SS-A	117	MW2-R8730B	108	MW2-S9030-B	105	MZ1-V4222	205
MU1-V42SS-C	117	MW2-R8730E	108	MW2-S9624-A	104	MZ1-V4815	205
MU1-V4824-A	115	MW2-R8730R	108	MW2-S9624-B	104	MZ1-V4819	205
MU1-V4824-C	115	MW2-R9036B	109	MW2-S9630-A	105	MZ1-V4822	205
MU1-V4830-A	115	MW2-R9036E	109	MW2-S9630-B	105	MZ1-V6015	205
MU1-V4830-C	115	MW2-R9036R	109	MW2-T4224-B	110	MZ1-V6019	205
MU1-V48DS-A	117	MW2-S2424-A	104	MW2-T4830-B	110	MZ1-V6022	205
MU1-V48DS-C	117	MW2-S2424-B	104	MW2-V3618-A	107	MZ1-V7215	205
MU1-V48SS-A	117	MW2-S3018-B	103	MW2-V3624-A	107	MZ1-V7219	205
MU1-V48SS-C	117	MW2-S3024-A	104	MW2-V3624-C	107	MZ1-V7222	205
MU1-W36A	123	MW2-S3024-B	104	MW2-V4224-A	107	RO1-CB	200
MU1-W42A	123	MW2-S3030-A	105	MW2-V4224-C	107	RO1-DPB	200
MU1-W48A	123	MW2-S3030-B	105	MW2-V4230-A	107	RO1-ECB	200
MU1-Y36S-AL	124	MW2-S3618-B	103	MW2-V4230-C	107	RO1-EPB	200
MU1-Y36S-AR	124	MW2-S3624-A	104	MW2-V4824-A	107	RO1-GB	201
MU1-Y36S-B	124	MW2-S3624-B	104	MW2-V4824-C	107	RO1-HP12	194, 195, 197, 199
MU1-Y42S-AL	124	MW2-S3630-A	105	MW2-V4830-A	107	RO1-HP15	194, 195, 197, 199
MU1-Y42S-AR	124	MW2-S3630-B	105	MW2-V4830-C	107	RO1-HP6	194, 195, 197, 199
MU1-Y42S-B	124	MW2-S4218-B	103	MWM-J	188, 201	RO1-HP9	194, 195, 197, 199
MU1-Y48S-AL	124	MW2-S4224-A	104	MZ1-B3015	204	RO1-MPB	200
MU1-Y48S-AR	124	MW2-S4224-B	104	MZ1-B3019	204	RO1-PULL	201
MU1-Y48S-B	124	MW2-S4230-A	105	MZ1-B3022	204	RO1-RCB	200
MU1-Y60S-AL	124	MW2-S4230-B	105	MZ1-B3615	204	RO1-RPB	200
MU1-Y60S-AR	124	MW2-S4818-B	103	MZ1-B3619	204	RO1-WMF2	201
MU1-Y60S-B	124	MW2-S4824-A	104	MZ1-B3622	204	RO1-WMF3	201
MU1-YTS	124	MW2-S4824-B	104	MZ1-B4215	204	RO1-WMF4	201
MV1-BP5624	207	MW2-S4830-A	105	MZ1-B4219	204	RO2-NS20	164, 200
MV1-BP6424	207	MW2-S4830-B	105	MZ1-B4222	204	RO2-NS21	164, 200
MV1-DAS	207	MW2-S5418-B	103	MZ1-B4815	204	RO3-A30NL	202
MV1-DFC	207	MW2-S5424-A	104	MZ1-B4819	204	RO3-A30NN	202
MV1-DFCX	207	MW2-S5424-B	104	MZ1-B4822	204	RO3-A30PL	202
MV1-DTC	207	MW2-S5430-A	105	MZ1-B5415	204	RO3-A30PN	202
MV1-DTCX	207	MW2-S5430-B	105	MZ1-B5419	204	RO3-A36NL	202
MV1-SAS	207	MW2-S6018-B	103	MZ1-B5422	204	RO3-A36NN	202
MV1-SFC	207	MW2-S6024-A	104	MZ1-B6015	204	RO3-A36PL	202
MV1-SFCX	207	MW2-S6024-B	104	MZ1-B6019	204	RO3-A36PN	202
MV1-STCX	207	MW2-S6030-A	105	MZ1-B6022	204	RO3-A42NL	202
MV2-D18S-(L/R)	207	MW2-S6030-B	105	MZ1-B6615	204	RO3-A42NN	202
MV2-S18S-(L/R)	207	MW2-S6618-B	103	MZ1-B6619	204	RO3-A42PL	202
MV2-STC	207	MW2-S6624-A	104	MZ1-B6622	204	RO3-A42PN	202
MV3-D56F-(L/R)	207	MW2-S6624-B	104	MZ1-B7215	204	RO3-A48NL	202
MV3-D64F-(L/R)	207	MW2-S6630-A	105	MZ1-B7219	204	RO3-A48NN	202



<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
RO3-A48PL	202	RS1-WMF42	201
RO3-A48PN	202	RS1-WMF48	201
RO3-A60NL	202	RS1-WMF60	201
RO3-A60NN	202	RTAT5E19	203
RO3-A60PL	202	RTAT5E25	203
RO3-A60PN	202	RTAT5E37	203
RO3-A72NL	202	RTAT5E49	203
RO3-A72NN	202	RTAT5E61	203
RO3-A72PL	202		
RO3-A72PN	202		
RO3-M24	196		
RO3-M30	196		
RO3-M36	196		
RO3-M42	196		
RO3-M48	196		
RO3-M60	196, 197		
RO3-M66	196, 197		
RO3-M72	196, 197		
RO3-N24	198		
RO3-N30	198		
RO3-N36	198		
RO3-N42	198		
RO3-N48	198		
RO3-N60	198		
RO3-N66	198		
RO3-N72	198		
RO3-OM30	195		
RO3-OM36	195		
RO3-OM42	195		
RO3-OM48	195		
RO3-OM60	195		
RO3-OM72	195		
RO3-ON30	195		
RO3-ON36	195		
RO3-ON42	195		
RO3-ON48	195		
RO3-ON60	195		
RO3-ON72	195		
RO3-RD30	195		
RO3-RD36	195		
RO3-RD42	195		
RO3-RD48	195		
RO3-RD60	195		
RO3-RD72	195		
RO3-VP	195, 197, 199		
RS1-DPB	200		
RS1-EPB	200		
RS1-M24	194		
RS1-M30	194		
RS1-M36	194		
RS1-M42	194		
RS1-M48	194		
RS1-M60	194		
RS1-MPB	200		
RS1-N24	194		
RS1-N30	194		
RS1-N36	194		
RS1-N42	194		
RS1-N48	194		
RS1-N60	194		
RS1-RPB	200		
RS1-VP	194		
RS1-WMF24	201		
RS1-WMF30	201		
RS1-WMF36	201		

# Selling Policy

---

	<p>This Selling Policy supercedes all previous selling policies. Prices, discounts and product offerings are subject to change without notice.</p>
<b>Terms &amp; Conditions of Sales</b>	<p>Sales by Knoll, Inc. or Knoll North America Corp. ("Seller") of Knoll Product Lines (hereinafter "Products") within the United States and Canada are made only on the terms which are contained in this Selling Policy. Seller hereby gives notice of its objection to any different or additional terms and conditions. This sale is expressly conditional upon Purchaser's assent to the terms and conditions set forth below. Additional terms and conditions may apply to KnollStudio and KnollTextiles orders. These terms and conditions may be modified or supplemented only by a written document signed by an authorized representative of Seller. These terms and conditions supercede any prior and/or contemporaneous agreements or correspondence between Purchaser and Seller. Written quotations expire thirty (30) days from the date of issuance and can be withdrawn by written notice anytime during that period. Where Purchaser and Seller have entered into the Knoll Electronic Terms and Conditions, all orders, acknowledgements, invoices and other business communications placed or transmitted in accordance with the Knoll Electronic Terms and Conditions shall be deemed to be in writing and signed and shall be valid for all purposes as if they were originated and maintained in documentary form.</p>
<b>Ordering Information</b>	<p>All orders must be in writing. The product pattern number(s) contained on Seller's order acknowledgement shall be the final expression of the order.</p>
<b>Order Confirmation</b>	<p>A purchase order is not binding on Seller until Purchaser has received Seller's order confirmation or acknowledgment.</p>
<b>Pricing Policies</b>	<p>List prices are subject to change without notice.</p> <p>List prices shall be those prices in effect on the date of receipt of a complete purchase order unless shipment is requested more than ninety (90) days after order entry in which case prices in effect on the date of shipment apply. List prices include specified freight costs. Unless specified in writing by Seller, no other charges are included in Seller's list prices.</p>
<b>Taxes</b>	<p>All sales, use, excise and other taxes applicable to the sale of the Products shall be paid by Purchaser. If Purchaser claims an exemption from any tax, Purchaser shall submit to Seller the appropriate exemption certificates.</p>
<b>Terms of Payment</b>	<p>Payment for one hundred percent (100%) of the net order amount is due within thirty (30) days of the date of invoice, which is issued upon shipment. In case of any discrepancies, such as shortages, and Seller is notified in writing within ten (10) days of receipt of Product, only that portion may be deducted and the balance paid. For orders greater than \$100,000 net, a one-third (1/3) deposit is due at the time of order placement, with the remainder due within thirty (30) days of the date of invoice.</p> <p>KnollStudio orders less than \$2,000 require payment for one hundred percent (100%) of the net order amount (including any applicable sales tax and charges for inside delivery, special packaging, etc.), due at time of order placement. For KnollStudio orders greater than \$2,000, a one-half (50%) deposit is due at time of order placement with the remainder (including any applicable sales tax and charges for inside delivery, special packaging, etc.) due prior to shipment.</p> <p>If, in the judgment of Seller, Purchaser's financial condition does not justify the terms of the payment, Seller may require full or partial payment in advance.</p> <p>Past due accounts shall be charged one and one-half percent (1.5%) per month, or the highest rate permitted by law, whichever is less, and will be added to the outstanding balance. In the event Purchaser defaults on payment, Purchaser shall be liable for all collection costs, including reasonable attorney's fees and costs.</p>
<b>Changes and Cancellation</b>	<p>Purchase orders may not be changed or cancelled, in whole or in part, without prior written consent of Seller. Changes may effect delivery dates. Expenses incurred because of changes shall be charged to Purchaser. In the event of cancellations, Purchaser will be liable for reasonable cancellation charges established by Seller. Orders for special Product, orders including "COM" (hereinafter defined) material and orders pursuant to expedited delivery programs, may not be canceled.</p>
<b>Freight Prepaid</b>	<p>Freight is prepaid and included in the price of all Products, except KnollTextiles, within the 48 contiguous United States and Canada, excluding the Yukon, Northwest Territories, Nunavut and Newfoundland. Packing is tested for rigorous motion and transportation but is not guaranteed to protect furniture from conditions over which the Seller has no control. If special packaging is required for any reason, please consult with your sales representative or dealer. Seller shall select the method of shipment and routing. All shipments shall be tailgate deliveries. Freight for all KnollTextiles orders is prepaid and added to the invoice.</p>
<b>Delivery/Freight Charges</b>	<p>Shipments outside the contiguous 48 United States and Canada shall be shipped F.O.B. Origin.</p> <p>For shipments outside the contiguous United States and Canada, Purchaser is responsible for the cost of freight from point of embarkation, including any handling and transportation charges incidental to loading at the point of departure and unloading at the final destination.</p> <p>Conditions beyond the control of Seller, including weather, available facilities and traffic conditions, may affect exact time of delivery. Seller shall not be responsible for specific carrier delivery date or time unless it has made a specific delivery commitment, in writing.</p> <p>Nonstandard methods of shipment and/or additional services are available upon request. Purchaser will be billed for the differential cost of any special services in excess of standard surface carrier freight costs. Premium charges, at Purchaser's request, will be added for airfreight, exclusive use of vehicle and extra, export or special packaging. Accessorial charges will be added for inside delivery, extra labor, reconsignment and redelivery.</p> <p>Partial shipments may be made and invoiced by Seller.</p>
<b>Claims</b>	<p>All shipments for all Knoll Products within the contiguous United States and Canada are F.O.B. Origin. Risk of loss passes to Purchaser at time of delivery to carrier. Purchaser shall inspect all Products upon receipt and notify Seller within ten (10) working days after receipt of any damage or defects which are, or should be, apparent from an inspection of the Product and its packaging. Failure of Purchaser to make a claim against carrier or notify Seller during the ten (10) working day period shall constitute acceptance of the Products and waiver of any apparent defects, errors or shortages. Seller will agree to repair or replace Product damaged in shipment if Purchaser has notified Seller of freight damage within ten (10) working days after receipt and assigns its rights against the carrier.</p>
<b>Seller's Security Interest</b>	<p>Until Seller receives the full payment for the Product, Seller shall have a security interest in the Product. Purchaser agrees to perform all acts, including but not limited to the execution and filing of documentation, which may be necessary to perfect and assure the security interest of Seller.</p>
<b>Returns</b>	<p>The return of Products without a written authorization by Seller shall not be accepted. To receive authorization for Product return, please call Customer Service. All Products that are returned pursuant to a valid authorization shall be subject to a twenty-five percent (25%) of list restocking charge. Products not currently offered for sale by Seller (including COM) shall not be authorized for return. All returned Products must be unused, in original condition and in the original Seller packing cartons. No refund or credit shall be given for damaged Products.</p>
<b>Held Orders/Storage</b>	<p>If Purchaser requests that an order be held or delayed, prices and terms and conditions in effect at the time of shipment shall apply. If Purchaser requests a delay after the time when Seller can defer production, Purchaser will be invoiced for the Product, payable in accordance with standard terms, when the order is ready for shipment. Seller may transfer the Product to storage, in which case all expenses incurred in connection with storage, including demurrage, preparation for storage, storage charges and handling shall be payable by Purchaser upon submission of invoices by Seller. Risk of loss to the Product shall pass to the Purchaser upon delivery of the Product into storage.</p>

# Selling Policy

<b>Customer's Own Material</b>	<p>A Purchaser who requests a fabric or other surface material not standard to Seller's line of Products ("COM") must submit samples of the requested material to Seller prior to entry of a purchaser order. Seller shall determine if the material is suitable to its manufacturing processes and meets any requirements of Underwriters Laboratories. If the COM is acceptable, Seller will then establish a price for using the COM or the Product in question. For a description of the procedures for submitting samples and testing, contact customer resources or your sales representative. Seller shall have no responsibility for the appearance, condition, performance, durability, colorfastness or any other physical attribute of the COM. Purchaser shall indemnify and hold Seller harmless for any damages, injuries or losses arising out of or related to use of the COM on the Product.</p>
<b>Warranty</b>	<p>Seller warrants to the original Purchaser only that the Products Seller manufactures and sells to Purchaser are free of defects in workmanship and materials, during the applicable warranty period set forth below.</p> <p>Should any failure to conform with this limited warranty appear to a Product listed below during the applicable warranty period from the date of shipment, Seller shall, upon prompt written notice, repair or replace, at its option and costs, the affected part or parts.</p> <p><i>Product and Period of Warranty</i></p> <p><i>Lifetime: AutoStrada, Calibre, Crinion Open Table, Currents, Dividends, Equity, Morrison, Reff</i> laminate and other non-wood components (except cascade edge worksurfaces, operational parts, controls, electrical, special or custom products, see below)</p> <p><i>10 Years: AutoStrada, Crinion Open Table and Reff</i> wood components, wood casegoods, <i>Interaction</i> tables (except height adjustment mechanisms for <i>Counterforce</i>, crank-adjustable, and split-top tables and worksurfaces, see below), <i>Reuter</i> overheads, <i>Reuter</i> vertical storage, <i>Bulldog, Chadwick, Essentials Work Chairs, Life, RPM</i> and <i>Sapper</i> seating structural and operational parts, controls, casters, pneumatic cylinders, seat and back mesh (except seating upholstery, finishes and labor, see below)</p> <p><i>5 Years:</i> Operational parts, controls, electrical (except light ballasts and bulbs, see below), cascade edge worksurfaces, special or custom product, wood veneer products, <i>A3, Currents</i> handcrank, <i>Interaction Counterforce, Interaction</i> crank-adjustable, and split-top mechanisms, <i>KnollStudio, KnollExtra</i> adjustable keyboard supports, VDT carousel, monitor platform, equipment storage drawers and all universal storage drawers, <i>Open Up, Visor</i> and <i>SoHo</i> seating structural and operational parts, controls, pneumatic cylinders (except seating upholstery, finishes and labor, see below)</p> <p><i>3 Years:</i> Upholstery, finishes and labor to repair the following chairs: <i>Bulldog, Chadwick, Life, Open Up, Parachute, RPM, Sapper</i> and <i>SoHo</i>.</p> <p><i>2 Years:</i> All other <i>KnollExtra</i> product</p> <p><i>1 Year:</i> Light ballasts and bulbs and <i>Equity</i> fiberglass panels, seating upholstered armpads and soft armpads, <i>Visor</i> finishes and labor to repair.</p> <p>This warranty does not apply to:</p> <ul style="list-style-type: none"><li>• Damage caused by a carrier other than the Seller.</li><li>• Normal wear and tear or acts or omissions of parties other than Seller (including user modification).</li><li>• COM or other third party materials applied to Products.</li><li>• Products not installed by or under the auspices of a certified dealer of Seller.</li><li>• Dramatic temperature variations or exposure to unusual conditions.</li><li>• Except as specifically noted above, textiles and upholstery supplied by <i>KnollTextiles</i> (consult current <i>KnollTextiles</i> price list for applicable warranty).</li><li>• Labor to repair or replace Essential Work Chairs affected part or parts.</li></ul> <p>Natural variations occurring in wood, marble, and leather shall not be considered defects, and the Seller does not guarantee the colorfastness or matching of the colors, grains or textures, or surface hardness of such materials. The Seller also does not guarantee the colorfastness of fiberglass panel surfaces. THE EXPRESS WARRANTIES CONTAINED HEREIN ARE IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY WARRANTIES OF MERCHANTABILITY AND FITNESS FOR PARTICULAR PURPOSE AND ALL OTHER WARRANTIES ARISING FROM COURSE OF DEALING OR USAGE OF TRADE.</p> <p>The remedies provided above are the Purchaser's sole remedies for any failure of Seller to comply with its obligations regarding the workmanship of its Products. Correction of any nonconformity in the manner and for the period of time provided shall constitute complete fulfillment of all liabilities of Seller, with respect to or arising out of the Product furnished hereunder.</p>
<b>Delay/Force Majeure</b>	<p>Seller shall not be liable for failure to perform or for delay in performance due to fire, flood, strike or other labor difficulty, act of God, act of any governmental authority or of the Purchaser, riot, embargo, fuel or energy shortage, wrecks or delay in transportation, inability to obtain necessary labor, materials or manufacturing facilities from usual sources or failure of suppliers to meet their contractual obligations, or due to any cause beyond its reasonable control. If any such event occurs, Seller may extend delivery dates by a period of time necessary to overcome the effect of such delay, allocate available Product or cancel any purchase order.</p>
<b>Compliance with Law</b>	<p>PURCHASER IS SOLELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, ORDINANCES, REGULATIONS, RULES AND STANDARDS RELATING TO THE INSTALLATION, MAINTENANCE, USE AND OPERATION OF THE PRODUCTS.</p>
<b>Patents</b>	<p>Subject to the following provisions, Seller shall, at its own expense, defend or, at its option, settle any claim, suit or proceeding brought against the Purchaser, and/or its vendees, mediate and immediate, so far as based on an allegation that any Product or any part thereof furnished hereunder constitutes a direct or a contributory infringement of any claim of any patent of the United States or Canada. This obligation shall be effective only if Purchaser shall have made all payments then due hereunder and if Seller is notified promptly in writing and given authority, information and assistance for the defense of said claim, suit or proceeding. Seller shall pay all damages and costs awarded in such suit or proceedings so defended.</p> <p>The foregoing indemnity does not apply to the following:</p> <ul style="list-style-type: none"><li>• Products supplied according to a design other than that of Seller, and which is required by the Purchaser.</li><li>• Combination of the Product with another product not furnished hereunder unless Seller is a contributory infringer.</li><li>• Any settlements of a suit or proceeding made without Seller's written consent.</li></ul>
<b>Limitations of Liability</b>	<p><b>SELLER, ITS CONTRACTORS, AUTHORIZED DEALERS AND SUBCONTRACTORS OR SUPPLIERS OF ANY TIER SHALL NOT BE LIABLE TO PURCHASER FOR ANY SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES ARISING FROM A BREACH OF THIS AGREEMENT.</b></p> <p>Purchaser's remedies set forth herein are exclusive and the liability of Seller with respect to the breach of this agreement or any contract entered into between the parties pursuant hereto shall not exceed the price of the Product or part on which such liability is based.</p>

# KnollKey Lock Program

## KnollKey Lock Program General Information

Following is the KnollKey lock policy, applicable to all products.

### Key-alike

For the convenience of the user, furniture may be keyed alike at no charge. Write "Key-alike" in the description of your purchase order for any pedestal, overhead, file or other item you wish to have keyed alike.

Using the key-alike instructions, order cores and keys as line items on your purchase order. Do NOT submit a key-alike form. The Knoll East Greenville Lock Center will select key numbers from the standard range of K 001 - K 250. Key numbers will not be repeated unless over 250 sets are ordered. Lock cores keyed-alike will ship separately from the product, ready for field installation.

There is no charge for key-alike orders if placed with the furniture order.

**IF THE KEY-ALIKE ORDER IS NOT PLACED AT LEAST TWO WEEKS PRIOR TO THE FURNITURE SHIP DATE, A \$50 HANDLING CHARGE AND AIR FREIGHT CHARGES WILL APPLY.**

**If product is ordered and shipped random-keyed, additional lock cores for key-alike are billable.**

### Random-Keying

To specify product keyed-random, write "key-random" in the product description. Random-keyed product is shipped with the lock core factory installed. A shrouded key is included. Random means no effort has been made to match key numbers, or to make them different.

### Keys

A Knoll shrouded key is shipped with every lock core. 250 Key numbers are available. For numbers above 250, contact Custom Product Development. Additional keys and key blanks are available. See service parts for more information.

### Master Keying

Knoll locks can be controlled by means of a master key. There is no additional per-lock charge for master keying. A letter of approval from the client must accompany orders for master keys.

### Installing Lock Cores

Lock cores can be installed or removed in the field by using a change key. Cores must be in the unlocked position to be removed. See service parts for change key pattern number and pricing.


### Lock Distribution

All orders for key-alike lock cores/keys are packaged and shipped from the East Greenville Lock Center, regardless of where the pedestals, overhead, or other units are produced. Random keyed product will have cores factory-installed.

## How to Specify Key-Alike

Following is an example of how to specify key-alike for a cluster of 10 workstations.

**Step 1** - Using the project floorplan, count the number of locks in each workstation.



**Step 2** - Count the number of workstations with the same quantity of locks. Group together the workstations with a like number of locks.

5 workstations with 2 locks per station  
3 workstations with 4 locks per station  
2 workstations with 5 locks per station

**Step 3** - For the first group (5 sets of 2 locks), enter the number of workstations in the quantity column.

Qty	Pattern #	Description	Unit List	Ext. List
5				

**Step 4** - Then enter the pattern number "KSPEC\_ \_" and add a suffix for the number of locks for that group (i.e., for 2 locks per station, add the suffix "2"). Up to 30 lock cores are available in a set (i.e., KSPEC 30).

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C

**Step 5** - Repeat for other groups.

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C
3	KSPEC 4	Set of 4 cores/keys	N / C	N / C
2	KSPEC 5	Set of 5 cores/keys	N / C	N / C

Your Key instructions are complete.

Knoll will select key numbers for each set from 250 available numbers. Additional key numbers are available through Custom Product Development. **For additions to existing installations, specify desired key numbers in the description.**

## Service Parts

Pattern #	Description	List Price
KKEY_ _ _	Shrouded Key Specify key number desired	\$5
KBLANK	Shrouded Key Blank	\$5
KSPECB_ _ _	Retrofit Universal Core/Key Specify key number desired	\$18
KCHANGE	Change Key	\$5
KMASTER*	Master Key	\$5

\*Note: A letter of approval on company letterhead from the client must accompany all orders for master keys.

# General Ordering Information

---

## **The Products**

This guide encompasses all standard products for this product group.

## **Sizes**

Dimensions listed in this guide are indicated as:

H = height

W = width

D = depth

Dia. = diameter

Rad. = radius

## **Pricing**

All prices shown are list.

## **How to Order**

Select pattern numbers and quantities required for your complete installation. Product questions can be addressed in the specific sections of this guide or by contacting your sales representative or customer resource representative at 1-800-343-5665.

Next, select options (if required), along with colors and finishes appropriate to each product. Reference the Finishes and Fabrics pages for color designations.

On large installations, an item's "designated area" can be specified to assist in product organization and handling.

To expedite complete / correct entry of your order, be certain all pattern numbers, quantities, colors and area identifications are completely specified. Also, include complete purchase order numbers, bill-to and ship-to addresses, a contact name and specific factory shipping dates required.

## **Mail all orders to:**

Knoll, Inc.  
1235 Water Street  
P.O. Box 157  
East Greenville, PA 18041  
Attention: Order Entry

Once your order is entered at Knoll, an acknowledgment will be mailed to you. You will be advised of your scheduled shipping date within five days of the original acknowledgment. If it is necessary to revise your order, please contact your customer resource representative.

## Sustainability Statement

---

Sustainable design is a key component of Knoll's environmental focus. Our commitment to social responsibility and a healthy environment has prompted us to further articulate our longstanding environmental programs and, with encouragement and support from our colleagues in the industry, we have re-energized our focus on such "green" initiatives as life cycle analysis and LEED™ certification. Knoll is proud to have contributed to projects that have received LEED certification from the U.S. Green Building Council.

For the latest information on Knoll products that help our customers achieve LEED certification, log on to [knoll.com](http://knoll.com), click on "About Knoll" and then "Environmental Focus."