Introduction	Knoll and Sustainable Design	3
	Knoll Color Program Finishes	4
	Dividends Legacy Finishes	6
	Dividends Horizon Fabrics	7
Planning Guidelines	Panel Specifications	8
Panels, Pre-Configured	Monolithic Panels	14
	Tiled Panels	22
	Beltway Panels	40
Panels, Build-To-Spec	Topway and Full View Panel Frame Assemblies	46
	Stack Frames	52
	Monolithic Panel Fabric Inserts	56
	Monolithic Laminate Inserts	60
	Tiled Fabric Inserts	66
	Tiled Laminate Inserts	70
	Beltway Inserts	74
	High Acoustic Core Inserts	78
	Window Insert Kits	80
	Markerboard Tiles	82
	Steel Insert Kits	86
	Slatwall Tiles	94
	Technology Tiles	96
	Rolling Door	100
	Open Weave and Glass Screens	102
	Open Weave and Glass Stacking Screens	110
	Frameless Add Up	116
Post Connectors/End Trim	Dividends Horizon DP7 Post Assemblies	120
	Dividends Horizon DP7 Post Components	122
	Legacy Post Assemblies	128
	Legacy Post Components	130
	Panel End Trim and Panel Top Caps	134
	Panel Wall Starter, Panel-to-Panel Top Cap Transition	140
	Wall Mount Tracks and Components	142
	Panel Rigidizer Brackets, Coat Hooks and Reveal Fillers	146
Alternative Planning	Concealed Post	150
	120° Planning	170
Electrical/Data Components	Electrical Specifications	178
	Base Raceway Electrical	181
	Receptacles	186
	Vertical Electrical	188
	Desktop Power and Data Modules	192
	Beltway Electrical	194
	Electrical Infeeds and Power Poles	198
	New York City, San Francisco and Chicago Electrical	202
	Cable Management	206
Storage Components	Flip-Up Door Overheads	210
	Sliding Door Overheads	214
	Up Mounted Overheads	226
	Overhead Bookshelf and Corner Shelf	228
	Mounting Brackets and Accessories	230
	Task Lights	234
	Pedestals	236
	Credenzas	244
	Flip-up Door Overdesk and Tackboards	266
	Sliding Door Overdesks	270
	Sliding Door Overdesks with Tackboard	279

Copyright © 2012 Knoll, Inc.
All rights reserved.
All prices effective 7/15/2011.

Worksurfaces	Worksurface Specifications	290
	Rectangular Worksurfaces	294
	Curvilinear Wave End Worksurfaces	300
	Smooth Wave Worksurfaces	302
	Trapezoidal Worksurfaces	303
	Corner Worksurfaces	304
	Peninsula Worsurfaces	310
	Curvilinear Half- and Corner-Round Worksurfaces	312
	Transaction Counter Worksurfaces	314
Cascade Edge Worksurfaces	Rectangular with Cascade Edge	316
	Blended “D” and Curvilinear Corner with Cascade Edge	317
	Blended “L” with Cascade Edge	318
	Half Round and Corner Round with Cascade Edge	319
	Wave End with Cascade Edge	320
Worksurface Supports	Panel Mounted Worksurface Brackets	322
	Screen-to-Worksurface Brackets	326
	Panel Mounted Worksurface Supports	328
	Peninsula Worksurface Supports	330
Tables	Y Leg Tables	332
	X Base Tables	340
	Table Supports	345
	Conference Tables	348
Freestanding Desks	Preconfigured Desks	352
	Desk Components	364
	Desk Accessories	370
Wall Mounting of Knoll Products		373
Alpha-Numeric Index		375
Selling Policy		387
KnollKey Lock Program		389
General Ordering Information		390

Knoll and Sustainable Design

Each year Knoll sets key initiatives in our journey to sustainability. We are members of a global consortium on energy, have adopted a scientific, metrics-based approach to sustainable product design, and maintain a leadership position in establishing universal, verifiable, sustainability standards for our industry.

Knoll promotes independent third-party certification because it provides the most impartial and trustworthy foundation for industry-wide environmental compliance. Certification by established and respected third parties ensures that all manufacturers are held to the same high standards and that customers can trust a company's declaration about the environmental benefits of its products. Knoll third-party partners include: the International Standards Organization (ISO); Forest Stewardship Council (FSC®); Rainforest Alliance; GREENGUARD® Environmental Institute; and The Business and Institutional Furniture Manufacturer's Association (BIFMA) level® certification from Scientific Certification Systems (SCS).

In addition, Knoll is aligned with the U.S. Green Building Council and can help companies, healthcare organizations and educational institutions achieve Leadership in Energy and Environmental Design (LEED®) workplace certification.

Global Climate Change

- Knoll is a sponsor of the Clinton Global Initiative, which brings together a community of global leaders to devise and implement solutions to some of the world's most pressing challenges, including environmental change.
- Knoll has a comprehensive Energy Management Program to increase energy efficiency in products and processes.

Life Cycle Assessment (LCA) Tool

- Life Cycle Assessment is a science-based measurement of a product's environmental impacts throughout its life cycle, from raw materials sourcing through manufacture, shipping, use and re-use or end-of-life. LCA enables cradle-to-cradle implementation of sustainable practices.
- Knoll has partnered with The Green Standard.org to develop an affordable, universal ISO-compliant computer-based LCA tool that can be used by the entire contract furniture industry and is partnering on the development of an Environmental Product Declaration System (EPDs) for Knoll products. EPDs are verified documents containing LCA results and additional environmental performance information about a product.

Setting Industry Standards

- Knoll partners with MTS (The Institue for Market Transformation to Sustainability) to develop the SMaRT© Consensus Sustainable Products Standards, a set of consensus-based sustainable product standards based on the LEED® model, for all building products, fabric, apparel, flooring and carpet. MTS, the developer of SMaRT©, is an accredited American National Standards Institute (ANSI) standard developer.
- Knoll also partners with BIFMA (Business and Institutional Furniture Manufacturers Association) to promote level® sustainability standards for the contract furniture industry.
- Knoll has established FSC® (Forest Stewardship Council) certified wood as the standard for general office open plan office systems, casegoods and tables.
- Knoll has launched Full Circle, a resource recovery program developed with ANEW, to help customers extend the life cycle of surplus furniture, fixtures and equipment (FF&E) in an economically, socially and environmentally responsible manner.
- Our goal is to encourage all manufacturers in the contract furniture industry and related industries to adopt standards that will lead to sustainable products and practices.

For more information about Knoll and sustainable design, visit knoll.com/environment.

Specify Core finishes for all new customers

Paint Finishes:
Beige Mist Metallic (611T)
Bright White (118T)
Brown (112T)
Dark Grey (113T)
Folkstone Grey (114T)
Jet Black (111T)
Medium Grey (115T)
Medium Metallic Grey (612T)
Sandstone (116T)
Silver (613)
Soft Grey (117T)

Paint Finish Applications:
Panel base raceway covers
Screen frames
Steel and slatwall tile inserts
D1 style tile supports
DP7 metal panel trim
DP7 power poles
Worksurface supports
Overhead and overdesk cases and doors
Credenza case, top and door
Pedestal case and fronts
Table bases

Laminate Finishes:
Bright White (118)
Brushed Grey (123)
Brushed Sand (122)
Fog (128)
Folkstone Grey (114)
Jet Black (111)
Medium Cherry (124)
Micro Grey (121)
Micro Sand (129)
Natural Cherry (126)
Natural Maple (125)
Pumice (119)
Soft Grey (117)
Walnut (127)

Laminate Finish Applications:
Worksurfaces
Overhead and overdesk doors
Credenza top and door
Laminate tile inserts
Freestanding desk worksurfaces
Table tops

2mm Edgeband Finishes:
Bright White (118)
Fog (128)
Folkstone Grey (114)
Jet Black (111)
Medium Cherry (124)
Natural Cherry (126)
Natural Maple (125)
Pumice (119)
Soft Grey (117)
Walnut (127)

2mm Edgeband Finish Applications:
Worksurfaces
Freestanding desk worksurfaces
Table tops

Cascade Worksurface Finishes:
Bright White (118)
Folkstone Grey (114)
Medium Cherry (124)
Natural Cherry (126)
Natural Maple (125)
Pumice (119)
Soft Grey (117)
Walnut (127)

Cascade Worksurface Finish Applications:
Cascade edge worksurface

Techwood Finishes:
Black Oak (Y851)
Blond Maple (Y821) (formerly known as maple techgrain)
Cherry (Y319)
Dark Grey Oak (Y343)
Dark Mahogany (Y326)
Espresso (Y344)
Light Cherry (Y831) (formerly known as cherry techgrain)
Light Oak (Y327)
Maple (Y316)
Medium Oak (Y329)
Medium Teak (Y342)
Medium Walnut (Y323)
Natural (Y811)
Wenge (Y341)

Techwood Finish Applications:
Worksurfaces
Overhead and overdesk doors
Credenza top and door
Panel trim
Veneer tile inserts
Table tops

Plastic Trim Finishes:
Dark Grey (113)
Medium Grey (115)
Soft Grey (117)

Plastic Trim Finish Applications:
Plastic panel trim
Beltway covers
Legacy power pole covers

DS1 Storage Plastic Finishes:
Bright White (118)
Brown (112)
Dark Grey (113)
Folkstone Grey (114)
Jet Black (111)
Medium Grey (115)
Sandstone (116)
Soft Grey (117)

DS1 Storage Plastic Finish Applications:
DS1 pedestal drawer plugs and handles
DS1 overhead door end plugs

Note: All Dividends Horizon products except DS1 and DS2 pedestals and doublewide pedestals are painted with a textured finish excluding 613 Silver, which is available as a smooth finish only. X and Y base tables and the freestanding screen kits are always painted with a textured finish, including 613 Silver.

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Note: Worksurfaces, overhead and overdesk doors, credenza tops and doors, and veneer tile inserts will have the same Techwood finish on the surface and the edge.

Order Code	Color Name	Old Order Code	Paint Grade	Paint Finishes	Laminate Finishes	2mm Edgeband Finishes	Cascade Worksurface Finishes	Techwood Finishes	Plastic Trim Finishes	DS1 Storage Plastic Finishes
Paints and Laminates										
611T*	Beige Mist Metallic		P2	•						
118T*	Bright White	LH	P3	•	•	•	•			•
112T*	Brown		P1	•						•
123	Brushed Grey				•					
122	Brushed Sand				•					
113T*	Dark Grey	Y3	P1	•		•			•	•
128	Fog	G			•	•				
114T*	Folkstone Grey		P1	•	•	•	•			•
111T*	Jet Black	27	P1	•	•	•				•
124	Medium Cherry				•	•	•			
115T*	Medium Grey	Y2	P1	•		•			•	•
612T*	Medium Metallic Grey	J	P2	•						
121	Micro Grey				•					
129	Micro Sand				•					
126	Natural Cherry				•	•	•			
125	Natural Maple				•	•	•			
119	Pumice	LB, F			•	•	•			
116T*	Sandstone		P1	•						•
613	Silver	3	P3	•						
117T*	Soft Grey	E, M42	P1	•	•	•	•		•	•
127	Walnut				•	•	•			
Techwoods										
Y851	Black Oak							•		
Y821	Blond Maple (formerly known as maple techgrain)							•		
Y319	Cherry							•		
Y343	Dark Grey Oak							•		
Y326	Dark Mahogany							•		
Y344	Espresso							•		
Y831	Light Cherry (formerly known as cherry techgrain)							•		
Y327	Light Oak							•		
Y316	Maple							•		
Y329	Medium Oak							•		
Y342	Medium Teak							•		
Y323	Medium Walnut							•		
Y811	Natural							•		
Y341	Wenge							•		

*'T' suffix is for paint finish only

Most products introduced after 2004 are not available in Legacy finishes. See individual pricing pages for availability.

Specify Legacy finishes to match existing product only. Legacy finishes are not available for new customers.

Trim Finishes

Panel top caps
Panel post trim
Pedestal drawer top caps
Overhead drawer top caps
Pedestal drawer pulls

Y1 Pewter

Paint Finishes

Panel base raceway covers
Panel tiled insert supports
Solid Steel panel inserts
Perforated steel panel inserts
Embossed steel panel inserts
Overhead storage components
Pedestals
Desk components
Metal panel topcaps and trim

P1 Finishes

Y1 Pewter

P2 Finishes

H Beige Metallic
W Light Tan Metallic

All other Knoll paint finishes and custom finishes (Series 2 components only)

Laminates

Worksurfaces

An upcharge applies where specifying Legacy laminates. Add an amount equal to 10% of the solid PVC edgeband list price to the price of any product specified with a Legacy laminate.

MC Caramel Maple
CM Clear Maple
M1 Light Grey
PA Pearwood
SD Sand
B Snow
WM Warm Cherry
MR6 Winter Grey Matrix

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Worksurface Edges

2mm edgeband

MC Caramel Maple
CM Clear Maple
Y3 Dark Grey
Y2 Medium Grey
MT Metal
Y1 Pewter
SD Sand
B Snow
WM Warm Cherry

Fabric Options

Grade 10
Bailey II (W359)
Element (W1077)
Foundation (W351)
Growth Spurt (W692)
Newbury (W812)
Solid Crepe (W257)
Symbolic Details (W693)
Versatility (W432)

Grade 20
Bauhaus Block (W296)
Circle Line (W1146)
Clarity (W281)
Criss Cross (W305)
Devon (W809)
Photon (W1293)
Reflect (W884)
Resolution (W280)
Weave Three (W298)

Grade 30
Basket Draft (W249)
Flow (W565)
Harmony (W232)
Interknit (W1090)
Micro (W465)
Progression (W403)

Grade 40
Amplify (W1215)
Bandwidth (W1219)
Clarkson (W1218)
Ornament (W1078)
Palladium (W1030)

Grade 45
Dristi (K872)

Grade 50
Knoll Hopsack (K1206)
Presto (K1000)
Ricochet (K498)

Grade 55
Transition (W816)

Open Weave Fabrics

Warpnet
White (W1113/1)
Medium Grey (W1113/2)
Dark Value Grey (W1113/3)
Warm Cool Neutral (W1113/4)
Brushed Gold (W1113/5)

COM (Customer's Own Material)
COM can be applied to Dividends Horizon product on a select basis. Please consult your Knoll Customer Service Representative for details on the COM approval process and testing requirements.

Pricing for COM fabrics is at Grade 10.

Note: Always contact your Customer Service Representative prior to sending any COM (including pre-approved KnollTextiles) to the manufacturing facility.

Dividends Horizon Panels
Dividends Horizon is a furniture system comprised of a wide variety of panels, hanging components, storage, screens and freestanding desks.

At the heart of the system is a universal panel frame. The universal frame is an open design that accepts many styles of panel inserts. These include:

- Monolithic Fabric Insert
- Monolithic Laminate Insert
- Tiled Fabric Insert
- Tiled Laminate Insert
- Beltway Electrical
- Technology Tile
- Painted Steel
- Perforated Steel
- Embossed Steel
- Window Kits
- Markerboard

Panel Dimensions
- Widths: 15", 18",24",30",36", 42",48" and 60"
- Heights: worksurface height, 36",42",50", 57", 64" and 78"
- Thickness: 3"

Panel Frame Options
Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels.

Topway panel frames feature an integral top cable trough, and are used with D1 style stack frames.

Full View frames have no top trough, leaving a larger window opening in the top position. Full View frames are used with D2 style stack frames.

Panel Frame Construction
Panel frames are robotically welded and consist of vertical channels, horizontal rails and panel feet with leveling glides.

- Topway trough: 22-gauge roll-formed steel (topway frames only)
- Vertical channels: 16-gauge roll-formed steel with 5/8" integral slotted standard with adjustments in 11/2" increments
- Horizontal rails: 15-gauge roll-formed steel
- Panel feet: extruded aluminum
- Leveling glides: Steel threads with 1-1/2" height adjustment and 1-1/2" diameter nylon foot

Preconfigured Panels

Dividends Horizon panels can be specified "Preconfigured" in various styles including:

- Monolithic Panel
- Tiled Panel
- Beltway Panel

Monolithic Panel Components
Monolithic panels provide a single fabric or laminate insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with panel frame, base components, top cap, panel to panel connection hardware and one full height panel insert per side.

Tiled Panel Components
Individual tiled panels allow for a "segmented" aesthetic. Individual tile supports create separation within the panel frame.

"Preconfigured" Dividends Horizon panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, tile supports and tiles.

Beltway Panel Components
Beltway panels allow for electrical and/or data to be accessed above worksurface height. Beltway electrical/data can be specified on one or both sides of a panel.

"Preconfigured" Dividends Horizon beltway panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, beltway panel inserts, beltway covers and beltway insert supports.

Base Options
- Base Raceway
- Open Base
- Tile to the Floor

Note: Standard base, Open base and Tile to the floor components can be retrofitted in either a topway or full view frame.

Stack Frames
Dividends Horizon stack frames increase the overall height of a standard panel.

The stack frame is available in three panel heights, 14", 21" and 28". Dividends Horizon stack panels may be attached to standard 36", 42", 50",57", 64" and 78" high panel. Maximum stacking height above a base panel height is 28".

Dividends Horizon Panels and Components (Base Raceway shown)



Monolithic Panel



Beltway Panel



Tiled Panel



Topway Frame Construction



Panel Foot Construction

Open Position Planner
Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panels in virtually any configuration.

This powerful specification tool eliminates the need for most built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to electronic specification users, and is not available in this price list.

"Build-to-Spec" Panels
"Build-to-Spec" panels are specified by component for special applications. These include: when a different fabric is required on each panel side and when retrofitting existing panels to another style. Panels and components are not shipped assembled.

Universal Panel Connectors
Universal panel connectors are included with Dividends panels. Panel connection hardware is universal to allow:

- Same-height straight panel-to-panel connections
- High-low straight panel-to-panel connections
- Straight high-low panel-to-post connections

Included with universal panel connection hardware:

- Upper wedge block connector
- Lower cactus connectors

Universal panel connection hardware construction:

- Lower connectors: Welded 14-gauge steel cactus style connectors
- Upper connector: Die cast wedge block with 13-gauge steel alignment bracket and 4 1/2" tension screw

Panel Attachment
The lower cactus style connectors engage the lower frames of adjacent panels. The upper wedge block engages the upper frames. The connection is secured by tightening the upper connector's tension screw.

Panel-to-Panel Top Cap Transition
Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.

- **Construction**: Trim-color black when used with veneer top caps
- **Size**: 1" wide by 3" deep
- **Attachment**: Snaps between top cap sections in straight, same-height panel configurations

Note: Panel-to-panel top cap transitions are ordered separately from panels.

Top Cap
Top cap is included with preconfigured panels.

- **Construction**: Plastic top caps are trim colored, softly radiused plastic extrusion. Veneer top caps are techgrain veneer over plastic extrusion. Metal top caps, available in both radius and flat profiles, are powder coated steel.
- **Attachment**: Snaps onto the trough of a topway panel frame. Retainer clips are used to attach the top cap to the top rail of a full view frame.

Panel End Trim
Panel end trim matches the aesthetics of the panel top cap. It is used to end a panel run and for high-low, panel-to-panel applications.

Four panel trim options are available:
- Enhanced smooth plastic
- Radius Metal
- Flat Metal
- Thin Profile Flat

Note: Panel end trim is ordered separately from panels. Included with the panel end trim are panel end trim brackets.

- **Construction**: Standard panel end trims are trim colored, softly radiused plastic extrusions with a plastic injection molded end cap.

  Metal trim is extruded aluminum with powder coat finish.
- **Attachment**: Panel-mount brackets are fastened to the panel with thread-forming screws into pre-punched holes. End trim snaps onto panel mount brackets.

  The panel end top cap snaps over the panel end trim and panel top trim.



Monolithic Panel



Panel Connection Hardware


Panel Attachment



Panel End Trim Attachment

Post Connectors
Post connectors are required for all “L”, “T”, and “X” configurations. For same-height applications, post connectors are available as an assembly and include the post, vertical trim and top cap.

For high-low panel-to-post applications, post connectors are specified by component.

Post and Post Component Construction

- Post: 3" square extruded aluminum
- Plastic Post Cover: Trim-color plastic extrusion
- Metal Post Cover: 18 gauge steel with powder coat finish
- Post Top Cap: Trim-colored injection-molded plastic

Attachment: Post connectors use the universal panel connection hardware from adjacent panels

Electrical and data access: Posts have cut-outs that match the wire and cable access channels provided by panel frames. This allows wire conduits and data cables to be routed through the post at the topway, beltway and base raceway.

Electrical and Communications
Dividends Horizon provides a logical approach for planning and installing electrical systems and communication cables.

Power is installed along the base raceway with access available in both the base raceway and optional beltway.

Topway Panel Frame Electrical
Allows data cables to be routed horizontally and vertically within the panel.

- Interior dimension: 2 1/2"H x 3/4"W

Cables can be routed along the tops of panels, routed through the interior of panels and along both the beltway and base raceway. The primary channel for distributing cable is provided in the horizontal topway along the top of panels. The topway allows cables to be easily laid-in during initial installation and additional cables to be added as required. It also separates data from power to reduce the chance of interference. A vertical wire pathway is provided in the center of the topway. This allows cables to be run vertically through the interior of the panel to the beltway or base raceway without the use of exterior cable managers.

Data Cabling Bend Radius



Topway Panel Frame Trough



"L" Post Connection



"L" Post Cover Attachment



Topway Panel Frame Cable Routing



Beltway Electrical
Provides duplex receptacle and data port access at desk-height level.

- Exterior dimension: 4 1/4"H x 3"D
- Interior dimension: 3 1/2"H x 2 3/4"D
- Height from floor: 32 3/4" to center of beltway cover
- Beltway cover construction: Trim-color plastic extrusion
- Beltway cover attachment: Snaps onto beltway panel insert supports
- Duplex access: 30" and wider beltway covers have two duplex knockouts per panel side (18" and 24" wide beltways do not have duplex knockouts)
- Duplex location: Knockouts located 12" on center from each end of cover
- Data access: All beltway covers (except 30 wide) have one center-located data port knockout per panel side
- Additional data access: In panels 30" and wider, the two duplex knockouts can be used as additional data ports when the beltway is not used for duplex receptacles.
- Power capacity: One power module per panel (single or double-sided).

Panel Base Options
Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor.

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway
Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)
- Duplex location: 9" on center from each end
- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper

Note: Knockouts are standard unless specified without.

Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric or steel tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.

Beltway Electrical



Base Raceway Electrical



Cable Management Capacities
This chart shows the number of category 5, 4-pair cables that can be routed through various Dividends Horizon pathways. Cable capacities are based on 0.160, 0.200, and 0.250 diameter cables at a full fill capacity.

Pathway Description	Cable Pathway Area (Square Inches)	Cable Dia. 0.16"	Cable Dia. 0.20"	Cable Dia. 0.25"
Panel Top Way	3.00	109	75	41
Panel Base Raceway (w/o electrical)	8.52	270	178	108
Panel Base Raceway (with electrical)	3.65	162	102	56
Beltway (w/o electrical)	1.50	72	50	32
Beltway (with electrical)	1.10	26	18	11
Vertical Drop (within panel)	1.90	28	24	15

Panel Planning Guidelines

The following panel planning guidelines are provided to ensure stability of Dividends Horizon panels.

Three different scenarios are shown:

- Panel run supported by panels on one end
- Panel run supported by panels on both ends
- High density storage

Panel Run Supported by Panels at One End

- Minimum of an "L" panel connection on one end
- Maximum number of panels in run: 4
- End of panel run must be supported by a pedestal, panel-mounted Open Leg Support, C-leg Support or any height panel

Formula for Depth of Return



Panel Run Supported by Panels at One End





End of Run Supported by Pedestal





End of Run Supported by Panel Mount C-Leg Support





End of Run Supported by Open Leg Support





End of Run Supported by Panel of Any Height

Panel Run Supported by Panels at Both Ends

- Minimum of an "L" panel connection on both ends (see Formulas 2 and 3 below)
- Maximum length panel run: 12'
- Maximum number of panels in run: 4
- Both ends of panel run must be supported by matching height panels (see Formulas 2 and 3 below)
- Panel run must be floor supported every 8' with a pedestal, panel mounted Open Support Leg or C-Leg support

High Density Storage

If hanging more than one overhead component vertically per panel side the following is required:

- Panel must be supported by matching height return panels on both ends of the panel

Panel Run Supported by Panels at Both Ends







Pedestal, Open Support Leg,
C-Leg support, or pedestal every 8'



Pedestal, Open Support Leg,
C-Leg support, or pedestal every 8'

High Density Storage





Formulas for Depth Return

Formula 1



Formula 2



Formula 3



Return panel must be a minimum of 36" wide when laminate tiles are used along the spine panel run.

Monolithic Panel
Monolithic panels provide a single fabric insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with topway or full view panel frame, base components, top cap, panel to panel connection hardware and one full height fabric panel insert per side.

Panels may also be ordered by components for “Build-to-Spec” applications. This includes when different fabric insert is required on each side of the panel.

Monolithic Panel Insert Construction
Fabric laminated with web adhesive heat-cured to $^{7}/_{16}$" thick tackable acoustical board.

Monolithic Panel Ratings
- Noise Reduction Coefficient (NRC) rating: .70
- Sound Transmission Class (STC) rating: 11

Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furnishings.

Monolithic Panel Insert Attachment
Fabric panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting spring clips are attached to inserts for connection to the vertical frame for additional support. No tools are required for the insert attachment.

Top Cap Options
Three top cap options are available:

- Smooth Radius Plastic
- Radius Metal
- Flat Metal

Top Cap Construction
Smooth radiused plastic top caps are made from extruded plastic. Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment
Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to a full view frame.

If additional support for monolithic panel inserts is required, a beltway cable tray can be installed.

Three Base Options Available:
- Base Raceway
- Tile to the Floor
- Open Base

Base Raceway covers are available with or without knockouts.

See the preconfigured tiled panel pages for more information on base options.

Carpet Grippers
Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Carpet grippers have a black finish.

Universal Panel Connectors
Dividends Horizon panels include universal panel connectors to allow same-height straight panel-to-panel connections, high-low straight panel-to-panel connections and straight and high-low panel-to-post connections.

Electrical
Panels 24" and wider will accept two duplex receptacles per panel base side. 18" wide panels will provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

Preconfigured Monolithic Panel



Panel Base Options



Monolithic Panels
Standard Base Raceway
Worksurface Height, 36", 42" and 50" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
Worksurface Height Monolithic Standard Base Raceway	28½"	15"	3"	**DP7CMMRRWH15**	$356.	$370.	$386.	$391.	$406.	$412.	$418.	$428.
	28½"	18"	3"	**DP7CMMRRWH18**	356.	370.	386.	391.	406.	412.	418.	428.
	28½"	24"	3"	**DP7CMMRRWH24**	400.	412.	432.	439.	450.	458.	467.	477.
	28½"	30"	3"	**DP7CMMRRWH30**	420.	434.	454.	462.	474.	483.	491.	504.
	28½"	36"	3"	**DP7CMMRRWH36**	474.	490.	515.	522.	539.	548.	557.	572.
	28½"	42"	3"	**DP7CMMRRWH42**	528.	545.	572.	582.	597.	608.	618.	636.
	28½"	48"	3"	**DP7CMMRRWH48**	560.	577.	604.	614.	632.	643.	655.	671.
	28½"	60"	3"	**DP7CMMRRWH60**	673.	692.	725.	739.	761.	775.	788.	806.
36" High, Monolithic Standard Base Raceway	35⅛"	15"	3"	**DP7CMMRR3615**	356.	370.	386.	391.	406.	412.	418.	428.
	35⅛"	18"	3"	**DP7CMMRR3618**	356.	370.	386.	391.	406.	412.	418.	428.
	35⅛"	24"	3"	**DP7CMMRR3624**	400.	412.	432.	439.	450.	458.	467.	477.
	35⅛"	30"	3"	**DP7CMMRR3630**	420.	434.	454.	462.	474.	483.	491.	504.
	35⅛"	36"	3"	**DP7CMMRR3636**	474.	490.	515.	522.	539.	548.	557.	572.
	35⅛"	42"	3"	**DP7CMMRR3642**	528.	545.	572.	582.	597.	608.	618.	636.
	35⅛"	48"	3"	**DP7CMMRR3648**	560.	577.	604.	614.	632.	643.	655.	671.
	35⅛"	60"	3"	**DP7CMMRR3660**	673.	692.	725.	739.	761.	775.	788.	806.
42" High, Monolithic Standard Base Raceway	42 3/16"	15"	3"	**DP7CMMRR4215**	374.	386.	406.	413.	423.	432.	439.	449.
	42 3/16"	18"	3"	**DP7CMMRR4218**	374.	386.	406.	413.	423.	432.	439.	449.
	42 3/16"	24"	3"	**DP7CMMRR4224**	406.	417.	438.	444.	457.	466.	472.	485.
	42 3/16"	30"	3"	**DP7CMMRR4230**	444.	458.	481.	490.	504.	514.	521.	537.
	42 3/16"	36"	3"	**DP7CMMRR4236**	486.	501.	525.	537.	551.	560.	570.	583.
	42 3/16"	42"	3"	**DP7CMMRR4242**	539.	554.	581.	591.	607.	618.	630.	645.
	42 3/16"	48"	3"	**DP7CMMRR4248**	571.	587.	616.	628.	645.	656.	667.	686.
	42 3/16"	60"	3"	**DP7CMMRR4260**	686.	706.	740.	755.	776.	789.	802.	822.
50" High, Monolithic Standard Base Raceway	49½"	15"	3"	**DP7CMMRR5015**	400.	412.	432.	439.	450.	458.	467.	477.
	49½"	18"	3"	**DP7CMMRR5018**	400.	412.	432.	439.	450.	458.	467.	477.
	49½"	24"	3"	**DP7CMMRR5024**	434.	447.	468.	476.	489.	496.	506.	519.
	49½"	30"	3"	**DP7CMMRR5030**	480.	494.	518.	527.	544.	553.	562.	577.
	49½"	36"	3"	**DP7CMMRR5036**	528.	545.	572.	582.	597.	608.	618.	636.
	49½"	42"	3"	**DP7CMMRR5042**	583.	600.	630.	642.	660.	671.	681.	698.
	49½"	48"	3"	**DP7CMMRR5048**	631.	649.	680.	693.	712.	724.	736.	757.
	49½"	60"	3"	**DP7CMMRR5060**	757.	780.	817.	832.	854.	871.	885.	906.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Monolithic Panel with Standard Base Raceway:

1. Pattern number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway trim finish
6. Panel fabric

Order Code

Monolithic Panel Standard Base Raceway

Example:	**DP7CMMRR3618 4/117/K/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
RR	Base Raceway
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
B191	Fairfield fabric

Included with:

Monolithic Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts (2)
- Base raceway covers
- Top cap
- Connection hardware

Note: Preconfigured Worksurface Height panels are not available with plastic top caps.

Options

Monolithic Panel with Standard Base Raceway Options:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal add $38 P1, $40 P2, $42 P3 paint grades

Raceway Options:
(K) = Knockouts both side
(N) = No Knockouts

Monolithic Panels
Standard Base Raceway
57", 64" and 78" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
57" High, Monolithic Standard Base Raceway	56 13/16"	15"	3"	**DP7CMMRR5715**	$432.	$444.	$466.	$473.	$488.	$495.	$504.	$518.
	56 13/16"	18"	3"	**DP7CMMRR5718**	432.	444.	466.	473.	488.	495.	504.	518.
	56 13/16"	24"	3"	**DP7CMMRR5724**	467.	480.	504.	514.	527.	538.	547.	560.
	56 13/16"	30"	3"	**DP7CMMRR5730**	519.	537.	561.	572.	587.	597.	607.	624.
	56 13/16"	36"	3"	**DP7CMMRR5736**	570.	587.	614.	628.	644.	655.	666.	682.
	56 13/16"	42"	3"	**DP7CMMRR5742**	619.	639.	670.	681.	700.	712.	724.	745.
	56 13/16"	48"	3"	**DP7CMMRR5748**	668.	688.	722.	735.	756.	768.	782.	802.
	56 13/16"	60"	3"	**DP7CMMRR5760**	758.	781.	819.	834.	856.	872.	886.	908.
64" High, Monolithic Standard Base Raceway	64 1/16"	15"	3"	**DP7CMMRR6415**	462.	474.	499.	508.	521.	531.	542.	554.
	64 1/16"	18"	3"	**DP7CMMRR6418**	462.	474.	499.	508.	521.	531.	542.	554.
	64 1/16"	24"	3"	**DP7CMMRR6424**	499.	515.	541.	549.	563.	574.	584.	599.
	64 1/16"	30"	3"	**DP7CMMRR6430**	558.	576.	603.	613.	630.	641.	653.	668.
	64 1/16"	36"	3"	**DP7CMMRR6436**	608.	628.	658.	668.	689.	698.	712.	729.
	64 1/16"	42"	3"	**DP7CMMRR6442**	656.	676.	708.	722.	740.	756.	767.	789.
	64 1/16"	48"	3"	**DP7CMMRR6448**	706.	726.	763.	778.	798.	814.	825.	850.
	64 1/16"	60"	3"	**DP7CMMRR6460**	849.	874.	918.	931.	960.	976.	993.	1,019.
78" High, Monolithic Standard Base Raceway	78 9/16"	15"	3"	**DP7CMMRR7815**	661.	680.	714.	726.	750.	761.	773.	793.
	78 9/16"	18"	3"	**DP7CMMRR7818**	661.	680.	714.	726.	750.	761.	773.	793.
	78 9/16"	24"	3"	**DP7CMMRR7824**	728.	754.	790.	803.	825.	838.	855.	879.
	78 9/16"	30"	3"	**DP7CMMRR7830**	792.	816.	855.	871.	895.	913.	926.	950.
	78 9/16"	36"	3"	**DP7CMMRR7836**	865.	893.	934.	952.	980.	996.	1,014.	1,040.
	78 9/16"	42"	3"	**DP7CMMRR7842**	938.	969.	1,018.	1,035.	1,061.	1,080.	1,101.	1,129.
	78 9/16"	48"	3"	**DP7CMMRR7848**	1,003.	1,034.	1,085.	1,103.	1,134.	1,154.	1,174.	1,203.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Monolithic Panel with Standard Base Raceway:

1. Pattern number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway trim finish
6. Panel fabric

Order Code

Monolithic Panel Standard Base Raceway

Example:	**DP7CMMRR3618 4/117/K/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
RR	Base Raceway
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
B191	Fairfield fabric

Included with:

Monolithic Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts (2)
- Base raceway covers
- Top cap
- Connection hardware

Options

Monolithic Panel with Standard Base Raceway Options:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal add $38 P1, $40 P2, $42 P3 paint grades

Raceway Options:
(K) = Knockouts both side
(N) = No Knockouts

Monolithic Panels
Open Base
Worksurface Height, 36", 42" and 50" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
Worksurface Height, Monolithic Open Base	28½″	18″	3″	**DP7CMMLLWH18**	$356.	$370.	$386.	$391.	$406.	$412.	$418.	$428.
	28½″	24″	3″	**DP7CMMLLWH24**	400.	412.	432.	439.	450.	458.	467.	477.
	28½″	30″	3″	**DP7CMMLLWH30**	420.	434.	454.	462.	474.	483.	491.	504.
	28½″	36″	3″	**DP7CMMLLWH36**	474.	490.	515.	522.	539.	548.	557.	572.
	28½″	42″	3″	**DP7CMMLLWH42**	528.	545.	572.	582.	597.	608.	618.	636.
	28½″	48″	3″	**DP7CMMLLWH48**	560.	577.	604.	614.	632.	643.	655.	671.
	28½″	60″	3″	**DP7CMMLLWH60**	673.	692.	725.	739.	761.	775.	788.	806.
36″ High, Monolithic Open Base 	35⅛″	18″	3″	**DP7CMMLL3618**	356.	370.	386.	391.	406.	412.	418.	428.
	35⅛″	24″	3″	**DP7CMMLL3624**	400.	412.	432.	439.	450.	458.	467.	477.
	35⅛″	30″	3″	**DP7CMMLL3630**	420.	434.	454.	462.	474.	483.	491.	504.
	35⅛″	36″	3″	**DP7CMMLL3636**	474.	490.	515.	522.	539.	548.	557.	572.
	35⅛″	42″	3″	**DP7CMMLL3642**	528.	545.	572.	582.	597.	608.	618.	636.
	35⅛″	48″	3″	**DP7CMMLL3648**	560.	577.	604.	614.	632.	643.	655.	671.
	35⅛″	60″	3″	**DP7CMMLL3660**	673.	692.	725.	739.	761.	775.	788.	806.
42″ High, Monolithic Open Base 	42 3⁄16″	18″	3″	**DP7CMMLL4218**	374.	386.	406.	413.	423.	432.	439.	449.
	42 3⁄16″	24″	3″	**DP7CMMLL4224**	406.	417.	438.	444.	457.	466.	472.	485.
	42 3⁄16″	30″	3″	**DP7CMMLL4230**	444.	458.	481.	490.	504.	514.	521.	537.
	42 3⁄16″	36″	3″	**DP7CMMLL4236**	486.	501.	525.	537.	551.	560.	570.	583.
	42 3⁄16″	42″	3″	**DP7CMMLL4242**	539.	554.	581.	591.	607.	618.	630.	645.
	42 3⁄16″	48″	3″	**DP7CMMLL4248**	571.	587.	616.	628.	645.	656.	667.	686.
	42 3⁄16″	60″	3″	**DP7CMMLL4260**	686.	706.	740.	755.	776.	789.	802.	822.
50″ High, Monolithic Open Base 	49½″	18″	3″	**DP7CMMLL5018**	400.	412.	432.	439.	450.	458.	467.	477.
	49½″	24″	3″	**DP7CMMLL5024**	434.	447.	468.	476.	489.	496.	506.	519.
	49½″	30″	3″	**DP7CMMLL5030**	480.	494.	518.	527.	544.	553.	562.	577.
	49½″	36″	3″	**DP7CMMLL5036**	528.	545.	572.	582.	597.	608.	618.	636.
	49½″	42″	3″	**DP7CMMLL5042**	583.	600.	630.	642.	660.	671.	681.	698.
	49½″	48″	3″	**DP7CMMLL5048**	631.	649.	680.	693.	712.	724.	736.	757.
	49½″	60″	3″	**DP7CMMLL5060**	757.	780.	817.	832.	854.	871.	885.	906.

Dimensions listed under h w d are actual to the nearest 1⁄16″

Ordering Information

Monolithic Panel with Open Base:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base finish
5. Panel fabric

Order Code

Monolithic Panel with Open Base

Example:	**DP7CMMLL 3618 4/117/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
LL	Open base
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Open Base:

- Panel frame
- Acoustic panel inserts (2)
- Open base
- Top cap
- Connection hardware

Note: Preconfigured Worksurface Height panels are not available with plastic top caps.

Options

Monolithic Panel with Open Base:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Monolithic Panels
Open Base
57", 64" and 78" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
57" High, Monolithic Open Base	56 13/16"	18"	3"	**DP7CMMLL5718**	$432.	$444.	$466.	$473.	$488.	$495.	$504.	$518.
	56 13/16"	24"	3"	**DP7CMMLL5724**	467.	480.	504.	514.	527.	538.	547.	560.
	56 13/16"	30"	3"	**DP7CMMLL5730**	519.	537.	561.	572.	587.	597.	607.	624.
	56 13/16"	36"	3"	**DP7CMMLL5736**	570.	587.	614.	628.	644.	655.	666.	682.
	56 13/16"	42"	3"	**DP7CMMLL5742**	619.	639.	670.	681.	700.	712.	724.	745.
	56 13/16"	48"	3"	**DP7CMMLL5748**	668.	688.	722.	735.	756.	768.	782.	802.
	56 13/16"	60"	3"	**DP7CMMLL5760**	758.	781.	819.	834.	856.	872.	886.	908.
64" High, Monolithic Open Base	64 1/16"	18"	3"	**DP7CMMLL6418**	462.	474.	499.	508.	521.	531.	542.	554.
	64 1/16"	24"	3"	**DP7CMMLL6424**	499.	515.	541.	549.	563.	574.	584.	599.
	64 1/16"	30"	3"	**DP7CMMLL6430**	558.	576.	603.	613.	630.	641.	653.	668.
	64 1/16"	36"	3"	**DP7CMMLL6436**	608.	628.	658.	668.	689.	698.	712.	729.
	64 1/16"	42"	3"	**DP7CMMLL6442**	656.	676.	708.	722.	740.	756.	767.	789.
	64 1/16"	48"	3"	**DP7CMMLL6448**	706.	726.	763.	778.	798.	814.	825.	850.
	64 1/16"	60"	3"	**DP7CMMLL6460**	849.	874.	918.	931.	960.	976.	993.	1,019.
78" High, Monolithic Open Base	78 9/16"	18"	3"	**DP7CMMLL7818**	661.	680.	714.	726.	750.	761.	773.	793.
	78 9/16"	24"	3"	**DP7CMMLL7824**	728.	754.	790.	803.	825.	838.	855.	879.
	78 9/16"	30"	3"	**DP7CMMLL7830**	792.	816.	855.	871.	895.	913.	926.	950.
	78 9/16"	36"	3"	**DP7CMMLL7836**	865.	893.	934.	952.	980.	996.	1,014.	1,040.
	78 9/16"	42"	3"	**DP7CMMLL7842**	938.	969.	1,018.	1,035.	1,061.	1,080.	1,101.	1,129.
	78 9/16"	48"	3"	**DP7CMMLL7848**	1,003.	1,034.	1,085.	1,103.	1,134.	1,154.	1,174.	1,203.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Monolithic Panel with Open Base:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base finish
5. Panel fabric

Order Code

Monolithic Panel with Open Base

Example:	**DP7CMMLL3618 4/117/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
LL	Open Base
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Open Base:

- Panel frame
- Acoustic panel inserts (2)
- Open base
- Top cap
- Connection hardware

Options

Monolithic Panel with Open Base:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Monolithic Panels
Tile to Floor One Side
Worksurface Height, 36" and 42" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
Worksurface Height, Monolithic Tile to Floor 	28½"	15"	3"	**DP7CMMFRWH15**	$388.	$402.	$418.	$423.	$438.	$444.	$451.	$460.
	28½"	18"	3"	**DP7CMMFRWH18**	388.	402.	418.	423.	438.	444.	450.	460.
	28½"	24"	3"	**DP7CMMFRWH24**	432.	444.	464.	471.	482.	490.	499.	509.
	28½"	30"	3"	**DP7CMMFRWH30**	452.	466.	486.	494.	506.	515.	523.	536.
	28½"	36"	3"	**DP7CMMFRWH36**	506.	522.	547.	554.	571.	580.	589.	604.
	28½"	42"	3"	**DP7CMMFRWH42**	560.	577.	604.	614.	629.	640.	650.	668.
	28½"	48"	3"	**DP7CMMFRWH48**	592.	609.	636.	646.	664.	675.	687.	703.
	28½"	60"	3"	**DP7CMMFRWH60**	705.	724.	757.	771.	793.	807.	820.	838.
36" High, Monolithic Tile to Floor 	35⅛"	15"	3"	**DP7CMMFR3615**	388.	402.	418.	423.	438.	444.	450.	460.
	35⅛"	18"	3"	**DP7CMMFR3618**	388.	402.	418.	423.	438.	444.	450.	460.
	35⅛"	24"	3"	**DP7CMMFR3624**	432.	444.	464.	471.	482.	490.	499.	509.
	35⅛"	30"	3"	**DP7CMMFR3630**	452.	466.	486.	494.	506.	515.	523.	536.
	35⅛"	36"	3"	**DP7CMMFR3636**	506.	522.	547.	554.	571.	580.	589.	604.
	35⅛"	42"	3"	**DP7CMMFR3642**	560.	577.	604.	614.	629.	640.	650.	668.
	35⅛"	48"	3"	**DP7CMMFR3648**	592.	609.	636.	646.	664.	675.	687.	703.
	35⅛"	60"	3"	**DP7CMMFR3660**	705.	724.	757.	771.	793.	807.	820.	838.
42" High, Monolithic Tile to Floor 	42 3/16"	15"	3"	**DP7CMMFR4215**	406.	418.	438.	445.	455.	464.	471.	481.
	42 3/16"	18"	3"	**DP7CMMFR4218**	406.	418.	438.	445.	455.	464.	471.	481.
	42 3/16"	24"	3"	**DP7CMMFR4224**	438.	449.	470.	476.	489.	498.	504.	517.
	42 3/16"	30"	3"	**DP7CMMFR4230**	476.	490.	513.	522.	536.	546.	553.	569.
	42 3/16"	36"	3"	**DP7CMMFR4236**	518.	533.	557.	569.	583.	592.	602.	615.
	42 3/16"	42"	3"	**DP7CMMFR4242**	571.	586.	613.	623.	639.	650.	662.	677.
	42 3/16"	48"	3"	**DP7CMMFR4248**	603.	619.	648.	660.	677.	688.	699.	718.
	42 3/16"	60"	3"	**DP7CMMFR4260**	718.	738.	772.	787.	808.	821.	834.	854.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Monolithic Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Base raceway finish
6. Panel fabric

Order Code

Monolithic Panel with Tile to Floor

Example:	**DP7CMMFR 3618 4/117/K/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
FR	Tile to Floor
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts one side
117	Soft Grey base raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts (2)
- Top cap
- Connection hardware
- Base raceway on one side

Note: Preconfigured Worksurface Height panels are not available with plastic top caps.

Options

Monolithic Panel with Tile to Floor:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in patternnumber to "RF".

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Monolithic Panels
Tile to Floor One Side
50″, 57″ and 64″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
50″ High, Monolithic Tile to Floor 	49 1/2″	15″	3″	**DP7CMMFR5015**	$432.	$444.	$464.	$471.	$482.	$490.	$499.	$509.
	49 1/2″	18″	3″	**DP7CMMFR5018**	432.	444.	464.	471.	482.	490.	499.	509.
	49 1/2″	24″	3″	**DP7CMMFR5024**	466.	479.	500.	508.	521.	528.	538.	551.
	49 1/2″	30″	3″	**DP7CMMFR5030**	512.	526.	550.	559.	576.	585.	594.	609.
	49 1/2″	36″	3″	**DP7CMMFR5036**	560.	577.	604.	614.	629.	640.	650.	668.
	49 1/2″	42″	3″	**DP7CMMFR5042**	615.	632.	662.	674.	692.	703.	713.	730.
	49 1/2″	48″	3″	**DP7CMMFR5048**	663.	681.	712.	725.	744.	756.	768.	789.
	49 1/2″	60″	3″	**DP7CMMFR5060**	789.	812.	849.	864.	886.	903.	917.	938.
57″ High, Monolithic Tile to Floor 	56 13/16″	15″	3″	**DP7CMMFR5715**	464.	476.	498.	505.	520.	527.	536.	550.
	56 13/16″	18″	3″	**DP7CMMFR5718**	464.	476.	498.	505.	520.	527.	536.	550.
	56 13/16″	24″	3″	**DP7CMMFR5724**	499.	512.	536.	546.	559.	570.	579.	592.
	56 13/16″	30″	3″	**DP7CMMFR5730**	551.	569.	593.	604.	619.	629.	639.	656.
	56 13/16″	36″	3″	**DP7CMMFR5736**	602.	619.	646.	660.	676.	687.	698.	714.
	56 13/16″	42″	3″	**DP7CMMFR5742**	651.	671.	702.	713.	732.	744.	745.	777.
	56 13/16″	48″	3″	**DP7CMMFR5748**	700.	720.	754.	767.	788.	800.	814.	834.
	56 13/16″	60″	3″	**DP7CMMFR5760**	790.	813.	851.	866.	888.	904.	918.	940.
64″ High, Monolithic Tile to Floor 	64 1/16″	15″	3″	**DP7CMMFR6415**	494.	506.	531.	540.	553.	563.	574.	586.
	64 1/16″	18″	3″	**DP7CMMFR6418**	494.	506.	531.	540.	553.	563.	574.	586.
	64 1/16″	24″	3″	**DP7CMMFR6424**	531.	547.	573.	581.	595.	606.	616.	631.
	64 1/16″	30″	3″	**DP7CMMFR6430**	590.	608.	635.	645.	662.	673.	685.	700.
	64 1/16″	36″	3″	**DP7CMMFR6436**	640.	660.	690.	700.	721.	730.	744.	761.
	64 1/16″	42″	3″	**DP7CMMFR6442**	688.	708.	740.	754.	772.	788.	799.	821.
	64 1/16″	48″	3″	**DP7CMMFR6448**	739.	759.	796.	811.	831.	847.	858.	883.
	64 1/16″	60″	3″	**DP7CMMFR6460**	881.	906.	950.	963.	992.	1,008.	1,025.	1,051.

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Monolithic Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Base raceway finish
6. Panel fabric

Order Code

Monolithic Panel with Tile to Floor

Example:	**DP7CMMFR 3618 4/117/K/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
FR	Tile to Floor
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts one side
117	Soft Grey raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts (2)
- Top cap
- Connection hardware
- Base raceway on one side

Options

Monolithic Panel with Tile to Floor:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change “FR” in patternnumber to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Monolithic Panels
Tile to Floor One Side
78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45
78″ High, Monolithic Tile to Floor	78 9/16″	15″	3″	**DP7CMMFR7815**	$693.	$712.	$746.	$758.	$782.	$793.	$805.	$825.
	78 9/16″	18″	3″	**DP7CMMFR7818**	693.	712.	746.	758.	782.	793.	805.	825.
	78 9/16″	24″	3″	**DP7CMMFR7824**	760.	786.	822.	835.	857.	870.	887.	911.
	78 9/16″	30″	3″	**DP7CMMFR7830**	824.	848.	887.	903.	927.	945.	958.	982.
	78 9/16″	36″	3″	**DP7CMMFR7836**	897.	925.	966.	984.	1,012.	1,028.	1,046.	1,072.
	78 9/16″	42″	3″	**DP7CMMFR7842**	970.	1,001.	1,050.	1,067.	1,093.	1,112.	1,133.	1,161.
	78 9/16″	48″	3″	**DP7CMMFR7848**	1,035.	1,066.	1,117.	1,135.	1,166.	1,186.	1,206.	1,235.

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Monolithic Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Base raceway finish
6. Panel fabric

Order Code

Monolithic Panel with Tile to Floor

Example:	**DP7CMMFR 3618 4/117/K/117/B191**
DP7	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
FR	Tile to Floor
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts one side
117	Soft Grey raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts (2)
- Top cap
- Connection hardware
- Base raceway on one side

Options

Monolithic Panel with Tile to Floor:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change “FR” in patternnumber to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Tiled Panels
Specifications

Tiled Panel Components
"Preconfigured" Dividends Horizon tiled panels ship completely assembled with a topway or full view panel frame, choice of standard base options including a standard raceway, open base, and tile to the floor. Also, included with every tiled panel are the panel-to-panel connection hardware, top cap, tile inserts and supports.

Tiled Panel Insert Construction
Fabric laminated with roll coat adhesive, heat-cured to $^{7}/_{16}$" thick tackable acoustical board.

One-Sided Tiled Panel
Tiled panels are available with fabric tiled inserts attached to one or both panel sides. Non-tiled panel side will have a monolithic insert.

Tiled Panel Insert Supports
All Dividends Horizon panel frames are prepunched to accept tiled panel insert supports which span horizontally across the panel frame. Tiled panel insert supports are mounted above a tiled insert with the exception of the uppermost tile. D2 style recessed insert supports are available in black only.

Tiled Panel Insert Attachment
Tiled panel inserts attach to the troughs in the horizontal panel frame and tiled insert supports. Mounting clips are attached to inserts for connection to frame for additional support. No tools are required for attachment.

Top Cap Options
Three Top Cap Options Available:

- Smooth Radius Plastic
- Radius Metal
- Flat Metal

Top Cap Construction
Smooth radiused plastic top caps are made from extruded plastic. Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment
Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Tiled Panel



Tiled Panel Standard Configurations
Tiled panels include the following inserts and insert supports per panel side:



36" High
- Two 14"H tiles
- One tile supports

42" High
- One 7"H tile and two 14"H tiles
- Two tile supports

50" High
- Three 14"H tiles
- Two tile supports

57" High
- One 7"H tile and three 14"H tiles
- Three tile supports

64" High
- Four 14"H tiles
- Three tile supports

78" High
- Five 14"H tiles
- Four tile supports

Tiled Panels
Specifications

Panel Base Options
Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

Open Base panels feature two extruded aluminum feet with triangular profile, positioned at the end of each panel. Open base panels offer a lighter aesthetic and improved ventilation over raceway panels.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If electrical access is required, one-sided electrical and one-sided base cable trays must be used.

Open Position Planner
Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panel frames in virtually any configuration.

This powerful specification tool eliminates the need for built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to Electronic Specification users, and is not available in this price list.

Panels may be ordered by component throughout the “Built-to-Spec” option, allowing personalized combinations of the tile types and colors.

Note: Standard configurations of “Preconfigured” tiled panels are also available with 28" base tiles with a standard base raceway, open base or tile to the floor options.

Note: Overheads can only be attached to the upper most position of tiled panels. On 78" high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.

Note: Insert dimensions are nominal

Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)



Open Base

Tiled Panels
Base Raceway
36", 42" and 50" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic One Side
36" High Tiled Standard Base Raceway	35 1/8"	15"	3"	**DP7CTTRR3615**	$578.	$594.	$625.	$636.	$653.	$664.	$675.	$692.	$85.
	35 1/8"	18"	3"	**DP7CTTRR3618**	578.	594.	625.	636.	653.	664.	675.	692.	85.
	35 1/8"	24"	3"	**DP7CTTRR3624**	614.	633.	664.	676.	693.	706.	719.	736.	86.
	35 1/8"	30"	3"	**DP7CTTRR3630**	652.	671.	701.	717.	734.	752.	762.	782.	87.
	35 1/8"	36"	3"	**DP7CTTRR3636**	714.	731.	768.	787.	804.	821.	834.	855.	89.
	35 1/8"	42"	3"	**DP7CTTRR3642**	765.	789.	825.	839.	864.	881.	895.	920.	88.
	35 1/8"	48"	3"	**DP7CTTRR3648**	802.	825.	866.	884.	905.	923.	937.	964.	90.
	35 1/8"	60"	3"	**DP7CTTRR3660**	963.	992.	1,040.	1,058.	1,087.	1,105.	1,126.	1,153.	92.
42" High Tiled Standard Base Raceway	42 3/16"	15"	3"	**DP7CTTRR4215**	593.	610.	641.	653.	671.	681.	693.	712.	85.
	42 3/16"	18"	3"	**DP7CTTRR4218**	593.	610.	641.	653.	671.	681.	693.	712.	85.
	42 3/16"	24"	3"	**DP7CTTRR4224**	630.	649.	679.	692.	711.	723.	735.	756.	86.
	42 3/16"	30"	3"	**DP7CTTRR4230**	675.	694.	728.	746.	763.	778.	791.	813.	87.
	42 3/16"	36"	3"	**DP7CTTRR4236**	723.	748.	782.	796.	817.	831.	848.	866.	89.
	42 3/16"	42"	3"	**DP7CTTRR4242**	775.	797.	835.	852.	873.	890.	902.	927.	88.
	42 3/16"	48"	3"	**DP7CTTRR4248**	816.	838.	882.	897.	922.	935.	953.	980.	90.
	42 3/16"	60"	3"	**DP7CTTRR4260**	981.	1,010.	1,058.	1,077.	1,107.	1,127.	1,145.	1,175.	92.
50" High Tiled Standard Base Raceway	49 1/2"	15"	3"	**DP7CTTRR5015**	614.	633.	664.	676.	693.	706.	719.	736.	84.
	49 1/2"	18"	3"	**DP7CTTRR5018**	614.	633.	664.	676.	693.	706.	719.	736.	84.
	49 1/2"	24"	3"	**DP7CTTRR5024**	663.	681.	717.	727.	752.	762.	776.	795.	87.
	49 1/2"	30"	3"	**DP7CTTRR5030**	700.	723.	758.	770.	793.	805.	821.	839.	84.
	49 1/2"	36"	3"	**DP7CTTRR5036**	746.	765.	802.	819.	838.	855.	870.	893.	79.
	49 1/2"	42"	3"	**DP7CTTRR5042**	792.	817.	856.	871.	895.	913.	926.	951.	74.
	49 1/2"	48"	3"	**DP7CTTRR5048**	835.	861.	901.	921.	943.	962.	979.	1,003.	72.
	49 1/2"	60"	3"	**DP7CTTRR5060**	1,001.	1,030.	1,080.	1,101.	1,130.	1,151.	1,171.	1,201.	92.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information

Tiled Panel with Standard Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway finish
6. Tile Support profile
7. Panel fabric

Order Code

Tiled Panel with Standard Base Raceway

Example:	**DP7CTTRR3618 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
RR	Base raceway
36	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Top cap
- Connection hardware

Options

Tiled Panels with Standard Base Raceway:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Monolithic Side Option:
For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) =Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Base Raceway
57", 64" and 78" High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
57" High Tiled Standard Base Raceway	56 13/16"	15"	3"	**DP7CTTRR5715**	$748.	$767.	$805.	$820.	$842.	$857.	$873.	$895.	$106.
	56 13/16"	18"	3"	**DP7CTTRR5718**	748.	767.	805.	820.	842.	857.	873.	895.	106.
	56 13/16"	24"	3"	**DP7CTTRR5724**	802.	825.	865.	882.	904.	922.	937.	963.	110.
	56 13/16"	30"	3"	**DP7CTTRR5730**	849.	874.	918.	931.	960.	976.	993.	1,019.	113.
	56 13/16"	36"	3"	**DP7CTTRR5736**	901.	928.	974.	993.	1,020.	1,037.	1,054.	1,084.	115.
	56 13/16"	42"	3"	**DP7CTTRR5742**	956.	985.	1,031.	1,051.	1,079.	1,099.	1,118.	1,145.	117.
	56 13/16"	48"	3"	**DP7CTTRR5748**	1,009.	1,040.	1,090.	1,109.	1,139.	1,159.	1,179.	1,212.	119.
	56 13/16"	60"	3"	**DP7CTTRR5760**	1,212.	1,246.	1,307.	1,331.	1,367.	1,393.	1,416.	1,451.	121.
64" High Tiled Standard Base Raceway	64 1/16"	15"	3"	**DP7CTTRR6415**	790.	815.	853.	868.	893.	906.	924.	948.	127.
	64 1/16"	18"	3"	**DP7CTTRR6418**	790.	815.	853.	868.	893.	906.	924.	948.	127.
	64 1/16"	24"	3"	**DP7CTTRR6424**	849.	872.	918.	930.	957.	974.	992.	1,019.	134.
	64 1/16"	30"	3"	**DP7CTTRR6430**	897.	925.	969.	988.	1,017.	1,030.	1,051.	1,077.	130.
	64 1/16"	36"	3"	**DP7CTTRR6436**	953.	985.	1,029.	1,050.	1,077.	1,098.	1,115.	1,144.	131.
	64 1/16"	42"	3"	**DP7CTTRR6442**	1,011.	1,041.	1,093.	1,112.	1,142.	1,162.	1,182.	1,214.	133.
	64 1/16"	48"	3"	**DP7CTTRR6448**	1,066.	1,098.	1,149.	1,171.	1,203.	1,226.	1,246.	1,277.	134.
	64 1/16"	60"	3"	**DP7CTTRR6460**	1,277.	1,316.	1,382.	1,407.	1,445.	1,471.	1,495.	1,535.	134.
78" High Tiled Standard Base Raceway	78 9/16"	15"	3"	**DP7CTTRR7815**	1,242.	1,277.	1,341.	1,365.	1,401.	1,428.	1,452.	1,489.	228.
	78 9/16"	18"	3"	**DP7CTTRR7818**	1,242.	1,277.	1,341.	1,365.	1,401.	1,428.	1,452.	1,489.	228.
	78 9/16"	24"	3"	**DP7CTTRR7824**	1,335.	1,373.	1,443.	1,468.	1,511.	1,536.	1,561.	1,604.	236.
	78 9/16"	30"	3"	**DP7CTTRR7830**	1,416.	1,457.	1,525.	1,556.	1,599.	1,625.	1,656.	1,695.	230.
	78 9/16"	36"	3"	**DP7CTTRR7836**	1,513.	1,558.	1,633.	1,662.	1,710.	1,740.	1,770.	1,815.	250.
	78 9/16"	42"	3"	**DP7CTTRR7842**	1,604.	1,651.	1,729.	1,762.	1,812.	1,842.	1,876.	1,923.	255.
	78 9/16"	48"	3"	**DP7CTTRR7848**	1,698.	1,751.	1,836.	1,872.	1,921.	1,955.	1,989.	2,039.	306.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information

Tiled Panel with Standard Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway finish
6. Tile support profile
7. Tile support finish
8. Panel fabric

Order Code

Tiled Panel with Standard Base Raceway

Example:	**DP7CTTRR3618 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
RR	Base raceway
36	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Top cap
- Connection hardware

Otpions

Tiled Panels with Standard Base Raceway:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Monolithic Side Option:
For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) =Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Open Base
36″, 42″ and 50″ High

description	h	w	d	pattern no.	10	15	20	25	30	35	40	45	Deduct for Monolithic One Side
36″ High Tiled Open Base	35 1/8″	18″	3″	**DP7CTTLL3618**	$578.	$594.	$625.	$636.	$653.	$664.	$675.	$692.	$85.
	35 1/8″	24″	3″	**DP7CTTLL3624**	614.	633.	664.	676.	693.	706.	719.	736.	86.
	35 1/8″	30″	3″	**DP7CTTLL3630**	652.	671.	701.	717.	734.	752.	762.	782.	87.
	35 1/8″	36″	3″	**DP7CTTLL3636**	714.	731.	768.	787.	804.	821.	834.	855.	89.
	35 1/8″	42″	3″	**DP7CTTLL3642**	765.	789.	825.	839.	864.	881.	895.	920.	88.
	35 1/8″	48″	3″	**DP7CTTLL3648**	802.	825.	866.	884.	905.	923.	937.	964.	90.
	35 1/8″	60″	3″	**DP7CTTLL3660**	963.	992.	1,040.	1,058.	1,087.	1,105.	1,126.	1,153.	92.
42″ High Tiled Open Base	42 3/16″	18″	3″	**DP7CTTLL4218**	593.	610.	641.	653.	671.	681.	693.	712.	85.
	42 3/16″	24″	3″	**DP7CTTLL4224**	630.	649.	679.	692.	711.	723.	735.	756.	86.
	42 3/16″	30″	3″	**DP7CTTLL4230**	675.	694.	728.	746.	763.	778.	791.	813.	87.
	42 3/16″	36″	3″	**DP7CTTLL4236**	723.	748.	782.	796.	817.	831.	848.	866.	89.
	42 3/16″	42″	3″	**DP7CTTLL4242**	775.	797.	835.	852.	873.	890.	902.	927.	88.
	42 3/16″	48″	3″	**DP7CTTLL4248**	816.	838.	882.	897.	922.	935.	953.	980.	90.
	42 3/16″	60″	3″	**DP7CTTLL4260**	981.	1,010.	1,058.	1,077.	1,107.	1,127.	1,145.	1,175.	92.
50″ High Tiled Open Base	49 1/2″	18″	3″	**DP7CTTLL5018**	614.	633.	664.	676.	693.	706.	719.	736.	85.
	49 1/2″	24″	3″	**DP7CTTLL5024**	663.	681.	717.	727.	752.	762.	776.	795.	87.
	49 1/2″	30″	3″	**DP7CTTLL5030**	700.	723.	758.	770.	793.	805.	821.	839.	85.
	49 1/2″	36″	3″	**DP7CTTLL5036**	746.	765.	802.	819.	838.	855.	870.	893.	79.
	49 1/2″	42″	3″	**DP7CTTLL5042**	792.	817.	856.	871.	895.	913.	926.	951.	74.
	49 1/2″	48″	3″	**DP7CTTLL5048**	835.	861.	901.	921.	943.	962.	979.	1,003.	72.
	49 1/2″	60″	3″	**DP7CTTLL5060**	1,001.	1,030.	1,080.	1,101.	1,130.	1,151.	1,171.	1,201.	92.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with Open Base:

1. Pattern Number
2. Top cap type
3. Top Cap finish
4. Base finish
5. Tile support profile
6. Panel fabric

Order Code

Tiled Panel with Open Base

Example:	**DP7CTTLL3618 4/117/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
LL	Open base
36	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Open Base:

- Panel frame
- Acoustic panel inserts
- Open base
- Top cap
- Connection hardware

Options

Tiled Panel with Open Base:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For one side tiled, one side monolithic, change “TT” in pattern number to “MT” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Open Base
57″, 64″ and 78″ High

description	h	w	d	pattern no.	10	15	20	25	30	35	40	45	deduct for Monolithic One Side
57″ High Tiled Open Base	56 13/16″	18″	3″	**DP7CTTLL5718**	$748.	$767.	$805.	$820.	$842.	$857.	$873.	$895.	$106.
	56 13/16″	24″	3″	**DP7CTTLL5724**	802.	825.	865.	882.	904.	922.	937.	963.	110.
	56 13/16″	30″	3″	**DP7CTTLL5730**	849.	874.	918.	931.	960.	976.	993.	1,019.	113.
	56 13/16″	36″	3″	**DP7CTTLL5736**	901.	928.	974.	993.	1,020.	1,037.	1,054.	1,084.	115.
	56 13/16″	42″	3″	**DP7CTTLL5742**	956.	985.	1,031.	1,051.	1,079.	1,099.	1,118.	1,145.	117.
	56 13/16″	48″	3″	**DP7CTTLL5748**	1,009.	1,040.	1,090.	1,109.	1,139.	1,159.	1,179.	1,212.	119.
	56 13/16″	60″	3″	**DP7CTTLL5760**	1,212.	1,246.	1,307.	1,331.	1,367.	1,393.	1,416.	1,451.	121.
64″ High Tiled Open Base	64 1/16″	18″	3″	**DP7CTTLL6418**	790.	815.	853.	868.	893.	906.	924.	948.	127.
	64 1/16″	24″	3″	**DP7CTTLL6424**	849.	872.	918.	930.	957.	974.	992.	1,019.	134.
	64 1/16″	30″	3″	**DP7CTTLL6430**	897.	925.	969.	988.	1,017.	1,030.	1,051.	1,077.	130.
	64 1/16″	36″	3″	**DP7CTTLL6436**	953.	985.	1,029.	1,050.	1,077.	1,098.	1,115.	1,144.	131.
	64 1/16″	42″	3″	**DP7CTTLL6442**	1,011.	1,041.	1,093.	1,112.	1,142.	1,162.	1,182.	1,214.	133.
	64 1/16″	48″	3″	**DP7CTTLL6448**	1,066.	1,098.	1,149.	1,171.	1,203.	1,226.	1,246.	1,277.	134.
	64 1/16″	60″	3″	**DP7CTTLL6460**	1,277.	1,316.	1,382.	1,407.	1,445.	1,471.	1,495.	1,535.	134.
78″ High Tiled Open Base 	78 9/16″	18″	3″	**DP7CTTLL7818**	1,242.	1,277.	1,341.	1,365.	1,401.	1,428.	1,452.	1,489.	228.
	78 9/16″	24″	3″	**DP7CTTLL7824**	1,335.	1,373.	1,443.	1,468.	1,511.	1,536.	1,561.	1,604.	236.
	78 9/16″	30″	3″	**DP7CTTLL7830**	1,416.	1,457.	1,525.	1,556.	1,599.	1,625.	1,656.	1,695.	230.
	78 9/16″	36″	3″	**DP7CTTLL7836**	1,513.	1,558.	1,633.	1,662.	1,710.	1,740.	1,770.	1,815.	250.
	78 9/16″	42″	3″	**DP7CTTLL7842**	1,604.	1,651.	1,729.	1,762.	1,812.	1,842.	1,876.	1,923.	255.
	78 9/16″	48″	3″	**DP7CTTLL7848**	1,698.	1,751.	1,836.	1,872.	1,921.	1,955.	1,989.	2,039.	306.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with Open Base:

1. Pattern Number
2. Top cap type
3. Top Cap finish
4. Base finish
5. Tile support profile
6. Panel fabric

Order Code

Tiled Panel with Open Base

Example:	**DP7CTTLL3618 4/117/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
LL	Open base
36	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Open Base:

- Panel frame
- Acoustic panel inserts
- Open base
- Top cap
- Connection hardware

Options

Tiled Panel with Open Base:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For one side tiled, one side monolithic, change “TT” in pattern number to “MT” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Tile To Floor One Side
36″ and 42″ High

description	h	w	d	pattern no.	10	15	20	25	30	35	40	45	Deduct for Monolithic One Sideide 1
36″ High Tiled Panel Tile to Floor One Side	35 1/8″	15″	3″	**DP7CTTFR3615**	$610.	$626.	$657.	$668.	$685.	$696.	$707.	$724.	$85.
	35 1/8″	18″	3″	**DP7CTTFR3618**	610.	626.	657.	668.	685.	696.	707.	724.	85.
	35 1/8″	24″	3″	**DP7CTTFR3624**	646.	665.	696.	708.	725.	738.	751.	768.	86.
	35 1/8″	30″	3″	**DP7CTTFR3630**	684.	703.	733.	749.	766.	784.	794.	814.	87.
	35 1/8″	36″	3″	**DP7CTTFR3636**	746.	763.	800.	819.	836.	853.	866.	887.	89.
	35 1/8″	42″	3″	**DP7CTTFR3642**	797.	821.	857.	871.	896.	913.	927.	952.	88.
	35 1/8″	48″	3″	**DP7CTTFR3648**	834.	857.	898.	916.	937.	955.	969.	996.	90.
	35 1/8″	60″	3″	**DP7CTTFR3660**	995.	1,024.	1,072.	1,090.	1,119.	1,137.	1,158.	1,185.	92.
42″ High Tiled Panel Tile to Floor One Side 	42 3/16″	15″	3″	**DP7CTTFR4215**	625.	642.	673.	685.	703.	713.	725.	744.	85.
	42 3/16″	18″	3″	**DP7CTTFR4218**	625.	642.	673.	685.	703.	713.	725.	744.	85.
	42 3/16″	24″	3″	**DP7CTTFR4224**	662.	681.	711.	724.	743.	755.	767.	788.	86.
	42 3/16″	30″	3″	**DP7CTTFR4230**	707.	726.	760.	778.	795.	810.	823.	845.	87.
	42 3/16″	36″	3″	**DP7CTTFR4236**	755.	780.	814.	828.	849.	863.	880.	898.	89.
	42 3/16″	42″	3″	**DP7CTTFR4242**	807.	829.	867.	884.	905.	922.	934.	959.	88.
	42 3/16″	48″	3″	**DP7CTTFR4248**	848.	870.	914.	929.	954.	967.	985.	1,012.	90.
	42 3/16″	60″	3″	**DP7CTTFR4260**	1,013.	1,042.	1,090.	1,109.	1,139.	1,159.	1,177.	1,207.	92.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway finish
5. Tile support profile
6. Panel fabric

Order Code

Tiled Panel with Tile to Floor

Example:	**DP7CTTFR3618 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
FR	Tile to floor side one, raceway side two
36	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Knockouts for one-sided base raceway
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout one side
- Tile to the floor one side

Options

Tiled Panels With Tile To Floor One Side:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 tiled, change “TT” in pattern number to “MT” and deduct amount in far right column.

Tile to Floor Side Option:
Tile to floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts on raceway side

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Tile To Floor One Side
50″ and 57″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
50″ High Tiled Panel Tile to Floor One Side 	49½″	15″	3″	**DP7CTTFR5015**	$646.	$665.	$696.	$708.	$725.	$738.	$751.	$768.	$85.
	49½″	18″	3″	**DP7CTTFR5018**	646.	665.	696.	708.	725.	738.	751.	768.	84.
	49½″	24″	3″	**DP7CTTFR5024**	695.	713.	749.	759.	784.	794.	808.	827.	87.
	49½″	30″	3″	**DP7CTTFR5030**	732.	755.	790.	802.	825.	837.	853.	871.	84.
	49½″	36″	3″	**DP7CTTFR5036**	778.	797.	834.	851.	870.	887.	902.	925.	79.
	49½″	42″	3″	**DP7CTTFR5042**	824.	849.	888.	903.	927.	945.	958.	983.	85.
	49½″	48″	3″	**DP7CTTFR5048**	867.	893.	933.	953.	975.	994.	1,011.	1,035.	82.
	49½″	60″	3″	**DP7CTTFR5060**	1,033.	1,062.	1,112.	1,133.	1,162.	1,183.	1,203.	1,233.	92.
57″ High Tiled Panel Tile to Floor One Side 	56 13/16″	15″	3″	**DP7CTTFR5715**	780.	799.	837.	852.	874.	889.	905.	927.	106.
	56 13/16″	18″	3″	**DP7CTTFR5718**	780.	799.	837.	852.	874.	889.	905.	927.	106.
	56 13/16″	24″	3″	**DP7CTTFR5724**	834.	857.	897.	914.	936.	954.	969.	995.	110.
	56 13/16″	30″	3″	**DP7CTTFR5730**	881.	906.	950.	963.	992.	1,008.	1,025.	1,051.	113.
	56 13/16″	36″	3″	**DP7CTTFR5736**	933.	960.	1,006.	1,025.	1,052.	1,069.	1,086.	1,116.	115.
	56 13/16″	42″	3″	**DP7CTTFR5742**	988.	1,017.	1,063.	1,083.	1,111.	1,131.	1,150.	1,177.	117.
	56 13/16″	48″	3″	**DP7CTTFR5748**	1,041.	1,072.	1,122.	1,141.	1,171.	1,191.	1,211.	1,244.	119.
	56 13/16″	60″	3″	**DP7CTTFR5760**	1,244.	1,278.	1,339.	1,363.	1,399.	1,425.	1,448.	1,483.	121.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway finish
5. Tile support profile
6. Panel fabric

Order Code

Tiled Panel with Tile to Floor

Example:	**DP7CTTFR5018 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
FR	Tile to floor side one, raceway side two
50	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Knockouts for one-sided base raceway
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout one side
- Tile to the floor one side

Options

Tiled Panels With Tile To Floor One Side:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monlithic Side Options:
For side 1 monolithic, side 2 tiled, change “TT” in pattern number to “MT” and deduct amount in far right column.

Tile to Floor Side Option:
Tile to floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts on raceway side

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
Tile To Floor One Side
64″ and 78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
64″ High Tiled Panel Tile to Floor One Side	64 1/16″	15″	3″	**DP7CTTFR6415**	$822.	$847.	$885.	$900.	$925.	$938.	$956.	$980.	$127.
	64 1/16″	18″	3″	**DP7CTTFR6418**	822.	847.	885.	900.	925.	938.	956.	980.	127.
	64 1/16″	24″	3″	**DP7CTTFR6424**	881.	904.	950.	962.	989.	1,006.	1,024.	1,051.	134.
	64 1/16″	30″	3″	**DP7CTTFR6430**	929.	957.	1,001.	1,020.	1,049.	1,062.	1,083.	1,109.	130.
	64 1/16″	36″	3″	**DP7CTTFR6436**	985.	1,017.	1,061.	1,082.	1,109.	1,130.	1,147.	1,176.	131.
	64 1/16″	42″	3″	**DP7CTTFR6442**	1,043.	1,073.	1,125.	1,144.	1,174.	1,194.	1,214.	1,246.	133.
	64 1/16″	48″	3″	**DP7CTTFR6448**	1,098.	1,130.	1,181.	1,203.	1,235.	1,258.	1,278.	1,309.	134.
	64 1/16″	60″	3″	**DP7CTTFR6460**	1,309.	1,348.	1,414.	1,439.	1,477.	1,503.	1,527.	1,567.	134.

78″ High Tiled Panel Tile to Floor One Side	78 9/16″	15″	3″	**DP7CTTFR7815**	1,274.	1,309.	1,373.	1,397.	1,433.	1,460.	1,484.	1,521.	228.
	78 9/16″	18″	3″	**DP7CTTFR7818**	1,274.	1,309.	1,373.	1,397.	1,433.	1,460.	1,484.	1,521.	228.
	78 9/16″	24″	3″	**DP7CTTFR7824**	1,367.	1,405.	1,475.	1,500.	1,543.	1,568.	1,593.	1,636.	236.
	78 9/16″	30″	3″	**DP7CTTFR7830**	1,448.	1,489.	1,557.	1,588.	1,631.	1,657.	1,688.	1,727.	230.
	78 9/16″	36″	3″	**DP7CTTFR7836**	1,545.	1,590.	1,665.	1,694.	1,742.	1,772.	1,802.	1,847.	250.
	78 9/16″	42″	3″	**DP7CTTFR7842**	1,636.	1,683.	1,761.	1,794.	1,844.	1,874.	1,908.	1,955.	255.
	78 9/16″	48″	3″	**DP7CTTFR7848**	1,730.	1,783.	1,868.	1,904.	1,953.	1,987.	2,021.	2,071.	306.



Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with Tile to Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway finish
5. Tile support profile
6. Panel fabric

Order Code

Tiled Panel with Tile to Floor

Example:	**DP7CTTFR6418 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
TT	Tiled both sides
FR	Tile to floor side one, raceway side two
64	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Knockouts for one-sided base raceway
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Tile to Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout one side
- Tile to the floor one side

Options

Tiled Panels With Tile To Floor One Side:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Options:
For side 1 monolithic, side 2 tiled, change “TT” in pattern number to “MT” and deduct amount in far right column.

Tile to Floor Side Option:
Tile to floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts on raceway side

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Base Raceway
42″ and 50″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic One Side
42″ High Tiled Panel with 28″ Lower Tile and Base Raceway 	42 3/16″	15″	3″	**DP7CPPRR4215**	$537.	$552.	$582.	$595.	$612.	$624.	$637.	$653.	$57.
	42 3/16″	18″	3″	**DP7CPPRR4218**	537.	552.	582.	595.	612.	624.	637.	653.	57.
	42 3/16″	24″	3″	**DP7CPPRR4224**	572.	591.	622.	636.	652.	666.	677.	696.	57.
	42 3/16″	30″	3″	**DP7CPPRR4230**	617.	638.	672.	686.	703.	719.	730.	755.	60.
	42 3/16″	36″	3″	**DP7CPPRR4236**	666.	688.	723.	737.	760.	774.	790.	808.	60.
	42 3/16″	42″	3″	**DP7CPPRR4242**	716.	739.	777.	794.	815.	831.	845.	870.	60.
	42 3/16″	48″	3″	**DP7CPPRR4248**	758.	780.	823.	839.	864.	878.	896.	921.	61.
	42 3/16″	60″	3″	**DP7CPPRR4260**	922.	950.	1,000.	1,020.	1,049.	1,068.	1,089.	1,117.	62.
50″ High Tiled Panel with 28″ Lower Tile and Base Raceway	49 1/2″	15″	3″	**DP7CPPRR5015**	556.	576.	605.	618.	637.	648.	662.	678.	56.
	49 1/2″	18″	3″	**DP7CPPRR5018**	556.	576.	605.	618.	637.	648.	662.	678.	56.
	49 1/2″	24″	3″	**DP7CPPRR5024**	604.	624.	660.	671.	692.	702.	717.	736.	58.
	49 1/2″	30″	3″	**DP7CPPRR5030**	643.	666.	698.	712.	734.	749.	764.	781.	56.
	49 1/2″	36″	3″	**DP7CPPRR5036**	686.	706.	746.	762.	780.	797.	812.	835.	52.
	49 1/2″	42″	3″	**DP7CPPRR5042**	731.	760.	798.	813.	837.	854.	868.	894.	49.
	49 1/2″	48″	3″	**DP7CPPRR5048**	777.	802.	844.	863.	887.	901.	920.	943.	48.
	49 1/2″	60″	3″	**DP7CPPRR5060**	941.	973.	1,023.	1,043.	1,072.	1,094.	1,112.	1,142.	62.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with 28″ Lower Tile and Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway trim finish
6. Tile support profile
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Base Raceway

Example:	**DP7CPPRR4218 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
RR	Raceway both sides
42	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panel with Standard Base Raceway and 28″ Base Tile:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Top cap
- Connection hardware

Options

Tiled Panel with 28″ Lower Tile and Base Raceway:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 tiled, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Base Raceway
57″ and 64″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic One Side
57″ High Tiled Panel with 28″ Lower Tile and Base Raceway	56 13/16″	15″	3″	**DP7CPPRR5715**	$688.	$708.	$749.	$763.	$784.	$799.	$815.	$837.	$71.
	56 13/16″	18″	3″	**DP7CPPRR5718**	688.	708.	749.	763.	784.	799.	815.	837.	71.
	56 13/16″	24″	3″	**DP7CPPRR5724**	746.	768.	806.	823.	848.	864.	880.	902.	74.
	56 13/16″	30″	3″	**DP7CPPRR5730**	791.	816.	860.	874.	899.	918.	934.	962.	76.
	56 13/16″	36″	3″	**DP7CPPRR5736**	844.	871.	916.	934.	963.	980.	996.	1,024.	77.
	56 13/16″	42″	3″	**DP7CPPRR5742**	897.	925.	974.	993.	1,022.	1,041.	1,060.	1,089.	79.
	56 13/16″	48″	3″	**DP7CPPRR5748**	949.	982.	1,030.	1,051.	1,080.	1,101.	1,121.	1,152.	80.
	56 13/16″	60″	3″	**DP7CPPRR5760**	1,152.	1,190.	1,247.	1,272.	1,310.	1,334.	1,358.	1,394.	83.
64″ High Tiled Panel with 28″ Lower Tile and Base Raceway	64 1/16″	15″	3″	**DP7CPPRR6415**	729.	757.	795.	811.	835.	850.	866.	891.	86.
	64 1/16″	18″	3″	**DP7CPPRR6418**	729.	757.	795.	811.	835.	850.	866.	891.	86.
	64 1/16″	24″	3″	**DP7CPPRR6424**	791.	814.	860.	873.	898.	916.	933.	962.	90.
	64 1/16″	30″	3″	**DP7CPPRR6430**	839.	867.	909.	928.	960.	973.	993.	1,020.	87.
	64 1/16″	36″	3″	**DP7CPPRR6436**	896.	925.	972.	992.	1,020.	1,040.	1,058.	1,088.	88.
	64 1/16″	42″	3″	**DP7CPPRR6442**	951.	984.	1,034.	1,054.	1,086.	1,104.	1,123.	1,154.	89.
	64 1/16″	48″	3″	**DP7CPPRR6448**	1,009.	1,040.	1,093.	1,112.	1,144.	1,168.	1,190.	1,221.	90.
	64 1/16″	60″	3″	**DP7CPPRR6460**	1,221.	1,259.	1,323.	1,348.	1,387.	1,413.	1,438.	1,476.	90.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with 28″ Lower Tile and Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway trim finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Base Raceway

Example:	**DP7CPPRR5718 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
RR	Raceway both sides
57	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
2	D2 style tile support
B191	Fairfield light fabric

Included with:

Tiled Panel with Standard Base Raceway and 28″ Base Tile:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Top cap
- Connection hardware

Options

Tiled Panels with 28″ Lower Tile and Base Raceway:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 tiled, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Base Raceway
78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
78″ High Tiled Panel with 28″ Lower Tile and Base Raceway 	78 9/16″	15″	3″	**DP7CPPRR7815**	$1,186.	$1,221.	$1,282.	$1,308.	$1,343.	$1,368.	$1,395.	$1,433.	$153.
	78 9/16″	18″	3″	**DP7CPPRR7818**	1,186.	1,221.	1,282.	1,308.	1,343.	1,368.	1,395.	1,433.	153.
	78 9/16″	24″	3″	**DP7CPPRR7824**	1,276.	1,316.	1,385.	1,410.	1,452.	1,477.	1,502.	1,545.	158.
	78 9/16″	30″	3″	**DP7CPPRR7830**	1,358.	1,399.	1,468.	1,497.	1,540.	1,568.	1,598.	1,639.	155.
	78 9/16″	36″	3″	**DP7CPPRR7836**	1,455.	1,499.	1,574.	1,604.	1,652.	1,683.	1,711.	1,756.	168.
	78 9/16″	42″	3″	**DP7CPPRR7842**	1,545.	1,593.	1,671.	1,703.	1,752.	1,784.	1,818.	1,866.	171.
	78 9/16″	48″	3″	**DP7CPPRR7848**	1,642.	1,693.	1,779.	1,814.	1,864.	1,897.	1,931.	1,982.	205.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panel with 28″ Lower Tile and Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Raceway knockout option
5. Raceway trim finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Base Raceway

Example:	**DP7CPPRR7818 4/117/K/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
RR	Raceway both sides
78	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
2	D2 style tile support
B191	Fairfield light fabric

Included with:

Tiled Panel with Standard Base Raceway and 28″ Base Tile:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Top cap
- Connection hardware

Options

Tiled Panels with 28″ Lower Tile and Base Raceway:

Full View Frame Option:
To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 tiled, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Open Base
42″ and 50″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic One Side
42″ High Tiled Panel with 28″ Lower Tile and Open Base	42 3/16″	18″	3″	**DP7CPPLL4218**	$537.	$552.	$582.	$595.	$612.	$624.	$637.	$653.	$57.
	42 3/16″	24″	3″	**DP7CPPLL4224**	572.	591.	622.	636.	652.	666.	677.	696.	57.
	42 3/16″	30″	3″	**DP7CPPLL4230**	617.	638.	672.	686.	703.	719.	730.	755.	58.
	42 3/16″	36″	3″	**DP7CPPLL4236**	666.	688.	723.	737.	760.	774.	790.	808.	60.
	42 3/16″	42″	3″	**DP7CPPLL4242**	716.	739.	777.	794.	815.	831.	845.	870.	60.
	42 3/16″	48″	3″	**DP7CPPLL4248**	758.	780.	823.	839.	864.	878.	896.	921.	61.
	42 3/16″	60″	3″	**DP7CPPLL4260**	922.	950.	1,000.	1,020.	1,049.	1,068.	1,089.	1,117.	62.
50″ High Tiled Panel with 28″ Lower Tile and Open Base 	49 1/2″	18″	3″	**DP7CPPLL5018**	556.	576.	605.	618.	637.	648.	662.	678.	56.
	49 1/2″	24″	3″	**DP7CPPLL5024**	604.	624.	660.	671.	692.	702.	717.	736.	58.
	49 1/2″	30″	3″	**DP7CPPLL5030**	643.	666.	698.	712.	734.	749.	764.	781.	56.
	49 1/2″	36″	3″	**DP7CPPLL5036**	686.	706.	746.	762.	780.	797.	812.	835.	52.
	49 1/2″	42″	3″	**DP7CPPLL5042**	731.	760.	798.	813.	837.	854.	868.	894.	49.
	49 1/2″	48″	3″	**DP7CPPLL5048**	777.	802.	844.	863.	887.	901.	920.	943.	48.
	49 1/2″	60″	3″	**DP7CPPLL5060**	941.	973.	1,023.	1,043.	1,072.	1,094.	1,112.	1,142.	62.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panels with 28″ Lower Tile and Open Base:

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Base support trim finish
5. Tile support style
6. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Open Base

Example:	**DP7CPPLL4218 4/117/KK/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
LL	Open Base
42	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base support finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Open Base:

- Panel frame
- Acoustic panel inserts
- Open base
- Top cap
- Connection hardware

Options

Tiled Panels with 28″ Lower Tile and Open Base:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Open Base
57″ and 64″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
57″ High Tiled Panel with 28″ Lower Tile and Open Base	56 13/16″	18″	3″	**DP7CPPLL5718**	$688.	$708.	$749.	$763.	$784.	$799.	$815.	$837.	$71.
	56 13/16″	24″	3″	**DP7CPPLL5724**	746.	768.	806.	823.	848.	864.	880.	902.	74.
	56 13/16″	30″	3″	**DP7CPPLL5730**	791.	816.	860.	874.	899.	918.	934.	962.	76.
	56 13/16″	36″	3″	**DP7CPPLL5736**	844.	871.	916.	934.	963.	980.	996.	1,024.	77.
	56 13/16″	42″	3″	**DP7CPPLL5742**	897.	925.	974.	993.	1,022.	1,041.	1,060.	1,089.	79.
	56 13/16″	48″	3″	**DP7CPPLL5748**	949.	982.	1,030.	1,051.	1,080.	1,101.	1,121.	1,152.	80.
	56 13/16″	60″	3″	**DP7CPPLL5760**	1,152.	1,190.	1,247.	1,272.	1,310.	1,334.	1,358.	1,394.	83.
64″ High Tiled Panel with 28″ Lower Tile and Open Base	64 1/16″	18″	3″	**DP7CPPLL6418**	729.	757.	795.	811.	835.	850.	866.	891.	86.
	64 1/16″	24″	3″	**DP7CPPLL6424**	791.	814.	860.	873.	898.	916.	933.	962.	90.
	64 1/16″	30″	3″	**DP7CPPLL6430**	839.	867.	909.	928.	960.	973.	993.	1,020.	87.
	64 1/16″	36″	3″	**DP7CPPLL6436**	896.	925.	972.	992.	1,020.	1,040.	1,058.	1,088.	88.
	64 1/16″	42″	3″	**DP7CPPLL6442**	951.	984.	1,034.	1,054.	1,086.	1,104.	1,123.	1,154.	89.
	64 1/16″	48″	3″	**DP7CPPLL6448**	1,009.	1,040.	1,093.	1,112.	1,144.	1,168.	1,190.	1,221.	90.
	64 1/16″	60″	3″	**DP7CPPLL6460**	1,221.	1,259.	1,323.	1,348.	1,387.	1,413.	1,438.	1,476.	90.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panels with 28″ Lower Tile and Open Base:

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Base support trim finish
5. Tile support style
6. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Open Base

Example:	**DP7CPPLL5718 4/117/KK/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
LL	Open Base
57	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base support finish
2	D2 style tile support
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Open Base:

- Panel frame
- Acoustic panel inserts
- Open base
- Top cap
- Connection hardware

Options

Tiled Panels with 28″ Lower Tile and Open Base:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Open Base
78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for Monolithic One Side
78″ High Tiled Panel with 28″ Lower Tile and Open Base	78 9/16″	18″	3″	**DP7CPPLL7818**	$1,186.	$1,221.	$1,282.	$1,308.	$1,343.	$1,368.	$1,395.	$1,433.	$153.
	78 9/16″	24″	3″	**DP7CPPLL7824**	1,276.	1,316.	1,385.	1,410.	1,452.	1,477.	1,502.	1,545.	158.
	78 9/16″	30″	3″	**DP7CPPLL7830**	1,358.	1,399.	1,468.	1,497.	1,540.	1,568.	1,598.	1,639.	155.
	78 9/16″	36″	3″	**DP7CPPLL7836**	1,455.	1,499.	1,574.	1,604.	1,652.	1,683.	1,711.	1,756.	168.
	78 9/16″	42″	3″	**DP7CPPLL7842**	1,545.	1,593.	1,671.	1,703.	1,752.	1,784.	1,818.	1,866.	171.
	78 9/16″	48″	3″	**DP7CPPLL7848**	1,642.	1,693.	1,779.	1,814.	1,864.	1,897.	1,931.	1,982.	205.



Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panels with 28″ Lower Tile and Open Base:

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Base support trim finish
5. Tile support style
6. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Open Base

Example:	**DP7CPPLL7818 4/117/KK/117/2/B191**
DP7	Dividends Horizon Panel
C	Topway frame
PP	Tiled both sides, 28″ Lower Tile
LL	Open Base
78	Height
18	Width
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey base support finish
2	D2 style tile support
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Open Base:

- Panel frame
- Acoustic panel inserts
- Open base
- Top cap
- Connection hardware

Options

Tiled Panels with 28″ Lower Tile and Open Base:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Tile To Floor
42″ and 50″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for 1 side Monolithic
42″ High Tiled Panel with 28″ Lower Tile and Tile to Floor 	42 3/16″	15″	3″	**DP7CPPFR4215**	$569.	$584.	$614.	$627.	$644.	$656.	$669.	$685.	$57.
	42 3/16″	18″	3″	**DP7CPPFR4218**	569.	584.	614.	627.	644.	656.	669.	685.	57.
	42 3/16″	24″	3″	**DP7CPPFR4224**	604.	623.	654.	668.	684.	698.	709.	728.	57.
	42 3/16″	30″	3″	**DP7CPPFR4230**	649.	670.	704.	718.	735.	751.	762.	787.	58.
	42 3/16″	36″	3″	**DP7CPPFR4236**	698.	720.	755.	769.	792.	806.	822.	840.	60.
	42 3/16″	42″	3″	**DP7CPPFR4242**	748.	771.	809.	826.	847.	863.	877.	902.	60.
	42 3/16″	48″	3″	**DP7CPPFR4248**	790.	812.	855.	871.	896.	910.	928.	953.	61.
	42 3/16″	60″	3″	**DP7CPPFR4260**	954.	982.	1,032.	1,052.	1,081.	1,100.	1,121.	1,148.	62.
50″ High Tiled Panel with 28″ Lower Tile and Tile to Floor 	49 1/2″	15″	3″	**DP7CPPFR5015**	588.	608.	637.	650.	669.	680.	694.	710.	56.
	49 1/2″	18″	3″	**DP7CPPFR5018**	588.	608.	637.	650.	669.	680.	694.	710.	56.
	49 1/2″	24″	3″	**DP7CPPFR5024**	636.	656.	692.	703.	724.	734.	749.	768.	58.
	49 1/2″	30″	3″	**DP7CPPFR5030**	675.	698.	730.	744.	766.	781.	796.	813.	56.
	49 1/2″	36″	3″	**DP7CPPFR5036**	719.	739.	779.	795.	813.	830.	845.	868.	52.
	49 1/2″	42″	3″	**DP7CPPFR5042**	763.	792.	830.	845.	869.	886.	900.	926.	59.
	49 1/2″	48″	3″	**DP7CPPFR5048**	809.	834.	876.	895.	919.	933.	952.	975.	48.
	49 1/2″	60″	3″	**DP7CPPFR5060**	973.	1,005.	1,055.	1,075.	1,104.	1,126.	1,144.	1,174.	62.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panels with 28″ Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Example:	**DP7CPPFF4218 4/117/K/117/2B191**
DP7CPP FF4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Tile to floor side 1
- Base raceway with knockout when required side 2

Options

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column. **Top Cap Options:**
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Tile To Floor
57″ and 64″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for 1 side Monolithic
57″ High Tiled Panel with 28″ Lower Tile and Tile to Floor 	56 13/16″	15″	3″	**DP7CPPFR5715**	$720.	$740.	$781.	$795.	$816.	$831.	$847.	$869.	$71.
	56 13/16″	18″	3″	**DP7CPPFR5718**	720.	740.	781.	795.	816.	831.	847.	869.	71.
	56 13/16″	24″	3″	**DP7CPPFR5724**	778.	800.	838.	855.	880.	896.	912.	934.	74.
	56 13/16″	30″	3″	**DP7CPPFR5730**	823.	848.	892.	906.	931.	950.	966.	994.	76.
	56 13/16″	36″	3″	**DP7CPPFR5736**	876.	903.	948.	966.	995.	1,012.	1,028.	1,056.	77.
	56 13/16″	42″	3″	**DP7CPPFR5742**	929.	957.	1,006.	1,025.	1,054.	1,073.	1,092.	1,121.	79.
	56 13/16″	48″	3″	**DP7CPPFR5748**	981.	1,014.	1,062.	1,083.	1,112.	1,133.	1,153.	1,184.	80.
	56 13/16″	60″	3″	**DP7CPPFR5760**	1,184.	1,222.	1,279.	1,304.	1,342.	1,366.	1,390.	1,426.	83.
64″ High Tiled Panel with 28″ Lower Tile and Tile to Floor 	64 1/16″	15″	3″	**DP7CPPFR6415**	761.	789.	827.	843.	867.	882.	898.	923.	86.
	64 1/16″	18″	3″	**DP7CPPFR6418**	761.	789.	827.	843.	867.	882.	898.	923.	86.
	64 1/16″	24″	3″	**DP7CPPFR6424**	823.	846.	892.	905.	930.	948.	965.	994.	90.
	64 1/16″	30″	3″	**DP7CPPFR6430**	871.	899.	941.	960.	992.	1,005.	1,025.	1,052.	87.
	64 1/16″	36″	3″	**DP7CPPFR6436**	928.	957.	1,004.	1,024.	1,052.	1,072.	1,090.	1,120.	88.
	64 1/16″	42″	3″	**DP7CPPFR6442**	983.	1,016.	1,066.	1,086.	1,118.	1,136.	1,155.	1,186.	89.
	64 1/16″	48″	3″	**DP7CPPFR6448**	1,041.	1,072.	1,125.	1,144.	1,176.	1,200.	1,222.	1,253.	90.
	64 1/16″	60″	3″	**DP7CPPFR6460**	1,253.	1,291.	1,355.	1,380.	1,419.	1,445.	1,470.	1,508.	90.

Dimensions listed under h w d are actual to the nearest 1/8″

Ordering Information

Tiled Panels with 28″ Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Example:	**DP7CPPFF4218 4/117/K/117/2/B191**
DP7CPP FF4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Tile to floor side 1
- Base raceway with knockout when required side 2

Options

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels
28″ Lower Tile and Tile To Floor
78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	deduct for 1 side Monolithic
78″ High Tiled Panel with 28″ Lower Tile and Tile to Floor	78 9/16″	15″	3″	**DP7CPPFR7815**	$1,218.	$1,253.	$1,314.	$1,340.	$1,375.	$1,400.	$1,427.	$1,465.	$153.
	78 9/16″	18″	3″	**DP7CPPFR7818**	1,218.	1,253.	1,314.	1,340.	1,375.	1,400.	1,427.	1,465.	153.
	78 9/16″	24″	3″	**DP7CPPFR7824**	1,308.	1,348.	1,417.	1,442.	1,484.	1,509.	1,534.	1,577.	158.
	78 9/16″	30″	3″	**DP7CPPFR7830**	1,390.	1,431.	1,500.	1,529.	1,572.	1,600.	1,630.	1,671.	155.
	78 9/16″	36″	3″	**DP7CPPFR7836**	1,487.	1,531.	1,606.	1,636.	1,684.	1,715.	1,743.	1,788.	168.
	78 9/16″	42″	3″	**DP7CPPFR7842**	1,577.	1,625.	1,703.	1,735.	1,784.	1,816.	1,850.	1,898.	171.
	78 9/16″	48″	3″	**DP7CPPFR7848**	1,674.	1,725.	1,811.	1,846.	1,896.	1,929.	1,963.	2,014.	205.



Ordering Information

Tiled Panels with 28″ Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Example:	**DP7CPPFF4218 4/117/K/117/2/B191**
DP7CPP FF4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28″ Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout when required

Options

Tiled Panels with 28″ Lower Tile and Tile To Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Tile to Floor Side Option:
Tile to Floor standard on side 2. To specify tile to floor on side 1, change “FR” in pattern number to “RF”.

Monolithic Side Option:
To specify monolithic on side one of panel, change “PP” in pattern number to “MP” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:
(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Beltway Panels
Specifications

Beltway Panel Components
"Preconfigured" Dividends Horizon beltway panels ship completely assembled with a universal panel frame, choice of standard base raceway, open base or tiled to the floor base options, top cap, panel-to-panel connection hardware and beltway inserts.

Beltway panels may be ordered by component for "Build-to-Spec" applications. This includes when panel inserts are required on one side only or when a different fabric color or material is required on opposite panel sides.

Beltway Panel Insert Supports
All Dividends Horizon panel frames are pre-punched to accept beltway supports which span horizontally across the panel frame. Beltway panel inserts are mounted above and below the beltway and attach to the upper and lower panel frame and the beltway supports. Beltway supports are painted black.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Panel Insert Construction
Fabric inserts are constructed of fabric laminated with a web adhesive and heat cured to $^1/_2$" thick tackable acoustic board. Laminate inserts are constructed of a particle board core with laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish.

Beltway Cover Construction
Trim-colored plastic extrusion available in smooth finish.

Electrical
Panel base raceways 24" and wider will accept two duplex receptacles per panel side. 18" wide panels provide pass-through electrical only. Beltway raceways 30" and wider will accept two duplex receptacles per panel side. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel
Beltway panels are available with one beltway per panel or per panel sides. Non-beltway side will have a monolithic insert.

Three Top Cap Options Available
- Smooth Radius Plastic
- Radius Metal
- Flat Metal

Top Cap Construction
Smooth radiused top caps are made from extruded plastic. Radius and flat metal top caps are made from extruded aluminum.

Top Cap Attachment
Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Beltway Panel



Panel Base Options


Base Raceway


Tile-to-Floor (single-sided only)


Open Base

Beltway Panel Standard Configurations

42"H Panels
- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert





50"H Panels
- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert

57"H Panels
- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



78"H Panels
- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert



64"H Panels
- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



Beltway Panels
Standard Base Raceway
42″ and 50″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic on side 2
42″ Beltway Panels with Standard Base Raceway	42 3/16″	18″	3″	**DP7CBBRR4218**	$577.	$593.	$624.	$633.	$652.	$663.	$674.	$691.	$89.
	42 3/16″	24″	3″	**DP7CBBRR4224**	655.	675.	706.	721.	739.	755.	765.	788.	111.
	42 3/16″	30″	3″	**DP7CBBRR4230**	719.	740.	778.	791.	814.	826.	839.	863.	119.
	42 3/16″	36″	3″	**DP7CBBRR4236**	789.	813.	852.	865.	891.	903.	922.	947.	132.
	42 3/16″	42″	3″	**DP7CBBRR4242**	855.	882.	924.	938.	967.	985.	1,000.	1,025.	138.
	42 3/16″	48″	3″	**DP7CBBRR4248**	914.	937.	987.	1,003.	1,029.	1,050.	1,067.	1,095.	149.
	42 3/16″	60″	3″	**DP7CBBRR4260**	1,036.	1,067.	1,119.	1,140.	1,171.	1,193.	1,213.	1,243.	149.
50″ Beltway Panels with Standard Base Raceway	49 1/2″	18″	3″	**DP7CBBRR5018**	599.	617.	648.	660.	676.	689.	700.	719.	88.
	49 1/2″	24″	3″	**DP7CBBRR5024**	687.	706.	740.	756.	776.	790.	802.	823.	112.
	49 1/2″	30″	3″	**DP7CBBRR5030**	748.	766.	803.	820.	839.	856.	871.	894.	116.
	49 1/2″	36″	3″	**DP7CBBRR5036**	808.	831.	872.	889.	914.	928.	943.	969.	121.
	49 1/2″	42″	3″	**DP7CBBRR5042**	873.	900.	943.	963.	989.	1,006.	1,024.	1,051.	127.
	49 1/2″	48″	3″	**DP7CBBRR5048**	931.	962.	1,008.	1,026.	1,054.	1,073.	1,094.	1,121.	132.
	49 1/2″	60″	3″	**DP7CBBRR5060**	1,059.	1,091.	1,143.	1,164.	1,197.	1,218.	1,239.	1,270.	132.

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Beltway Panel with Standard Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway knockout option
5. Base raceway finish
6. Beltway finish
7. Panel fabric

Order Code

Beltway Panel with Standard Base Raceway

Example:	**DP7CBBRR4218 4/117/K/117/117/B191**
DP7CBB RR4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base Raceway with knockouts both sides
117	Soft Grey base raceway finish
117	Beltway finish
B191	Fairfield light fabric

Included with:

Beltway Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Beltway covers
- Top cap
- Connection hardware

Options

Beltway Panel with Standard Raceway Options:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Monolithic Side Option:
To specify monolithic on side one of panel, change "BB" in pattern number to "MB" and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Beltway Panels
Standard Base Raceway
57″, 64″ and 78″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic on side 2
57″ Beltway Panels with Standard Base Raceway	56 13/16″	18″	3″	**DP7CBBRR5718**	$641.	$661.	$691.	$703.	$723.	$736.	$751.	$768.	$88.
	56 13/16″	24″	3″	**DP7CBBRR5724**	726.	751.	787.	801.	821.	836.	851.	873.	112.
	56 13/16″	30″	3″	**DP7CBBRR5730**	787.	810.	849.	864.	889.	902.	920.	942.	116.
	56 13/16″	36″	3″	**DP7CBBRR5736**	864.	890.	933.	950.	977.	994.	1,011.	1,036.	121.
	56 13/16″	42″	3″	**DP7CBBRR5742**	927.	956.	1,002.	1,021.	1,049.	1,067.	1,086.	1,113.	127.
	56 13/16″	48″	3″	**DP7CBBRR5748**	995.	1,024.	1,074.	1,095.	1,125.	1,143.	1,163.	1,195.	132.
	56 13/16″	60″	3″	**DP7CBBRR5760**	1,120.	1,153.	1,211.	1,233.	1,266.	1,288.	1,311.	1,344.	132.
64″ Beltway Panels with Standard Base Raceway	64 1/16″	18″	3″	**DP7CBBRR6418**	680.	700.	734.	752.	767.	784.	796.	817.	95.
	64 1/16″	24″	3″	**DP7CBBRR6424**	766.	791.	828.	847.	866.	884.	897.	922.	117.
	64 1/16″	30″	3″	**DP7CBBRR6430**	824.	851.	891.	905.	930.	949.	965.	991.	117.
	64 1/16″	36″	3″	**DP7CBBRR6436**	920.	947.	992.	1,010.	1,036.	1,055.	1,073.	1,101.	134.
	64 1/16″	42″	3″	**DP7CBBRR6442**	984.	1,012.	1,060.	1,079.	1,109.	1,130.	1,147.	1,177.	142.
	64 1/16″	48″	3″	**DP7CBBRR6448**	1,056.	1,090.	1,141.	1,162.	1,195.	1,216.	1,236.	1,268.	154.
	64 1/16″	60″	3″	**DP7CBBRR6460**	1,194.	1,229.	1,288.	1,313.	1,348.	1,371.	1,396.	1,433.	154.
78″ Beltway Panels with Standard Base Raceway	78 9/16″	18″	3″	**DP7CBBRR7818**	855.	882.	924.	938.	967.	985.	1,000.	1,025.	86.
	78 9/16″	24″	3″	**DP7CBBRR7824**	960.	988.	1,035.	1,053.	1,080.	1,101.	1,121.	1,147.	99.
	78 9/16″	30″	3″	**DP7CBBRR7830**	1,028.	1,059.	1,112.	1,133.	1,163.	1,183.	1,203.	1,236.	102.
	78 9/16″	36″	3″	**DP7CBBRR7836**	1,139.	1,174.	1,230.	1,252.	1,288.	1,311.	1,334.	1,367.	119.
	78 9/16″	42″	3″	**DP7CBBRR7842**	1,225.	1,262.	1,320.	1,345.	1,385.	1,408.	1,434.	1,468.	122.
	78 9/16″	48″	3″	**DP7CBBRR7848**	1,348.	1,391.	1,457.	1,485.	1,523.	1,552.	1,580.	1,619.	151.

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Beltway Panel with Standard Base Raceway:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway knockout option
5. Base raceway finish
6. Beltway finish
7. Panel fabric

Order Code

Beltway Panel with Standard Base Raceway

Example:	**DP7CBBRR4218 4/117/K/117/117/B191**
DP7CBB RR4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base Raceway with knockouts both sides
117	Soft Grey base raceway finish
117	Beltway finish
B191	Fairfield light fabric

Included with:

Beltway Panel with Standard Base Raceway:

- Panel frame
- Acoustic panel inserts
- Base raceway covers
- Beltway covers
- Top cap
- Connection hardware

Options

Beltway Panel with Standard Raceway Options:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
To specify monolithic on side one of panel, change “BB” in pattern number to “MB” and deduct amount in far right column.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Beltway Panels
Tile to the Floor
42″ and 50″ High

description	h	w	d	pattern no.	grade 10	15	20	25	30	35	40	45	Deduct for Monolithic side 1
42″ Beltway Panels with Tile to the Floor	42 3/16″	18″	3″	**DP7CBBFR4218**	$609.	$625.	$656.	$665.	$684.	$695.	$706.	$723.	$89.
	42 3/16″	24″	3″	**DP7CBBFR4224**	687.	707.	738.	753.	771.	787.	797.	820.	111.
	42 3/16″	30″	3″	**DP7CBBFR4230**	751.	772.	810.	823.	846.	858.	871.	895.	119.
	42 3/16″	36″	3″	**DP7CBBFR4236**	821.	845.	884.	897.	923.	935.	954.	979.	132.
	42 3/16″	42″	3″	**DP7CBBFR4242**	887.	914.	956.	970.	999.	1,017.	1,032.	1,057.	138.
	42 3/16″	48″	3″	**DP7CBBFR4248**	946.	969.	1,019.	1,035.	1,061.	1,082.	1,099.	1,127.	149.
	42 3/16″	60″	3″	**DP7CBBFR4260**	1,068.	1,099.	1,151.	1,172.	1,203.	1,225.	1,245.	1,275.	149.
50″ Beltway Panels with Tile to the Floor	49 1/2″	18″	3″	**DP7CBBFR5018**	631.	649.	680.	692.	708.	721.	732.	751.	88.
	49 1/2″	24″	3″	**DP7CBBFR5024**	719.	738.	772.	788.	808.	822.	834.	855.	112.
	49 1/2″	30″	3″	**DP7CBBFR5030**	780.	798.	835.	852.	871.	888.	903.	926.	116.
	49 1/2″	36″	3″	**DP7CBBFR5036**	840.	863.	904.	921.	946.	960.	975.	1,001.	121.
	49 1/2″	42″	3″	**DP7CBBFR5042**	905.	932.	975.	995.	1,021.	1,038.	1,056.	1,083.	127.
	49 1/2″	48″	3″	**DP7CBBFR5048**	963.	994.	1,040.	1,058.	1,086.	1,105.	1,126.	1,153.	132.
	49 1/2″	60″	3″	**DP7CBBFR5060**	1,091.	1,123.	1,175.	1,196.	1,229.	1,250.	1,271.	1,302.	132.

Dimensions listed under h w c are actual to the nearest 1/16″

Ordering Information

Beltway Panel with Tile to the Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway knockout option
5. Base raceway finish
6. Beltway finish
7. Panel fabric

Order Code

Beltway Panel with Tile to the Floor:

Example:	**DP7CBBFR4218 4/117/K/117/117/B191**
DP7CBB FR4218	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
117	Soft Grey beltway cover finish
B191	Fairfield light fabric

Included with:

Beltway Panel with Tile to the Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway side 2
- Beltway with covers
- Tile to the floor side 1

Options

Beltway Panel with Tile to the Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column.

Tile to Floor Side Option:
Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF".

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Beltway Panels
Tile to the Floor
57″ and 64″ High

description	height	width	depth	pattern number	10	15	20	25	30	35	40	45	Deduct for Monolithic side 1
57″ Beltway Panels with Tile to the Floor	56 13/16″	18″	3″	**DP7CBBFR5718**	$673.	$693.	$723.	$735.	$755.	$768.	$783.	$800.	$88.
	56 13/16″	24″	3″	**DP7CBBFR5724**	758.	783.	819.	833.	853.	868.	883.	905.	112.
	56 13/16″	30″	3″	**DP7CBBFR5730**	820.	843.	882.	897.	922.	935.	953.	975.	116.
	56 13/16″	36″	3″	**DP7CBBFR5736**	897.	923.	966.	983.	1,010.	1,027.	1,044.	1,069.	121.
	56 13/16″	42″	3″	**DP7CBBFR5742**	960.	989.	1,035.	1,054.	1,082.	1,100.	1,119.	1,146.	127.
	56 13/16″	48″	3″	**DP7CBBFR5748**	1,028.	1,057.	1,107.	1,128.	1,158.	1,176.	1,196.	1,228.	132.
	56 13/16″	60″	3″	**DP7CBBFR5760**	1,153.	1,186.	1,244.	1,266.	1,299.	1,320.	1,344.	1,377.	132.
64″ Beltway Panels with Tile to the Floor	64 1/16″	18″	3″	**DP7CBBFR6418**	713.	733.	767.	785.	800.	817.	829.	850.	95.
	64 1/16″	24″	3″	**DP7CBBFR6424**	799.	824.	861.	880.	899.	917.	930.	955.	117.
	64 1/16″	30″	3″	**DP7CBBFR6430**	857.	884.	924.	938.	963.	982.	998.	1,024.	117.
	64 1/16″	36″	3″	**DP7CBBFR6436**	953.	980.	1,025.	1,043.	1,069.	1,088.	1,106.	1,134.	134.
	64 1/16″	42″	3″	**DP7CBBFR6442**	1,017.	1,045.	1,093.	1,112.	1,142.	1,163.	1,180.	1,210.	142.
	64 1/16″	48″	3″	**DP7CBBFR6448**	1,089.	1,123.	1,174.	1,195.	1,228.	1,249.	1,269.	1,301.	154.
	64 1/16″	60″	3″	**DP7CBBFR6460**	1,227.	1,262.	1,320.	1,346.	1,381.	1,404.	1,429.	1,466.	154.

Dimensions listed under h w c are actual to the nearest 1/16″

Ordering Information

Beltway Panel with Tile to the Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway knockout option
5. Base raceway finish
6. Beltway finish
7. Panel fabric

Order Code

Beltway Panel with Tile to the Floor:

Example:	**DP7CBBFR5718 4/117/K/117/117/B191**
DP7CBB FR5718	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
117	Soft Grey beltway cover finish
B191	Fairfield light fabric

Included with:

Beltway Panel with Tile to the Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway
- Beltway with covers
- Tile to the floor side 1

Options

Beltway Panel with Tile to the Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 beltway, change “BB” in pattern number to “MB” and deduct amount in far right column.

Tile to Floor Side Option:
Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change “FR” in pattern number to “RF”.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Beltway Panels
Tile to the Floor
78″ High

description	height	width	depth	pattern number	10	15	20	25	30	35	40	45	Deduct for Monolithci side 1
78″ Beltway Panels with Tile to the Floor	78⅜″	18″	3″	**DP7CBBFR7818**	$887.	$914.	$956.	$970.	$999.	$1,017.	$1,032.	$1,057.	$86.
	78⅜″	24″	3″	**DP7CBBFR7824**	992.	1,020.	1,067.	1,085.	1,112.	1,133.	1,153.	1,179.	99.
	78⅜″	30″	3″	**DP7CBBFR7830**	1,060.	1,091.	1,144.	1,165.	1,195.	1,215.	1,235.	1,268.	102.
	78⅜″	36″	3″	**DP7CBBFR7836**	1,171.	1,206.	1,262.	1,284.	1,320.	1,343.	1,366.	1,399.	119.
	78⅜″	42″	3″	**DP7CBBFR7842**	1,257.	1,294.	1,352.	1,377.	1,417.	1,440.	1,466.	1,500.	122.
	78⅜″	48″	3″	**DP7CBBFR7848**	1,381.	1,423.	1,490.	1,518.	1,556.	1,585.	1,613.	1,652.	151.

Dimensions listed under h w c are actual to the nearest 1/16″

Ordering Information

Beltway Panel with Tile to the Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base raceway knockout option
5. Base raceway finish
6. Beltway finish
7. Panel fabric

Order Code

Beltway Panel with Tile to the Floor:

Example:	**DP7CBBFR7818 4/117/K/117/117/B191**
DP7CBB FR7818	Pattern number
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts both sides
117	Soft Grey base raceway finish
117	Soft Grey beltway cover finish
B191	Fairfield light fabric

Included with:

Beltway Panel with Tile to the Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway
- Beltway with covers
- Tile to the floor side 1

Options

Beltway Panel with Tile to the Floor:

Full View Frame Option:
To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Monolithic Side Option:
For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column.

Tile to Floor Side Option:
Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF".

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Knockout Options:
(K) = Knockouts on raceway side
(N) = No Knockouts

Topway and Full View Panel Frame Assemblies
Specifications

Panel Frame Options
Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels, and may also be specified in CAP.

Dividends Horizon panel frames may be specified separately for "Build-to-Spec" applications. These include when panel inserts are only required on one side or when a beltway is required on one side and tiled inserts are on the other.

Panel frames may be specified with a standard base raceway, an open base or a tile to the floor. Panel frames ship complete with the base components, top cap and universal connection hardware. Raceway cover knockouts are standard with standard base raceway. If not required raceway covers without knockouts may can be specified.

Topway panel frames feature an integral top cable trough, and are used with D1 style stack panels.

Full View frames have no top trough, leaving a larger window opening in the top position. Full view panels frames are designed for use with windows in the top position. They are also required when stacking with D2 style stack frames or DP7 stacking screens.

Topway and full view panel frames are offered in worksurface height, 36", 42", 50", 57", 64" and 78" high.

Three Top Cap Options Available:
- Smooth Radius Plastic
- Radius Metal
- Flat Metal

Top Cap Construction
Smooth radiused plastic top caps are made from extruded plastic. Radius and flat metal top caps are made from steel.

Top Cap Attachment
Full view frames ordered with top caps include top cap attachment clips on the panel frame.

If top caps are ordered separately, top cap attachment clips ship with the top cap and must be field-installed to the panel frame.

Open Position Planner
Open Position Planner allows specifiers to design and order factory assembled panels in virtually any configuration. Open Position Planner is available only through CAP, and is not available in this price list.



Topway Panel Frame



Full View Panel Frame

Panel Base Options
Dividends Horizon panels are available with three base options:
- Base Raceway
- Open Base
- Tile-to-Floor.

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway
Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)
- Duplex location: 9" on center from each end

Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)



Open Base

- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper

Note: Knockouts are standard unless specified without.

Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Note: 24"H inserts are to only be used below beltways.

Monolithic and Tiled Panel Standard Configuration

Worksurface Height

Monolithic
- One worksurface height monolithic insert

36"H Panel Frames

Monolithic
- One 28"H monolithic insert

Tiled
- Two 14"H tiled inserts

42"H Panel Frames

Monolithic
- One 35"H monolithic insert

Tiled
- One 7"H tiled insert
- Two 14"H tiled inserts

Beltway
- One 7"H upper insert
- One 4"H beltway cover
- One 24"H lower insert

50"H Panel Frames



Monolithic
- One 42"H monolithic insert



Tiled
- Three 14"H tiled inserts



Beltway
- One 14"H upper insert
- One 4"H beltway cover
- One 24"H lower insert

57"H Panel Frames

Monolithic
- One 49"H monolithic insert



Tiled
- One 7"H tiled inserts
- Three 14"H tiled inserts



Beltway
- One 7"H tiled insert
- One 14"H tiled insert
- One 4"H beltway cover
- One 24"H lower insert

64"H Panel Frames

Monolithic
- One 56"H monolithic insert

Tiled
- Four 14" H tiled inserts



Beltway
- One 28"H upper insert
- One 4"H beltway cover
- One 24"H lower insert

78"H Panel Frames

Monolithic
- One 70"H monolithic insert

Tiled
- Five 14"H tiled inserts



Beltway
- One 50"H Upper insert
- One 4"H Beltway cover
- One 24"H Lower insert

Note: Insert dimensions are nominal. Inserts are for one side only.

Topway and Full View Panel Frame Assemblies
Worksurface Height, 36″ and 42″ High

description	h	w	d	pattern no.	list
Worksurface Height Panel Frame Assembly Standard Base Raceway 	28 1/2″	15″	3″	**DP7( )RRWH15**	$215.
	28 1/2″	18″	3″	**DP7( )RRWH18**	215.
	28 1/2″	24″	3″	**DP7( )RRWH24**	221.
	28 1/2″	30″	3″	**DP7( )RRWH30**	230.
	28 1/2″	36″	3″	**DP7( )RRWH36**	245.
	28 1/2″	42″	3″	**DP7( )RRWH42**	273.
	28 1/2″	48″	3″	**DP7( )RRWH48**	273.
	28 1/2″	60″	3″	**DP7( )RRWH60**	315.
36″ High Panel Frame Assembly Standard Base Raceway  *(topway and full view shown)*	35 1/8″	15″	3″	**DP7( )RR3615**	215.
	35 1/8″	18″	3″	**DP7( )RR3618**	215.
	35 1/8″	24″	3″	**DP7( )RR3624**	221.
	35 1/8″	30″	3″	**DP7( )RR3630**	230.
	35 1/8″	36″	3″	**DP7( )RR3636**	245.
	35 1/8″	42″	3″	**DP7( )RR3642**	273.
	35 1/8″	48″	3″	**DP7( )RR3648**	273.
	35 1/8″	60″	3″	**DP7( )RR3660**	315.
42″ High Panel Frame Assembly Standard Base Raceway  *(topway and full view shown)*	42 3/16″	15″	3″	**DP7( )RR4215**	193.
	42 3/16″	18″	3″	**DP7( )RR4218**	193.
	42 3/16″	24″	3″	**DP7( )RR4224**	199.
	42 3/16″	30″	3″	**DP7( )RR4230**	215.
	42 3/16″	36″	3″	**DP7( )RR4236**	230.
	42 3/16″	42″	3″	**DP7( )RR4242**	249.
	42 3/16″	48″	3″	**DP7( )RR4248**	261.
	42 3/16″	60″	3″	**DP7( )RR4260**	300.

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel Frame Assembly

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Raceway knockout option
5. Base raceway finish if required

Order Code

Topway Panel Frame Assembly

Example:	**DP7CRR6448 4/117K/117**
DP7CRR 6448	Topway Panel Frame Assemblies with Base Raceway
4	Radius metal topcap
117	Soft Grey top cap finish
K	Raceway knockouts
117	Soft Grey raceway finish

Included with:

Panel Frame Assembly:

- Panel frame
- Top cap (optional)
- Connection hardware
- Base raceway

Note: Worksurface Height panel frame assemblies are not available with plastic top caps.

Note: 15″ wide panels are only available with standard base raceway or tile to floor.

Options

Panel Frame Assembly:

Option:
(C) = Topway Panel Frame
(V) = Full View Panel Frame

Panel Base Options

Open Panel Base Option:
For open panel base, change 'RR' to 'LL'.

Tile to Floor Option:
For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add $32 to list price.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:
(for RR and RF bases only)
(K) = Knockouts on raceway side
(N) = No knockouts

Topway and Full View Panel Frame Assemblies
50″, 57″ and 64″ High

description	h	w	d	pattern no.	list
50″ High Panel Frame Assembly Standard Base Raceway	49 1/2″	15″	3″	**DP7( )RR5015**	$199.
	49 1/2″	18″	3″	**DP7( )RR5018**	199.
	49 1/2″	24″	3″	**DP7( )RR5024**	208.
	49 1/2″	30″	3″	**DP7( )RR5030**	224.
	49 1/2″	36″	3″	**DP7( )RR5036**	236.
	49 1/2″	42″	3″	**DP7( )RR5042**	254.
	49 1/2″	48″	3″	**DP7( )RR5048**	267.
	49 1/2″	60″	3″	**DP7( )RR5060**	290.
57″ High Panel Frame Assembly Standard Base Raceway	56 13/16″	15″	3″	**DP7( )RR5715**	199.
	56 13/16″	18″	3″	**DP7( )RR5718**	199.
	56 13/16″	24″	3″	**DP7( )RR5724**	208.
	56 13/16″	30″	3″	**DP7( )RR5730**	219.
	56 13/16″	36″	3″	**DP7( )RR5736**	234.
	56 13/16″	42″	3″	**DP7( )RR5742**	248.
	56 13/16″	48″	3″	**DP7( )RR5748**	262.
	56 13/16″	60″	3″	**DP7( )RR5760**	277.
64″ High Panel Frame Assembly Standard Base Raceway	64 1/16″	15″	3″	**DP7( )RR6415**	210.
	64 1/16″	18″	3″	**DP7( )RR6418**	210.
	64 1/16″	24″	3″	**DP7( )RR6424**	227.
	64 1/16″	30″	3″	**DP7( )RR6430**	236.
	64 1/16″	36″	3″	**DP7( )RR6436**	251.
	64 1/16″	42″	3″	**DP7( )RR6442**	267.
	64 1/16″	48″	3″	**DP7( )RR6448**	282.
	64 1/16″	60″	3″	**DP7( )RR6460**	327.



(topway and full view shown)



(topway and full view shown)



(topway and full view shown)

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel Frame Assembly

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Raceway knockout option
5. Base raceway finish if required

Order Code

Topway Panel Frame Assembly

Example:	**DP7CRR6448 4/117K/117**
DP7CRR 6448	Topway Panel Frame Assembly with Base Raceway
4	Radius metal topcap
117	Soft Grey top cap finish
K	Raceway knockouts
117	Soft Grey raceway finish

Included with:

Panel Frame Assembly:

- Panel frame
- Top cap (optional)
- Connection hardware
- Base raceway

Note: 15″ wide panels are only available with a standard base raceway or tile to floor.

Options

Panel Frame Assembly:

Option:
(C) = Topway Panel Frame
(V) = Full View Panel Frame

Panel Base Options

Open Panel Base Option:
For open panel base, change 'RR' to 'LL'.

Tile to Floor Option:
For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add $32 to list price.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:
(for RR and RF base only)
(K) = Knockouts on raceway side
(N) = No knockouts

Topway and Full View Panel Frame Assemblies
78″ High

description	h	w	d	pattern no.	list
78″ High Panel Frame Assembly Standard Base Raceway	78 9/16″	15″	3″	**DP7( )RR7815**	$322.
	78 9/16″	18″	3″	**DP7( )RR7818**	322.
	78 9/16″	24″	3″	**DP7( )RR7824**	341.
	78 9/16″	30″	3″	**DP7( )RR7830**	354.
	78 9/16″	36″	3″	**DP7( )RR7836**	381.
	78 9/16″	42″	3″	**DP7( )RR7842**	402.
	78 9/16″	48″	3″	**DP7( )RR7848**	419.

(topway and full view shown)

Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel Frame Assembly

1. Pattern Number
2. Top cap type
3. Top cap trim finish
4. Raceway knockout option
5. Base raceway finish if required

Order Code

Topway Panel Frame Assembly

Example:	**DP7CRR7848 4/117K/117**
DP7CRR 7848	Topway Panel Frame Assembly with Base Raceway
4	Radius metal topcap
117	Soft Grey top cap finish
K	Raceway knockouts
117	Soft Grey raceway finish

Included with:

Panel Frame Assembly:

- Panel frame
- Top cap (optional)
- Connection hardware
- Base raceway

Note: 15″ wide panels are only available with a standard base raceway or tile to floor.

Options

Panel Frame Assembly:

Option:
(C) = Topway Panel Frame
(V) = Full View Panel Frame

Panel Base Options

Open Panel Base Option:
For open panel base, change 'RR' to 'LL'.

Tile to Floor Option:
For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add $31 to list price.

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3 paint grades
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Base Raceway Knockout Options:
(for RR and RF base only)
(K) = Knockouts on raceway side
(N) = No knockouts

This page intentionally left blank

Stack Frames
Specifications

Stack Frames
Dividends Horizon stack frames provide the flexibility to increase the overall height of a standard Dividends Horizon panel.

Stack frames are available in three panel heights, 14", 21" and 28" all capable of attaching to any panel height. Maximum stacking height above the “base” standard panel is 28". This can be accomplished with one 28" high stack panel or by stacking two 14" high panels on each other.

21" stack panel frames may be attached to 42" standard Dividends Horizon panels allowing the overall panel height to be 64" or to 57" panels for an overall height of 78 .

The 28" high stack panel frame is prepunched to accept tile insert support rails to provide a tiled look if required.

Stack Frame Options
Dividends Horizon offers two stack panel frame options, which are selected depending on customer’s aesthetic and functional needs.

D1 Style Stack Frame Planning
D1 style stack frames feature a D1 style painted aluminum horizontal trim at the bottom of each stack frame. D1 style stack frames mount on top of Dividends Horizon topway panel frames only. D1 style stack panels are load bearing on the first tier only.

Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway to be able to accept the second tier stack frame.

D2 Style Stack Frame Planning
D2 style stack frames feature a D2 style black recessed horizontal reveal at the bottom of each stack frame. D2 style stack frames mount on top of Dividends Horizon DP7V full view panel frames only. D2 style stack frames are load bearing on the first or second tier, and are designed to align overhead storage components hung at 64" with overhead components hung off 64" full height panels. Components hung on stack panels at 50" or 57" will not align with components hung off 50" or 57" full height panels.

D2 style stack frames also have the option to be used with tiled or monolithic tiles on one or both side of the base/stack panel assembly. See options on panel pricing page.

Note: The single and double pane window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with single or double pane window insert kits.

Note: D2 style stack frames are not compatible with slatwall tiles.

Stack Panel Dimensions
- Widths: 18", 24", 30", 36", 42", and 48"
- Heights: 14", 21" and 28"
- Thickness: 3"

Construction
The stack panel frame is an all-welded steel construction.

- Topway: 22-gauge roll-formed steel (if applicable)
- Vertical channels: 16-gauge roll-formed steel
- Horizontal rails: 16-gauge steel tubing

Panel Trim
When stack panels are installed, the “base” standard panel’s top cap is utilized by attaching to the top of the stack panel.

Panel end trim is ordered separately from the stack panel. To specify panel end trim for the end of a panel run, simply add the stack panel and base panel frame height (i.e, a 50" high base panel frame with one 14 high stack panel will require a 64" high panel end trim kit).

In a high-to-low panel-to-panel application where stack panels are used, simply deduct the panel height difference between the two panels to determine size of the high-to-low panel end trim required.

Post Trim
Post trim covers must match the overall height of the “base” standard post and stack post.

Stack Post (Same-height panels)
When two or more stack panels are connected together in a 2-way “L”, 3-way “T” or a 4-way “X” condition, and all the panel heights are of the same height, a stack panel post kit may be used.

The stack post kit attaches to the top of a base universal post and is available in a 14" or 28" height and ships with connecting hardware.

Stack Post (Multi-height panels)
When stack panels are used in a high-to-low panel-to-post applications, high-to-low post trim must be ordered separately.

Note: A universal post must match the height of the tallest base standard panel being connected.

Construction
Posts are 3" square extruded aluminum construction.



Stack Frame



Stack Post (Same-Height Panels)

Stack Frames
D1 Style With External Reveal
(For Use With Topway Panels Only)

description	h	w	d	pattern no.	with topway	full view (without topway)
28″ High Stack Panel Frame Only (full view shown)	29 1/4″	18″	3″	**DP2S(T/N)F 2818**	$168.	$201.
	29 1/4″	24″	3″	**DP2S(T/N)F 2824**	171.	212.
	29 1/4″	30″	3″	**DP2S(T/N)F 2830**	186.	225.
	29 1/4″	36″	3″	**DP2S(T/N)F 2836**	209.	243.
	29 1/4″	42″	3″	**DP2S(T/N)F 2842**	224.	262.
	29 1/4″	48″	3″	**DP2S(T/N)F 2848**	236.	271.
21″ High Stack Panel Frame Only	21 7/8″	18″	3″	**DP2STF 2118**	172.	n/a
	21 7/8″	24″	3″	**DP2STF 2124**	184.	n/a
	21 7/8″	30″	3″	**DP2STF 2130**	199.	n/a
	21 7/8″	36″	3″	**DP2STF 2136**	217.	n/a
	21 7/8″	42″	3″	**DP2STF 2142**	239.	n/a
	21 7/8″	48″	3″	**DP2STF 2148**	249.	n/a
14″ High Stack Panel, load bearing	14″	18″	3″	**DP2 STFL1418**	140.	n/a
	14″	24″	3″	**DP2 STFL1424**	145.	n/a
	14″	30″	3″	**DP2 STFL1430**	168.	n/a
	14″	36″	3″	**DP2 STFL1436**	185.	n/a
	14″	42″	3″	**DP2 STFL1442**	206.	n/a
	14″	48″	3″	**DP2 STFL1448**	220.	n/a
14″ High Stack Panel non-load bearing	14″	18″	3″	**DP2S(T/N)F 1418**	140.	168.
	14″	24″	3″	**DP2S(T/N)F 1424**	145.	171.
	14″	30″	3″	**DP2S(T/N)F 1430**	168.	186.
	14″	36″	3″	**DP2S(T/N)F 1436**	185.	209.
	14″	42″	3″	**DP2S(T/N)F 1442**	206.	224.
	14″	48″	3″	**DP2S(T/N)F 1448**	220.	236.

NOTE: D1 Stack Frames may be used with Topway Panels only.

Ordering Information

Stack Panel Frame

1. Pattern Number
2. Trim Finish

Order Code

Stack Panel Frame

Example:	**DP2STF 1448, 113**
DP1STF	Pattern Number
1448	
113	Dark grey paint finish

Stack Panel Post

Example:	**DP2ASPO 14**
DP2ASPO	Pattern Number
14	

Included with:

Stack Panel Frame

Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway trough to be able to accept the second tier stack frame.

Options

Stack Panel Frame
Stack frame option:
(T) = with topway
(N) = without topway

Note: 21″ stack panel frame not available without a topway.

Note: D1 Stack Frames are load bearing on first tier only.

Stack Frames
D2 Style With Recessed Reveal
(For Use With DP7 Full View Panels Only)

description	w	h	d	pattern no.	list
14″ High Dividends Stack Frame	18″	14 5/8″	3″	**DPS7V1418( )**	$212.
	24″	14 5/8″	3″	**DPS7V1424( )**	215.
	30″	14 5/8″	3″	**DPS7V1430( )**	234.
	36″	14 5/8″	3″	**DPS7V1436( )**	254.
	42″	14 5/8″	3″	**DPS7V1442( )**	262.
	48″	14 5/8″	3″	**DPS7V1448( )**	270.
21″ High Dividends Stack Frame	18″	21 7/8″	3″	**DPS7V2118( )**	246.
	24″	21 7/8″	3″	**DPS7V2124( )**	259.
	30″	21 7/8″	3″	**DPS7V2130( )**	271.
	36″	21 7/8″	3″	**DPS7V2136( )**	288.
	42″	21 7/8″	3″	**DPS7V2142( )**	298.
	48″	21 7/8″	3″	**DPS7V2148( )**	307.
28″ High Dividends Stack Frame	18″	29 1/4″	3″	**DPS7V2818( )**	235.
	24″	29 1/4″	3″	**DPS7V2824( )**	248.
	30″	29 1/4″	3″	**DPS7V2830( )**	263.
	36″	29 1/4″	3″	**DPS7V2836( )**	284.
	42″	29 1/4″	3″	**DPS7V2842( )**	298.
	48″	29 1/4″	3″	**DPS7V2848( )**	308.

NOTE: D2 Stack Frames may be used with DP7 Full View Panels only.

Ordering Information

Stack Frames:

1. Pattern Number
2. Tile Support Configuration

Order Code

Stack Panel Frame Assembly

Example:	**DPS7V1418TT**
DPS7	Stack Panel Frame
V	Full View
14	Height
18	Width
TT	Segmented Tile Supports Both Side

Included with:

Stack Panel Frame:

- Stack Frame

Note: Slatwall tiles, single pane and double pane window kits cannot be used with D2 stack frames.

Note: D2 Stack Frames are load bearing on first and second tier.

Options

Tile Options/Pattern Number Suffix:

(TT) = Tile support located at the base of stacker to support segmented tiles on both sides of a panel.

(TM) = Tile support located at the base of the stacker to support segmented tiles on one side and a monolithic tile on the other side of the panel.

(MM) = Monolithic tiles on both sides of the panel.

This page intentionally left blank

Monolithic Panel Fabric Inserts
Specifications

Monolithic Fabric Inserts
Dividends Horizon monolithic inserts are available by component for use with panel frames or wall mount tracks for “Build-to-Spec” applications. These applications include when inserts are only required on one panel side, when a different fabric is required on each panel side, or when wall mount tracks are being used.

Tile to floor option available for worksurface height, 36", 42", 50", 57", 64" and 78" panel heights.

Monolithic Fabric Insert Construction
Fabric laminated with adhesive, heat-cured to $^{7}/_{16}$" thick tackable acoustical board.

Monolithic Fabric Insert Ratings
Noise Reduction Coefficient (NRC) rating: .70
Sound Transmission Class (STC) rating: 11

The materials in Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furniture.

Monolithic Fabric Insert Attachment
Panel inserts flex to attach to the troughs in the upper and lower horizontal panel frame supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to panel inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: If additional mid-span support for monolithic panel inserts is required, a beltway cable tray can be installed.

Note: Insert dimensions are nominal. Inserts are for one side only.

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Fabric Insert





Monolithic Fabric Insert Attachment

Monolithic Fabric Insert Configurations

Worksurface Height
- One worksurface height monolithic insert

36"H Panel Frames
- One 28"H monolithic insert

42"H Panel Frames
- One 35"H monolithic insert



50"H Panel Frames
- One 42"H monolithic insert

57"H Panel Frames
- One 49"H monolithic insert

64"H Panel Frames
- One 56"H monolithic insert

78"H Panel Frames
- One 70"H monolithic insert

Monolithic Panel Fabric Inserts
For Worksurface Height, 36″, 42″ and 50″ High Panel Frames

description	w*	w	h	d	pattern no.	grade 10	15	20	25	30	35	40	45
Worksurface Height Individual Monolithic Fabric Insert (For worksurface height Panel Frame only)	15″	14 5/8″	22 1/2″	3″	**DP1SOWH15**	$89.	$97.	$102.	$109.	$113.	$117.	$123.	$127.
	18″	17 5/8″	22 1/2″	3″	**DP1SOWH18**	89.	97.	102.	109.	113.	117.	123.	127.
	24″	23 5/8″	22 1/2″	3″	**DP1SOWH24**	111.	115.	127.	133.	138.	141.	146.	158.
	30″	29 5/8″	22 1/2″	3″	**DP1SOWH30**	121.	127.	138.	144.	150.	158.	162.	171.
	36″	35 5/8″	22 1/2″	3″	**DP1SOWH36**	132.	138.	150.	159.	168.	174.	178.	184.
	42″	41 5/8″	22 1/2″	3″	**DP1SOWH42**	137.	143.	152.	160.	170.	175.	182.	190.
	48″	47 5/8″	22 1/2″	3″	**DP1SOWH48**	143.	150.	162.	171.	176.	183.	193.	203.
	60″	59 5/8″	22 1/2″	3″	**DP1SOWH60**	163.	168.	175.	178.	184.	187.	197.	208.
28″ High Individual Monolithic Fabric Insert (For 36″H Panel Frame)	15″	14 5/8″	29″	7/16″	**DP1SO2815**	93.	97.	100.	107.	109.	114.	119.	124.
	18″	17 5/8″	29″	7/16″	**DP1SO2818**	93.	97.	100.	107.	109.	114.	119.	124.
	24″	23 5/8″	29″	7/16″	**DP1SO2824**	108.	114.	124.	129.	135.	138.	142.	152.
	30″	29 5/8″	29″	7/16″	**DP1SO2830**	118.	124.	135.	140.	146.	152.	157.	166.
	36″	35 5/8″	29″	7/16″	**DP1SO2836**	128.	135.	146.	153.	164.	170.	174.	179.
	42″	41 5/8″	29″	7/16″	**DP1SO2842**	133.	139.	147.	156.	165.	171.	177.	184.
	48″	47 5/8″	29″	7/16″	**DP1SO2848**	139.	146.	157.	166.	172.	178.	185.	199.
	60″	59 5/8″	29″	7/16″	**DP1SO2860**	164.	168.	176.	179.	183.	187.	193.	197.
35″ High Individual Monolithic Fabric Insert (For 42″H Panel Frame)	15″	14 5/8″	36 3/8″	7/16″	**DP1SO4215**	103.	109.	118.	125.	130.	132.	138.	142.
	18″	17 5/8″	36 3/8″	7/16″	**DP1SO4218**	103.	109.	118.	125.	130.	132.	138.	142.
	24″	23 5/8″	36 3/8″	7/16″	**DP1SO4224**	118.	124.	133.	138.	144.	150.	153.	161.
	30″	29 5/8″	36 3/8″	7/16″	**DP1SO4230**	130.	138.	150.	153.	164.	167.	171.	177.
	36″	35 5/8″	36 3/8″	7/16″	**DP1SO4236**	144.	152.	166.	171.	173.	183.	187.	197.
	42″	41 5/8″	36 3/8″	7/16″	**DP1SO4242**	165.	171.	184.	193.	200.	205.	210.	219.
	48″	47 5/8″	36 3/8″	7/16″	**DP1SO4248**	173.	180.	199.	203.	213.	219.	225.	234.
	60″	59 5/8″	36 3/8″	7/16″	**DP1SO4260**	180.	185.	196.	200.	204.	207.	210.	216.
42″ High Individual Monolithic Fabric Insert (For 50″H Panel Frame)	15″	14 5/8″	43 11/16″	7/16″	**DP1SO5015**	115.	121.	130.	133.	140.	144.	150.	156.
	18″	17 5/8″	43 11/16″	7/16″	**DP1SO5018**	115.	121.	130.	133.	140.	144.	150.	156.
	24″	23 5/8″	43 11/16″	7/16″	**DP1SO5024**	128.	135.	146.	150.	156.	164.	167.	173.
	30″	29 5/8″	43 11/16″	7/16″	**DP1SO5030**	144.	152.	166.	171.	177.	183.	187.	196.
	36″	35 5/8″	43 11/16″	7/16″	**DP1SO5036**	166.	173.	185.	193.	200.	204.	212.	220.
	42″	41 5/8″	43 11/16″	7/16″	**DP1SO5042**	183.	194.	208.	213.	222.	228.	235.	244.
	48″	47 5/8″	43 11/16″	7/16″	**DP1SO5048**	202.	213.	227.	235.	244.	250.	256.	268.
	60″	59 5/8″	43 11/16″	7/16″	**DP1SO5060**	232.	240.	251.	255.	263.	267.	271.	279.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Monolithic Fabric Inserts

Example:	**DP1 SO6442, W351-3**
DP1 SO6442	Pattern Number
W351-3	Foundation Corn Silk Fabric

Included with:

Monolithic Fabric Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Fabric Inserts

Tile to Floor Option:
To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add $10 to the list price.

Note: Tile to floor option available for Worksurface Heights, 36″, 42″, 50″, 57″, 64″ and 78″ panel heights.

Monolithic Panel Fabric Inserts
For 57", 64" and 78" High Panel Frames

description	w*	w	h	d	pattern no.	grade 10	15	20	25	30	35	40	45
49″ High Individual Monolithic Fabric Insert (For 57″H Panel Frame)	15″	14 5/8″	50 1/16″	7/16″	**DP1SO5715**	$127.	$130.	$138.	$140.	$144.	$146.	$149.	$152.
	18″	17 5/8″	50 1/16″	7/16″	**DP1SO5718**	127.	130.	138.	140.	144.	146.	149.	152.
	24″	23 5/8″	50 1/16″	7/16″	**DP1SO5724**	141.	144.	151.	155.	159.	163.	166.	170.
	30″	29 5/8″	50 1/16″	7/16″	**DP1SO5730**	163.	167.	175.	177.	181.	185.	188.	195.
	36″	35 5/8″	50 1/16″	7/16″	**DP1SO5736**	181.	187.	198.	201.	205.	209.	213.	219.
	42″	41 5/8″	50 1/16″	7/16″	**DP1SO5742**	201.	206.	216.	220.	226.	230.	235.	241.
	48″	47 5/8″	50 1/16″	7/16″	**DP1SO5748**	219.	225.	234.	241.	246.	251.	254.	263.
	60″	59 5/8″	50 1/16″	7/16″	**DP1SO5760**	252.	260.	271.	278.	285.	291.	296.	302.
56″ High Individual Monolithic Fabric Insert (For 64″H Panel Frame)	15″	14 5/8″	58 1/4″	7/16″	**DP1SO6415**	140.	147.	161.	166.	172.	177.	180.	188.
	18″	17 5/8″	58 1/4″	7/16″	**DP1SO6418**	140.	147.	161.	166.	172.	177.	180.	188.
	24″	23 5/8″	58 1/4″	7/16″	**DP1SO6424**	152.	161.	174.	178.	185.	194.	197.	205.
	30″	29 5/8″	58 1/4″	7/16″	**DP1SO6430**	178.	187.	202.	209.	217.	222.	228.	238.
	36″	35 5/8″	58 1/4″	7/16″	**DP1SO6436**	199.	209.	225.	229.	241.	245.	252.	262.
	42″	41 5/8″	58 1/4″	7/16″	**DP1SO6442**	216.	226.	243.	250.	260.	265.	273.	285.
	48″	47 5/8″	58 1/4″	7/16″	**DP1SO6448**	236.	245.	264.	272.	284.	291.	298.	309.
	60″	59 5/8″	58 1/4″	7/16″	**DP1SO6460**	244.	251.	264.	268.	274.	281.	287.	294.
70″ High Individual Monolithic Fabric Insert (For 78″H Panel Frame)	15″	14 5/8″	72 7/8″	7/16″	**DP1SO7815**	164.	167.	174.	177.	183.	185.	188.	196.
	18″	17 5/8″	72 7/8″	7/16″	**DP1SO7818**	164.	167.	174.	177.	183.	185.	188.	196.
	24″	23 5/8″	72 7/8″	7/16″	**DP1SO7824**	193.	197.	205.	209.	214.	219.	222.	228.
	30″	29 5/8″	72 7/8″	7/16″	**DP1SO7830**	216.	222.	234.	238.	244.	249.	252.	259.
	36″	35 5/8″	72 7/8″	7/16″	**DP1SO7836**	241.	246.	259.	264.	271.	274.	283.	289.
	42″	41 5/8″	72 7/8″	7/16″	**DP1SO7842**	268.	277.	290.	296.	302.	309.	315.	323.
	48″	47 5/8″	72 7/8″	7/16″	**DP1SO7848**	294.	302.	319.	324.	333.	340.	344.	351.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Monolithic Fabric Inserts

Example:	**DP1 SO6442, W351-3**
DP1 SO6442	Pattern Number
W351-3	Foundation Corn Silk Fabric

Included with:

Monolithic Fabric Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Fabric Inserts

Tile to Floor Option:
To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add $10 to the list price.

Note: Tile to floor option available for Worksurface Heights, 36″, 42″, 50″ 57″, 64″ and 78″ panel heights.

This page intentionally left blank

Monolithic Laminate Inserts
Specifications

Monolithic Laminate Inserts
Dividends Horizon monolithic laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Monolithic tile sizes are for use with frames from worksurface height to 57", and widths of up to 48" in tile to raceway, open base and tile to floor applications. Monolithic laminate tiles may also be wall mounted using wall mount tracks. Monolithic laminate inserts with matching surface and edge are available in the following finishes:

(114) Folkstone Grey
(117) Soft Grey
(118) Bright White
(119) Pumice

Legacy finishes are not available.

Monolithic Laminate Insert Construction
Surface material: laminate on front and back surface

Edge material: .5mm edgeband

Core material: particle board

Thickness: 7/16 inches

Monolithic Laminate Insert Attachment
Laminate tiles are installed on one side or both sides of a panel frame, or attach to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Note: Insert dimensions are nominal. Insert configurations shown below are for one side only.

Note: Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP).

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Insert



Monolithic Laminate Insert Configurations

Worksurface Height
- One worksurface height monolithic insert

36"H Panel Frames
- One 28"H monolithic insert

42"H Panel Frames
- One 35"H monolithic insert



50"H Panel Frames
- One 42"H monolithic insert

57"H Panel Frames
- One 49"H monolithic insert

Monolithic Laminate Inserts
For Worksurface Height, 36″ and 42″ High Panel Frames Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
Worksurface Height Individual Monolithic Laminate Insert Base Raceway or Open Base (For worksurface height panel frame only)	15″	14 5/8″	22 1/2″	7/16″	**DP3L1WH15**	$160.
	18″	17 5/8″	22 1/2″	7/16″	**DP3L1WH18**	169.
	24″	23 5/8″	22 1/2″	7/16″	**DP3L1WH24**	194.
	30″	29 5/8″	22 1/2″	7/16″	**DP3L1WH30**	226.
	36″	35 5/8″	22 1/2″	7/16″	**DP3L1WH36**	244.
	42″	41 5/8″	22 1/2″	7/16″	**DP3L1WH42**	291.
	48″	47 5/8″	22 1/2″	7/16″	**DP3L1WH48**	296.
28″ High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 36″H Panel Frame)	15″	14 5/8″	29″	7/16″	**DP3L12815**	160.
	18″	17 5/8″	29″	7/16″	**DP3L12818**	169.
	24″	23 5/8″	29″	7/16″	**DP3L12824**	194.
	30″	29 5/8″	29″	7/16″	**DP3L12830**	226.
	36″	35 5/8″	29″	7/16″	**DP3L12836**	244.
	42″	41 5/8″	29″	7/16″	**DP3L12842**	291.
	48″	47 5/8″	29″	7/16″	**DP3L12848**	296.
35″ High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 42″H Panel Frame)	15″	14 5/8″	36 3/8″	7/16″	**DP3L14215**	193.
	18″	17 5/8″	36 3/8″	7/16″	**DP3L14218**	211.
	24″	23 5/8″	36 3/8″	7/16″	**DP3L14224**	241.
	30″	29 5/8″	36 3/8″	7/16″	**DP3L14230**	288.
	36″	35 5/8″	36 3/8″	7/16″	**DP3L14236**	391.
	42″	41 5/8″	36 3/8″	7/16″	**DP3L14242**	412.
	48″	47 5/8″	36 3/8″	7/16″	**DP3L14248**	416.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example:	**DP3L14224**
DP3L1 4224	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Laminate Inserts
Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

Monolithic Laminate Inserts
For Worksurface Height, 36″ and 42″ High Panel Frames
Tile To Floor

description	w *	w	d	pattern no.	List
Worksurface Height Individual Monolithic Laminate Insert Tile To Floor (For worksurface height panel frame only)	15″	14 5/8″	7/16″	**DP3L1WH15F**	$160.
	18″	17 5/8″	7/16″	**DP3L1WH18F**	169.
	24″	23 5/8″	7/16″	**DP3L1WH24F**	194.
	30″	29 5/8″	7/16″	**DP3L1WH30F**	226.
	36″	35 5/8″	7/16″	**DP3L1WH36F**	244.
	42″	41 5/8″	7/16″	**DP3L1WH42F**	291.
	48″	47 5/8″	7/16″	**DP3L1WH48F**	296.
36″ High Individual Monolithic Laminate Insert Tile To Floor (For 36″H panel frame)	15″	14 5/8″	7/16″	**DP3L12815F**	160.
	18″	17 5/8″	7/16″	**DP3L12818F**	169.
	24″	23 5/8″	7/16″	**DP3L12824F**	194.
	30″	29 5/8″	7/16″	**DP3L12830F**	226.
	36″	35 5/8″	7/16″	**DP3L12836F**	244.
	42″	41 5/8″	7/16″	**DP3L12842F**	291.
	48″	47 5/8″	7/16″	**DP3L12848F**	296.
42″ High Individual Monolithic Laminate Insert Tile To Floor (For 42″H panel frame)	15″	14 5/8″	7/16″	**DP3L14215F**	196.
	18″	17 5/8″	7/16″	**DP3L14218F**	226.
	24″	23 5/8″	7/16″	**DP3L14224F**	252.
	30″	29 5/8″	7/16″	**DP3L14230F**	291.
	36″	35 5/8″	7/16″	**DP3L14236F**	394.
	42″	41 5/8″	7/16″	**DP3L14242F**	416.
	48″	47 5/8″	7/16″	**DP3L14248F**	419.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example:	**DP3L14224F**
DP3L1 4224F	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Laminate Inserts
Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

Monolithic Laminate Inserts
For 50" and 57" High Panel Frames
Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
42″ High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 50″H Panel Frame)	15″	14 5/8″	43 11/16″	7/16″	**DP3L15015**	$198.
	18″	17 5/8″	43 11/16″	7/16″	**DP3L15018**	228.
	24″	23 5/8″	43 11/16″	7/16″	**DP3L15024**	254.
	30″	29 5/8″	43 11/16″	7/16″	**DP3L15030**	294.
	36″	35 5/8″	43 11/16″	7/16″	**DP3L15036**	396.
	42″	41 5/8″	43 11/16″	7/16″	**DP3L15042**	417.
	48″	47 5/8″	43 11/16″	7/16″	**DP3L15048**	421.
49″ High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 57″H Panel Frame)	15″	14 5/8″	50 1/16″	7/16″	**DP3L15715**	230.
	18″	17 5/8″	50 1/16″	7/16″	**DP3L15718**	247.
	24″	23 5/8″	50 1/16″	7/16″	**DP3L15724**	295.
	30″	29 5/8″	50 1/16″	7/16″	**DP3L15730**	370.
	36″	35 5/8″	50 1/16″	7/16″	**DP3L15736**	401.
	42″	41 5/8″	50 1/16″	7/16″	**DP3L15742**	491.
	48″	47 5/8″	50 1/16″	7/16″	**DP3L15748**	495.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example:	**DP3L15024**
DP3L1 5024	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Laminate Inserts
Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

Monolithic Laminate Inserts
For 50″ and 57″ High Panel Frames
Tile To Floor

description	w *	w	d	pattern no.	List
50″ High Individual Monolithic Laminate Insert Tile To Floor (For 50″H panel frame)	15″	14 5/8″	7/16″	**DP3L15015F**	$229.
	18″	17 5/8″	7/16″	**DP3L15018F**	245.
	24″	23 5/8″	7/16″	**DP3L15024F**	293.
	30″	29 5/8″	7/16″	**DP3L15030F**	368.
	36″	35 5/8″	7/16″	**DP3L15036F**	399.
	42″	41 5/8″	7/16″	**DP3L15042F**	488.
	48″	47 5/8″	7/16″	**DP3L15048F**	492.
57″ High Individual Monolithic Laminate Insert Tile To Floor (for 57″H panel frame)	15″	14 5/8″	7/16″	**DP3L15715F**	234.
	18″	17 5/8″	7/16″	**DP3L15718F**	250.
	24″	23 5/8″	7/16″	**DP3L15724F**	298.
	30″	29 5/8″	7/16″	**DP3L15730F**	373.
	36″	35 5/8″	7/16″	**DP3L15736F**	405.
	42″	41 5/8″	7/16″	**DP3L15742F**	493.
	48″	47 5/8″	7/16″	**DP3L15748F**	497.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example:	**DP3L15024F**
DP3L1 5024F	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- **Attachment clips**

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Options

Monolithic Laminate Inserts
Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

This page intentionally left blank

Tiled Fabric Inserts
Specifications

Tiled Inserts
Dividends Horizon tiled inserts are available by component for use with panel frames or wall mount tracks for "Build-to-Spec" applications. These applications include when inserts are only required on one panel side, when fabrics are mixed tile-to-tile or side-to-side, or when wall mount tracks are being used.

Tiled inserts are also included in "Preconfigured" tiled panel assemblies.

Tiled Insert Construction
Fabric laminated with web adhesive, heat-cured to $^{7}/_{16}$" thick tackable acoustical board.

Tiled Insert Supports
All Dividends Horizon panel frames and wall mount tracks are pre-punched to accept tiled panel insert supports which span horizontally across the panel frame.

Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets
D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.

Tiled Insert Attachment
Tiled inserts attach to the troughs in the horizontal panel frame and tiled insert supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: When attaching cantilevers to tiled panels, they can only be hung at the 28 $^{1}/_{2}$" worksurface height.

Note: Insert dimensions are nominal. Inserts and tiled supports are for one side only.

Note: Overheads can only be attached to the uppermost position of tiled panels. On 78" H panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.



D1 External Reveal Tile Supports

D2 Recessed Reveal Tile Supports

Tiled Insert Configurations



36"H Panels
- Two 14"H tiled inserts
- One tile support

42"H Panels
- One 7"H tiled insert
- Two 14"H tiled inserts
- Two tile supports

50"H Panels
- Three 14"H tiled inserts
- Two tile supports

57"H Panels
- One 7"H tiled insert
- Three 14"H tiled inserts
- Three tile supports



64"H Panels
- Four 14"H tiled inserts
- Three tile supports

78"H Panels
- Five 14"H tiled inserts
- Four tile supports

Tiled Insert Attachment (D1 Style)



Tiled Insert Attachment (D2 Style)



Tiled Fabric Inserts
7″, 10″ and 14″ High

description	w *	w	h	d	pattern no.	grade 10	15	20	25	30	35	40	45
7″ High Individual Tiled Fabric Insert	15″	14 5/8″	7 3/16″	7/16″	**DP1SO715**	$41.	$44.	$48.	$53.	$58.	$59.	$61.	$66.
	18″	17 5/8″	7 3/16″	7/16″	**DP1SO718**	41.	44.	48.	53.	58.	59.	61.	66.
	24″	23 5/8″	7 3/16″	7/16″	**DP1SO724**	44.	47.	56.	58.	60.	64.	65.	67.
	30″	29 5/8″	7 3/16″	7/16″	**DP1SO730**	50.	56.	61.	64.	67.	69.	72.	76.
	36″	35 5/8″	7 3/16″	7/16″	**DP1SO736**	58.	60.	67.	69.	72.	73.	76.	79.
	42″	41 5/8″	7 3/16″	7/16″	**DP1SO742**	61.	66.	71.	73.	77.	79.	81.	87.
	48″	47 5/8″	7 3/16″	7/16″	**DP1SO748**	66.	70.	74.	77.	81.	84.	93.	96.
	60″	59 5/8″	7 3/16″	7/16″	**DP1SO760**	72.	74.	78.	79.	82.	83.	84.	87.
10″ High Individual Tiled Fabric Insert	15″	14 5/8″	10 7/8″	7/16″	**DP1SO1015**	59.	61.	66.	67.	70.	72.	73.	76.
	18″	17 5/8″	10 7/8″	7/16″	**DP1SO1018**	59.	61.	66.	67.	70.	72.	73.	76.
	24″	23 5/8″	10 7/8″	7/16″	**DP1SO1024**	64.	66.	71.	72.	74.	77.	79.	83.
	30″	29 5/8″	10 7/8″	7/16″	**DP1SO1030**	66.	69.	73.	76.	78.	81.	83.	87.
	36″	35 5/8″	10 7/8″	7/16″	**DP1SO1036**	70.	73.	78.	79.	84.	87.	95.	96.
	42″	41 5/8″	10 7/8″	7/16″	**DP1SO1042**	73.	76.	83.	84.	93.	96.	98.	100.
	48″	47 5/8″	10 7/8″	7/16″	**DP1SO1048**	78.	79.	89.	95.	98.	99.	101.	108.
	60″	59 5/8″	10 7/8″	7/16″	**DP1SO1060**	83.	85.	90.	91.	94.	95.	97.	99.
14″ High Individual Tiled Fabric Insert	15″	14 5/8″	14 3/16″	7/16″	**DP1SO1415**	59.	61.	66.	67.	70.	72.	73.	76.
	18″	17 5/8″	14 3/16″	7/16″	**DP1SO1418**	59.	61.	66.	67.	70.	72.	73.	76.
	24″	23 5/8″	14 3/16″	7/16″	**DP1SO1424**	64.	66.	71.	72.	74.	77.	79.	83.
	30″	29 5/8″	14 3/16″	7/16″	**DP1SO1430**	66.	69.	73.	76.	78.	81.	83.	87.
	36″	35 5/8″	14 3/16″	7/16″	**DP1SO1436**	70.	73.	78.	79.	84.	87.	95.	96.
	42″	41 5/8″	14 3/16″	7/16″	**DP1SO1442**	73.	76.	83.	84.	93.	96.	98.	100.
	48″	47 5/8″	14 3/16″	7/16″	**DP1SO1448**	78.	79.	89.	95.	98.	99.	101.	108.
	60″	59 5/8″	14″ 3/16″	7/16″	**DP1SO1460**	83.	85.	90.	91.	94.	95.	97.	99.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Tiled Inserts

1. Pattern Number
2. Fabric

Order Code

Tiled Inserts

Example:	**DP1 SO1436, W234-5**
DP1 SO1436	Pattern Number
W234-5	Peano Sand fabric

Included with:

Tiled Inserts

- **Attachment clips**

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).

Options

Tiled Inserts

Tile to Floor Option:
To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add $10 to the list price.

Note: Tile to floor option available for 14″ and 28″ High inserts.

Tiled Fabric Inserts
21″ and 28″ High

description	w *	w	h	d	pattern no.	grade 10	15	20	25	30	35	40	45
21″ High Individual Tiled Fabric Insert	15″	14 5/8″	21 3/16″	7/16″	**DP1SO2115**	$85.	$94.	$99.	$103.	$109.	$114.	$118.	$123.
	18″	17 5/8″	21 3/16″	7/16″	**DP1SO2118**	85.	94.	99.	103.	109.	114.	118.	123.
	24″	23 5/8″	21 3/16″	7/16″	**DP1SO2124**	107.	111.	123.	128.	133.	136.	141.	151.
	30″	29 5/8″	21 3/16″	7/16″	**DP1SO2130**	116.	123.	133.	139.	144.	151.	156.	165.
	36″	35 5/8″	21 3/16″	7/16″	**DP1SO2136**	127.	133.	144.	152.	161.	168.	173.	178.
	42″	41 5/8″	21 3/16″	7/16″	**DP1SO2142**	132.	138.	146.	153.	164.	170.	176.	183.
	48″	47 5/8″	21 3/16″	7/16″	**DP1SO2148**	138.	144.	156.	165.	171.	177.	184.	197.
	60″	59 5/8″	21 3/16″	7/16″	**DP1SO2160**	151.	156.	164.	167.	172.	175.	177.	181.
28″ High Individual Tiled Fabric Insert	15″	14 5/8″	29″	7/16″	**DP1SO2815**	93.	97.	100.	107.	109.	114.	119.	124.
	18″	17 5/8″	29″	7/16″	**DP1SO2818**	93.	97.	100.	107.	109.	114.	119.	124.
	24″	23 5/8″	29″	7/16″	**DP1SO2824**	108.	114.	124.	129.	135.	138.	142.	152.
	30″	29 5/8″	29″	7/16″	**DP1SO2830**	118.	124.	135.	140.	146.	152.	157.	166.
	36″	35 5/8″	29″	7/16″	**DP1SO2836**	128.	135.	146.	153.	164.	170.	174.	179.
	42″	42 5/8″	29″	7/16″	**DP1SO2842**	133.	139.	147.	156.	165.	171.	177.	184.
	48″	47 5/8″	29″	7/16″	**DP1SO2848**	139.	146.	157.	166.	172.	178.	185.	199.
	60″	59 5/8″	29″	7/16″	**DP1SO2860**	164.	168.	176.	179.	183.	187.	193.	197.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Tiled Inserts

1. Pattern Number
2. Fabric

Order Code

Tiled Inserts

Example:	**DP1 SO1436, W234-5**
DP1 SO1436	Pattern Number
W234-5	Peano Sand fabric

Included With:

Tiled Inserts

- **Attachment clips**

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).

Options

Tiled Inserts

Tile to Floor Option:
To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add $10 to the list price.

Note: Tile to floor option available for 14″ and 28″ High inserts.

Tiled Fabric Inserts
Tile Supports

description	w *	d	pattern no.	list
D1 Tile Support/ External Reveal	15″	5/8″	**DP1SOS15**	$28.
	18″	5/8″	**DP1SOS18**	28.
	24″	5/8″	**DP1SOS24**	29.
	30″	5/8″	**DP1SOS30**	32.
	36″	5/8″	**DP1SOS36**	33.
	42″	5/8″	**DP1SOS42**	35.
	48″	5/8″	**DP1SOS48**	35.
	60″	5/8″	**DP1SOS60**	38.
D2 Tile Support/ Recessed Reveal	15″		**DP2SOS15**	25.
	18″		**DP2SOS18**	25.
	24″		**DP2SOS24**	26.
	30″		**DP2SOS30**	28.
	36″		**DP2SOS36**	29.
	42″		**DP2SOS42**	32.
	48″		**DP2SOS48**	32.
	60″		**DP2SOS60**	35.
D2 Tile Support Mounting Brackets (pair)			**DP2SOSC**	7.
				

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

D1 Tile Support / External Reveal

1. Pattern Number
2. Trim Finish

D2 Tile Support / Recessed Reveal

1. Pattern Number

Order Code

D1 Tile Support / External Reveal Supports

Example:	**DP1 SOS18, 117**
DP1 SOS18	Pattern Number
117	Soft Grey trim finish

Included with:

Note: D2 insert supports require mounting brackets.

Options

Tiled Insert Supports

Tiled Laminate Inserts
Specifications

Tiled Laminate Inserts
Dividends Horizon tiled laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Tiled sizes are for use with frames from 36" to 78" high, and widths of up to 48" in tile to raceway, open base and tile to floor applications. Tiled laminate inserts may also be wall mounted using wall mount tracks. Tiled laminate inserts with matching surface and edge are available in the following finishes:

(114) Folkstone Grey
(117) Soft Grey
(118) Bright White
(119) Pumice

Legacy finishes are not available.

Tiled Laminate Insert Construction
- Surface material: laminate on front and back surface
- Edge material: .5 mm edgeband
- Core material: particle board
- Thickness: 7/16"

Tiled Insert Supports
All Dividends Horizon panel frames are pre-punched to accept tiled panel insert supports, which span horizontally across the panel frame. Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets
D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.

Tiled Laminate Insert Attachment
Laminate tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Tiled Laminate Insert Planning Guidelines
Insert dimensions are nominal. Insert configurations shown below are for one side only. Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP). When attaching cantilevers to tiled panels, they can only be hung at 28-1/2" worksurface height. Overheads can only be attached to the uppermost position of tiled panels. On 78"-high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.



Tiled Insert Configurations



36"H Panels
- Two 14"H tiled inserts
- One tile support

42"H Panels
- One 7"H tiled insert
- Two 14"H tiled inserts
- Two tile supports

50"H Panels
- Three 14"H tiled inserts
- Two tile supports

57"H Panels
- One 7"H tiled insert
- Three 14"H tiled inserts
- Three tile supports



64"H Panels
- Four 14"H tiled inserts
- Three tile supports

78"H Panels
- Five 14"H tiled inserts
- Four tile supports

Tiled Laminate Inserts
7″, 10″, 14″, 21″ and 28″ High
Base Raceway or Open Base

description	w*	w	h	d	pattern no.	list
7″ High Individual Tiled Laminate Insert Base Raceway or Open Base	15″	14 5/8″	7 3/16″	7/16″	**DP3L10715**	$107.
	18″	17 5/8″	7 3/16″	7/16″	**DP3L10718**	109.
	24″	23 5/8″	7 3/16″	7/16″	**DP3L10724**	112.
	30″	29 5/8″	7 3/16″	7/16″	**DP3L10730**	116.
	36″	35 5/8″	7 3/16″	7/16″	**DP3L10736**	131.
	42″	41 5/8″	7 3/16″	7/16″	**DP3L10742**	135.
	48″	47 5/8″	7 3/16″	7/16″	**DP3L10748**	139.
10″ High Individual Tiled Laminate Insert Base Raceway or Open Base	15″	14 5/8″	10 3/16″	7/16″	**DP3L11015**	110.
	18″	17 5/8″	10 3/16″	7/16″	**DP3L11018**	112.
	24″	23 5/8″	10 3/16″	7/16″	**DP3L11024**	116.
	30″	29 5/8″	10 3/16″	7/16″	**DP3L11030**	128.
	36″	35 5/8″	10 3/16″	7/16″	**DP3L11036**	146.
	42″	41 5/8″	10 3/16″	7/16″	**DP3L11042**	151.
	48″	47 5/8″	10 3/16″	7/16″	**DP3L11048**	156.
14″ High Individual Tiled Laminate Insert Base Raceway or Open Base	15″	14 5/8″	14 3/16″	7/16″	**DP3L11415**	112.
	18″	17 5/8″	14 3/16″	7/16″	**DP3L11418**	114.
	24″	23 5/8″	14 3/16″	7/16″	**DP3L11424**	125.
	30″	29 5/8″	14 3/16″	7/16″	**DP3L11430**	138.
	36″	35 5/8″	14 3/16″	7/16″	**DP3L11436**	162.
	42″	41 5/8″	14 3/16″	7/16″	**DP3L11442**	166.
	48″	47 5/8″	14 3/16″	7/16″	**DP3L11448**	169.
21″ High Individual Tiled Laminate Insert Base Raceway or Open Base 	15″	14 5/8″	21 3/16″	7/16″	**DP3L12115**	123.
	18″	17 5/8″	21 3/16″	7/16″	**DP3L12118**	135.
	24″	23 5/8″	21 3/16″	7/16″	**DP3L12124**	159.
	30″	29 5/8″	21 3/16″	7/16″	**DP3L12130**	163.
	36″	35 5/8″	21 3/16″	7/16″	**DP3L12136**	234.
	42″	41 5/8″	21 3/16″	7/16″	**DP3L12142**	237.
	48″	47 5/8″	21 3/16″	7/16″	**DP3L12148**	241.
28″ High Individual Tiled Laminate Insert Base Raceway or Open Base 	15″	14 5/8″	29″	7/16″	**DP3L12815**	160.
	18″	17 5/8″	29″	7/16″	**DP3L12818**	169.
	24″	23 5/8″	29″	7/16″	**DP3L12824**	194.
	30″	29 5/8″	29″	7/16″	**DP3L12830**	226.
	36″	35 5/8″	29″	7/16″	**DP3L12836**	244.
	42″	41 5/8″	29″	7/16″	**DP3L12842**	291.
	48″	47 5/8″	29″	7/16″	**DP3L12848**	296.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Tiled Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Tiled Laminate Inserts

Example:	**DP3L10724**
DP3L1 0724	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Tiled Laminate Inserts

- **Attachment clips**

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

Options

Tiled Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Tiled Laminate Inserts
14″ and 28″ High
Tile To Floor

description	w*	w	d	pattern no.	list
14″ High Individual Tiled Laminate Insert Tile to Floor 	15″	14 5/8″	7/16″	**DP3L11415F**	$118.
	18″	17 5/8″	7/16″	**DP3L11418F**	126.
	24″	23 5/8″	7/16″	**DP3L11424F**	137.
	30″	29 5/8″	7/16″	**DP3L11430F**	155.
	36″	35 5/8″	7/16″	**DP3L11436F**	183.
	42″	41 5/8″	7/16″	**DP3L11442F**	197.
	48″	47 5/8″	7/16″	**DP3L11448F**	200.
28″ High Individual Tiled Laminate Insert Tile to Floor 	15″	14 5/8″	7/16″	**DP3L12815F**	160.
	18″	17 5/8″	7/16″	**DP3L12818F**	169.
	24″	23 5/8″	7/16″	**DP3L12824F**	194.
	30″	29 5/8″	7/16″	**DP3L12830F**	226.
	36″	35 5/8″	7/16″	**DP3L12836F**	244.
	42″	41 5/8″	7/16″	**DP3L12842F**	291.
	48″	47 5/8″	7/16″	**DP3L12848F**	296.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Tiled Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Tiled Laminate Inserts

Example:	**DP3L11424F**
DP3L1 1424F	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Tiled Laminate Inserts

- **Attachment clips**

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

Options

Tiled Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

This page intentionally left blank

Beltway Inserts
Lower Inserts
Specifications

Beltway Inserts
Dividends Horizon beltway panel inserts are available by component for use with panel frames for "build-to-spec" applications. These applications include when inserts are only required on one panel side and when fabrics or materials are mixed insert-to-insert or side-to-side.

Beltway inserts are also included in "Preconfigured" beltway panel assemblies.

Beltway Insert Construction
Fabric inserts are constructed of fabric laminated with web adhesive and heat-cured to $^{7}/_{16}$" thick acoustical board. Laminate inserts are constructed of a particle laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish. 24" high inserts are to only be used below beltways.

Beltway Insert Attachment
Beltway panel inserts attach to the troughs in the upper and lower horizontal frame supports and beltway insert supports. Beltway top and bottom panel inserts require beltway cover and insert supports. Mounting clips attach to panel inserts and connect to vertical frame for additional support. No tools are required for insert attachment.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Cover
Beltway covers snap into the beltway supports and are constructed of extruded plastic. Beltway covers include knockouts with covers for duplex receptacles centered 12" from each panel end (except for 18 and 24" wide). A single communications knockout cover in the center of the beltway is included on all beltways except for 30" wide. Electrical knockouts are the same size as communications knockouts and can be used for communications cables and data ports if terminal blocks are not installed within the beltway.

Beltway covers and insert supports can be installed on one or both sides of panels. Beltway cover and insert supports require top and bottom beltway panel inserts.

Beltway Cover Construction
Color injected plastic extrusion that is available in smooth finish.

Electrical
Beltways 30" and wider accept two duplex receptacles per beltway. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel
Beltway panels are available with one beltway per panel or per panel side.

Note: Insert dimensions are nominal. Inserts and beltway cover/supports are for one side only.

Beltway Insert Locations



Beltway Insert Attachment



Beltway Insert Locations



Beltway Insert Configurations

42"H Panels
- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert





50"H Panels
- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert

57"H Panels
- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



64"H Panels
- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert





78"H Panels
- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert

Beltway Inserts
Lower Fabric Inserts
Beltway Cover and Insert Supports

description	w*	w	h	d	pattern no.	grade 10	15	20	25	30	35	40	45
24″ High Fabric Beltway Lower Insert, (For Beltway Panels only)	18″	17 5/8″	25 1/2″	7/16″	**DP1SO2418**	$89.	$97.	$102.	$109.	$113.	$117.	$123.	$127.
	24″	23 5/8″	25 1/2″	7/16″	**DP1SO2424**	111.	115.	127.	133.	138.	141.	146.	158.
	30″	29 5/8″	25 1/2″	7/16″	**DP1SO2430**	121.	127.	138.	144.	150.	158.	162.	171.
	36″	35 5/8″	25 1/2″	7/16″	**DP1SO2436**	132.	138.	150.	159.	168.	174.	178.	184.
	42″	41 5/8″	25 1/2″	7/16″	**DP1SO2442**	137.	143.	152.	160.	170.	175.	182.	190.
	48″	47 5/8″	25 1/2″	7/16″	**DP1SO2448**	143.	150.	162.	171.	176.	183.	193.	203.
	60″	59 5/8″	25 1/2″	7/16″	**DP1SO2460**	163.	168.	175.	178.	184.	187.	197.	208.
Beltway Cover and Insert Supports		18″		7/16″	**DP2BC18K**	97.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		24″		7/16″	**DP2BC24K**	113.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		30″		7/16″	**DP2BC30K**	125.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		36″		7/16″	**DP2BC36K**	137.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		42″		7/16″	**DP2BC42K**	152.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		48″		7/16″	**DP2BC48K**	170.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
		60″		7/16″	**DP2BC60K**	198.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Beltway Knockout Replacement Cover for Electrical and Data	Pkg of 10				**DE1 KCBW**	44.	n/a	n/a	n/a	n/a	n/a	n/a	n/a

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Beltway Cover/Insert Supports

1. Pattern Number
2. Beltway Cover/Trim Finish

Beltway Inserts

1. Pattern Number
2. Fabric

Order Code

Beltway Inserts

Example:	**DP1 SO2442, W257-6**
DP1 SO2442	Pattern Number
W257-6	Solid Crepe Blue Pine fabric

Beltway Cover/Insert Supports

Example:	**DP2 BC42K, 117**
DP2 BC42K	Pattern Number
117	Soft Grey Beltway Cover Trim

Included with:

Beltway Inserts

Beltway Cover/Insert Supports

- Individual beltway cover
- Insert supports (top and bottom rail)
- Attachment hardware
- Beltway knockout covers

Note: 24″H inserts are to only be used below beltways.

Options

Beltway Panel Inserts

Beltway Cover/Insert Supports
Beltway cover has a smooth finish

Tile to Floor Option:
To specify tile to floor, add an "F" suffix to the pattern number and add $10 to the list price.

Note: Tile to floor option available for 24″ high inserts.

Beltway Inserts
Lower Steel Inserts

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
24″ High Solid Steel Insert	18″	17 5/8″	25 1/2″	7/16″	**DP3SS( )2418**	$98.	$118.	$127.	$171.	$201.	$219.
	24″	23 5/8″	25 1/2″	7/16″	**DP3SS( )2424**	123.	140.	153.	214.	244.	266.
	30″	29 5/8″	25 1/2″	7/16″	**DP3SS( )2430**	130.	152.	165.	228.	266.	288.
	36″	35 5/8″	25 1/2″	7/16″	**DP3SS( )2436**	146.	166.	184.	253.	288.	321.
	42″	41 5/8″	25 1/2″	7/16″	**DP3SS( )2442**	151.	167.	185.	264.	293.	325.
	48″	47 5/8″	25 1/2″	7/16″	**DP3SS( )2448**	155.	177.	194.	273.	313.	342.
24″ High Perforated Steel Insert	18″	17 5/8″	25 1/2″	7/16″	**DP3PSB( )2418**	149.	176.	193.	256.	302.	328.
	24″	23 5/8″	25 1/2″	7/16″	**DP3PSB( )2424**	183.	210.	230.	321.	368.	402.
	30″	29 5/8″	25 1/2″	7/16″	**DP3PSB( )2430**	198.	228.	246.	344.	402.	433.
	36″	35 5/8″	25 1/2″	7/16″	**DP3PSB( )2436**	220.	248.	277.	381.	433.	480.
	42″	41 5/8″	25 1/2″	7/16″	**DP3PSB( )2442**	227.	250.	278.	397.	440.	488.
	48″	47 5/8″	25 1/2″	7/16″	**DP3PSB( )2448**	232.	265.	289.	413.	470.	512.
24″ High Embossed Steel Insert	18″	17 5/8″	25 1/2″	7/16″	**DP3ESB( )2418**	149.	176.	193.	256.	302.	328.
	24″	23 5/8″	25 1/2″	7/16″	**DP3ESB( )2424**	183.	210.	230.	321.	368.	402.
	30″	29 5/8″	25 1/2″	7/16″	**DP3ESB( )2430**	198.	228.	246.	344.	402.	433.
	36″	35 5/8″	25 1/2″	7/16″	**DP3ESB( )2436**	220.	248.	277.	381.	433.	480.
	42″	41 5/8″	25 1/2″	7/16″	**DP3ESB( )2442**	227.	250.	278.	397.	440.	488.
	48″	47 5/8″	25 1/2″	7/16″	**DP3ESB( )2448**	232.	265.	289.	413.	470.	512.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Steel Insert

1. Pattern number
2. Paint finish

Order Code

Steel Insert

Example:	**DP3SS( )2418 115**
DP3 SS22418	Pattern number
115	Medium Grey paint

Included with:

Steel Insert

Note: 24″H inserts are to only be used below beltways.

Options

Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack or $31 for a double pack.

Note: Tile to Floor option available for 24″ high inserts.

Beltway Inserts
Lower Laminate Inserts

description	w*	w	d	pattern no.	list
24″ High Laminate Beltway Lower Insert Base Raceway or Open Base	15″	14 5/8″	7/16″	**DP3L12415**	$135.
	18″	17 5/8″	7/16″	**DP3L12418**	144.
	24″	23 5/8″	7/16″	**DP3L12424**	161.
	30″	29 5/8″	7/16″	**DP3L12430**	193.
	36″	35 5/8″	7/16″	**DP3L12436**	236.
	42″	41 5/8″	7/16″	**DP3L12442**	240.
	48″	47 5/8″	7/16″	**DP3L12448**	243.
24″ High Laminate Beltway Lower Insert Tile to Floor	15″	14 5/8″	7/16″	**DP3L12415F**	135.
	18″	17 5/8″	7/16″	**DP3L12418F**	144.
	24″	23 5/8″	7/16″	**DP3L12424F**	161.
	30″	29 5/8″	7/16″	**DP3L12430F**	193.
	36″	35 5/8″	7/16″	**DP3L12436F**	236.
	42″	41 5/8″	7/16″	**DP3L12442F**	240.
	48″	47 5/8″	7/16″	**DP3L12448F**	243.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Beltway Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Beltway Laminate Inserts

Example:	**DP3L12436**
DP3L1 2436	Pattern Number
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Beltway Laminate Inserts

- **Attachment clips**

Note: 24″H inserts are to only be used below beltways.

Options:

Beltway Laminate Inserts Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

High Acoustic Core Inserts
Specifications

High Acoustic Core Inserts and Sound Transmission Septum Inserts
Optional high acoustic core inserts or sound transmission septum inserts combine with tiles to provide enhanced acoustics.

High acoustic core inserts can be installed in monolithic and tiled panels but must be field-cut to be installed in beltway panels.

Sound transmission septum inserts can be installed in monolithic and tiled panels and single-sided beltway panels.

High Acoustic Core Insert Construction
1 1/2" thick, three-ply insert with an inner septum and outer fiberglass with polywrap.

Sound Transmission Septum Insert Construction
1/16" thick black asphalt paper.

Core Insert Attachment
High acoustic core inserts and sound transmission septum inserts are inserted into the center of the panel frame. Core inserts are sized to fit into the panel frame without the use of fasteners. In-field installation is required.

High Acoustic Core Insert Panel Ratings
Noise Reduction Coefficient (NRC) rating: .80 when combined with tiles.

Sound Transmission Class (STC) rating: 26 when combined with tiles.

Sound Transmission Septum Insert Panel Ratings
Noise Reduction Coefficient (NRC) rating: .60 when combined with tiles.

Sound Transmission Class (STC) rating: 17 when combined with tiles.

Available Sizes
High acoustic core inserts and sound transmission septum inserts are available for all widths of 50", 64" and 78" high monolithic and tiled panels.

Beltway electrical panels require the high acoustic core inserts or the sound transmission septum inserts to be field-cut prior to installation.

Packaging
High acoustic cores and sound transmission septum inserts are shipped in separate containers.

High Acoustic Core Insert



High Acoustic Core Insert Construction



Sound Transmission Septum Insert Construction



High Acoustic Core Inserts
Sound Transmission Septum Inserts

description	type	pattern no.	High Acoustic Core Insert	Sound Transmission Septum Insert
50″ High	For 18″ panel width	**DP1( ) 5018**	$27.	$13.
	For 24″ panel width	**DP1( ) 5024**	32.	13.
	For 30″ panel width	**DP1( ) 5030**	35.	13.
	For 36″ panel width	**DP1( ) 5036**	39.	22.
	For 42″ panel width	**DP1( ) 5042**	44.	22.
	For 48″ panel width	**DP1( ) 5048**	53.	22.
64″ High	For 18″ panel width	**DP1( ) 6418**	36.	13.
	For 24″ panel width	**DP1( ) 6424**	41.	13.
	For 30″ panel width	**DP1( ) 6430**	47.	13.
	For 36″ panel width	**DP1( ) 6436**	56.	22.
	For 42″ panel width	**DP1( ) 6442**	65.	22.
	For 48″ panel width	**DP1( ) 6448**	72.	22.
78″ High	For 18″ panel width	**DP1( ) 7818**	47.	25.
	For 24″ panel width	**DP1( ) 7824**	56.	25.
	For 30″ panel width	**DP1( ) 7830**	64.	25.
	For 36″ panel width	**DP1( ) 7836**	70.	27.
	For 42″ panel width	**DP1( ) 7842**	79.	27.
	For 48″ panel width	**DP1( ) 7848**	93.	27.

Ordering Information

Inserts

1. Pattern Number

Order Code

Inserts

Example: **DP1(AC) 6448**

DP1(AC) Pattern Number
6448

Included with:

Inserts

- High Acoustic Core Insert
- Sound Transmission Septum Insert

Options

Inserts

Insert the appropriate letters for insert required within the parentheses of the pattern number.
(AC) = High Acoustic
(ST) = Sound Transmission

Window Insert Kits
Specifications

Single Pane Window Insert Kit
Single pane windows are available for three applications:

- Top position, with topway - for use in the top position of panels and D1 style stack frame with a topway trough.
- Top position, full view - for use in the top position of full view panels and D1 style stack frames.
- Middle position - for use in the middle positions of topway and full view panels.

Note: Window insert kits may not be specified in the bottom position of panels. Specify D2 tile supports and insert support mounting brackets separately.

Note: Single and double pane window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with top position single or double pane window insert kits.

Construction
Single pane windows are shipped in two components - an “open” frame, and a “window” frame. Each frame snaps onto a Dividends Horizon panel frame. Both frames are constructed of extruded, then robotically-welded aluminum. Single pane windows have 1/4" tempered glass inserts with PVC glazing strip.

Single Pane Window Insert Kit Available Sizes
- Heights: 14", 21" and 28"
- Widths: 24", 30", 36", 42", and 48"

Attachment
Window insert kits are installed on each side of a panel frame. Glazed insert kits consist of two inserts. Individual tile support rails must be ordered separately.

Note: Window types are aesthetically different, and are not designed to be mixed together within a single installation.

Single Pane Window Insert Kit



Window Insert Kits
Single Pane Windows

description	h	w	pattern no.	P1	P2	P3
Window, top position with topway	14″	24″	**D2P1( )T1424**	$377.	$399.	$417.
	14″	30″	**D2P1( )T1430**	438.	458.	481.
	14″	36	**D2P1( )T1436**	493.	518.	544.
	14″	42″	**D2P1( )T1442**	586.	616.	645.
	14″	48″	**D2P1( )T1448**	599.	630.	661.
	21″	24″	**D2P1( )T2124**	440.	462.	483.
	21″	30″	**D2P1( )T2130**	518.	545.	571.
	21″	36″	**D2P1( )T2136**	557.	586.	613.
	21″	42″	**D2P1( )T2142**	666.	700.	731.
	21″	48″	**D2P1( )T2148**	741.	781.	817.
	28″	24″	**D2P1( )T2824**	483.	508.	535.
	28″	30″	**D2P1( )T2830**	571.	599.	629.
	28″	36″	**D2P1( )T2836**	613.	645.	675.
	28″	42″	**D2P1( )T2842**	731.	770.	808.
	28″	48″	**D2P1( )T2848**	817.	857.	898.
Window, top position full view	14″	24″	**D2P1( )VT1424**	377.	399.	417.
	14″	30″	**D2P1( )VT1430**	438.	458.	481.
	14″	36″	**D2P1( )VT1436**	493.	518.	544.
	14″	42″	**D2P1( )VT1442**	586.	616.	645.
	14″	48″	**D2P1( )VT1448**	599.	630.	661.
	21″	24″	**D2P1( )VT2124**	440.	462.	483.
	21″	30″	**D2P1( )VT2130**	518.	545.	571.
	21″	36″	**D2P1( )VT2136**	557.	586.	613.
	21″	42″	**D2P1( )VT2142**	666.	700.	731.
	21″	48″	**D2P1( )VT2148**	741.	781.	817.
	28″	24″	**D2P1( )VT2824**	483.	508.	535.
	28″	30″	**D2P1( )VT2830**	571.	599.	629.
	28″	36″	**D2P1( )VT2836**	613.	645.	675.
	28″	42″	**D2P1( )VT2842**	731.	770.	808.
	28″	48″	**D2P1( )VT2848**	817.	857.	898.
Window, middle position	14″	24″	**D2P1( )VL1424**	377.	399.	417.
	14″	30″	**D2P1( )VL1430**	438.	458.	481.
	14″	36″	**D2P1( )VL1436**	493.	518.	544.
	14″	42″	**D2P1( )VL1442**	586.	616.	645.
	14″	48″	**D2P1( )VL1448**	599.	630.	661.

Ordering Information

Single Pane Window Kit

1. Pattern number
2. Paint finish

Order Code

Single Pane Window Kit

Example:	**D2P1GT1448, 117**
D2P1	Single Pane Window w/
GT1448	Clear Glass
117	Soft Grey Paint

Included with:

Single Pane Window Kit

Note: The single pane window insert kit is not compatible with the D2 style stack frame. Use D1 style stack frames with single pane window insert kits.

Note: Use top position window insert kits when using with D1 style stack frames.

Options

Single Pane Window Kit

Note: Single Pane Window Kit must be used with D2 Style Supports

Glass Options:
(G) = Clear Tempered Glass
(F) = Powder Glass

Markerboard Tiles
Specifications

Markerboard Tiles
Markerboard tiles may be attached to any Dividends Horizon universal panel frame or wall mount tracks.

Construction
Markerboard tiles are constructed of 20 gauge steel, powder coated with paint suitable for use with standard dry erase markers.

Available Sizes
- Heights: 7", 10", 14", 21", 24" and 28"
- Widths: 18", 24", 30", 36", 42", and 48"

Attachment
Markerboard tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.

Markerboard Trays
Markerboard trays are positioned directly below markerboard tiles, and are designed to hold dry erase markers and erasers. Trays mount to the outside of tile frames, and replace a D1 or D2 tile support.

Markerboard trays may not be positioned directly above or below a beltway raceway and may not be used with stack frames.

Note: Markerboard tiles can use D1 or D2 tile supports. Legacy D1 and D2 Markerboard tiles use D1 tile supports only.

Markerboard Tile





DP7 Stack Frame/Steel Tile Planning Note
When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP7 SSTK ($10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

Markerboard Tiles
Specifications

Proper use and regular cleaning of your markerboard surface is essential for preventing permanent stains and/or ghosting typically associated with dry erase markers. By following the care and use instructions below, you will minimize the possibility of permanent stains and ghosting.

Initial Cleaning of Markerboards Before First Use:

- Using a clean, dry cloth and a nonabrasive cleaner, gently clean the entire board to loosen any residue
- Using a dry cloth, wipe the entire surface to remove all dirt and residue from the prior step
- Rinse the entire board with clean water
- Using a dry cloth, wipe dry the entire surface

Daily Use, Care and Maintenance:

- *Use the proper markers.* All dry erase markers will write legibly on the marker board surface, but not all will erase properly due to their composition. Do not use low odor dry erase markers or permanent (indelible) markers. Use of these markers will lead to staining or ghosting, even with regular cleaning.
- *Clean the markerboard regularly.* It is recommended that markerboards be erased daily using an eraser designated for use with dry erase markers. If the markerboard is used daily, we recommend that a complete cleaning is performed at least 2-3 times a week using EXPO® whiteboard cleaner.
- *Remove ghosting*. Using EXPO® whiteboard cleaner and a paper towel, wipe the entire surface and let dry. Mix Joy® dishwashing detergent with warm water and apply to the board using a paper towel, then wipe dry with a clean cloth. Repeat as necessary.
- *Remove permanent marker.* Using a dry erase marker, write on top of the permanent marker, erase with a dry eraser, and then clean with EXPO® whiteboard cleaner.

Note: Do not use other painted tiles as markerboards or product damage will occur and the tile warranty will be voided.

Markerboard Tiles
7″, 10″, 14″ and 21″ High

description	h	w	pattern no.	1 pack	6 pack
D3 7″ Markerboard tile	7″	18″	**DP3MB( )718**	$72.	$319.
	7″	24″	**DP3MB( )724**	76.	339.
	7″	30″	**DP3MB( )730**	83.	376.
	7″	36″	**DP3MB( )736**	99.	437.
	7″	42″	**DP3MB( )742**	108.	467.
	7″	48″	**DP3MB( )748**	111.	495.
D3 10″ Markerboard tile	10″	18″	**DP3MB( )1018**	99.	446.
	10″	24″	**DP3MB( )1024**	108.	474.
	10″	30″	**DP3MB( )1030**	109.	495.
	10″	36″	**DP3MB( )1036**	121.	525.
	10″	42″	**DP3MB( )1042**	125.	555.
	10″	48″	**DP3MB( )1048**	132.	594.
D3 14″ Markerboard tile	14″	18″	**DP3MB( )1418**	99.	446.
	14″	24″	**DP3MB( )1424**	108.	474.
	14″	30″	**DP3MB( )1430**	109.	495.
	14″	36″	**DP3MB( )1436**	121.	525.
	14″	42″	**DP3MB( )1442**	125.	555.
	14″	48″	**DP3MB( )1448**	132.	594.
D3 21″ Markerboard tile	21″	18″	**DP3MB( )2118**	128.	665.
	21″	24″	**DP3MB( )2124**	159.	832.
	21″	30″	**DP3MB( )2130**	171.	893.
	21″	36″	**DP3MB( )2136**	193.	992.
	21″	42″	**DP3MB( )2142**	198.	1,029.
	21″	48″	**DP3MB( )2148**	202.	1,071.

Ordering Information	**Order Code**	**Included with:**	**Options**
Markerboard Tiles 1. Pattern Number	**Markerboard Tiles** *Example:* **DP3MB(1) 1436** **DP3MB(1)** Pattern Number **1436**	**Markerboard Tiles**	**Markerboard Tiles** **(1)** = 1 Pack **(6) =** 6 Pack

Markerboard Tiles
24″ and 28″ High and Markerboard Tray

description	height	width	pattern number	1 pack	2 pack	P1	P2	P3
D3 24″ Markerboard tile 	24″	18″	**DP3MB( )2418**	$128.	$221.			
	24″	24″	**DP3MB( )2424**	159.	277.			
	24″	30″	**DP3MB( )2430**	171.	297.			
	24″	36″	**DP3MB( )2436**	193.	331.			
	24″	42″	**DP3MB( )2442**	198.	344.			
	24″	48″	**DP3MB( )2448**	202.	356.			
D3 28″ Markerboard tile 	28″	18″	**DP3MB( )2818**	139.	242.			
	28″	24″	**DP3MB( )2824**	161.	281.			
	28″	30″	**DP3MB( )2830**	172.	303.			
	28″	36″	**DP3MB( )2836**	193.	337.			
	28″	42″	**DP3MB( )2842**	198.	347.			
	28″	48″	**DP3MB( )2848**	202.	358.			
Markerboard Tray		24″	**DP1MBT24**			111.	117.	122.
		30″	**DP1MBT30**			114.	119.	125.
		36″	**DP1MBT36**			116.	122.	127.
		42″	**DP1MBT42**			118.	124.	129.
		48″	**DP1MBT48**			121.	126.	132.

Ordering Information

Markerboard Tiles

1. Pattern Number

Markerboard Tray

1. Pattern Number
2. Paint Finish

Order Code

Markerboard Tiles

Example: **DP3MB(1) 1436**

DP3MB(1) Pattern Number
1436

Included with:

Markerboard Tiles

Options

Markerboard Tiles
(1) = 1 Pack
(2) = 2 Pack

Steel Insert Kits
Specifications

Solid Steel Inserts
Solid steel tiles are painted solid steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction
Steel tiles are made of 20-gauge formed steel that is painted in any Dividends Horizon paint color.

Embossed Steel Inserts
Embossed steel tiles are painted embossed steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction
Embossed steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color

Perforated Steel Inserts
Perforated steel tiles are painted perforated steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction
Perforated steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color.

Available Sizes
- Height: 7", 10", 14", 21", 24" and 28"
- Widths: 15", 18", 24", 30", 36", 42" and 48"

Attachment
Steel tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.

One-sided Attachment
For applications with perforated inserts on one side of panel only, specify sound transmission septums.

Tile-to-Floor Option
14" and 28" high steel tiles are available to be specified Tile-to-Floor.

Solid Steel Tile Insert



Perforated and Embossed Steel Tile Inserts





DP7 Stack Frame/Steel Tile Planning Note
When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP7 SSTK ($10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

Steel Insert Kits
7″, 10″, 14″ and 21″ High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7″ High Solid Steel Insert	15″	14 5/8″	7 3/16″	7/16″	**DP3SS( )715**	$55.	$65.	$76.	$244.	$283.	$338.
	18″	17 5/8″	7 3/16″	7/16″	**DP3SS( )718**	55.	65.	76.	244.	283.	338.
	24″	23 5/8″	7 3/16″	7/16″	**DP3SS( )724**	58.	72.	78.	259.	321.	350.
	30″	29 5/8″	7 3/16″	7/16″	**DP3SS( )730**	66.	80.	88.	290.	357.	388.
	36″	35 5/8″	7 3/16″	7/16″	**DP3SS( )736**	77.	91.	96.	338.	388.	419.
	42″	41 5/8″	7 3/16″	7/16″	**DP3SS( )742**	82.	94.	102.	357.	413.	449.
	48″	47 5/8″	7 3/16″	7/16″	**DP3SS( )748**	85.	97.	104.	381.	436.	472.
D3 10″ High Solid Steel Insert	15″	14 5/8″	10 3/16″	7/16″	**DP3SS( )1015**	77.	89.	92.	344.	388.	406.
	18″	17 5/8″	10 3/16″	7/16″	**DP3SS( )1018**	77.	89.	92.	344.	388.	406.
	24″	23 5/8″	10 3/16″	7/16″	**DP3SS( )1024**	82.	93.	96.	368.	419.	436.
	30″	29 5/8″	10 3/16″	7/16″	**DP3SS( )1030**	83.	96.	100.	381.	442.	457.
	36″	35 5/8″	10 3/16″	7/16″	**DP3SS( )1036**	92.	104.	111.	406.	466.	488.
	42″	41 5/8″	10 3/16″	7/16″	**DP3SS( )1042**	95.	109.	121.	426.	488.	535.
	48″	47 5/8″	10 3/16″	7/16″	**DP3SS( )1048**	100.	122.	126.	457.	549.	572.
D3 14″ High Solid Steel Insert	15″	14 5/8″	14 3/16″	7/16″	**DP3SS( )1415**	77.	89.	92.	344.	388.	406.
	18″	17 5/8″	14 3/16″	7/16″	**DP3SS( )1418**	77.	89.	92.	344.	388.	406.
	24″	23 5/8″	14 3/16″	7/16″	**DP3SS( )1424**	82.	93.	96.	368.	419.	436.
	30″	29 5/8″	14 3/16″	7/16″	**DP3SS( )1430**	83.	96.	100.	381.	442.	457.
	36″	35 5/8″	14 3/16″	7/16″	**DP3SS( )1436**	92.	104.	111.	406.	466.	488.
	42″	41 5/8″	14 3/16″	7/16″	**DP3SS( )1442**	95.	109.	121.	426.	488.	535.
	48″	47 5/8″	14 3/16″	7/16″	**DP3SS( )1448**	100.	122.	126.	457.	549.	572.
D3 21″ High Solid Steel Insert	15	14 5/8″	21 3/16″	7/16″	**DP3SS( )2115**	98.	118.	127.	512.	603.	656.
	18″	17 5/8″	21 3/16″	7/16″	**DP3SS( )2118**	98.	118.	127.	512.	603.	656.
	24″	23 5/8″	21 3/16″	7/16″	**DP3SS( )2124**	123.	140.	153.	641.	730.	801.
	30″	29 5/8″	21 3/16″	7/16″	**DP3SS( )2130**	130.	152.	165.	687.	801.	862.
	36″	35 5/8″	21 3/16″	7/16″	**DP3SS( )2136**	146.	166.	184.	763.	862.	962.
	42″	41 5/8″	21 3/16″	7/16″	**DP3SS( )2142**	151.	167.	185.	793.	878.	977.
	48″	47 5/8″	21 3/16″	7/16″	**DP3SS( )2148**	155.	177.	194.	823.	937.	1,022.

Ordering Information

Solid Steel Insert

1. Pattern number
2. Paint finish

Order Code

Solid Steel Insert

Example:	**DP3SS( )1418 115**
DP3	Pattern number
SS21418	
115	Medium Grey paint

Included with:

Solid Steel Insert

Options

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14″, Worksurface Height, 24″ and 28″. To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

Steel Insert Kits
Worksurface Height and 28″ High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Solid Steel Insert 	15″	14 5/8″	22 1/2″	7/16″	**DP3SS( )WH15**	$98.	$118.	$127.	$171.	$201.	$219.
	18″	17 5/8″	22 1/2″	7/16″	**DP3SS( )WH18**	98.	118.	127.	171.	201.	219.
	24″	23 5/8″	22 1/2″	7/16″	**DP3SS( )WH24**	123.	140.	153.	214.	244.	266.
	30″	29 5/8″	22 1/2″	7/16″	**DP3SS( )WH30**	130.	152.	165.	228.	266.	288.
	36″	35 5/8″	22 1/2″	7/16″	**DP3SS( )WH36**	146.	166.	184.	253.	288.	321.
	42″	41 5/8″″	22 1/2″	7/16″	**DP3SS( )WH42**	151.	167.	185.	264.	293.	325.
	48″	47 5/8″	22 1/2″	7/16″	**DP3SS( )WH48**	155.	177.	194.	273.	313.	342.
D3 28″ High Solid Steel Insert 	15″	14 5/8″	29″	7/16″	**DP3SS( )2815**	107.	107.	126.	185.	203.	219.
	18″	17 5/8″	29″	7/16″	**DP3SS( )2818**	107.	107.	126.	185.	203.	219.
	24″	23 5/8″	29″	7/16″	**DP3SS( )2824**	124.	124.	153.	216.	246.	268.
	30″	29 5/8″	29″	7/16″	**DP3SS( )2830**	132.	152.	166.	234.	268.	293.
	36″	35 5/8″	29″	7/16″	**DP3SS( )2836**	146.	166.	184.	256.	293.	325.
	42″	41 5/8″	29″	7/16″	**DP3SS( )2842**	151.	168.	184.	266.	295.	328.
	48″	47 5/8″	29″	7/16″	**DP3SS( )2848**	155.	177.	195.	277.	315.	344.

Ordering Information

Solid Steel Insert

1. Pattern number
2. Paint finish

Order Code

Solid Steel Insert

Example:	**DP3SS( )2118 115**
DP3 SS22118	Pattern number
115	Medium Grey paint

Included with:

Solid Steel Insert

Options

Solid Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14″, Worksurface Height, 24″ and 28″. To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

Steel Insert Kits
7", 10", 14" and 21" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Perforated Steel Insert	15"	14 5/8"	7 3/16"	7/16"	**DP3PSB( )715**	$83.	$95.	$116.	$368.	$426.	$503.
	18"	17 5/8"	7 3/16"	7/16"	**DP3PSB( )718**	83.	95.	116.	368.	426.	503.
	24"	23 5/8"	7 3/16"	7/16"	**DP3PSB( )724**	89.	109.	119.	388.	480.	526.
	30"	29 5/8"	7 3/16"	7/16"	**DP3PSB( )730**	97.	122.	129.	436.	543.	587.
	36"	35 5/8"	7 3/16"	7/16"	**DP3PSB( )736**	118.	136.	145.	503.	587.	633.
	42"	41 5/8"	7 3/16"	7/16"	**DP3PSB( )742**	125.	141.	155.	543.	617.	678.
	48"	47 5/8"	7 3/16"	7/16"	**DP3PSB( )748**	128.	147.	159.	572.	656.	708.
D3 10" High Perforated Steel Insert	15"	14 5/8"	10 3/16"	7/16"	**DP3PSB( )1015**	118.	132.	138.	518.	587.	610.
	18"	17 5/8"	10 3/16"	7/16"	**DP3PSB( )1018**	118.	132.	138.	518.	587.	610.
	24"	23 5/8"	10 3/16"	7/16"	**DP3PSB( )1024**	125.	140.	145.	549.	633.	656.
	30"	29 5/8"	10 3/16"	7/16"	**DP3PSB( )1030**	126.	145.	152.	572.	664.	687.
	36"	35 5/8"	10 3/16"	7/16"	**DP3PSB( )1036**	138.	159.	167.	610.	701.	730.
	42"	41 5/8"	10 3/16"	7/16"	**DP3PSB( )1042**	144.	165.	179.	641.	730.	801.
	48"	47 5/8"	10 3/16"	7/16"	**DP3PSB( )1048**	152.	181.	192.	687.	823.	862.
D3 14" High Perforated Steel Insert	15"	14 5/8"	14 3/16"	7/16"	**DP3PSB( )1415**	118.	132.	138.	518.	587.	610.
	18"	17 5/8"	14 3/16"	7/16"	**DP3PSB( )1418**	118.	132.	138.	518.	587.	610.
	24"	23 5/8"	14 3/16"	7/16"	**DP3PSB( )1424**	125.	140.	145.	549.	633.	656.
	30"	29 5/8"	14 3/16"	7/16"	**DP3PSB( )1430**	126.	145.	152.	572.	664.	687.
	36"	35 5/8"	14 3/16"	7/16"	**DP3PSB( )1436**	138.	159.	167.	610.	701.	730.
	42"	41 5/8"	14 3/16"	7/16"	**DP3PSB( )1442**	144.	165.	179.	641.	730.	801.
	48"	47 5/8"	14 3/16"	7/16"	**DP3PSB( )1448**	152.	181.	192.	687.	823.	862.
D3 21" High Perforated Steel Insert	15"	14 5/8"	21 3/16"	7/16"	**DP3PSB( )2115**	149.	176.	193.	770.	906.	985.
	18"	17 5/8"	21 3/16"	7/16"	**DP3PSB( )2118**	149.	176.	193.	770.	906.	985.
	24"	23 5/8"	21 3/16"	7/16"	**DP3PSB( )2124**	183.	210.	230.	962.	1,099.	1,204.
	30"	29 5/8"	21 3/16"	7/16"	**DP3PSB( )2130**	198.	228.	246.	1,028.	1,204.	1,298.
	36"	35 5/8"	21 3/16"	7/16"	**DP3PSB( )2136**	220.	248.	277.	1,143.	1,298.	1,442.
	42"	41 5/8"	21 3/16"	7/16"	**DP3PSB( )2142**	227.	250.	278.	1,191.	1,319.	1,465.
	48"	47 5/8"	21 3/16"	7/16"	**DP3PSB( )2148**	232.	265.	289.	1,236.	1,411.	1,534.

Ordering Information

Perforated Steel Insert

1. Pattern number
2. Paint finish

Order Code

Perforated Steel Insert

Example:	**DP3PBS21430 117**
DP3	Pattern number
PSB21430	
117	Soft Grey paint

Included with:

Perforated Steel Insert

Options

Perforated Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

Tile to Floor Option not available on DP2 perforated steel tile insert.

Steel Insert Kits

14", Worksurface Height and 28" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Perforated Steel Insert 	15″	14 5/8″	22 1/2″	7/16″	**DP3PSB( )WH15**	$149.	$176.	$193.	$256.	$302.	$328.
	18″	17 5/8″	22 1/2″	7/16″	**DP3PSB( )WH18**	149.	176.	193.	256.	302.	328.
	24″	23 5/8″	22 1/2″	7/16″	**DP3PSB( )WH24**	183.	210.	230.	321.	368.	402.
	30″	29 5/8″	22 1/2″	7/16″	**DP3PSB( )WH30**	198.	228.	246.	344.	402.	433.
	36″	35 5/8″	22 1/2″	7/16″	**DP3PSB( )WH36**	220.	248.	277.	381.	433.	480.
	42″	41 5/8″	22 1/2″	7/16″	**DP3PSB( )WH42**	227.	250.	278.	397.	440.	488.
	48″	47 5/8″	22 1/2″	7/16″	**DP3PSB( )WH48**	232.	265.	289.	413.	470.	512.
D3 28″ High Perforated Steel Insert 	15″	14 5/8″	29″	7/16″	**DP3PSB( )2815**	161.	161.	192.	279.	306.	328.
	18″	17 5/8″	29″	7/16″	**DP3PSB( )2818**	161.	161.	192.	279.	306.	328.
	24″	24 5/8″	29″	7/16″	**DP3PSB( )2824**	185.	185.	230.	325.	372.	406.
	30″	29 5/8″	29″	7/16″	**DP3PSB( )2830**	199.	228.	248.	350.	406.	440.
	36″	35 5/8″	29″	7/16″	**DP3PSB( )2836**	220.	248.	277.	386.	440.	488.
	42″	41 5/8″	29″	7/16″	**DP3PSB( )2842**	227.	251.	277.	402.	442.	493.
	48″	47 5/8″	29″	7/16″	**DP3PSB( )2848**	232.	265.	290.	417.	472.	516.
D2 14″ High Perforated Steel Insert 	18″	17 5/8″	14 3/16″	7/16″	**DP2PS( )1418**	102.	114.	119.	193.	208.	217.
	24″	23 5/8″	14 3/16″	7/16″	**DP2PS( )1424**	136.	147.	157.	254.	283.	295.
	30″	29 5/8″	14 3/16″	7/16″	**DP2PS( )1430**	138.	151.	159.	260.	285.	298.
	36″	35 5/8″	14 3/16″	7/16″	**DP2PS( )1436**	140.	153.	163.	263.	289.	300.
	42″	41 5/8″	14 3/16″	7/16″	**DP2PS( )1442**	140.	156.	163.	266.	294.	307.
	48″	47 5/8″	14 3/16″	7/16″	**DP2PS( )1448**	144.	159.	166.	271.	298.	312.

Ordering Information

Perforated Steel Insert

1. Pattern number
2. Paint finish

Order Code

Perforated Steel Insert

Example: **DP3PBS21430 117**

DP3 PSB21430	Pattern number
117	Soft Grey paint

Included with:

Perforated Steel Insert

Options

Perforated Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14″, Worksurface Height, 24″ and 28″. To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

Tile to Floor Option not available on DP2 perforated steel tile insert.

Steel Insert Kits
7″, 10″, 14″ and 21″ High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7″ High Embossed Steel Insert	15″	14 5/8″	7 3/16″	7/16″	**DP3ESB( )715**	$83.	$95.	$116.	$368.	$426.	$503.
	18″	17 5/8″	7 3/16″	7/16″	**DP3ESB( )718**	83.	95.	116.	368.	426.	503.
	24″	23 5/8″	7 3/16″	7/16″	**DP3ESB( )724**	89.	109.	119.	388.	480.	526.
	30″	30 5/8″	7 3/16″	7/16″	**DP3ESB( )730**	97.	122.	129.	436.	543.	587.
	36″	35 5/8″	7 3/16″	7/16″	**DP3ESB( )736**	118.	136.	145.	503.	587.	633.
	42″	41 5/8″	7 3/16″	7/16″	**DP3ESB( )742**	125.	141.	155.	543.	617.	678.
	48″	47 5/8″	7 3/16″	7/16″	**DP3ESB( )748**	128.	147.	159.	572.	656.	708.
D3 10″ High Embossed Steel Insert	15″	14 5/8″	10 3/16″	7/16″	**DP3ESB( )1015**	118.	132.	138.	518.	587.	610.
	18″	17 5/8″	10 3/16″	7/16″	**DP3ESB( )1018**	118.	132.	138.	518.	587.	610.
	24″	23 5/8″	10 3/16″	7/16″	**DP3ESB( )1024**	125.	140.	145.	549.	633.	656.
	30″	29 5/8″	10 3/16″	7/16″	**DP3ESB( )1030**	126.	145.	152.	572.	664.	687.
	36″	35 5/8″	10 3/16″	7/16″	**DP3ESB( )1036**	138.	159.	167.	610.	701.	730.
	42″	41 5/8″	10 3/16″	7/16″	**DP3ESB( )1042**	144.	165.	179.	641.	730.	801.
	48″	47 5/8″	10 3/16″	7/16″	**DP3ESB( )1048**	152.	181.	192.	687.	823.	862.
D3 14″ High Embossed Steel Insert	15″	14 5/8″	14 3/16″	7/16″	**DP3ESB( )1415**	118.	132.	138.	518.	587.	610.
	18″	17 5/8″	14 3/16″	7/16″	**DP3ESB( )1418**	118.	132.	138.	518.	587.	610.
	24″	23 5/8″	14 3/16″	7/16″	**DP3ESB( )1424**	125.	140.	145.	549.	633.	656.
	30″	29 5/8″	14 3/16″	7/16″	**DP3ESB( )1430**	126.	145.	152.	572.	664.	687.
	36″	35 5/8″	14 3/16″	7/16″	**DP3ESB( )1436**	138.	159.	167.	610.	701.	730.
	42″	41 5/8″	14 3/16″	7/16″	**DP3ESB( )1442**	144.	165.	179.	641.	730.	801.
	48″	47 5/8″	14 3/16″	7/16″	**DP3ESB( )1448**	152.	181.	192.	687.	823.	862.
D3 21″ Embossed Steel Insert	15″	14 5/8″	21″	7/16″	**DP3ESB( )2115**	149.	176.	193.	770.	906.	985.
	18″	17 5/8″	21″	7/16″	**DP3ESB( )2118**	149.	176.	193.	770.	906.	985.
	24″	23 5/8″	21″	7/16″	**DP3ESB( )2124**	183.	210.	230.	962.	1,099.	1,204.
	30″	29 5/8″	21″	7/16″	**DP3ESB( )2130**	198.	228.	246.	1,028.	1,204.	1,298.
	36″	35 5/8″	21″	7/16″	**DP3ESB( )2136**	220.	248.	277.	1,143.	1,298.	1,442.
	42″	41 5/8″	21″	7/16″	**DP3ESB( )2142**	227.	250.	278.	1,191.	1,319.	1,465.
	48″	47 5/8″	21″	7/16″	**DP3ESB( )2148**	232.	265.	289.	1,236.	1,411.	1,534.

Ordering Information

Embossed Steel Insert

1. Pattern number
2. Paint finish

Order Code

Embossed Steel Insert

Example: **DP3ESB21430 117**

DP3	Pattern number
ESB21430	
117	Soft Grey paint

Included with:

Embossed Steel Insert

Options

Embossed Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14″, Worksurface Height, 24″ and 28″. To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

Steel Insert Kits
Worksurface Height and 28″ High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Embossed Steel Insert	15″	14 5/8″	22 1/2″	7/16″	**DP3ESB( )WH15**	$149.	$176.	$193.	$256.	$302.	$328.
	18″	17 5/8″	22 1/2″	7/16″	**DP3ESB( )WH18**	149.	176.	193.	256.	302.	328.
	24″	23 5/8″	22 1/2″	7/16″	**DP3ESB( )WH24**	183.	210.	230.	321.	368.	402.
	30″	39 5/8″	22 1/2″	7/16″	**DP3ESB( )WH30**	198.	228.	246.	344.	402.	433.
	36″	35 5/8″	22 1/2″	7/16″	**DP3ESB( )WH36**	220.	248.	277.	381.	433.	480.
	42″	41 5/8″	22 1/2″	7/16″	**DP3ESB( )WH42**	227.	250.	278.	397.	440.	488.
	48″	47 5/8″	22 1/2″	7/16″	**DP3ESB( )WH48**	232.	265.	289.	413.	470.	512.
D3 28″ High Embossed Steel Insert	15″	14 5/8″	29″	7/16″	**DP3ESB( )2815**	161.	161.	192.	279.	306.	328.
	18″	17 5/8″	29″	7/16″	**DP3ESB( )2818**	161.	161.	192.	279.	306.	328.
	24″	23 5/8″	29″	7/16″	**DP3ESB( )2824**	185.	185.	230.	325.	372.	406.
	30″	29 5/8″	29″	7/16″	**DP3ESB( )2830**	199.	228.	248.	350.	406.	440.
	36″	35 5/8″	29″	7/16″	**DP3ESB( )2836**	220.	248.	277.	386.	440.	488.
	42″	41 5/8″	29″	7/16″	**DP3ESB( )2842**	227.	251.	277.	402.	442.	493.
	48″	47 5/8″	29″	7/16″	**DP3ESB( )2848**	232.	265.	290.	417.	472.	516.

Ordering Information

Embossed Steel Insert

1. Pattern number
2. Paint finish

Order Code

Embossed Steel Insert

Example:	**DP3ESB22130 117**
DP3 ESB22130	Pattern number
117	Soft Grey paint

Included with:

Embossed Steel Insert

Options

Embossed Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:
Tile to Floor available in heights of 14″, Worksurface Height, 24″ and 28″. To specify tile to floor, add an 'F' suffix to the pattern number and add $16 for a single pack, $31 for a double pack and $95 for a 6 pack to the list price.

This page intentionally left blank

Slatwall Tiles
Specifications

Slatwall Tiles
Slatwall tiles are designed to support KnollExtra Orchestra work tools. Slatwall tiles will support flat panel monitor arms with varying weight limitations based on mounting and application. Please refer to the KnollExtra price list for comprehensive mounting and weight limitation information by application. Slatwall kits include all mounting brackets and hardware for installation, and are fully assembled. SLATWALL TILES INCLUDE INTEGRAL TILE SUPPORT(S).

Slatwall tiles are field installed on Dividends Horizon DP7 panel frames. To specify, select the slatwall width to match the width of the panel frame, in either top or middle position locations.

Specify slatwall tiles along with built-to-spec panel frames and other tiles for a complete panel. Slatwall tiles may not be specified directly above or below other slatwall tiles, beltway, stack frames, or stacking screens. Slatwall tiles may not be specified on stack frames

Construction
Slatwall is constructed of heat treated extruded aluminum, powder coated in any Knoll Core paint color. 16 gauge steel reinforcements with integral hooks and tri-lobular screws on the back of slatwall provide reinforcement for heavy loads.

N**ote**: Due to design improvements with the slatwall tile, monitor arm reinforcements are no longer required when hanging monitor arms from Dividends Horizon slatwall.

Top Position Slatwall Tiles
Top position slatwall tiles may be installed at the top of any Dividends Horizon DP7 panel frame, and include all required hardware. Top position slatwall is available in heights of 7, 14, 21 and 28 inches.

TOP POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE BOTTOM, REPLACING THE SEPARATE D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.

Middle Position Slatwall Tiles
Middle position slatwall tiles may be installed at the middle of any Dividends Horizon DP7 panel frame, and include all necessary hardware. Middle position slatwall is available in heights of 7, 14 and 21 inches.

MIDDLE POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE TOP AND BOTTOM, REPLACING D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.

Top Position Slatwall



Middle Position Slatwall



Slatwall Tiles
7″, 14″, 21″ and 28″ High

description	w	h	d	pattern no.	P1	P2	P3
7″ High Slatwall Tile	24″	7″	7/16″	**DP1SW0724( )**	$206.	$226.	$236.
	30″	7″	7/16″	**DP1SW0730( )**	219.	243.	252.
	36″	7″	7/16″	**DP1SW0736( )**	236.	259.	269.
	42″	7″	7/16″	**DP1SW0742( )**	249.	273.	285.
	48″	7″	7/16″	**DP1SW0748( )**	263.	289.	301.
14″ High Slatwall Tile	24″	14″	7/16″	**DP1SW1424( )**	276.	304.	333.
	30″	14″	7/16″	**DP1SW1430( )**	325.	357.	388.
	36″	14″	7/16″	**DP1SW1436( )**	373.	410.	448.
	42″	14″	7/16″	**DP1SW1442( )**	407.	448.	486.
	48″	14″	7/16″	**DP1SW1448( )**	441.	484.	531.
21″ High Slatwall Tile	24″	21″	7/16″	**DP1SW2124( )**	366.	402.	439.
	30″	21″	7/16″	**DP1SW2130( )**	440.	482.	526.
	36″	21″	7/16″	**DP1SW2136( )**	513.	565.	616.
	42″	21″	7/16″	**DP1SW2142( )**	567.	623.	680.
	48″	21″	7/16″	**DP1SW2148( )**	618.	681.	744.
28″ Top Position Slatwall Tile	24″	28″	7/16″	**DP1SW2824( )**	454.	501.	546.
	30″	28″	7/16″	**DP1SW2830( )**	553.	608.	663.
	36″	28″	7/16″	**DP1SW2836( )**	652.	716.	782.
	42″	28″	7/16″	**DP1SW2842( )**	723.	794.	866.
	48″	28″	7/16″	**DP1SW2848( )**	793.	873.	952.

Ordering Information

Post Assemblies

1. Pattern Number
2. Paint Finish

Order Code

Post Assemblies

Example: **DP1 S2824T, 111**

DP1 S2824	Pattern Number
T	
111	Jet Black Paint

Included with:

Note: Middle position slatwall tiles are able to be used on topway or full view panels.

Options

Panel Options:
(T) = for topway panel top position
(F) = for full view panel top position
(M) = for middle position

Technology Tiles
Specifications

Technology Tile
Dividends Horizon technology tiles are 14", worksurface height or 28" high fabric or painted steel tiles with a factory installed technology port for above worksurface power and/or data access. Technology ports may be specified on the left, right, or both sides of technology tiles.

Each technology port has two openings: duplex power receptacles are positioned to the outside of the panel, while data ports may be positioned in either of the two positions. For applications where only one of the two openings is used, a knockout filler is included with each data port to fill this opening.

Technology tiles with one port accommodate one power and one data or two data outlets. Technology tiles with two ports accommodate up to two power receptacles and two data outlets, or four data outlets.

Specify vertical power modules, power receptacles, and data components separately.

Construction
Steel inserts are made of 20-gauge formed painted steel. Fabric inserts are made with a roll-coat adhesive, heat-cured to $^{7}/_{16}$" thick tackable acoustical board.

Available Sizes
Heights: 14", worksurface height, 28"
Widths: 18", 24", 30", 42", 48" and 60"

Note: Steel technology tiles are only available in Knoll Core finishes

Note: Technology tiles are not able to be specified in the top position of 36" high topway panel.

14" High Technology Tile



Worksurface Height Technology Tile



28" High Technology Tile



Technology Tiles
Fabric

description	h	w	pattern no.	grade 10	15	20	25	30	35	40	45
14″ High, Technology Tile Fabric	14″	18″	**DP6TF( )1418**	$153.	$157.	$163.	$164.	$167.	$170.	$171.	$175.
	14″	24″	**DP6TF( )1424**	160.	163.	168.	170.	172.	177.	179.	184.
	14″	30″	**DP6TF( )1430**	163.	165.	171.	175.	178.	181.	184.	188.
	14″	36″	**DP6TF( )1436**	167.	171.	178.	179.	185.	188.	200.	201.
	14″	42″	**DP6TF( )1442**	171.	175.	184.	185.	197.	201.	204.	207.
	14″	48″	**DP6TF( )1448**	178.	179.	193.	200.	204.	205.	208.	214.
	14″	60″	**DP6TF( )1460**	184.	186.	194.	195.	198.	200.	202.	205.
Worksurface Height, Technology Tile Fabric	22½″	18″	**DP6TF( )WH18**	201.	207.	211.	218.	221.	227.	235.	241.
	22½″	24″	**DP6TF( )WH24**	219.	227.	241.	248.	256.	260.	266.	279.
	22½″	30″	**DP6TF( )WH30**	234.	241.	256.	263.	271.	279.	285.	297.
	22½″	36″	**DP6TF( )WH36**	246.	256.	271.	281.	294.	301.	307.	314.
	22½″	42″	**DP6TF( )WH42**	253.	261.	273.	283.	296.	303.	311.	323.
	22½″	48″	**DP6TF( )WH48**	261.	271.	285.	297.	304.	312.	324.	341.
	22½″	60″	**DP6TF( )WH60**	276.	286.	299.	312.	314.	325.	340.	367.
28″ High, Technology Tile Fabric	28″	18″	**DP6TF( )2818**	201.	207.	211.	218.	221.	227.	235.	241.
	28″	24″	**DP6TF( )2824**	219.	227.	241.	248.	256.	260.	266.	279.
	28″	30″	**DP6TF( )2830**	234.	241.	256.	263.	271.	279.	285.	297.
	28″	36″	**DP6TF( )2836**	246.	256.	271.	281.	294.	301.	307.	314.
	28″	42″	**DP6TF( )2842**	253.	261.	273.	283.	296.	303.	311.	323.
	28″	48″	**DP6TF( )2848**	261.	271.	285.	297.	304.	312.	324.	341.
	28″	60″	**DP6TF( )2860**	294.	300.	310.	314.	321.	327.	332.	338.

Ordering Information

Technology Tile Fabric:

1. Pattern Number
2. Fabric
3. Bezel location

Order Code

Technology Tile Fabric

Example:	**DP3TFL1418/ W352-4**
DP3TF	Technology Tile Fabric
L	Left Hand Bezel Location
14	Heigh
18	Width
W352-4	Labrynth Sage Fabric

Included with:

Technology Tile Fabric

- Fabric Technology Tile
- Bezel

Options

Technology Tile Fabric

Bezel Location Options:
(L) = Left Hand Bezel
(R) = Right Hand Bezel
(D) = Double Bezel - add $43

Tile to Floor Options:
Tile to Floor available in heights of 14″, Worksurface Height, and 28″. To specify tile to floor, add an "F" suffix to the pattern number and add $10 to the list price.

Technology Tiles
Steel

description	h	w	pattern no.	P1	P2	P3
14″ High, Technology Tile Steel	14″	18″	**DP6TS( )1418**	$134.	$142.	$145.
	14″	24″	**DP6TS( )1424**	140.	147.	152.
	14″	30″	**DP6TS( )1430**	141.	149.	153.
	14″	36″	**DP6TS( )1436**	149.	158.	164.
	14″	42″	**DP6TS( )1442**	152.	163.	167.
	14″	48″	**DP6TS( )1448**	158.	169.	173.
	14″	60″	**DP6TS( )1460**	168.	178.	182.
Worksurface Height, Technology Tile Steel	22½″	18″	**DP6TS( )WH18**	164.	173.	178.
	22½″	24″	**DP6TS( )WH24**	179.	194.	199.
	22½″	30″	**DP6TS( )WH30**	188.	201.	207.
	22½″	36″	**DP6TS( )WH36**	203.	218.	225.
	22½″	42″	**DP6TS( )WH42**	207.	222.	230.
	22½″	48″	**DP6TS( )WH48**	211.	226.	234.
	22½″	60″	**DP6TS( )WH60**	211.	226.	234.
28″ High, Technology Tile Steel	28″	18″	**DP6TS( )2818**	164.	173.	178.
	28″	24″	**DP6TS( )2824**	179.	194.	199.
	28″	30″	**DP6TS( )2830**	188.	201.	207.
	28″	36″	**DP6TS( )2836**	203.	218.	225.
	28″	42″	**DP6TS( )2842**	207.	222.	230.
	28″	48″	**DP6TS( )2848**	211.	226.	234.

Ordering Information

Technology Tile Steel

1. Pattern Number
2. Paint
3. Bezel location

Order Code

Technology Tile Steel

Example:	**DP3TSL1418/ 113**
DPSTS	Technology Tile Steel
L	Left Hand Bezel Location
14	Heigh
18	Width
113	Dark Grey Paint Finish

Included with:

Technology Tile Steel

- Steel Technology Tile
- Bezel

Note: Steel technology tiles are only available in Knoll core finishes.

Options

Technology Tile Steel

Bezel Location Options:
(L) = Left Hand Bezel
(R) = Right Hand Bezel
(D) = Double Bezel - add $43

Tile to Floor Options:
Tile to Floor available in heights of 14″, Worksurface Height, and 28″. To specify tile to floor, add an “F” suffix to the pattern number and add $16 to the list price.

This page intentionally left blank

Rolling Door
Specifications

Dividends Horizon rolling doors were developed for clients desiring increased privacy for focused work.

Rolling doors are available in 57, 64 and 78" overall heights, and widths to accommodate panel openings of 36 and 42 inches.

Planning
Rolling doors must be mounted to the end of an equal height Dividends Horizon panel or run of panels of equal or greater width. Doors may not be mounted to Dividends Horizon screens or universal posts.

Door jamb may be mounted directly to DP7 series universal posts – specify jamb to post attachment kit separately.

When fully open, the door will extend 2" beyond the end of the panel end trim on a panel of corresponding width.

Thresholds are included with door pattern number, and are required in all installations. The Dividends Horizon rolling door meets ADA 5 lb pull test requirements when used with the supplied threshold.

Specifying 57" and 64" Rolling Doors
57" and 64" rolling doors include:

- Rolling door
- Mounting brackets
- Door jamb (for door side opposite to mounting brackets)
- Threshold

To complete the specification, specify an end trim for the panel to which the door is mounted, and a jamb-compatible top cap for the panel to which the door jamb is attached.

Specifying 78" Rolling Doors
78" rolling doors include:

- Rolling door
- Header
- Mounting brackets,
- Door jamb (for door side opposite to mounting brackets)
- Panel end trim
- Threshold

78" high doors include a header, with vertical clearance of 76 1/2" from height of finished floor. Specify a top cap for the header separately. Extended length top caps are recommended in this application.

No additional end trim is required for 78" high doors, as it is included in the door pattern number.

Construction
Rolling door and door jamb are constructed of extruded aluminum, powder coated in any Knoll Core paint finish. Threshold is anodized extruded aluminum.

Door inserts are available in clear, powder or bronze frosted glass.

Locks are optional, and engage with door jamb. Standard KnollKey system keying guidelines apply.

Rolling Door
57″, 64″ and 78″ High

description	type	w	d	h	pattern no.	Temp	GL13 GL25	Plastic	Metal P1	Metal P2	Metal P3
Rolling Door	57″ High with lock	36″	3″	57″	**DPRD15736(L/R)L**	$2,454.	$2,528.				
		42″	3″	57″	**DPRD15742(L/R)L**	2,666.	2,739.				
	57″ High no lock	36″	3″	57″	**DPRD15736(L/R)N**	2,377.	2,450.				
		42″	3″	57″	**DPRD15742(L/R)N**	2,588.	2,662.				
	64″ High with lock	36″	3″	64″	**DPRD16436(L/R)L**	2,554.	2,645.				
		42″	3″	64″	**DPRD16442(L/R)L**	2,766.	2,856.				
	64″ High no lock	36″	3″	64″	**DPRD16436(L/R)N**	2,477.	2,568.				
		42″	3″	64″	**DPRD16442(L/R)N**	2,688.	2,779.				
	78″ High with lock	36″	3″	78″	**DPRD17836(L/R)L**	2,969.	3,093.				
		42″	3″	78″	**DPRD17842(L/R)L**	3,181.	3,304.				
	78″ High no lock	36″	3″	78″	**DPRD17836(L/R)N**	2,892.	3,016.				
		42″	3″	78″	**DPRD17842(L/R)N**	3,103.	3,227.				
Panel Top Caps for Jamb Side		18″			**DP( )PT18RD**			34.	61.	63.	65.
		24″			**DP( )PT24RD**			36.	61.	63.	65.
		30″			**DP( )PT30RD**			40.	61.	63.	65.
		36″			**DP( )PT36RD**			42.	61.	63.	65.
		42″			**DP( )PT42RD**			42.	61.	63.	65.
		48″			**DP( )PT48RD**			43.	61.	63.	65.
		54″			**DP( )PT54RD**			n/a	65.	67.	69.
		60″			**DP( )PT60RD**			47.	68.	70.	72.
		66″			**DP( )PT66RD**			n/a	72.	75.	78.
		72″			**DP( )PT72RD**			n/a	77.	81.	85.
		78″			**DP( )PT78RD**			n/a	84.	88.	91.
		84″			**DP( )PT84RD**			n/a	90.	93.	97.
		90″			**DP( )PT90RD**			n/a	96.	100.	103.
		96″			**DP( )PT96RD**			n/a	101.	106.	110.
Door Jamb Kit to mount to DP7 Post					**DPRD1JPM**			21.	0.	0.	0.

right hand shown

Ordering Information

Rolling Door

1. Pattern Number
2. Glass type

Top Cap

1. Pattern Number
2. Paint finish

Order Code

Rolling Door

Example:	**DPRD1 5736 RL**
DPRD1	Rolling Door
57	Height
36	Width
R	Right
L	Lock
118T	Bright White Textured
GL13	Frosted Glass

Included With:

Rolling Door

57″ and 64″ High

- Rolling Door
- Mounting Brackets
- Door jamb
- Threshold

78″ High

- Rolling Door
- Header
- Mounting Brackets
- Door jamb
- Panel end trim
- Threshold

Top Cap

- Top Cap
- End Plug

Options

Rolling Door

Mounting Options:
L = Left Hand
R = Right Hand

Paint Finish:
All Core paint finishes

Glass Type:
Temp = Clear Glass
GL13 = Frosted Glass
GL25 = Bronze Glass

Top Cap
Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(4) = Radius Metal
(5) = Flat Metal

Open Weave and Glass Screens
Specifications

Open Weave Screens
Open Weave screens are designed to allow light and transparency into the workstation, while providing limited visual privacy. When combined with Dividends Horizon freestanding components, open weave screen provide a layered aesthetic to the office.

Open Weave Screen Construction
Open weave screens feature Warp Net, a new open textile structure designed by Suzanne Tick. Warp net is constructed of 100% Earthtex, made from Olefin. Earthtex has passed the prestigious McDonough Braungart Design Chemistry Sustainability Protocol, and is fully recyclable.

Open weave screens have a triangular profile frame, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish.

Open Weave Screen Dimensions:
Widths: 24, 30, 36, 42, and 48 inches
Heights: 36, 42, 50, 57, and 64 inches
Thickness: 3 inches

Glass Screens
Glass Screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Glass Screen Construction
Glass screens are available in both triangular and rectangular frame profiles, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish. Glass is 4mm thick tempered glass.

Glass Screen Dimensions
Widths: 24, 30, 36, 42 and 48 inches
Heights: 42, 50, 57 and 64 inches
Thickness: 3 inches

Planning With Screens
Dividends Horizon open weave and glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components. Screens feature slots to allow use of a mid-span worksurface support at the standard 28 1/2" H worksurface height.

Screens attach to Dividends Horizon panels or connecting posts of the same or greater height, or other screens of the same height. In a “high/low” situation, screens do not attach to higher or lower screens, or lower panels. Screens ship with attachment hardware and topcap, if specified.

Open Weave Screen with Triangular Frame and Open Base Option



Glass Screen with Rectangular Frame and Open Base Option



Screen Base Options
Open weave screens are available with three base options: base raceway, open base, or frame to floor. Triangular frame glass screens are available with three base options: base raceway, open base, or frame to floor. Rectangular frame glass screens are available with two base options: base raceway or open base. All bases feature leveling glides with 2" of vertical travel. Raceway covers are standard without knockouts. Screens support electrical pass-thru's, but do not support power modules or electrical receptacles.

Note: 36"H screen may not be connected to a Legacy post.

Note: 64" open weave screen "L" or "U" configurations require minimum 36" wide panel return(s).

Note: Raceway covers are not available with knockouts.

Note: Screens are only available in Knoll core finishes.

Freestanding Open Weave Screen Kits
When used with Open Weave Screens with frame-to-floor (FF) option, new Freestanding Open Weave Screen kits allow open weave screens to be used in freestanding applications, creating a sense of enclosure without the need for conventional panel or screen planning.

Freestanding Open Weave Screen Kits may be used with open weave screens only, and are not compatible with panels or glass screens.

A single open weave screen of any height or width may become freestanding by specifying the appropriately sized freestanding open weave screen kit. Freestanding open weave screen kits for single screen applications include (2) flat steel feet and (1) ballast plate. The width of the screen determines which freestanding open weave screen kit is specified. For example, a 48" wide open weave screen would use DP7SWTFK48.

Two open weave screens of the same height and width may be attached together to create a double freestanding open weave screen. There is a single pattern number (DP7SWTFKD) for the freestanding open weave screen kit that should be specified to create a double freestanding open weave screen. The double freestanding open weave screen kit includes (3) flat steel feet.

Note: Freestanding open weave screen kits are finished with textured paint, including 613 silver.

Freestanding Open Weave Screen Kit Dimensions

Flat Steel Feet
Width: 4 inches
Thickness: 7/16 inches
Depth: 20 inches

Freestanding Open Weave Screen (Double Screen)



Open Weave and Glass Screens
Open Weave Screens
36", 42", 50" and 57" High

description	h	w	t	pattern no.	P1	P2	P3
36″ High Open Weave Screen	36″	24″	3″	**DP7SWT( )3624**	$957.	$975.	$995.
	36″	30″	3″	**DP7SWT( )3630**	1,053.	1,073.	1,095.
	36″	36″	3″	**DP7SWT( )3636**	1,054.	1,074.	1,096.
	36″	42″	3″	**DP7SWT( )3642**	1,102.	1,123.	1,146.
	36″	48″	3″	**DP7SWT( )3648**	1,149.	1,174.	1,197.
42″ High Open Weave Screen	42″	24″	3″	**DP7SWT( )4224**	1,032.	1,053.	1,073.
	42″	30″	3″	**DP7SWT( )4230**	1,099.	1,121.	1,143.
	42″	30″	3″	**DP7SWT( )4236**	1,169.	1,190.	1,214.
	42″	42″	3″	**DP7SWT( )4242**	1,178.	1,202.	1,226.
	42″	48″	3″	**DP7SWT( )4248**	1,189.	1,213.	1,236.
50″ High Open Weave Screen	50″	24″	3″	**DP7SWT( )5024**	1,108.	1,129.	1,152.
	50″	30″	3″	**DP7SWT( )5030**	1,146.	1,171.	1,194.
	50″	36″	3″	**DP7SWT( )5036**	1,185.	1,208.	1,232.
	50″	42″	3″	**DP7SWT( )5042**	1,256.	1,279.	1,305.
	50″	48″	3″	**DP7SWT( )5048**	1,324.	1,350.	1,377.
57″ High Open Weave Screen	57″	24″	3″	**DP7SWT( )5724**	1,129.	1,152.	1,175.
	57″	30″	3″	**DP7SWT( )5730**	1,201.	1,226.	1,248.
	57″	36″	3″	**DP7SWT( )5736**	1,272.	1,298.	1,323.
	57″	42″	3″	**DP7SWT( )5742**	1,298.	1,324.	1,349.
	57″	48″	3″	**DP7SWT( )5748**	1,324.	1,350.	1,377.

*Note: Frame to the floor shown

Ordering Information

Open Weave Screen:

1. Pattern number
2. Frame finish
3. Top cap style
4. Top cap finish
5. Base finish
6. Fabric finish

Order Code

Open Weave Screen:

Example:	**DP7SWTFF3636 117/4/117/117/W1113-1**
DP7SWT	Triangular open weave screen
FF	Screen to Floor
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish
W1113-1	Warp Net White

Included with:

Open Weave Screen

Note: 36″h screens are not compatible with Legacy post connectors.

Note: Screens are only available in Knoll core finishes.

Options

Open Weave Screen

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grade

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens
Open Weave Screens
64″ High and Freestanding Open Weave Screen Kits

description	type	h	w	d	pattern no.	P1	P2	P3
64″ High Open Weave Screen		64″	24″	3″	**DP7SWT( )6424**	$1,149.	$1,174.	$1,197.
		64″	30″	3″	**DP7SWT( )6430**	1,257.	1,280.	1,306.
		64″	36″	3″	**DP7SWT( )6436**	1,323.	1,349.	1,375.
		64″	42″	3″	**DP7SWT( )6442**	1,341.	1,367.	1,395.
		64″	48″	3″	**DP7SWT( )6448**	1,359.	1,387.	1,413.
Freestanding Open Weave Screen Kit	For use with 2 open weave screens				**DP7SWTFKD**	446.	490.	509.
	For use with 24″ wide open weave screen				**DP7SWTFK24**	416.	457.	475.
	For use with 30″ wide open weave screen				**DP7SWTFK30**	421.	464.	481.
	For use with 36″ wide open weave screen				**DP7SWTFK36**	432.	475.	494.
	For use with 42″ wide open weave screen				**DP7SWTFK42**	446.	490.	509.
	For use with 48″ wide open weave screen				**DP7SWTFK48**	446.	490.	509.

(single screen kit shown)

Ordering Information

Open Weave Screen:

1. Pattern number
2. Frame finish
3. Top cap style
4. Top cap finish
5. Base finish
6. Fabric finish

Freestanding Open Weave Screen Kits

1. Pattern number
2. Paint finish

Order Code

Open Weave Screen:

Example:	**DP7SWTFF3636 117/4/117/117/W1113-1**
DP7SWT	Triangular open weave screen
FF	Screen to Floor
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish
W1113-1	Warp Net White

Included with:

Open Weave Screen

Note: Freestanding open weave screen kits are finished with textured paint, including 613 Silver.

Note: Freestanding open weave screen kits only work with open weave screens with frame-to-floor (FF) base option.

Options:

Open Weave Screen

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grade

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens
Triangular Frame Screen with Glass 42″ and 50″ High

description	h	w	t	pattern no.	P1	P2	P3
42″ High Triangular Frame Screen with Glass 	42″	24″	3″	**DP7S( )T( )4224**	$971.	$991.	$1,010.
	42″	30″	3″	**DP7S( )T( )4230**	1,028.	1,050.	1,069.
	42″	36″	3″	**DP7S( )T( )4236**	1,088.	1,109.	1,130.
	42″	42″	3″	**DP7S( )T( )4242**	1,110.	1,133.	1,154.
	42″	48″	3″	**DP7S( )T( )4248**	1,133.	1,154.	1,177.
50″ High Triangular Frame Screen with Glass	50″	24″	3″	**DP7S( )T( )5024**	1,044.	1,065.	1,087.
	50″	30″	3″	**DP7S( )T( )5030**	1,071.	1,093.	1,113.
	50″	36″	3″	**DP7S( )T( )5036**	1,098.	1,119.	1,141.
	50″	42″	3″	**DP7S( )T( )5042**	1,190.	1,213.	1,236.
	50″	48″	3″	**DP7S( )T( )5048**	1,277.	1,304.	1,329.

*Note: Frame with raceway covers shown

Ordering Information

Triangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Triangular Frame with Glass:

Example:	**DP7SGTRR4236 117/4/117/117**
DP7SGT	Triangular frame with clear glass
RR	Raceway type
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish

Included with:

Triangular Frame with Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:
(G) = Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base

Frame to floor option not available on Triangular glass screens.

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens
Triangular Frame Screen with Glass 57″ and 64″ High

description	h	w	t	pattern no.	P1	P2	P3
57″ High Triangular Frame Screen with Glass 	57″	24″	3″	**DP7S( )T( )5724**	$1,071.	$1,093.	$1,113.
	57″	30″	3″	**DP7S( )T( )5730**	1,130.	1,152.	1,175.
	57″	36″	3″	**DP7S( )T( )5736**	1,191.	1,214.	1,238.
	57″	42″	3″	**DP7S( )T( )5742**	1,238.	1,262.	1,286.
	57″	48″	3″	**DP7S( )T( )5748**	1,283.	1,310.	1,335.
64″ High Triangular Frame Screen with Glass	64″	24″	3″	**DP7S( )T( )6424**	1,097.	1,118.	1,140.
	64″	30″	3″	**DP7S( )T( )6430**	1,190.	1,213.	1,236.
	64″	36″	3″	**DP7S( )T( )6436**	1,279.	1,307.	1,332.
	64″	42″	3″	**DP7S( )T( )6442**	1,284.	1,311.	1,337.
	64″	48″	3″	**DP7S( )T( )6448**	1,289.	1,315.	1,341.

*Note: Frame to the floor shown

Ordering Information

Triangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Triangular Frame with Glass:

Example:	**DP7SGTRR5736 117/4/117/117**
DP7SGT	Triangular frame with clear glass
RR	Raceway type
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish

Included with:

Triangular Frame with Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:
(G) = Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:
(2)= Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens
Rectangular Frame Screen with Glass 42″ and 50″ High

description	h	w	t	pattern no.	P1	P2	P3
42″ High Rectangular Frame Screen with Glass 	42″	24″	3″	**DP7S( )R( )4224**	$977.	$996.	$1,017.
	42″	30″	3″	**DP7S( )R( )4230**	1,036.	1,056.	1,077.
	42″	36″	3″	**DP7S( )R( )4236**	1,096.	1,117.	1,139.
	42″	42″	3″	**DP7S( )R( )4242**	1,118.	1,140.	1,162.
	42″	48″	3″	**DP7S( )R( )4248**	1,141.	1,164.	1,189.
50″ High Rectangular Frame Screen with Glass	50″	24″	3″	**DP7S( )R( )5024**	1,053.	1,074.	1,096.
	50″	30″	3″	**DP7S( )R( )5030**	1,080.	1,103.	1,125.
	50″	36″	3″	**DP7S( )R( )5036**	1,108.	1,130.	1,152.
	50″	42″	3″	**DP7S( )R( )5042**	1,200.	1,225.	1,247.
	50″	48″	3″	**DP7S( )R( )5048**	1,291.	1,317.	1,343.

Ordering Information

Rectangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Rectangular Frame with Glass:

Example:	**DP7SGRRR4236 117/4/117/117**
DP7SGR	Rectangular frame screen with clear glass
RR	Raceway type
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish

Included with:

Rectangular Frame Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Type:
(RR) = Raceway covers no knockouts
(LL) = Open base

Frame to floor option not available on Rectangular glass screens.

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens
Rectangular Frame Screen with Glass 57″ and 64″ High

description	h	w	t	pattern no.	P1	P2	P3
57″ High Rectangular Frame Screen with Glass 	57″	24″	3″	**DP7S( )R( )5724**	$1,078.	$1,101.	$1,122.
	57″	30″	3″	**DP7S( )R( )5730**	1,140.	1,163.	1,188.
	57″	36″	3″	**DP7S( )R( )5736**	1,201.	1,226.	1,248.
	57″	42″	3″	**DP7S( )R( )5742**	1,248.	1,273.	1,300.
	57″	48″	3″	**DP7S( )R( )5748**	1,298.	1,321.	1,348.
64″ High Rectangular Frame Screen with Glass	64″	24″	3″	**DP7S( )R( )6424**	1,104.	1,127.	1,147.
	64″	30″	3″	**DP7S( )R( )6430**	1,199.	1,224.	1,246.
	64″	36″	3″	**DP7S( )R( )6436**	1,292.	1,318.	1,344.
	64″	42″	3″	**DP7S( )R( )6442**	1,298.	1,321.	1,348.
	64″	48″	3″	**DP7S( )R( )6448**	1,301.	1,326.	1,351.

Ordering Information

Rectangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Rectangular Frame with Glass:

Example:	**DP7SGRRR5736 117/4/117/117**
DP7SGR	Rectangular frame screen with clear glass
RR	Raceway type
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish

Included with:

Rectangular Frame Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:
(2) = Extruded Plastic (Smooth Radius)
(3) = No Top Cap
(4) = Radius Metal, add $38 P1, $40 P2, $42 P3
(5) = Flat Metal, add $38 P1, $40 P2, $42 P3 paint grades

Raceway Type:
(RR) = Raceway covers no knockouts
(LL) = Open base

Frame to floor option not available on Rectangular glass screens.

Note: Raceway covers are not available with knockouts.

Open Weave and Glass Stacking Screens
Specifications

Stacking Open Weave Screens
Stacking open weave screens are designed to allow light and transparency into the workstation, while providing limited visual privacy. When combined with Dividends Horizon freestanding components, open weave screens provide a layered aesthetic to the office.

Stacking Open Weave Screen Construction
Open weave screens feature Warp Net, a new open textile structure designed by Suzanne Tick. Warp Net is constructed of 100% Earthtex, made from Olefin. Earthtex has passed the prestigious McDonough Braungart Design Chemistry Sustainability Protocol, and is fully recyclable.

Open weave screens have a triangular profile frame, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish.

Stacking Glass Screens
Stacking glass screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Stacking Glass Screen Construction
Stacking glass screens are constructed of extruded aluminum frame members, powder coated in any Knoll Core paint finish. Clear glass is 4mm tempered glass.

Stacking Screen Dimensions:
Widths: 24, 30, 36, 42, and 48 inches
Heights: 14, 21 and 28 inches
Thickness: 3 inches

Planning With Stacking Screens
Dividends Horizon open weave and glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components.

Stacking screens attach to any Dividends Horizon DP7V series full view panel frame, and may be stacked one tier high. Stacking screens do not stack on topway panel frames.

Stacking screens attach to Dividends Horizon DP7V panels or connecting posts of the same or greater height, or other screens of the same height.

Note: Stacking screens may be used with DP7 full view panel frames only.

Note: Screens are only available in Knoll core finishes.

Note: Knoll's three window types are aesthetically and functionally different, and are not designed to be mixed together within a single installation.

Triangular Stack Panel Screen with Open Weave Fabric insert



Rectangular Stack Panel Screen with Glass insert



Open Weave and Glass Stacking Screens
Triangular Frame Stacking Screen with Open Weave Fabric

description	h	w	t	pattern no.	P1	P2	P3
14″ High Triangular Frame Stacking Screen with Open Weave Fabric	14″	24″	3″	**DP7SSWT1424**	$553.	$564.	$576.
	14″	30″	3″	**DP7SSWT1430**	585.	597.	608.
	14″	36″	3″	**DP7SSWT1436**	618.	630.	642.
	14″	42″	3″	**DP7SSWT1442**	642.	655.	667.
	14″	48″	3″	**DP7SSWT1448**	665.	678.	691.
21″ High Triangular Frame Stacking Screen with Open Weave Fabric	21″	24″	3″	**DP7SSWT2124**	593.	605.	617.
	21″	30″	3″	**DP7SSWT2130**	631.	643.	656.
	21″	36″	3″	**DP7SSWT2136**	670.	683.	695.
	21″	42″	3″	**DP7SSWT2142**	695.	712.	724.
	21″	48″	3″	**DP7SSWT2148**	721.	735.	752.
28″ High Triangular Frame Stacking Screen with Open Weave Fabric 	28″	24″	3″	**DP7SSWT2824**	632.	644.	658.
	28″	30″	3″	**DP7SSWT2830**	677.	690.	703.
	28″	36″	3″	**DP7SSWT2836**	721.	735.	752.
	28″	42″	3″	**DP7SSWT2842**	752.	765.	781.
	28″	48″	3″	**DP7SSWT2848**	779.	794.	811.

Ordering Information

Triangular Frame Stacking Screen with Open Weave Fabric:

1. Pattern number
2. Frame finish
3. Fabric finish

Order Code

Triangular Frame Stacking Screen with Open Weave Fabric:

Example:	**DP7SSWT1436 117/W1113-1**
DP7SSWT	Stack, triangular frame, open weave
117	Frame finish
W1113-1	Fabric finish

Included with:

Triangular Frame Stacking Screen with Open Weave Fabric

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

NOTE: Stacking screens are compatible with DP7 Full View panels only.

Open Weave and Glass Stacking Screens
Triangular Frame Stacking Screen with Glass

description	h	w	t	pattern no.	P1	P2	P3
14″ High Triangular Frame Stacking Screen with Glass	14″	24″	3″	**DP7SS( )T1424**	$554.	$565.	$577.
	14″	30″	3″	**DP7SS( )T1430**	582.	593.	605.
	14″	36″	3″	**DP7SS( )T1436**	610.	622.	636.
	14″	42″	3″	**DP7SS( )T1442**	639.	650.	664.
	14″	48″	3″	**DP7SS( )T1448**	666.	678.	692.
	14″	54″	3″	**DP7SS( )T1454**	699.	720.	741.
	14″	60″	3″	**DP7SS( )T1460**	734.	756.	778.
	14″	66″	3″	**DP7SS( )T1466**	774.	794.	820.
	14″	72″	3″	**DP7SS( )T1472**	810.	834.	859.
	14″	78″	3″	**DP7SS( )T1478**	851.	877.	902.
	14″	84″	3″	**DP7SS( )T1484**	894.	921.	948.
	14″	90″	3″	**DP7SS( )T1490**	939.	967.	995.
	14″	96″	3″	**DP7SS( )T1496**	986.	1,016.	1,045.
21″ High Triangular Frame Stacking Screen with Glass	21″	24″	3″	**DP7SS( )T2124**	598.	610.	623.
	21″	30″	3″	**DP7SS( )T2130**	632.	645.	658.
	21″	36″	3″	**DP7SS( )T2136**	665.	677.	691.
	21″	42″	3″	**DP7SS( )T2142**	697.	712.	725.
	21″	48″	3″	**DP7SS( )T2148**	730.	749.	762.
	21″	54″	3″	**DP7SS( )T2154**	767.	789.	812.
	21″	60″	3″	**DP7SS( )T2160**	805.	829.	853.
	21″	66″	3″	**DP7SS( )T2166**	845.	870.	896.
	21″	72″	3″	**DP7SS( )T2172**	887.	914.	941.
	21″	78″	3″	**DP7SS( )T2178**	932.	960.	988.
	21″	84″	3″	**DP7SS( )T2184**	978.	1,008.	1,037.
	21″	90″	3″	**DP7SS( )T2190**	1,027.	1,058.	1,089.
	21″	96″	3″	**DP7SS( )T2196**	1,079.	1,111.	1,143.
28″ High Triangular Frame Stacking Screen with Glass 	28″	24″	3″	**DP7SS( )T2824**	643.	655.	668.
	28″	30″	3″	**DP7SS( )T2830**	681.	695.	708.
	28″	36″	3″	**DP7SS( )T2836**	719.	731.	750.
	28″	42″	3″	**DP7SS( )T2842**	760.	775.	790.
	28″	48″	3″	**DP7SS( )T2848**	798.	815.	830.
	28″	54″	3″	**DP7SS( )T2854**	838.	863.	888.
	28″	60″	3″	**DP7SS( )T2860**	880.	906.	933.
	28″	66″	3″	**DP7SS( )T2866**	924.	951.	979.
	28″	72″	3″	**DP7SS( )T2872**	970.	999.	1,028.
	28″	78″	3″	**DP7SS( )T2878**	1,018.	1,049.	1,080.
	28″	84″	3″	**DP7SS( )T2884**	1,069.	1,101.	1,134.
	28″	90″	3″	**DP7SS( )T2890**	1,123.	1,157.	1,190.

Ordering Information

Triangular Frame Stacking Screen

1. Pattern number
2. Frame finish
3. Glass

Order Code

Triangular Frame Stacking Screen

Example:	**DP7SSGT1424 / 117**
DP7SSGT	Stack, Triangular Frame, w/ clear tempered glass
117	Frame finish

Included with:

Triangular Frame Stacking Screen

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

Options

NOTE: Stacking screens are compatible with DP7 Full View panels only.

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Open Weave and Glass Stacking Screens
Triangular Frame Stacking Screen with Glass

description	h	w	t	pattern no.	P1	P2	P3
28″ High Triangular Frame Stacking Screen with Glass	28″	96″	3″	**DP7SS( )T2896**	$1,179.	$1,214.	$1,250.



Ordering Information

Triangular Frame Stacking Screen

1. Pattern number
2. Frame finish
3. Glass

Order Code

Triangular Frame Stacking Screen

Example:	**DP7SSGT1424 / 117**
DP7SSGT	Stack, Triangular Frame, w/ clear tempered glass
117	Frame finish

Included with:

Triangular Frame Stacking Screen

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

Options

NOTE: Stacking screens are compatible with DP7 Full View panels only.

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Open Weave and Glass Stacking Screens
Rectangular Frame Stacking Screen with Glass

description	h*	w	t	pattern no.	P1	P2	P3
14″ High Rectangular Frame Stacking Screen with Glass	14″	24″	3″	**DP7SS( )R1424**	$546.	$555.	$567.
	14″	30″	3″	**DP7SS( )R1430**	575.	586.	597.
	14″	36″	3″	**DP7SS( )R1436**	602.	613.	627.
	14″	42″	3″	**DP7SS( )R1442**	631.	644.	656.
	14″	48″	3″	**DP7SS( )R1448**	660.	672.	686.
	14″	54″	3″	**DP7SS( )R1454**	693.	714.	735.
	14″	60″	3″	**DP7SS( )R1460**	728.	749.	771.
	14″	66″	3″	**DP7SS( )R1466**	764.	787.	810.
	14″	72″	3″	**DP7SS( )R1472**	802.	826.	850.
	14″	78″	3″	**DP7SS( )R1478**	842.	868.	893.
	14″	84″	3″	**DP7SS( )R1484**	884.	911.	938.
	14″	90″	3″	**DP7SS( )R1490**	929.	957.	984.
	14″	96″	3″	**DP7SS( )R1496**	975.	1,004.	1,034.
21″ High Rectangular Frame Stacking Screen with Glass	21″	24″	3″	**DP7SS( )R2124**	590.	602.	613.
	21″	30″	3″	**DP7SS( )R2130**	624.	638.	648.
	21″	36″	3″	**DP7SS( )R2136**	658.	671.	685.
	21″	42″	3″	**DP7SS( )R2142**	692.	706.	720.
	21″	48″	3″	**DP7SS( )R2148**	725.	740.	756.
	21″	54″	3″	**DP7SS( )R2154**	761.	784.	807.
	21″	60″	3″	**DP7SS( )R2160**	799.	823.	847.
	21″	66″	3″	**DP7SS( )R2166**	839.	864.	890.
	21″	72″	3″	**DP7SS( )R2172**	881.	908.	934.
	21″	78″	3″	**DP7SS( )R2178**	925.	953.	981.
	21″	84″	3″	**DP7SS( )R2184**	972.	1,001.	1,030.
	21″	90″	3″	**DP7SS( )R2190**	1,020.	1,051.	1,081.
	21″	96″	3″	**DP7SS( )R2196**	1,071.	1,103.	1,135.
28″ High Rectangular Frame Stacking Screen with Glass 	28″	24″	3″	**DP7SS( )R2824**	637.	648.	662.
	28″	30″	3″	**DP7SS( )R2830**	674.	688.	700.
	28″	36″	3″	**DP7SS( )R2836**	714.	726.	745.
	28″	42″	3″	**DP7SS( )R2842**	755.	769.	786.
	28″	48″	3″	**DP7SS( )R2848**	794.	811.	824.
	28″	54″	3″	**DP7SS( )R2854**	834.	859.	884.
	28″	60″	3″	**DP7SS( )R2860**	875.	902.	928.
	28″	66″	3″	**DP7SS( )R2866**	919.	947.	974.
	28″	72″	3″	**DP7SS( )R2872**	965.	994.	1,023.
	28″	78″	3″	**DP7SS( )R2878**	1,013.	1,044.	1,074.
	28″	84″	3″	**DP7SS( )R2884**	1,064.	1,096.	1,128.
	28″	90″	3″	**DP7SS( )R2890**	1,117.	1,151.	1,184.

Ordering Information

Rectangular Frame Stacking Screen:

1. Pattern number
2. Frame finish
3. Glass

Order Code

Rectangular Frame Stacking Screen:

Example:	**DP7SSGR1424 /117**
DP7SSGR	Stack, Rectangular Frame, w/clear tempered glass
117	Raceway finish

Included with:

Rectangular Frame Stacking Screen:

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

Options

NOTE: Stacking screens are compatible with DP7 Full View panels only.

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Open Weave and Glass Stacking Screens
Rectangular Frame Stacking Screen with Glass

description	h*	w	t	pattern no.	P1	P2	P3
28″ High Rectangular Frame Stacking Screen with Glass	28″	96″	3″	**DP7SS( )R2896**	$1,173.	$1,208.	$1,243.



Ordering Information

Rectangular Frame Stacking Screen:

1. Pattern number
2. Frame finish
3. Glass

Order Code

Rectangular Frame Stacking Screen:

Example:	**DP7SSGR1424 /117**
DP7SSGR	Stack, Rectangular Frame, w/clear tempered glass
117	Raceway finish

Included with:

Rectangular Frame Stacking Screen:

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

Options

NOTE: Stacking screens are compatible with DP7 Full View panels only.

Glass Options:
(G)= Clear Tempered Glass
(F) = Powder Glass

Frameless Add Up
Specifications

Frameless Add Up
Frameless add ups provide additional privacy between workstations, while creating a lighter and more transparent space. Combining frameless glass add ups with Dividends Horizon panels provides a clean, light aesthetic.

Frameless add ups are available in clear or powder glass. 7" and 14" heights are available, which is consistent with Dividends Horizon panel frame height increments.

Frameless add ups replace flat top caps on panels, bolting onto the panel frame. Add ups are not available in radius profile.

Frameless Glass Add Up Construction
Frameless glass add ups feature an extruded aluminum base and are available in any Knoll Core paint finish. Legacy finishes are not available.

Clear tempered or powder glass is ½" thick with polished edge.

Frameless Glass Add Up Dimensions
- Widths: 15, 18, 24, 30, 36, 42, 48, 54, 60, 66, and 72 inches
- Heights: 7 and 14 inches
- Thickness: 3 inches

Planning with Frameless Add Ups
Frameless add ups attach to the top of any height Dividends or Dividends Horizon topway or full view panel frame or stack frame, regardless of production date.

Frameless add ups replace the panel top cap and can span over one or more panels up to 72" wide.

Dividends Horizon frameless add ups are designed for use in same-height panel applications, and also support change of height applications involving a post connection.

Use shortened frameless add ups in change of height applications with DP5 end trims. Frameless add ups are not compatible with DP6 thin profile end trims.

End caps are specified for each end of a run of add ups. End caps must be specified separately and are available in packages of ten.

Frameless Add Up Alignment Clip
A clear polycarbonate alignment clip maintains alignment between frameless add up inserts. One alignment clip is included with every frameless add up. Alignment clips do not need to be specified separately.

14" High Frameless Add Up



7" High Frameless Add Up



Frameless Add Up End Cap



Frameless Add Up
Clear, Powder and Bronze Glass

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25)
Frameless Add Up, 7″ High	15″	½″	7″	**DP1AU0715( )G**		$206.	$220.
	18″	½″	7″	**DP1AU0718( )G**		229.	248.
	24″	½″	7″	**DP1AU0724( )G**		251.	277.
	30″	½″	7″	**DP1AU0730( )G**		274.	304.
	36″	½″	7″	**DP1AU0736( )G**		310.	346.
	42″	½″	7″	**DP1AU0742( )G**		346.	387.
	48″	½″	7″	**DP1AU0748( )G**		382.	428.
	54″	½″	7″	**DP1AU0754( )G**		415.	468.
	60″	½″	7″	**DP1AU0760( )G**		449.	506.
	66″	½″	7″	**DP1AU0766( )G**		481.	546.
	72″	½″	7″	**DP1AU0772( )G**		514.	585.
	78″	½″	7″	**DP1AU0778( )G**		555.	632.
	84″	½″	7″	**DP1AU0784( )G**		599.	683.
	90″	½″	7″	**DP1AU0790( )G**		647.	738.
	96″	½″	7″	**DP1AU0796( )G**		699.	797.
Shortened Frameless Add Up, 7″ High	14″	½″	7″	**DP1AU0714( )G**		206.	220.
	17″	½″	7″	**DP1AU0717( )G**		229.	248.
	23″	½″	7″	**DP1AU0723( )G**		251.	277.
	29″	½″	7″	**DP1AU0729( )G**		274.	304.
	35″	½″	7″	**DP1AU0735( )G**		310.	346.
	41″	½″	7″	**DP1AU0741( )G**		346.	387.
	47″	½″	7″	**DP1AU0747( )G**		382.	428.
	53″	½″	7″	**DP1AU0753( )G**		415.	468.
	59″	½″	7″	**DP1AU0759( )G**		449.	506.
	65″	½″	7″	**DP1AU0765( )G**		481.	546.
	71″	½″	7″	**DP1AU0771( )G**		514.	585.
	77″	½″	7″	**DP1AU0777( )G**		555.	632.
	83″	½″	7″	**DP1AU0783( )G**		599.	683.
	89″	½″	7″	**DP1AU0789( )G**		647.	738.
	95″	½″	7″	**DP1AU0795( )G**		699.	797.

Ordering Information

Frameless Add Up with Clear Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Clear Glass

Example:	**DP1AU0736VG**
DP1AU	Frameless Add Up
07	7″ High
36	36″ Wide
V	Full view
G	Glass
117	Frame finish
TEMP	Clear glass finish

Included with:

Frameless Add Up with Clear Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Alignment Clip

Options

Frame Options:
(V) = Full view
(C) = Topway

Glass Options:
(TEMP) = Clear
(GL13) = Powder
(GL25) = Bronze

Frameless Add Up
Clear, Powder and Bronze Glass

description		w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25)
Frameless Add Up, 14″ High		15″	½″	14″	**DP1AU1415( )L**			
		15″	½″	14″	**DP1AU1415( )G**		254.	283.
		18″	½″	14″	**DP1AU1418( )G**		294.	333.
		24″	½″	14″	**DP1AU1424( )G**		334.	382.
		30″	½″	14″	**DP1AU1430( )G**		373.	431.
		36″	½″	14″	**DP1AU1436( )G**		427.	497.
		42″	½″	14″	**DP1AU1442( )G**		481.	563.
		48″	½″	14″	**DP1AU1448( )G**		538.	630.
		54″	½″	14″	**DP1AU1454( )G**		590.	693.
		60″	½″	14″	**DP1AU1460( )G**		642.	759.
		66″	½″	14″	**DP1AU1466( )G**		694.	822.
		72″	½″	14″	**DP1AU1472( )G**		748.	887.
		78″	½″	14″	**DP1AU1478( )G**		808.	958.
		84″	½″	14″	**DP1AU1484( )G**		873.	1,035.
		90″	½″	14″	**DP1AU1490( )G**		943.	1,118.
		96″	½″	14″	**DP1AU1496( )G**		1,018.	1,207.
Shortened Frameless Add Up, 14″ High		14″	½″	14″	**DP1AU1414( )G**		254.	283.
		17″	½″	14″	**DP1AU1417( )G**		294.	333.
		23″	½″	14″	**DP1AU1423( )G**		334.	382.
		29″	½″	14″	**DP1AU1429( )G**		373.	431.
		35″	½″	14″	**DP1AU1435( )G**		427.	497.
		41″	½″	14″	**DP1AU1441( )G**		481.	563.
		47″	½″	14″	**DP1AU1447( )G**		538.	630.
		53″	½″	14″	**DP1AU1453( )G**		590.	693.
		59″	½″	14″	**DP1AU1459( )G**		642.	759.
		65″	½″	14″	**DP1AU1465( )G**		694.	822.
		71″	½″	14″	**DP1AU1471( )G**		748.	887.
		77″	½″	14″	**DP1AU1477( )G**		808.	958.
		83″	½″	14″	**DP1AU1483( )G**		873.	1,035.
		89″	½″	14″	**DP1AU1489( )G**		943.	1,118.
		95″	½″	14″	**DP1AU1495( )G**		1,018.	1,207.
End Cap	Package of Ten				**DP1AUECTP**	36.		

Ordering Information

Frameless Add Up with Clear Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Clear Glass

Example:	**DP1AU0736VG**
DP1AU	Frameless Add Up
07	7″ High
36	36″ Wide
V	Full view
G	Glass
117	Frame finish
TEMP	Clear glass finish

Included with:

Frameless Add Up with Clear Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Alignment Clip

Options

Frame Options:
(V) = Full view
(C) = Topway

Glass Options:
(TEMP) = Clear
(GL13) = Powder
(GL25) = Bronze

This page intentionally left blank

Dividends Horizon DP7 Post Assemblies
Specifications

Dividends Horizon DP7 Post Assemblies
Post assemblies are required for all "L", "T", and "X" applications involving same-height panels. Included with post assemblies are the appropriate post, post cover, top cap and inside corner raceway filler.

Posts use the universal panel connection hardware, which is included with the post, for attachment.

For high-low and post-to-panel applications, posts and covers must be ordered separately by component.

Dividends Horizon Post and Trim Construction
Posts are 3" square extruded aluminum construction. Post covers are powder-coated 20 gauge steel.

Posts have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway. Refer to the Beltway Electrical Specification page for cable routing information.

The illustrations that follow are common same-height post assembly configurations. Choose the post assembly that matches the required application.

Note: Worksurface height panels do not attach to any other panel height.

Post ''L'' Configuration
"L" post assembly includes:
- Universal post
- Two-way top cap
- Corner post cover
- Inside corner raceway filler

Post ''T'' Configuration
"T" post assembly includes:
- Universal post
- Three-way top cap
- Straight post cover
- Inside corner raceway filler

Post ''X'' Configuration
"X" post assembly includes:
- Universal post
- Four-way top cap
- Inside corner raceway filler

Post ''X'' Configuration
Trim options available:
- Radius
- Flat

Two-way Post Connection



Post and Cover Plan Views





Post "L" Configuration



Post "T" Configuration



Post "X" Configuration



Dividends Horizon DP7 Post Assemblies
L, T and X Configurations

description	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon Two-Way Post Assembly ("L")	28½″	3″	3″	**DP7PAWH2( )**	$144.	$152.	$161.	$460.
	36″	3″	3″	**DP7PA362( )**	144.	152.	161.	462.
	42″	3″	3″	**DP7PA422( )**	144.	152.	161.	476.
	50″	3″	3″	**DP7PA502( )**	157.	166.	173.	519.
	57″	3″	3″	**DP7PA572( )**	184.	196.	203.	603.
	64″	3″	3″	**DP7PA642( )**	184.	196.	203.	626.
	78″	3″	3″	**DP7PA782( )**	267.	283.	296.	752.
Dividends Horizon Three-Way Post Assembly ("T")	28½″	3″	3″	**DP7PAWH3( )**	150.	159.	166.	437.
	36″	3″	3″	**DP7PA363( )**	150.	159.	166.	465.
	42″	3″	3″	**DP7PA423( )**	150.	159.	166.	474.
	50″	3″	3″	**DP7PA503( )**	161.	168.	176.	496.
	57″	3″	3″	**DP7PA573( )**	184.	197.	203.	536.
	64″	3″	3″	**DP7PA643( )**	184.	197.	203.	585.
	78″	3″	3″	**DP7PA783( )**	265.	278.	294.	673.
Dividends Horizon Four-Way Post Assembly ("X")	28½″	3″	3″	**DP7PAWH4( )**	139.	146.	153.	255.
	36″	3″	3″	**DP7PA364( )**	139.	146.	153.	259.
	42″	3″	3″	**DP7PA424( )**	139.	146.	153.	260.
	50″	3″	3″	**DP7PA504( )**	146.	156.	164.	272.
	57″	3″	3″	**DP7PA574( )**	168.	177.	185.	285.
	64″	3″	3″	**DP7PA644( )**	168.	177.	185.	296.
	78″	3″	3″	**DP7PA784( )**	243.	254.	267.	345.

Ordering Information

Post Assemblies

1. Pattern Number
2. Finish

Order Code

Post Assemblies

Example:	**DP7PA362,5,113**
613	Silver Paint Finish

Included with:

Post Assemblies

- Post
- Post top cap
- Post cover
- Connecting hardware
- Base inside corner fillers

Options

Post Assemblies

(4) = Radius Metal
(5) = Flat Metal
(V4) =Radius Veneer
(V5) = Flat Veneer

Note: Plastic versions not available.

Dividends Horizon DP7 Post Components
Specifications

High-Low Post Components
High-Low panel-to-post configurations require ordering the post covers by components.

Shown are common high-low panel-to-post configurations. Choose the high-low panel-to-post configuration that matches the required application.

Posts use the universal panel connection hardware for attachment, which is included with the post.

NOTE: 28½"H panels do not attach to 36"H posts in a high-low application. Panel-to-panel high-low applications are not affected.

High-Low ‘‘L’’ Post Connector Configuration (see Figure 1)
High-Low “L” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “one-way” post top cap DP7PT1(5)

3 One corner post covers that match height of tallest panel. DP7PC(64)2

4 One, high-low right hand post cover that matches high-low panel-to-post dimension. DP7PC(14)(R)H - Mirrored configuration would require left hand cover DP7PC(14)(L)H

High-Low ‘‘T’’ Post Connector Configuration A (see Figure 2)
High-Low “T” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “two-way” top cap DP7PT2(5)

3 One, straight post cover that matches height of tallest panel DP7PC(64)

4 One, high-low right hand post cover that matches high-low panel-to-post dimension DP7PC(14)(R)H - Mirrored configuration would require a left hand cover DP7PC(14)(L)H

High-Low ‘‘T’’ Post Connector Configuration B (see Figure 3)
High-Low “T” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “in-line” top cap DP7PTS(5)

3 One, straight post cover that matches height of tallest panel DP7PC(64)

4 One, high-low straight post cover that matches high-low panel-to-post dimension DP7PC(14)H

Hi-Low ‘‘T’’ Post Connector Configuration C (see Figure 4)
High-Low “T” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “one-way” top cap DP7PT1(5)

3 One, straight post cover that matches height of tallest panel DP7PC(64)

4 Two, high-low right hand post covers that match high-low panel-to-post dimension DP7PC(14)(R)H - Mirrored configuration would require left hand covers DP7PC(14)(L)H

Figure 1



Figure 2



Figure 3



Figure 4



Post Top Caps



Dividends Horizon DP7 Post Components
Specifications

High-Low ‘‘X’’ Post Connector Configuration A (see Figure 5)

High-Low “X” components required (best method of various options):

1 One universal post that matches height of tallest panel DP7PO(64)

2 One, “one-way” top cap DP7PT1(5)

3 One, high-low straight post cover that matches high-low panel-to-post dimensions DP7PC(14)H

4 Two, high-low right hand post covers that match high-low panel-to-post dimensions DP7PC(14)(R)H - Mirrored configuration would require left hand covers DP7PC(14)(L)H

High-Low ‘‘X’’ Post Connector Configuration B (see Figure 6)

High-Low “X” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “in-line” top cap DP7PTS(5)

3 Two, high-low straight post covers that match high-low panel-to-post dimensions DP7PC(14)H

High-Low ‘‘X’’ Post Connector Configuration C (see Figure 7)

High-Low “X” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “two-way” top cap DP7PT2(5)

3 One, high-low straight post cover that matches high-low panel-to-post dimension. DP7PC(14)H

4 One, high-low right hand post cover that matches high-low panel-to-post dimension. DP7PC(14)(R)H - Mirrored configuration would require left hand cover DP7PC(14)(L)H

High-Low ‘‘X’’ Post Connector Configuration D (see Figure 8)

High-Low “X” components required:

1 One, universal post that matches height of tallest panel DP7PO(64)

2 One, “three-way” top cap DP7PT3(5)

3 One, high-low straight post cover that matches high-low panel to-post dimension DP7PC(14)H

Figure 5



Figure 6



Figure 7



Figure 8



Post Plan View



Dividends Horizon DP7 Post Components

Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
Dividends Horizon Universal Post		28½″	3″	3″	**DP7POWH**	$77.				
		36″	3″	3″	**DP7PO36**	77.				
		42″	3″	3″	**DP7PO42**	77.				
		42″	3″	3″	**DP7PO50**	89.				
		57″	3″	3″	**DP7PO57**	107.				
		64″	3″	3″	**DP7PO64**	107.				
		78″	3″	3″	**DP7PO78**	183.				
14″ High Dividends Horizon Stack Panel Post		14⅝″	3″	3″	**DP7SPO14**	80.				
21″ High Dividends Horizon Stack Panel Post		21 15/16″	3″	3″	**DP7SPO21**	81.				
28″ High Dividends Horizon Stack Panel Post		29¼″	3″	3″	**DP7SPO28**	92.				
Worksurface Height Panel Change of Height Kit					**DP7HLCWH**		30.	33.	34.	
Dividends Horizon Post Top Caps 	Four-Way	½″	3″	3″	**DP7PT4( )**		8.	9.	9.	101.
	In-line Straght	½″	3″	3″	**DP7PTS( )**		8.	9.	9.	97.
	One-Way	½″	3″	3″	**DP7PT1( )**		8.	9.	9.	87.
	Three-Way	½″	3″	3″	**DP7PT3( )**		8.	9.	9.	98.
	Two-Way	½″	3″	3″	**DP7PT2( )**		8.	9.	9.	99.
Inside Corner Raceway Filler					**DP7BF**	10.				

Ordering Information

Post Top Cap

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example:	**DP7PT45**
613	Silver Paint Finish

Included with:

Options

Post Top Caps Options
(4) = Radius Metal
(5) = Flat Metal
(V4) = Radius Veneer
(V5) = Flat Veneer

An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.

Dividends Horizon DP7 Post Components
Post Covers and High Low Post Covers

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon Post Covers Full Height "T"	28½″ + 14″	**DP7PCWHS14**	$102.	$114.	$118.	n/a
	28½″ + 21″	**DP7PCWHS21**	113.	125.	130.	n/a
	28½″ + 28″	**DP7PCWHS28**	119.	131.	136.	n/a
	28½″	**DP7PCWH**	45.	48.	61.	178.
	42″	**DP7PC42**	45.	48.	61.	211.
	50″	**DP7PC50**	46.	50.	54.	220.
	57″	**DP7PC57**	53.	55.	58.	247.
	64″	**DP7PC64**	53.	55.	58.	285.
	78″	**DP7PC78**	58.	64.	66.	324.
Dividends Horizon Post Covers Full Height "L"	28½″ + 14″	**DP7PCWHS142**	108.	118.	123.	n/a
	28½″ + 21″	**DP7PCWHS212**	115.	127.	132.	n/a
	28½″ + 28″	**DP7PCWHS282**	121.	132.	137.	n/a
	28½″	**DP7PCWH2**	69.	72.	75.	244.
	36″	**DP7PC362**	69.	72.	75.	243.
	42″	**DP7PC422**	69.	72.	75.	255.
	50″	**DP7PC502**	72.	76.	80.	287.
	57″	**DP7PC572**	78.	83.	90.	357.
	64″	**DP7PC642**	78.	83.	90.	370.
	78″	**DP7PC782**	90.	94.	97.	446.
Dividends Horizon High Low Post Covers	28½″ - 42″	**DP7PCWH42( )**	88.	96.	100.	n/a
	28½″ - 50″	**DP7PCWH50( )**	100.	112.	116.	n/a
	28½″ - 57″	**DP7PCWH57( )**	101.	113.	117.	n/a
	28½″ - 64″	**DP7PCWH64( )**	102.	114.	118.	n/a
	28½″ - 78″	**DP7PCWH78( )**	107.	117.	122.	n/a
	36″ - 42″	**DP7PC07( )**	9.	11.	11.	138.
	36″ - 50″	**DP7PC14( )**	15.	20.	22.	157.
	36″ - 57″	**DP7PC21( )**	23.	24.	25.	170.
	36″ - 64″	**DP7PC28( )**	36.	39.	40.	186.
	36″ - 78″	**DP7PC42( )**	54.	57.	59.	243.
	42″ - 50″	**DP7PC07( )**	9.	11.	11.	138.
	42″ - 57″	**DP7PC14( )**	15.	20.	22.	157.
	42″ - 64″	**DP7PC21( )**	23.	24.	25.	170.
	42″ - 78″	**DP7PC36( )**	48.	53.	55.	222.
	50″ - 57″	**DP7PC07( )**	9.	11.	11.	138.
	50″ - 64″	**DP7PC14( )**	15.	20.	22.	157.
	50″ - 78″	**DP7PC28( )**	36.	39.	40.	186.
	57″ - 64″	**DP7PC07( )**	9.	11.	11.	138.
	57″ - 78″	**DP7PC21( )**	23.	24.	25.	170.

Ordering Information

Post Covers
1. Pattern number
2. Finish

Order Code

Post Top Caps

Example:	**DP7PT45**
613	Silver Paint Finish

Included with:

Options

Post Covers
Add a "V" suffix to the base pattern number for a veneer finish.

High Low Post Covers Options
(H) = Straight Condition
(RH) = Right Hand Condition
(LH) = Left Hand Condition

Dividends Horizon DP7 Post Components
Post Covers and High Low Post Covers

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon High Low Post Covers	64″ - 78″	**DP7PC14( )**	$15.	$20.	$22.	$157.
Dividends Horizon Post Covers Full Height Double Underlap	28½″	**DP7PCWHU**	113.	125.	130.	230.
	36″	**DP7PC36U**	118.	130.	135.	249.
	42″	**DP7PC42U**	122.	133.	138.	271.
	50″	**DP7PC50U**	134.	147.	155.	308.
	57″	**DP7PC57U**	135.	149.	156.	333.
	64″	**DP7PC64U**	147.	163.	169.	371.
	78″	**DP7PC78U**	203.	222.	231.	473.
Dividends Horizon High Low Post Covers Double Underlap	36″-42″	**DP7PC07UH**	88.	96.	100.	175.
	36″-50″	**DP7PC14UH**	92.	101.	107.	187.
	36″-57″	**DP7PC21UH**	91.	100.	104.	182.
	36″-64″	**DP7PC28UH**	98.	109.	113.	198.
	42″-50″	**DP7PC07UH**	88.	96.	100.	175.
	42″-57″	**DP7PC14UH**	92.	101.	107.	187.
	42″-64″	**DP7PC28UH**	98.	109.	113.	198.
	42″-78″	**DP7PC36UH**	108.	118.	123.	249.
	50″-57″	**DP7PC07UH**	88.	96.	100.	175.
	50″-64″	**DP7PC14UH**	92.	101.	107.	187.
	50″-78″	**DP7PC28UH**	98.	109.	113.	198.
	57″-64″	**DP7PC07UH**	88.	96.	100.	175.
	57″-78″	**DP7PC21UH**	91.	100.	104.	182.
	64″-78″	**DP7PC14UH**	92.	101.	107.	187.

Ordering Information

Post Covers
1. Pattern number
2. Finish

Order Code

Post Top Caps

Example:	**DP7PT45**
613	Silver Paint Finish

Included with:

Options

Post Covers
Add a “V” suffix to the base pattern number for a veneer finish.

High Low Post Covers Options
(H) = Straight Condition
(RH) = Right Hand Condition
(LH) = Left Hand Condition

This page intentionally left blank

Legacy Post Assemblies
Specifications

Legacy Post Assemblies
Post assemblies are required for all “L”, “T”, and “X” applications involving same-height panels. Included with post assemblies are the appropriate post, post cover and top cap.

Post connectors use the universal panel connection hardware for attachment, which is included with the post.

For high-low and post-to-panel applications, posts and covers must be ordered separately by component.

NOTE: LEGACY POSTS ARE FOR EXISTING CUSTOMERS ONLY.

Legacy Post and Trim Construction
Posts are 3" square extruded aluminum construction. Post covers are flat or radius profile, metal or smooth textured plastic extrusion with softly-radiused molded plastic top cap. Metal post covers are powder-coated 20 ga. steel.

Posts have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway. Refer to the Beltway Electrical Specification page for cable routing information.

The illustrations that follow are common same-height post assembly configurations. Choose the post assembly that matches the required application.

Post ‘‘L’’ Configuration
“L” assembly includes:
- Universal post
- Two-way top cap
- Corner post cover

Post ‘‘L’’ Configuration
“L” post assembly includes:
- Universal post
- Two-way top cap
- Corner post cover

Post ‘‘T’’ Configuration
“T” post assembly includes:
- Universal post
- Three-way top cap
- Straight post cover

Trim options available:
- Smooth Radius Plastic
- Radius Metal
- Flat Metal

Note: Not available with fabric covered post covers.

Through-Post Access for Power and Data


Topway Cable Access


Beltway Power and Cable


Base Raceway Power and Cable

Two-Way Post Connection



Post Top Cap for Enhanced Smooth Trim



Post and Cover Top Views


Corner Post Cover


Straight Post Cover

Post "L" Configurations



Post "T" Configurations



Post "X" Configurations



Legacy Post Assemblies
L, T and X Configurations

description	h *	w	d	pattern no.	Plastic list	Metal P1	Metal P2	Metal P3
Two-Way Post Assembly ("L")	36″	3″	3″	**DP( )PA362**	$122.	$156.	$164.	$174.
	42″	3″	3″	**DP( )PA422**	122.	156.	164.	174.
	50″	3″	3″	**DP( )PA502**	137.	169.	178.	185.
	57″	3″	3″	**DP( )PA572**	168.	200.	209.	218.
	64″	3″	3″	**DP( )PA642**	168.	200.	209.	218.
	78″	3″	3″	**DP( )PA782**	269.	287.	305.	318.
Three-Way Post Assembly ("T")	36″	3″	3″	**DP( )PA363**	112.	162.	171.	178.
	42″	3″	3″	**DP( )PA423**	112.	162.	171.	178.
	50″	3″	3″	**DP( )PA503**	124.	174.	180.	190.
	57″	3″	3″	**DP( )PA573**	152.	200.	209.	218.
	64″	3″	3″	**DP( )PA643**	152.	200.	209.	218.
	78″	3″	3″	**DP( )PA783**	249.	285.	300.	316.
Four-Way Post Assembly ("X")	36″	3″	3″	**DP( )PA364**	99.	150.	158.	166.
	42″	3″	3″	**DP( )PA424**	99.	150.	158.	166.
	50″	3″	3″	**DP( )PA504**	110.	158.	168.	176.
	57″	3″	3″	**DP( )PA574**	133.	180.	191.	201.
	64″	3″	3″	**DP( )PA644**	133.	180.	191.	201.
	78″	3″	3″	**DP( )PA784**	222.	262.	274.	287.

h = nominal height

Ordering Information

Post Assemblies

1. Pattern Number
2. Trim Finish

Order Code

Post Assemblies

Example:	**DP(2A)PA 642, 113**
DP(2A)PA 642	Pattern Number
113	Dark grey trim finish

Included with:

Post Assemblies

- Post assemblies
- Post top cap
- Post cover
- Connecting hardware

Options

Post Assemblies

Post Assembly Trim Options
(2A) = Plastic, Enhanced Smooth Radius
(4) = Metal, Radius
(5) = Metal, Flat

High-Low Post Components
High-Low panel-to-post configurations require ordering the post covers by components.

Shown are common high-low panel-to-post configurations. Choose the high-low panel-to-post configuration that matches the required application.

Post connectors use the universal panel connection hardware for attachment, which is included with the post.

Universal Post and High-Low Trim Construction
- Posts: 3" square extruded aluminum.
- Post covers: Flat-profile, plastic extrusion with a smooth finish
- Top cap: Softly-radiused injection molded plastic

High-Low ''L'' Post Connector Configuration (see Figure 1)
High-Low "L" components required:
1 One, universal post that matches height of tallest panel
2 One, "one-way" post top cap
3 Two straight post covers that match height of tallest panel
4 One, high-low straight post cover that matches high-low panel-to-post dimension

High-Low ''T'' Post Connector Configuration A (see Figure 2)
High-Low "T" components required:
1 One, universal post that matches height of tallest panel
2 One, "two-way" top cap
3 One, straight post cover that matches height of tallest panel
4 One, high-low straight post cover that matches high-low panel-to-post dimension

High-Low ''T'' Post Connector Configuration B (see Figure 3)
High-Low "T" components required:
1 One, universal post that matches height of tallest panel
2 One, "in-line" top cap
3 One, straight post cover that matches height of tallest panel
4 One, high-low straight post cover that matches high-low panel-to-post dimension

Hi-Lo ''T'' Post Connector Configuration C (see Figure 4)
High-Low "T" components required:
1 One, universal post that matches height of tallest panel
2 One, "one-way" top cap
3 One, straight post cover that matches height of tallest panel
4 Two, high-low straight post covers that match high-low panel-to-post dimensions

High-Low ''X'' Post Connector Configuration A (see Figure 5)
High-Low "X" components required:
1 One universal post that matches height of tallest panel
2 One, "one-way" top cap
3 Three, high-low straight post covers that match high-low panel-to-post dimensions

High-Low ''X'' Post Connector Configuration B (see Figure 6)
High-Low "X" components required:
1 One, universal post that matches height of tallest panel
2 One, "in-line" top cap
3 Two, high-low straight post covers that match high-low panel-to-post dimensions

High-Low ''X'' Post Connector Configuration C (see Figure 7)
High-Low "X" components required:
1 One, universal post that matches height of tallest panel
2 One, "two-way" top cap
3 Two, high-low straight post covers that match high-low panel-to-post dimensions

High-Low ''X'' Post Connector Configuration D (see Figure 8)
High-Low "X" components required:
1 One, universal post that matches height of tallest panel
2 One, "three-way" top cap
3 One, high-low straight post cover that matches high-low panel to-post dimension

Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7



Figure 8



Post Top Caps



One-Way Two-Way Three-Way Four-Way Inline

Legacy Post Components
Post, Post Top Caps and Post Covers

description	type	h	w	d	pattern no.	Price list	Metal P1	Metal P2	Metal P3
Universal Post (Post Only)		36″	3″	3″	**DP2APO36**	$92.			
		42″	3″	3″	**DP2APO42**	92.			
		50″	3″	3″	**DP2APO50**	105.			
		57″	3″	3″	**DP2APO57**	126.			
		64″	3″	3″	**DP2APO64**	126.			
		78″	3″	3″	**DP2APO78**	217.			
Post Top Caps 	Two-Way	½″	3″	3″	**DP( )PT2**	5.	10.	11.	11.
	Three-Way	½″	3″	3″	**DP( )PT3**	5.	10.	11.	11.
	Four-Way	½″	3″	3″	**DP( )PT4**	5.	10.	11.	11.
	One-Way	½″	3″	3″	**DP( )PT1**	5.	10.	11.	11.
	In-Line (Straight)	½″	3″	3″	**DP( )PTS**	5.	10.	11.	11.
Post Covers (Straight)		36″			**DP( )PC36SF**	11.	49.	53.	59.
		42″			**DP( )PC42S**	11.	49.	53.	59.
		50″			**DP( )PC50S**	12.	50.	56.	60.
		57″			**DP( )PC57S**	19.	59.	61.	63.
		64″			**DP( )PC64S**	19.	59.	61.	63.
		78″			**DP( )PC78S**	28.	63.	67.	69.
Post Covers (Corner)		36″			**DP( )PC36L**	26.	74.	77.	80.
		42″			**DP( )PC42L**	26.	74.	77.	80.
		50″			**DP( )PC50L**	29.	77.	81.	88.
		57″			**DP( )PC57L**	35.	84.	91.	97.
		64″			**DP( )PC64L**	35.	84.	91.	97.
		78″			**DP( )PC78L**	45.	97.	101.	105.
Post Covers (Straight) High-Low Connection	36″ - 42″	8″			**DP( )PC08S**	4.	11.	13.	13.
	42″ - 50″	8″			**DP( )PC08S**	4.	11.	13.	13.
	36″ - 50″	14″			**DP( )PC14S**	5.	16.	22.	23.
	50″ - 64″	14″			**DP( )PC14S**	5.	16.	22.	23.
	64″ - 78″	14″			**DP( )PC14S**	5.	16.	22.	23.
	42″ - 64″	22″			**DP( )PC22S**	6.	25.	26.	27.
	36″ - 64″	28″			**DP( )PC28S**	12.	40.	42.	43.
	50″ - 78″	28″			**DP( )PC28S**	12.	40.	42.	43.
	42″ - 78″	36″			**DP( )PC36S**	19.	53.	59.	61.
	36″ - 78″	42″			**DP( )PC42SH**	25.	60.	62.	64.

Ordering Information

Universal Post

1. Pattern Number

Post Top Cap

1. Pattern Number
2. Trim finish

Post Covers

1. Pattern Number
2. Trim finish

Order Code

Universal Post	
Example:	**DP2A P050**
DP2A	Pattern Number
P050	
Post Top Cap	
Example:	**DP2A PT4, V04**
DP2A PT4	Pattern Number
117	Soft grey
Post Covers	
Example:	**DP2A PC50S, 117**
DP(2A)	Pattern Number
PC50S	
117	Soft grey

Included with:

Universal Post

Connecting hardware

Panel Top Cap

Post Covers

Options

Universal Post

Panel Top Cap and Post Cover Options:

(2A)= Plastic, Enhanced Smooth Radius
(4) = Metal, Radius
(5) = Metal, Flat

Legacy Post Components
Stack Panel Posts

description	h	w	d	pattern no.	List Price
14″ High Stack Panel Posts	14 5/8″	3″	3″	**DP2ASPO 14**	$88.
21″ High Stack Panel Posts	21 15/16″	3″	3″	**DP2ASPO 21**	89.
28″ High Stack Panel Posts	29 1/4″	3″	3″	**DP2ASPO 28**	99.

Ordering Information

Stack Panel Frame

1. Pattern Number
2. Trim Finish

Stack Panel Post

1. Pattern Number

Order Code

Stack Panel Frame

Example:	**DP2STF 1448, 113**
DP1STF	Pattern Number
1448	
113	Dark grey paint finish

Stack Panel Post

Example:	**DP2ASPO 14**
DP2ASPO	Pattern Number
14	

Included with:

Stack Panel Frame

Stack Panel Post

Options

Stack Panel Post

This page intentionally left blank

Panel End Trim and Panel Top Caps
Specifications

Panel End Trim
Panel end trim in one of three trim types ends a panel run.

Trim options available:
- Smooth Radius Plastic
- Metal Radius
- Metal Flat

Metal trim is constructed of extruded aluminum, powder coated.

End trim includes the appropriate attachment hardware and the panel end cap for transition to panel top trim.

Thin Profile Panel End Trim
The thin profile panel end trim is an extruded aluminum end cover that is designed to attach to panel ends to provide a smooth end condition for the end of panel runs. The thin profile end trim and high low end trims are constructed of extruded aluminum with a powder coated finish. Thin profile panel end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

High-Low Panel-to-Panel End Trim
High-low panel-to-panel end trim is used to complete straight, high-low panel-to-panel connections.

Construction and attachment is identical to panel end trim and includes attachment hardware and top/bottom end caps.

Up to ten, category 5 cables can be laid-in to carry data from the upper panel topway to the lower panel topway.

High-Low Thin Profile End Trim
High-low panel to panel end trim is used to complete straight, high-low panel to panel connections. Construction and attachment is identical to the thin profile panel end trim and includes attachment hardware. High-low thin profile end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

Note: When using the high-low thin profile end trim, the higher and lower panels continue to use the standard full-width top cap.

Panel Top Caps
Smooth plastic and metal panel top caps are available in all panel widths.

Construction: Plastic top caps are constructed of injection molded colored plastic. Metal caps are powder coated steel.

Top caps with retainer clips must be ordered when using top caps on full view panels.

Shortened High-Low Panel Top Caps
When specifying the enhanced smooth or metal panel trim for a high-low panel end trim condition, the top cap on the lower panel must be shortened by 1 inch. Panel top caps can be field cut to the new length, or shortened top caps may be ordered separately.

Note: Thin profile end trim and high low end trim are available in Knoll core finishes only.

Panel End Trim



Enhanced High-Low Panel End Trim



Thin Profile End Trim



Panel End Trim and Panel Top Caps
Panel End and High-Low Panel End

description	type	h *	w	d	pattern no.	Plastic	Metal P1	Metal P2	Metal P3	Veneer
Panel End	28½″	28½″	3″	⅝″	**DP( )PEWH**	$20.	$59.	$65.	$67.	$205.
	28½″ + 14″	42½″	3″	⅝″	**DP( )PEWHS14**	0.	67.	73.	76.	n/a
	28½″ + 21″	49½″	3″	⅝″	**DP( )PEWHS21**	0.	70.	77.	80.	n/a
	28½″ + 28″	56½″	3″	⅝″	**DP( )PEWHS28**	0.	72.	79.	82.	n/a
	36″	36″	3″	⅝″	**DP( )PE36F**	20.	59.	65.	67.	215.
	42″	42″	3″	⅝″	**DP( )PE42**	22.	61.	66.	68.	230.
	50″	50″	3″	⅝″	**DP( )PE50**	23.	64.	67.	69.	258.
	57″	57″	3″	⅝″	**DP( )PE57**	25.	66.	69.	71.	288.
	64″	64″	3″	⅝″	**DP( )PE64**	25.	66.	69.	71.	312.
	78″	78″	3″	⅝″	**DP( )PE78**	30.	71.	75.	78.	341.
Panel End, High-Low	28½″ - 36″	7½″	3″	⅜″	**DP( )PEWH36**	0.	49.	55.	57.	n/a
	28½″ - 42″	13½″	3″	⅜″	**DP( )PEWH42**	0.	53.	58.	60.	n/a
	28½″ - 50″	21½″	3″	⅜″	**DP( )PEWH50**	0.	56.	61.	64.	n/a
	28½″ - 57″	28½″	3″	⅜″	**DP( )PEWH57**	0.	59.	66.	68.	n/a
	28½″ - 64″	35½″	3″	⅜″	**DP( )PEWH64**	0.	61.	68.	71.	n/a
	28½″ - 78″	49½″	3″	⅜″	**DP( )PEWH78**	0.	68.	74.	77.	n/a
	36″ - 42″	6″	3″	⅜″	**DP( )PE08**	7.	36.	39.	40.	159.
	36″ - 50″	14″	3″	⅜″	**DP( )PE14**	9.	39.	41.	42.	183.
	36″ - 57″	21″	3″	⅜″	**DP( )PE22**	13.	41.	44.	46.	195.
	36″ - 64″	28″	3″	⅜″	**DP( )PE28**	25.	50.	54.	57.	203.
	36″ - 78″	42″	3″	⅜″	**DP( )PE42H**	32.	61.	66.	68.	234.
	42″ - 50″	8″	3″	⅜″	**DP( )PE08**	7.	36.	39.	40.	159.
	42″ - 57″	15″	3″	⅜″	**DP( )PE14**	9.	39.	41.	42.	183.
	42″ - 64″	22″	3″	⅜″	**DP( )PE22**	13.	41.	44.	46.	195.
	42″ - 78″	36″	3″	⅜″	**DP( )PE36**	31.	59.	65.	67.	217.
	50″ - 57″	7″	3″	⅜″	**DP( )PE08**	7.	36.	39.	40.	159.
	50″ - 64″	14″	3″	⅜″	**DP( )PE14**	9.	39.	41.	42.	183.
	50″ - 78″	28″	3″	⅜″	**DP( )PE28**	25.	50.	54.	57.	203.
	57″ - 64″	7″	3″	⅜″	**DP( )PE08**	7.	36.	39.	40.	159.
	57″ - 78″	21″	3″	⅜″	**DP( )PE22**	13.	41.	44.	46.	195.
	64″ - 78″	14″	3″	⅜″	**DP( )PE14**	9.	39.	41.	42.	183.

h* = Nominal height
Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel End

1. Pattern Number
2. Trim Finish

High-Low Panel End

1. Pattern Number
2. Trim Finish

Order Code

Panel End

Example:	**DP2A PE42, 117**
DP2A	Pattern Number
PE42	
117	Soft grey

High-Low Panel End

Example:	**DP2A PE42 117**
DP2A	Pattern Number
PE42	
117	Soft Grey

Included with:

Panel End

- Panel end cover
- Connecting hardware

High-Low Panel End

- Panel end cover
- Connecting hardware
- Lower transition cap

Options

Panel End, High-Low Panel End and Top Caps

Trim options
(2A) = Enhanced Smooth Radius Plastic
(4) = Radius Metal
(5) = Flat Metal
(V4) = Radius Veneer
(V5) = Flat Veneer

Panel End Trim and Panel Top Caps
Thin Profile Panel End Trim and High-Low Panel End

description	type	h*	w	d	pattern no.	P1	P2	P3
Thin Profile Panel End	28½″	28½″	3″	⅝″	**DP6PEWH**	$92.	$92.	$92.
	28½″ + 14″	42½″	3″	⅝″	**DP6PEWHS14**	109.	119.	124.
	28½″ + 21″	49½″	3″	⅝″	**DP6PEWHS21**	117.	129.	134.
	28½″ + 28″	56½″	3″	⅝″	**DP6PEWHS28**	126.	138.	143.
	36″	36″	3″	⅝″	**DP6PE36F**	92.	92.	92.
	42″	42″	3″	⅝″	**DP6PE42**	99.	99.	99.
	50″	50″	3″	⅝″	**DP6PE50**	110.	110.	110.
	57″	57″	3″	⅝″	**DP6PE57**	119.	119.	119.
	64″	64″	3″	⅝″	**DP6PE64**	129.	129.	129.
	78″	78″	3″	⅝″	**DP6PE78**	150.	150.	150.
Thin Profile Panel End High-Low	28½″-36″	36″	3″	⅝″	**DP6PEWH36**	64.	70.	73.
	28½″-42″	42″	3″	⅝″	**DP6PEWH42**	72.	79.	82.
	28½″-50″	50″	3″	⅝″	**DP6PEWH50**	79.	88.	91.
	28½″-57″	57″	3″	⅝″	**DP6PEWH57**	87.	95.	99.
	28½″-64″	64″	3″	⅝″	**DP6PEWH64**	96.	107.	111.
	28½″-78″	78″	3″	⅝″	**DP6PEWH78**	116.	128.	133.
	36″-42″	6″	3″	⅝″	**DP6PE08**	46.	48.	48.
	36″-50″	14″	3″	⅝″	**DP6PE14**	58.	61.	61.
	36″-57″	21″	3″	⅝″	**DP6PE22**	70.	74.	74.
	36″-64″	28″	3″	⅝″	**DP6PE28**	81.	85.	85.
	36″-78″	42″	3″	⅝″	**DP6PE42H**	99.	107.	107.
	42″-50″	8″	3″	⅝″	**DP6PE08**	46.	48.	48.
	42″-57″	15″	3″	⅝″	**DP6PE14**	58.	61.	61.
	42″-64″	22″	3″	⅝″	**DP6PE22**	70.	74.	74.
	42″-78″	36″	3″	⅝″	**DP6PE36**	92.	96.	96.
	50″-57″	7″	3″	⅝″	**DP6PE08**	46.	48.	48.
	50″-64″	14″	3″	⅝″	**DP6PE14**	58.	61.	61.
	50″-78″	28″	3″	⅝″	**DP6PE28**	81.	85.	85.
	57″-64″	7″	3″	⅝″	**DP6PE08**	46.	48.	48.
	57″-78″	21″	3″	⅝″	**DP6PE22**	70.	74.	74.
	64″-78″	14″	3″	⅝″	**DP6PE14**	58.	61.	61.

h* = Nominal height
Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Thin Profile End Trim

1. Pattern Number
2. Finish

Order Code

Thin Profile End Trim

Example:	**DP6PE42 117**
DP	Dividends Panel
6	Thin Profile
PE	Panel End
42	Height
117	Finish

Included with:

Thin Panel End Trim

Attachment hardware

Note: Thin profile end trim is only available in Knoll core paint finishes.

Options

Panel End Trim and Panel Top Caps
Topway and Full View Frame Top Caps

description	w	pattern no.	Plastic	Metal P1	Metal P2	Metal P3	Veneer
Panel Top Caps	15″	**DP( )PT15**	$13.	$40.	$42.	$44.	$83.
	18″	**DP( )PT18**	13.	40.	42.	44.	91.
	24″	**DP( )PT24**	15.	40.	42.	44.	104.
	30″	**DP( )PT30**	20.	40.	42.	44.	118.
	36″	**DP( )PT36**	22.	40.	42.	44.	133.
	42″	**DP( )PT42**	22.	40.	42.	44.	149.
	48″	**DP( )PT48**	23.	40.	42.	44.	168.
	54″	**DP( )PT54**	n/a	44.	46.	48.	187.
	60″	**DP( )PT60**	27.	47.	49.	52.	210.
	66″	**DP( )PT66**	n/a	52.	55.	58.	231.
	72″	**DP( )PT72**	n/a	57.	61.	65.	244.
	78″	**DP( )PT78**	n/a	64.	67.	70.	258.
	84″	**DP( )PT84**	n/a	69.	72.	76.	272.
	90″	**DP( )PT90**	n/a	75.	79.	82.	288.
	96″	**DP( )PT96**	n/a	80.	85.	90.	306.

Ordering Information

Panel Top Cap

1. Pattern Number
2. Trim Finish

Order Code

Panel Top Cap

Example:	**DP5PT18, 117**
DP5PT18	Pattern number
117	Soft Grey trim finish

Included with:

Panel Top Cap

- Panel Top Cap

Options

Panel Top Caps

Trim options
(2A) = Enhanced Smooth Radius Plastic
(4) = Radius Metal
(5) = Flat Metal
(V4) = Radius Veneer
(V5) = Flat Veneer

Panel End Trim and Panel Top Caps
Shortened Panel Top Caps

description	w	pattern no.	Plastic	Metal P1	Metal P2	Metal P3	Veneer
Shortened Panel Top Caps (for lower panel on high-low panel to panel application) Not for use with DP6 Thin profile panel ends	14″	**DP( )PT14**	$13.	$40.	$42.	$44.	$83.
	17″	**DP( )PT17**	13.	40.	42.	44.	91.
	23″	**DP( )PT23**	15.	40.	42.	44.	104.
	29″	**DP( )PT29**	20.	40.	42.	44.	118.
	35″	**DP( )PT35**	22.	40.	42.	44.	133.
	41″	**DP( )PT41**	22.	40.	42.	44.	149.
	47″	**DP( )PT47**	23.	40.	42.	44.	168.
	53″	**DP( )PT53**	n/a	44.	46.	48.	187.
	59″	**DP( )PT59**	27.	47.	49.	52.	210.
	65″	**DP( )PT65**	n/a	52.	55.	58.	231.
	71″	**DP( )PT71**	n/a	57.	61.	65.	244.
	77″	**DP( )PT77**	n/a	64.	67.	70.	258.
	83″	**DP( )PT83**	n/a	69.	72.	76.	272.
	89″	**DP( )PT89**	n/a	75.	79.	82.	288.
	95″	**DP( )PT95**	n/a	80.	85.	90.	306.

h* = Nominal height
Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel Top Cap
1. Pattern Number
2. Trim Finish

Panel-to-Panel Top Cap Transition
1. Pattern Number
2. Trim Finish

Order Code

Panel Top Cap

Example:	**DP5PT18, 117**
DP5PT18	Pattern number
117	Soft Grey trim finish

Included with:

Panel Top Cap
- Panel Top Cap

Options

Panel Top Caps

Trim options
(2A) = Enhanced Smooth Radius Plastic
(4) = Radius Metal
(5) = Flat Metal
(V4) = Radius Veneer
(V5) = Flat Veneer

This page intentionally left blank

Panel Wall Starter, Panel-to-Panel Top Cap Transition
Off-Module Panel Connector
Specifications

Panel Wall Starter

Panel wall starters mount to reinforced building walls to begin a perpendicular topway or full view panel run. Wall starters consist of a wall bracket and upper and lower panel-mounting brackets. Wall fasteners are not included or supplied by Knoll. Choice of wall fasteners is critical and must be selected to match the wall construction, wall surface and loading conditions.

Wall starters are available in all Dividends Horizon panel heights. Black finish only.

NOTE: KNOLL, INC. ASSUMES NO RESPONSIBILITY FOR WALL CONSTRUCTION OR PERFORMANCE OF FASTENERS USED.

Off-Module Panel Connector

The off-module connector allows for panel attachment anywhere along the width of the perpendicular panel. The off-module connector can be used with same height topway or full view panels only. The connector consists of a height specific connector and attaching hardware. The 3-way (DP1PT3) or 4-way (DP1PT4) post top cap must be ordered separately when radius metal top caps are being used. Specify connector height to match panel height. Black finish only.

When using the off-module panel connector, the attached connector will deface the perpendicular fabric panel insert.

Electrical components and data cables cannot be routed through the off-module panel.

Panel-to-Panel Top Cap Transition

Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.

- Construction: Trim-colored, softly-radiused molded plastic
- Size: 1" wide by 3" deep
- Attachment: Snaps between top cap sections in straight, same-height panel configurations

NOTE: PANEL-TO-PANEL TOP CAP TRANSITIONS ARE ORDERED SEPARATELY FROM PANELS.

Panel Wall Starter Connection



Off-Module Panel Connector



Panel-To-Panel Transition for Enhanced Smooth Panel Trim



Panel Wall Starter, Panel-to-Panel Top Cap Transition *and Off-Module Panel Connector*

description	type	h *	h	w	d	pattern no.	Single pack list	10 pack list
Panel/Screen Wall Starter		36″	28″	2″	¾″	**DP3PWS36**	$94.	n/a
		42″	35⅜″	2″	¾″	**DP3PWS42**	98.	n/a
		50″	42 11/16″	2″	¾″	**DP3PWS50**	102.	n/a
		57″	50″	2″	¾″	**DP3PWS57**	105.	n/a
		64″	57¼″	2″	¾″	**DP3PWS64**	111.	n/a
		78″	71⅞″	2″	¾″	**DP3PWS78**	116.	n/a
Panel-to-Panel Top Cap Transition		¾″	1″	3″		**DP( ) TCT( )**	3.	25.
Off-Module Panel Connector		36″	28″	2″	¾″	**DP2PMS36**	61.	n/a
		42″	35⅜″	2″	¾″	**DP2PMS42**	61.	n/a
		50″	42 11/16″	2″	¾″	**DP2PMS50**	69.	n/a
		57″	50″	2″	¾″	**DP2PMS57**	72.	n/a
		64″	57¼″	2″	¾″	**DP2PMS64**	74.	n/a
		78″	71⅞″	2″	¾″	**DP2PMS78**	89.	n/a
Radius Post Top Cap (for use with off-module panel connector when radius metal top caps are used)	three-way		½″	3″	3″	**DP1PT3**	5.	n/a
	four-way		½″	3″	3″	**DP1PT4**	5.	n/a

h* = nominal height
Dimensions listed under h w d are actual to the nearest 1/16″

Ordering Information

Panel Wall Starter
1. Pattern Number

Off-Module Panel Connector
1. Pattern Number

Panel-to-Panel Top Cap Transition
1. Pattern Number
2. Trim Finish

Order Code

Panel Wall Starter

Example:	**DP1 PWS 64**
DP1 PW	Pattern Number
64	

Off-Module Panel Connector

Example:	**DP1 PMS50**
DP1 PMS50	Pattern Number

Panel-to-Panel Top Cap Transition

Example:	**DP1 TCT, 117**
DP1 TCT	Pattern Number
117	Soft Grey

Included with:

Panel Wall Starter

Off-Module Panel Connector

Panel-to-Panel Top Cap Transition

Note: Three-way or four-way post top cap must be ordered separately when radius metal panel top caps are being used.

Options

Panel Wall Starter

Off-Module Panel Connector

Panel-to-Panel Top Cap Transition

Trim Option:
(2A) = Enhanced Smooth Radius Plastic
(4) = Radius Metal
(5) = Flat Metal
(V4) = Radius Veneer
(V5) = Flat Veneer

Panel-to-Panel Top Cap Transition

Add an 'SP' suffix to the base pattern number for single pack or 'TP' suffix for a 10 pack.

Wall Mount Tracks and Components
Specifications

Dividends Horizon Wall System
The Dividends Horizon Wall System allows designers to transform the aesthetic and function of private offices.

With the use of vertical wall tracks, building walls can support worksurfaces and storage, while fabric, slatwall, and marker board tiles improve aesthetic and function.

Wall System Dimensions
The Dividends Horizon wall system is available in heights of 57, 64, 71 and 78" from the finished floor. Wall tracks are designed to be positioned 5" from top of finished floor to accommodate building base molding and uneven floors.

Horizontal elements like bottom trim channels and top trims are available on 6" increments, from 24" to 48" wide. The maximum distance between wall tracks is 48".

Wall Tracks
Wall tracks work like the vertical elements of a Dividends Horizon panel frame, and are shipped in pairs which include a left and right track. Tracks feature slotted standards on the standard Dividends Horizon 1 1/2" increment.

Wall tracks are attached to building walls at 7" height increments. Available in all Knoll Core paint finishes.

End Trim
While wall tracks are painted, end trims are available for applications where a finished end is desired. Match end trim height to wall track height.

Top Cap
Top caps are available for applications with a lower horizon height, and are optional. Top caps conceal the space between tiles and the finished wall, and the top of the wall tracks.

Bottom Channel
The bottom channel is a “J” shaped channel that supports the bottom of the lowest tile. Bottom channels are also used during the installation process to accurately set the width between left and right wall tracks.





Wall Mount Tracks and Components
Specifications

Tile Supports
Tile supports are specified in the same manor as with Dividends Horizon panels, and are not required at the top of bottom of wall tracks, or with Slatwall. Specify Wall Track tile support mounting brackets for each tile support.

Tiles
Standard Dividends Horizon tiles are specified with Wall Tracks.

Wall tracks support monolithic or tiled applications, using standard fabric, steel, or Slatwall tiles. Specify bottom channels at the bottom of the lowest tile.

Unlike panels, Wall Tracks accommodate tile supports at 7" inch increments, increasing design flexibility. Both D1 and D2 tile supports may be used with Wall Tracks.

For tiled applications, specify standard tile supports, and DP1WTTSB tile support mounting brackets for D2 tile supports.

Worksurface Planning
Dividends Horizon worksurfaces up to 24" deep may be mounted to wall tracks, using the same cantilevers, end supports and end panels used in panel planning, and follow the same planning rules.

Wall Track Planning
Wall tracks may be positioned on 6" width increments, from 24" to a maximum of 48".

Worksurfaces are supported with standard supports, including cantilevers, end supports, and end panels. Maximum worksurface depth when cantilever supported is 24".

One overhead may be mounted on each wall track section.





Wall Mount Tracks and Components
57″, 64″, 71″ and 78″ High

description	w	h	d	pattern no.	NA Black	P1	P2	P3
Wall Mount Tracks (pair)	1 ½″	57″	1 ½″	**DP1WT57**	$213.	$213.	$235.	$244.
	1 ½″	64″	1 ½″	**DP1WT64**	221.	221.	244.	253.
	1 ½″	71″	1 ½″	**DP1WT71**	230.	230.	253.	264.
	1 ½″	78″	1 ½″	**DP1WT78**	239.	239.	263.	273.
End Trim for Wall Mount Tracks	1 ½″	57″	⅝″	**DP1WTET57**	n/a	78.	85.	89.
	1 ½″	64″	⅝″	**DP1WTET64**	n/a	85.	94.	98.
	1 ½″	71″	⅝″	**DP1WTET71**	n/a	85.	94.	98.
	1 ½″	78″	⅝″	**DP1WTET78**	n/a	85.	94.	98.
Top Cap for Wall Mount Tracks	15″	¾″	1 ½″	**DP1WTTC15**	n/a	62.	69.	72.
	18″	¾″	1 ½″	**DP1WTTC18**	n/a	66.	72.	75.
	24″	¾″	1 ½″	**DP1WTTC24**	n/a	69.	76.	79.
	30″	¾″	1 ½″	**DP1WTTC30**	n/a	77.	84.	88.
	36″	¾″	1 ½″	**DP1WTTC36**	n/a	87.	95.	99.
	42″	¾″	1 ½″	**DP1WTTC42**	n/a	94.	103.	109.
	48″	¾″	1 ½″	**DP1WTTC48**	n/a	94.	103.	109.
	54″	¾″	1 ½″	**DP1WTTC54**	n/a	112.	124.	129.
	60″	¾″	1 ½″	**DP1WTTC60**	n/a	113.	125.	130.
	66″	¾″	1 ½″	**DP1WTTC66**	n/a	113.	125.	130.
	72″	¾″	1 ½″	**DP1WTTC72**	n/a	113.	125.	130.
	78″	¾″	1 ½″	**DP1WTTC78**	n/a	118.	130.	135.
	84″	¾″	1 ½″	**DP1WTTC84**	n/a	159.	174.	181.
	90″	¾″	1 ½″	**DP1WTTC90**	n/a	163.	178.	185.
	96″	¾″	1 ½″	**DP1WTTC96**	n/a	167.	183.	192.
Bottom Tile Channel for Wall Mount Tracks	15″			**DP1WTBTC15**	n/a	45.	49.	52.
	18″			**DP1WTBTC18**	n/a	46.	50.	53.
	24″			**DP1WTBTC24**	n/a	49.	55.	57.
	30″			**DP1WTBTC30**	n/a	52.	57.	59.
	36″			**DP1WTBTC36**	n/a	62.	69.	72.
	42″			**DP1WTBTC42**	n/a	71.	78.	81.
	48″			**DP1WTBTC48**	n/a	81.	90.	93.

Ordering Information

Wall Mount Tracks

1. Pattern Number
2. Paint Finish

End Trim for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Top Cap for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Bottom Tile Channel for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Tile Support Brackets

1. Pattern Number

Order Code

Wall Mount Tracks

Example:	**DP1WT57613**
DP1WT57	Pattern Number
613	Paint Finish

Tile Support Brackets

Example:	**DP1WTTSB**
DP1WT	Pattern Number
TSB	

Included with:

Wall Mount Tracks

Wall fasteners are not included or supplied by Knoll.

Bottom Tile Channel for Wall Mount Tracks

- Hardware

Tile Support Brackets for Wall Mount Tracks

- Hardware

Options

Wall Mount Tracks and Components
57″, 64″, 71″ and 78″ High

description	w	h	d	pattern no.	NA Black	P1	P2	P3
Tile Support Brackets for Wall Mount Tracks (pair)				**DP1WTTSB**	$11.	n/a	n/a	n/a

Ordering Information

Wall Mount Tracks
1. Pattern Number
2. Paint Finish

End Trim for Wall Mount Tracks
1. Pattern Number
2. Paint Finish

Top Cap for Wall Mount Tracks
1. Pattern Number
2. Paint Finish

Bottom Tile Channel for Wall Mount Tracks
1. Pattern Number
2. Paint Finish

Tile Support Brackets
1. Pattern Number

Order Code

Wall Mount Tracks

Example:	**DP1WT57613**
DP1WT57	Pattern Number
613	Paint Finish

Tile Support Brackets

Example:	**DP1WTTSB**
DP1WT	Pattern Number
TSB	

Included with:

Wall Mount Tracks

Wall fasteners are not included or supplied by Knoll.

Bottom Tile Channel for Wall Mount Tracks
- Hardware

Tile Support Brackets for Wall Mount Tracks
- Hardware

Options

Panel Rigidizer Brackets, Coat Hooks and Reveal Fillers
Specifications

Panel Rigidizer Brackets
Panel rigidizer brackets are used to reduce panel connection flex where panel to worksurface brackets cannot be used.

Panel rigidizer brackets are unnecessary if a panel can be properly secured with the use of a panel to worksurface bracket.

Rigidizer brackets are available for inline (straight), 2-way (L), 3-way (T) and 4-way (X) panel conditions.

High-low panel to post conditions cannot accommodate the panel rigidizer brackets. Full view panel frames without a topway cannot accommodate a panel rigidizer bracket.

Carpet grippers are recommended for use with panel rigidizer brackets.

Specify panel rigidizer brackets for appropriate panel attachment condition.

- 2-way (L) for panels of the same height in a 90 degree application
- 3-way (T) for 3 panels of the same height attached to a universal post.
- 4-way (X) for 4 panels of the same height attached to a universal post.

Carpet Grippers
Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Available in black finish only.

Panel-Mounted Coat Hook
The Dividends Horizon panel-mounted coat hook is made of extruded aluminum and is available in an anodized black finish or matte aluminum finish. The coat hook attaches to any Dividends Horizon panel by connecting over the top of the Dividends Horizon radius plastic and metal panel top caps only.

Slotted Standard Coat Hook
Independent of the top cap, the slotted standard coat hook attaches to the left or right vertical slotted standard of any Dividends Horizon panel. The die cast slotted standard coat hook is available in any of the Knoll Core paint finishes. The slotted standard coat hook is sold in packages of ten and is not compatible with laminate tiles or screens.

Panel Reveal Fillers
Panel reveal filler strips are used to cover unused vertical panel slots. Panel reveal fillers are designed to only be used with Legacy post panel applications. Panel reveal fillers should not be used with panel applications that are using DP7 posts. Panel reveal fillers are available in two thickness:

- $\frac{1}{2}$" for panel-to-panel and panel to end trim attachment.
- $\frac{1}{4}$" for panel-to-post attachment.

Panel reveal fillers are offered in a 74" length and are field cut to install into any Dividends Horizon panel height.

To determine the correct amount of reveal fillers to be specified, use the following formulas: For panels and end trim-2 x the number of straight panel connections plus the number of panel end trims. For panel to post connections, 4x the number of posts.

Panel Rigidizer Brackets



Two-way "L"



Inline (straight)



Three-way "T"



Four-way "X"

Carpet Gripper



Panel-Mounted Coat Hook (for radius plastic and metal trim only)

Slotted Standard Coat Hook



Panel Reveal Fillers



Slotted Standard Coat Hook Application



Panel Rigidizer Brackets, Coat Hooks and Reveal Fillers
Carpet Grippers

description	type	h	w	d	pattern no.	list	P1	P2	P3
Carpet Grippers	Package of 10				**DP1 CG**	$13.			
Coat Hook (For Panel Slotted Standard)	Package of 10				**DP2CHTP**		139.	139.	139.
Coat Hook (For radius metal and plastic trim only) (Package of 4)	Anodized Black Finish				**DP1 CHB**	121.			
	Matte Aluminum Finish				**DP1 CHP**	115.			
Panel Rigidizer Brackets for topway panel frames 	2-way-L	½″	5½″	5½″	**DP1PRBL**	89.			
	3-way-T	½″	5½″	5½″	**DP1PRBT**	107.			
	4-way-X	½″	5½″	5½″	**DP1PRBX**	178.			
	Straight	½″	5½″	⅝″	**DP1PRBS**	76.			
Panel Rigidizer Brackets for full view panel frames 	2-way-L	½″	5½″	5½″	**DP1FPRBL**	25.			
	3-way-T	½″	5½″	5½″	**DP1FPRBT**	43.			
	4-way-X	½″	5½″	5½″	**DP1FPRBX**	63.			
	Straight	½″	5½″	5½″	**DP1FPRBS**	30.			

Ordering Information

Panel Rigidizer Bracket

1. Pattern Number

Panel Reveal Filler

1. Pattern Number

Slotted Standard Coat Hook

1. Pattern Number
2. Paint Finish

Order Code

Panel Rigidizer Bracket	
Example:	**DP1 PRBL**
Panel Reveal Filler	
Example:	**DP1PRF N15**
Slotted Standard Coat Hook	
Example:	**DP2CH**
118	Bright White

Included with:

Panel Rigidizer Bracket

- Rigidizer Bracket
- Set Screws

Panel Reveal Filler

- Reveal Fillers (15 qty)

Options

Panel Rigidizer Bracket

Panel Reveal Filler

Note: Two narrow panel reveal fillers are required for inside corner on DP2/4/5 posts. They are used only on the outside of DP7 posts.

Panel Rigidizer Brackets, Coat Hooks and Reveal Fillers
Carpet Grippers

description	type	h	w	d	pattern no.	list	P1	P2	P3
Panel Reveal Filler (for panel-to-post attachment) for pre-DP7 panels/posts 	15 Fillers	74″			**DP1PRFN15**	$44.			
	250 Fillers	74″			**DP1PRFN250**	324.			
	70 Fillers	74″			**DP1PRFN70**	116.			
Wide Panel Reveal Filler (for panel-to-panel and panel-to-DP2/4/5 end trim)	15 Fillers	74″			**DP2PRFW15**	57.			
	70 Fillers	74″			**DP2PRFW70**	165.			
Narrow Panel Reveal Filler (for panel-to-post attachment and panel-to-DP6 end tirm)	15 Fillers	74″			**DP2PRFN15**	44.			
	70 Fillers	74″			**DP2PRFN70**	116.			
Corner Panel Reveal Filler (for inside corner of DP7 post)	15 Fillers	74″			**DP2PRFIC15**	165.			
	70 Fillers	74″			**DP2PRFIC70**	740.			

Ordering Information

Panel Rigidizer Bracket

1. Pattern Number

Panel Reveal Filler

1. Pattern Number

Slotted Standard Coat Hook

1. Pattern Number
2. Paint Finish

Order Code

Panel Rigidizer Bracket	
Example:	**DP1 PRBL**
Panel Reveal Filler	
Example:	**DP1PRF N15**
Slotted Standard Coat Hook	
Example:	**DP2CH**
118	Bright White

Included with:

Panel Rigidizer Bracket

- Rigidizer Bracket
- Set Screws

Panel Reveal Filler

- Reveal Fillers (15 qty)

Options

Panel Rigidizer Bracket

Panel Reveal Filler

Note: Two narrow panel reveal fillers are required for inside corner on DP2/4/5 posts. They are used only on the outside of DP7 posts.

This page intentionally left blank

Concealed Post
Planning Guidelines
Specifications

Concealed Post

Concealed posts eliminate visible post covers, creating a seamless aesthetic at three-way post connections. Larger widths of fabric or laminate tile-to-floor tiles are used to hide the concealed post. Panel top caps, up to 99" long, span concealed posts, which eliminate the need for post top caps. Concealed post applications are specified by individual components through “Build-to-Spec”.

Planning with Concealed Posts

Concealed posts are to be used in three-way post conditions where straight post covers want to be eliminated. The concealed post should be specified in place of a standard Dividends Horizon DP7 or Legacy post. Concealed post fabric or laminate tiles must be specified in the tile location that is covering the post. (See illustration below) Concealed post, half post or centered fabric and laminate tiles are designed to cover the concealed post with the edge of the tile ending in the center of the concealed post. Only concealed post fabric and laminate tile sizes are compatible with concealed posts.

A high low condition may be created by having a perpendicular panel at a lower height than the concealed post. Specify the height of the concealed post to be at the same height as the higher panels. A concealed post high low top cap must be specified in this situation. Panel top caps that span concealed posts are not designed for use in high-low concealed post applications, standard width panel top caps and a concealed post high low top cap should be used instead. A DP7 straight high low post cover should be specified in a concealed post high low application.

The two panels on the straight side of the three-way concealed post intersection must always be the same height. The concealed post is not designed to change height on the concealed post side of the three-way connection.

Concealed post panel top caps and frameless add ups are 3" wider than standard sizes, for applications wanting to span the concealed post. Panel top caps are available in lengths up to 99". Any concealed post application requiring panel top caps longer than 99” must specify panel top caps equal to the width of a panel or combination of panels and a concealed post same height top cap. Concealed post fabric and laminate tiles, post top caps, panel top caps, and frameless add ups are designed for use with the concealed post only.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP7 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.

Concealed Post Connection Plan View



Concealed Post Application



Concealed Post
Post Components
Specifications

Concealed Post Construction
Concealed posts are a square extruded aluminum construction. They have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway.

Concealed Post Same Height Top Cap
When all three panels in a concealed post application are the same height and standard length panel top caps are used, a concealed post same height top cap must be specified. A concealed post same height top cap covers the top of a concealed post and connects three panel top caps at the same height. (See illustration below)

Concealed Post High Low Top Cap
When the perpendicular panel in a three-way concealed post application is a lower height than the concealed post, a concealed post high low top cap must be specified. A concealed post high low top cap covers the top of the concealed post and connects the two same height panel top caps. (See illustration below) A DP7 high low straight post cover should be specified in a concealed post high low application.

Concealed Post Top Cap Construction
Concealed post flat and radius profile top caps are constructed of injection molded colored plastic.

Concealed Post Panel Top Caps
Concealed post panel top caps are 3" longer than standard panel top cap widths, so they can span over a concealed post. Panel top caps must be specified according to the panel type, either full view or topway, they are attaching to. Concealed post panel top caps are available in flat profile metal. Concealed post panel top caps are not compatible with a Dividends Horizon DP7 or Legacy post. Concealed post panel top caps that span a concealed post must be used in same height applications only. High low concealed post conditions must use concealed post high low top caps. (See illustration below)

Concealed Post Shortened Panel Top Caps
Concealed post shortened panel tops are 3" longer than standard shortened panel top cap widths, so they can span over a concealed post. A concealed post shortened panel top cap must be specified for the lower panel in a high low panel-to-panel condition when the panel top cap of the lower panel is spanning over the concealed post. (See illustration below) When the lower panel top cap is not spanning over the concealed post because a concealed post top cap is being used, specify standard shortened panel top cap widths. Standard DP5 high low panel end trim should be specified with concealed post shortened panel top caps in high low panel-to-panel applications.

Concealed Post Panel Top Cap Construction
Concealed post panel top caps are constructed of roll-formed steel.

Concealed Post



Concealed Post Same Height Top Cap



Concealed Post High Low Top Cap



Concealed Post Panel Top Cap



Concealed Post Shortened Panel Top Cap



Concealed Post
Post Components
Post and Post Top Caps

description	w	h	d	pattern no.	list	P1	P2	P3
Concealed Post	3″	28½″	3″	**DP7POWHCPF**	$126.			
	3″	36″	3″	**DP7PO36CPF**	142.			
	3″	42″	3″	**DP7PO42CPF**	153.			
	3″	50″	3″	**DP7PO50CPF**	166.			
	3″	57″	3″	**DP7PO57CPF**	179.			
	3″	64″	3″	**DP7PO64CPF**	200.			
Concealed Post Same Height Top Caps	3″	½″	3″	**DP7PTCP( )**		12.	13.	14.
Concealed Post High Low Top Caps	3″	½″	3″	**DP7PTCPH( )**		12.	13.	14.

Ordering Information

Concealed Post

1. Pattern Number
2. Paint Finish Code

Concealed Post Top Caps

1. Pattern Number
2. Paint Finish Code

Order Code

Concealed Post	
Example:	**DP7PO42CPF**
DP7PO42	Pattern Number
CPF	

Concealed Post Top Caps	
Example:	**DP7PTCP5**
DP7PTCP	Pattern Number
5	Flat profile
613	Silver paint finish

Included with:

Concealed Post

- Tile to floor filler

Concealed Post Top Caps

Options:

Post Top Cap Option:

(4) = Radius Profile
(5) = Flat Profile

Concealed Post
Post Components
Panel Top Caps

description	w	h	d	pattern no.	P1	P2	P3
Concealed Post Panel Top Caps for use with Topway Frames	33″	½″	3″	**DP( )PT30CP**	$61.	$68.	$71.
	39″	½″	3″	**DP( )PT36CP**	62.	69.	72.
	51″	½″	3″	**DP( )PT48CP**	64.	70.	73.
	63″	½″	3″	**DP( )PT60CP**	65.	71.	74.
	75″	½″	3″	**DP( )PT72CP**	67.	73.	76.
	87″	½″	3″	**DP( )PT84CP**	69.	76.	79.
	99″	½″	3″	**DP( )PT96CP**	70.	77.	80.
Concealed Post Shortened Panel Top Caps for use with Topway Frames	32″	½″	3″	**DP( )PT29CP**	61.	68.	71.
	38″	½″	3″	**DP( )PT35CP**	62.	69.	72.
	50″	½″	3″	**DP( )PT47CP**	64.	70.	73.
	62″	½″	3″	**DP( )PT59CP**	65.	71.	74.
	74″	½″	3″	**DP( )PT71CP**	67.	73.	76.
	86″	½″	3″	**DP( )PT83CP**	69.	76.	79.
	98″	½″	3″	**DP( )PT95CP**	70.	77.	80.

Ordering Information

Concealed Post Panel Top Caps

1. Pattern Number
2. Paint Finish Code

Order Code

Concealed Post Panel Top Caps

Example:	**DP5PT48CP**
DP5PT48	Pattern Number
CP	
117	Soft Grey paint finish

Included with:

Concealed Post Panel Top Caps

- Panel Top Caps

Options:

Trim Option:

(5) = Metal, Flat

Concealed Post
Monolithic Panel Inserts
Specifications

Concealed Post Monolithic Inserts
Concealed post monolithic inserts are designed to cover a concealed post and eliminate the need for a post cover. Concealed post monolithic tile-to-floor fabric inserts create a seamless aesthetic at a three-way connection. There are three types of concealed post monolithic tiles: half post, centered, and double with post. Concealed post monolithic inserts can be fabric or laminate and are only available tile-to-floor. Concealed post applications are specified by individual components through “Build-to-Spec”.

Concealed Post Monolithic Insert Construction
Fabric Tiles
Fabric laminated with adhesive and heat-cured to 7/18” thick acoustical board.

Laminate Tiles
The surface material is laminate on the front and back of a particle board core. Overall thickness is 7/16" with a 0.5 edgeband.

Concealed Post Monolithic Insert Attachment
Fabric Tiles
Panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting clips are attached to panel inserts for connection to the vertical frame for additional support. No tools are required for insert attachment.

Laminate Tiles
Laminate tiles are installed one side or both sides of a panel frame. Mounting clips are attached to laminate inserts for connection to the panel frame.

Planning with Concealed Post Half Post Tiles
Half post tiles attach to a panel frame or combination of panel frames that are connected to a concealed post. This type of tile covers the entire width of the panel frame(s) and half of the concealed post. Half post tiles are 1-1/2” wider than standard tile widths to cover half of the concealed post. Half post tiles are handed, either left or right.

The left edge of a left half post tile ends in the middle of a concealed post and the right edge of the tile ends on the furthest right edge of the panel(s). The right edge of a right half post tile ends in the middle of a concealed post and the left edge of the tile ends on the left side of the panel(s). (See illustration below) A half post tile must be used with either another half post tile or a centered tile, so the other half of the post is concealed by a tile.

Half Post Tile Application



Half Post Tile Plan View



Concealed Post
Monolithic Panel Inserts and Frameless Add Ups Specifications

Planning with Concealed Post Centered Tiles

Centered tiles attach to a panel frame or combination of panel frames that are connected to concealed posts. Centered tiles are centered on a panel frame(s) between two concealed posts. The left and right edge of the tile ends in the center of a concealed post. A centered tile is 3" wider than standard tile widths. Centered tiles must be centered on the panel frame(s) between the concealed posts. Neither the right nor left edge of a centered tile is able to end anywhere other than the center of a concealed post. (See illustration below) A centered tile must be used with either a half post tile or another centered tile, so the other half of the post is concealed by a tile.

Planning with Concealed Post Double with Post Tiles

A double with post tile attaches to two panel frames that are connected by a concealed post. The tile attaches to the panels and hides the concealed post connection. The concealed post must be between the panel frames. Double with post tiles are 3" wider than standard tile widths, so that they are able to cover a concealed post. (See illustration below) Neither the right nor left edge of a double with post tile is able to end anywhere other than the right or left edge of a panel frame.

Concealed Post Frameless Add Ups

Concealed post frameless add ups are 3" longer than standard frameless add up lengths, so they can span over a concealed post. Concealed post frameless add ups are not compatible with Dividends Horizon DP7 or Legacy posts.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP7 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.

Double With Post Tile Application



Centered Tile Application



Double With Post Tile Plan View



Centered Tile Plan View



Concealed Post
Monolithic Panel Half Post Fabric Inserts
Worksurface Height, 28" and 42" High

description	w *	w	h	d	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post Monolithic Panel Half Post Fabric Inserts	15″	16 1/2″	27 1/4″	7/16″	**DP1SOWH15( )F**	$99.	$102.	$108.	$111.	$112.	$115.	$116.	$119.
	18″	19 1/2″	27 1/4″	7/16″	**DP1SOWH18( )F**	112.	115.	121.	124.	125.	128.	130.	133.
	24″	25 1/2″	27 1/4″	7/16″	**DP1SOWH24( )F**	123.	127.	132.	135.	138.	141.	142.	146.
	30″	31 1/2″	27 1/4″	7/16″	**DP1SOWH30( )F**	134.	138.	144.	147.	151.	155.	157.	161.
	36″	37 1/2″	27 1/4″	7/16″	**DP1SOWH36( )F**	145.	150.	158.	161.	164.	167.	170.	174.
	42″	43 1/2″	27 1/4″	7/16″	**DP1SOWH42( )F**	157.	162.	169.	172.	177.	180.	182.	187.
	48″	49 1/2″	27 1/4″	7/16″	**DP1SOWH48( )F**	168.	173.	181.	184.	190.	194.	197.	202.
	60″	61 1/2″	27 1/4″	7/16″	**DP1SOWH60( )F**	177.	182.	192.	196.	201.	204.	207.	212.
28″ High Concealed Post Monolithic Panel Half Post Fabric Inserts (For 36″H Panel Frame)	15″	16 1/2″	33 13/16″	7/16″	**DP1SO2815( )F**	100.	103.	87.	89.	92.	94.	94.	96.
	18″	19 1/2″	33 13/16″	7/16″	**DP1SO2818( )F**	115.	119.	110.	113.	116.	118.	119.	123.
	24″	25 1/2″	33 13/16″	7/16″	**DP1SO2824( )F**	130.	133.	133.	135.	139.	142.	143.	146.
	30″	31 1/2″	33 13/16″	7/16″	**DP1SO2830( )F**	143.	147.	156.	159.	163.	166.	168.	172.
	36″	37 1/2″	33 13/16″	7/16″	**DP1SO2836( )F**	158.	163.	177.	181.	185.	188.	193.	198.
	42″	43 1/2″	33 13/16″	7/16″	**DP1SO2842( )F**	172.	176.	201.	204.	209.	213.	216.	221.
	48″	49 1/2″	33 13/16″	7/16″	**DP1SO2848( )F**	185.	192.	201.	205.	210.	213.	217.	222.
	60″	61 1/2″	33 13/16″	7/16″	**DP1SO2860( )F**	198.	203.	213.	216.	222.	227.	230.	237.
42″ High Concealed Post Monolithic Panel Half Post Fabric Inserts	15″	16 1/2″	41 3/16″	7/16″	**DP1SO4215( )F**	103.	107.	113.	113.	118.	121.	123.	125.
	18″	19 1/2″	41 3/16″	7/16″	**DP1SO4218( )F**	122.	125.	131.	132.	137.	139.	142.	144.
	24″	25 1/2″	41 3/16″	7/16″	**DP1SO4224( )F**	138.	141.	150.	151.	157.	160.	162.	166.
	30″	31 1/2″	41 3/16″	7/16″	**DP1SO4230( )F**	156.	160.	168.	170.	175.	178.	181.	185.
	36″	37 1/2″	41 3/16″	7/16″	**DP1SO4236( )F**	172.	177.	185.	188.	195.	198.	202.	206.
	42″	43 1/2″	41 3/16″	7/16″	**DP1SO4242( )F**	188.	195.	205.	208.	213.	217.	220.	227.
	48″	49 1/2″	41 3/16″	7/16″	**DP1SO4248( )F**	206.	212.	222.	227.	232.	237.	241.	247.
	60″	61 1/2″	41 3/16″	7/16″	**DP1SO4260( )F**	219.	227.	238.	242.	248.	253.	258.	264.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO2818CEF**
DP1SO 2818	Pattern Number
CE	Center left, End Right
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Configuration:
(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post
Monolithic Panel Half Post Fabric Inserts
50", 57" and 64" High

description	w *	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50″ High Concealed Post Monolithic Panel Half Post Fabric Inserts	15″	16 1/2″	48 1/2″	7/16″	**DP1SO5015( )F**	$108.	$110.	$115.	$117.	$121.	$123.	$125.	$128.
	18″	19 1/2″	48 1/2″	7/16″	**DP1SO5018( )F**	128.	130.	136.	139.	142.	145.	147.	152.
	24″	25 1/2″	48 1/2″	7/16″	**DP1SO5024( )F**	146.	151.	159.	161.	166.	168.	171.	175.
	30″	31 1/2″	48 1/2″	7/16″	**DP1SO5030( )F**	167.	171.	179.	182.	187.	192.	195.	200.
	36″	37 1/2″	48 1/2″	7/16″	**DP1SO5036( )F**	186.	192.	201.	205.	210.	214.	217.	224.
	42″	43 1/2″	48 1/2″	7/16″	**DP1SO5042( )F**	206.	212.	222.	226.	234.	237.	241.	247.
	48″	49 1/2″	48 1/2″	7/16″	**DP1SO5048( )F**	226.	232.	244.	248.	255.	260.	264.	271.
	60″	61 1/2″	48 1/2″	7/16″	**DP1SO5060( )F**	243.	249.	262.	266.	273.	279.	283.	290.
57″ High Concealed Post Monolithic Panel Half Post Fabric Inserts	15″	16 1/2″	55 3/8″	7/16″	**DP1SO5715( )F**	111.	114.	119.	121.	124.	127.	129.	132.
	18″	19 1/2″	55 3/8″	7/16″	**DP1SO5718( )F**	133.	137.	143.	145.	149.	153.	156.	160.
	24″	25 1/2″	55 3/8″	7/16″	**DP1SO5724( )F**	157.	161.	168.	170.	175.	178.	181.	185.
	30″	31 1/2″	55 3/8″	7/16″	**DP1SO5730( )F**	178.	183.	193.	196.	201.	205.	208.	213.
	36″	37 1/2″	55 3/8″	7/16″	**DP1SO5736( )F**	201.	207.	216.	220.	226.	231.	235.	241.
	42″	43 1/2″	55 3/8″	7/16″	**DP1SO5742( )F**	224.	230.	241.	245.	252.	256.	261.	267.
	48″	49 1/2″	55 3/8″	7/16″	**DP1SO5748( )F**	246.	253.	265.	270.	278.	283.	287.	295.
	60″	61 1/2″	55 3/8″	7/16″	**DP1SO5760( )F**	265.	272.	286.	291.	299.	304.	309.	319.
64″ High Concealed Post Monolithic Panel Half Post Fabric Inserts	15″	16 1/2″	63 1/16″	7/16″	**DP1SO6415( )F**	112.	114.	121.	124.	126.	129.	130.	135.
	18″	19 1/2″	63 1/16″	7/16″	**DP1SO6418( )F**	137.	140.	147.	152.	156.	159.	161.	166.
	24″	25 1/2″	63 1/16″	7/16″	**DP1SO6424( )F**	164.	168.	176.	179.	183.	187.	190.	197.
	30″	31 1/2″	63 1/16″	7/16″	**DP1SO6430( )F**	188.	195.	204.	208.	213.	217.	220.	227.
	36″	37 1/2″	63 1/16″	7/16″	**DP1SO6436( )F**	214.	220.	231.	237.	243.	247.	251.	258.
	42″	43 1/2″	63 1/16″	7/16″	**DP1SO6442( )F**	241.	248.	260.	264.	271.	277.	281.	288.
	48″	49 1/2″	63 1/16″	7/16″	**DP1SO6448( )F**	266.	274.	287.	293.	301.	306.	311.	320.
	60″	61 1/2″	63 1/16″	7/16″	**DP1SO6460( )F**	288.	297.	310.	316.	327.	332.	338.	346.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO5718CEF**
DP1SO 5718	Pattern Number
CE	Center left, End Right
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Configuration:
(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post
Monolithic Panel Half Post Laminate Inserts
Worksurface Height, 28″ and 42″ High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post Monolithic Panel Half Post Laminate Inserts	15″	16 1/2″	27 1/4″	7/16″	**DP3L1WH15( )F**	$169.
	18″	19 1/2″	27 1/4″	7/16″	**DP3L1WH18( )F**	194.
	24″	25 1/2″	27 1/4″	7/16″	**DP3L1WH24( )F**	226.
	30″	31 1/2″	27 1/4″	7/16″	**DP3L1WH30( )F**	244.
	36″	37 1/2″	27 1/4″	7/16″	**DP3L1WH36( )F**	291.
	42″	43 1/2″	27 1/4″	7/16″	**DP3L1WH42( )F**	296.
	48″	49 1/2″	27 1/4″	7/16″	**DP3L1WH48( )F**	390.
28″ High Concealed Post Monolithic Panel Half Post Laminate Inserts (For 36″H Panel Frame)	15″	16 1/2″	33 13/16″	7/16″	**DP3L12815( )F**	169.
	18″	19 1/2″	33 13/16″	7/16″	**DP3L12818( )F**	194.
	24″	25 1/2″	33 13/16″	7/16″	**DP3L12824( )F**	226.
	30″	31 1/2″	33 13/16″	7/16″	**DP3L12830( )F**	244.
	36″	37 1/2″	33 13/16″	7/16″	**DP3L12836( )F**	291.
	42″	43 1/2″	33 13/16″	7/16″	**DP3L12842( )F**	296.
	48″	49 1/2″	33 13/16″	7/16″	**DP3L12848( )F**	390.
42″ High Concealed Post Monolithic Panel Half Post Laminate Inserts	15″	16 1/2″	41 3/16″	7/16″	**DP3L14215( )F**	226.
	18″	19 1/2″	41 3/16″	7/16″	**DP3L14218( )F**	252.
	24″	25 1/2″	41 3/16″	7/16″	**DP3L14224( )F**	291.
	30″	31 1/2″	41 3/16″	7/16″	**DP3L14230( )F**	394.
	36″	37 1/2″	41 3/16″	7/16″	**DP3L14236( )F**	416.
	42″	43 1/2″	41 3/16″	7/16″	**DP3L14242( )F**	419.
	48″	49 1/2″	41 3/16″	7/16″	**DP3L14248( )F**	461.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L14236CEF**
DP3L1 4236	Pattern Number
CE	Center left, End Right
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Configuration:
(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post
Monolithic Panel Half Post Laminate Inserts
50″ and 57″ High

description	w *	w	h	d	pattern no.	list
50″ High Concealed Post Monolithic Panel Half Post Laminate Inserts	15″	16 1/2″	48 1/2″	7/16″	**DP3L15015( )F**	$245.
	18″	19 1/2″	48 1/2″	7/16″	**DP3L15018( )F**	293.
	24″	25 1/2″	48 1/2″	7/16″	**DP3L15024( )F**	368.
	30″	31 1/2″	48 1/2″	7/16″	**DP3L15030( )F**	399.
	36″	37 1/2″	48 1/2″	7/16″	**DP3L15036( )F**	488.
	42″	43 1/2″	48 1/2″	7/16″	**DP3L15042( )F**	492.
	48″	49 1/2″	48 1/2″	7/16″	**DP3L15048( )F**	637.
57″ High Concealed Post Monolithic Panel Half Post Laminate Inserts	15″	16 1/2″	55 3/8″	7/16″	**DP3L15715( )F**	250.
	18″	19 1/2″	55 3/8″	7/16″	**DP3L15718( )F**	298.
	24″	25 1/2″	55 3/8″	7/16″	**DP3L15724( )F**	373.
	30″	31 1/2″	55 3/8″	7/16″	**DP3L15730( )F**	405.
	36″	37 1/2″	55 3/8″	7/16″	**DP3L15736( )F**	493.
	42″	43 1/2″	55 3/8″	7/16″	**DP3L15742( )F**	497.
	48″	49 1/2″	55 3/8″	7/16″	**DP3L15748( )F**	641.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L15736CEF**
DP3L1 5736	Pattern Number
CE	Center left, End Right
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Finish Options:

114 **Folkstone Grey**
117 **Soft Grey**
118 **Bright White**
119 **Pumice**

Configuration:
(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post
Monolithic Panel Centered Fabric Inserts
Worksurface Height, 28" and 42" High

description	w *	w	d	h	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post Monolithic Panel Centered Fabric Insert	15″	18″	7/16″	27 1/4″	**DP1SOWH15CCF**	$139.	$142.	$151.	$152.	$159.	$161.	$164.	$168.
	18″	21″	7/16″	27 1/4″	**DP1SOWH18CCF**	143.	147.	157.	158.	164.	166.	179.	173.
	24″	27″	7/16″	27 1/4″	**DP1SOWH24CCF**	149.	152.	161.	163.	168.	171.	174.	178.
	30″	33″	7/16″	27 1/4″	**DP1SOWH30CCF**	153.	158.	166.	168.	173.	176.	179.	183.
	36″	39″	7/16″	27 1/4″	**DP1SOWH36CCF**	158.	163.	171.	173.	178.	181.	184.	188.
	42″	45″	7/16″	27 1/4″	**DP1SOWH42CCF**	163.	167.	175.	178.	182.	186.	190.	195.
	48″	51″	7/16″	27 1/4″	**DP1SOWH48CCF**	167.	172.	180.	183.	187.	193.	196.	200.
	60″	63″	7/16″	27 1/4″	**DP1SOWH60CCF**	176.	181.	190.	195.	200.	203.	206.	211.
28″ High Concealed Post Monolithic Panel Centered Fabric Insert (For 36″H Panel Frame)	15″	18″	7/16″	33 13/16″	**DP1SO2815CCF**	150.	156.	164.	166.	171.	173.	176.	181.
	18″	21″	7/16″	33 13/16″	**DP1SO2818CCF**	157.	162.	170.	172.	177.	179.	182.	187.
	24″	27″	7/16″	33 13/16″	**DP1SO2824CCF**	162.	167.	175.	178.	183.	186.	190.	196.
	30″	33″	7/16″	33 13/16″	**DP1SO2830CCF**	168.	173.	181.	184.	190.	194.	197.	202.
	36″	39″	7/16″	33 13/16″	**DP1SO2836CCF**	174.	179.	187.	192.	197.	200.	203.	208.
	42″	45″	7/16″	33 13/16″	**DP1SO2842CCF**	179.	184.	194.	198.	203.	207.	210.	215.
	48″	51″	7/16″	33 13/16″	**DP1SO2848CCF**	185.	192.	200.	204.	209.	213.	216.	221.
	60″	63″	7/16″	33 13/16″	**DP1SO2860CCF**	197.	203.	212.	216.	221.	226.	230.	236.
42″ High Concealed Post Monolithic Panel Centered Fabric Insert	15″	18″	7/16″	41 3/16″	**DP1SO4215CCF**	164.	168.	176.	178.	183.	187.	190.	197.
	18″	21″	7/16″	41 3/16″	**DP1SO4218CCF**	171.	175.	183.	186.	193.	197.	199.	205.
	24″	27″	7/16″	41 3/16″	**DP1SO4224CCF**	177.	182.	193.	195.	200.	204.	207.	213.
	30″	33″	7/16″	41 3/16″	**DP1SO4230CCF**	184.	190.	200.	203.	208.	212.	215.	221.
	36″	39″	7/16″	41 3/16″	**DP1SO4236CCF**	193.	198.	207.	211.	216.	220.	224.	230.
	42″	45″	7/16″	41 3/16″	**DP1SO4242CCF**	199.	205.	215.	218.	224.	228.	232.	239.
	48″	51″	7/16″	41 3/16″	**DP1SO4248CCF**	206.	212.	222.	227.	232.	237.	241.	247.
	60″	63″	7/16″	41 3/16″	**DP1SO4260CCF**	219.	227.	238.	242.	248.	253.	258.	264.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO2818CCF**
DP1SO 2818	Pattern Number
CC	Center Left, Center Right
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Concealed Post
Monolithic Panel Centered Fabric Inserts
50", 57" and 64" High

description	w *	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50″ High Concealed Post Monolithic Panel Centered Fabric Insert	15″	18″	48 1/2″	7/16″	**DP1SO5015CCF**	$177.	$180.	$192.	$195.	$199.	$203.	$206.	$212.
	18″	21″	48 1/2″	7/16″	**DP1SO5018CCF**	185.	188.	200.	204.	208.	212.	215.	221.
	24″	27″	48 1/2″	7/16″	**DP1SO5024CCF**	194.	199.	209.	212.	217.	221.	226.	232.
	30″	33″	48 1/2″	7/16″	**DP1SO5030CCF**	202.	207.	217.	221.	227.	231.	236.	242.
	36″	39″	48 1/2″	7/16″	**DP1SO5036CCF**	210.	215.	226.	231.	237.	241.	245.	251.
	42″	45″	48 1/2″	7/16″	**DP1SO5042CCF**	217.	225.	236.	240.	246.	250.	255.	262.
	48″	45″	48 1/2″	7/16″	**DP1SO5048CCF**	226.	234.	244.	249.	255.	260.	265.	271.
	60″	63″	48 1/2″	7/16″	**DP1SO5060CCF**	243.	250.	262.	267.	274.	279.	284.	291.
57″ High Concealed Post Monolithic Panel Centered Fabric Insert	15″	18″	55 3/8″	7/16″	**DP1SO5715CCF**	187.	195.	205.	208.	213.	217.	220.	226.
	18″	21″	55 3/8″	7/16″	**DP1SO5718CCF**	198.	204.	215.	218.	224.	228.	232.	238.
	24″	27″	55 3/8″	7/16″	**DP1SO5724CCF**	208.	214.	225.	229.	236.	240.	243.	249.
	30″	33″	55 3/8″	7/16″	**DP1SO5730CCF**	217.	224.	236.	240.	246.	250.	254.	261.
	36″	39″	55 3/8″	7/16″	**DP1SO5736CCF**	227.	234.	246.	250.	256.	261.	266.	272.
	42″	45″	55 3/8″	7/16″	**DP1SO5742CCF**	238.	244.	255.	261.	268.	272.	277.	284.
	48″	51″	55 3/8″	7/16″	**DP1SO5748CCF**	247.	253.	266.	271.	279.	283.	288.	296.
	60″	63″	55 3/8″	7/16″	**DP1SO5760CCF**	266.	273.	287.	293.	300.	305.	310.	320.
64″ High Concealed Post Monolithic Panel Centered Fabric Insert	15″	18″	63 1/16″	7/16″	**DP1SO6415CCF**	204.	208.	218.	224.	228.	234.	237.	244.
	18″	21″	63 1/16″	7/16″	**DP1SO6418CCF**	214.	219.	230.	236.	241.	246.	249.	256.
	24″	27″	63 1/16″	7/16″	**DP1SO6424CCF**	225.	230.	242.	247.	252.	258.	262.	269.
	30″	33″	63 1/16″	7/16″	**DP1SO6430CCF**	236.	242.	253.	259.	265.	270.	274.	282.
	36″	39″	63 1/16″	7/16″	**DP1SO6436CCF**	246.	253.	265.	270.	278.	283.	287.	295.
	42″	45″	63 1/16″	7/16″	**DP1SO6442CCF**	256.	264.	277.	282.	289.	295.	300.	307.
	48″	51″	63 1/16″	7/16″	**DP1SO6448CCF**	267.	276.	288.	294.	302.	307.	312.	321.
	60″	63″	63 1/16″	7/16″	**DP1SO6460CCF**	288.	298.	311.	319.	328.	333.	339.	347.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO5718CCF**
DP1SO	Pattern Number
5718	
CC	Center Left, Center Right
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Concealed Post
Monolithic Panel Centered Laminate Inserts
Worksurface Height, 28″ and 42″ High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post Monolithic Panel Centered Laminate Insert	15″	18″	27 1/4″	7/16″	**DP3L1WH15CCF**	$169.
	18″	21″	27 1/4″	7/16″	**DP3L1WH18CCF**	194.
	24″	27″	27 1/4″	7/16″	**DP3L1WH24CCF**	226.
	30″	33″	27 1/4″	7/16″	**DP3L1WH30CCF**	244.
	36″	39″	27 1/4″	7/16″	**DP3L1WH36CCF**	291.
	42″	45″	27 1/4″	7/16″	**DP3L1WH42CCF**	296.
	48″	51″	27 1/4″	7/16″	**DP3L1WH48CCF**	390.
28″ High Concealed Post Monolithic Panel Centered Laminate Insert (For 36″H Panel Frame)	15″	18″	33 13/16″	7/16″	**DP3L12815CCF**	169.
	18″	21″	33 13/16″	7/16″	**DP3L12818CCF**	194.
	24″	27″	33 13/16″	7/16″	**DP3L12824CCF**	226.
	30″	33″	33 13/16″	7/16″	**DP3L12830CCF**	244.
	36″	39″	33 13/16″	7/16″	**DP3L12836CCF**	291.
	42″	45″	33 13/16″	7/16″	**DP3L12842CCF**	296.
	48″	51″	33 13/16″	7/16″	**DP3L12848CCF**	390.
42″ High Concealed Post Monolithic Panel Centered Laminate Insert	15″	18″	41 3/16″	7/16″	**DP3L14215CCF**	226.
	18″	21″	41 3/16″	7/16″	**DP3L14218CCF**	252.
	24″	27″	41 3/16″	7/16″	**DP3L14224CCF**	291.
	30″	33″	41 3/16″	7/16″	**DP3L14230CCF**	394.
	36″	39″	41 3/16″	7/16″	**DP3L14236CCF**	416.
	42″	45″	41 3/16″	7/16″	**DP3L14242CCF**	419.
	48″	51″	41 3/16″	7/16″	**DP3L14248CCF**	461.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L14236CCF**
DP3L1 4236	Pattern Number
CC	Center Left, Center Right
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Concealed Post
Monolithic Panel Centered Laminate Inserts 50″ and 57″ High

description	w *	w	h	d	pattern no.	list
50″ High Concealed Post Monolithic Panel Centered Laminate Insert	15″	18″	48 1/2″	7/16″	**DP3L15015CCF**	$245.
	18″	21″	48 1/2″	7/16″	**DP3L15018CCF**	293.
	24″	27″	48 1/2″	7/16″	**DP3L15024CCF**	368.
	30″	33″	48 1/2″	7/16″	**DP3L15030CCF**	399.
	36″	39″	48 1/2″	7/16″	**DP3L15036CCF**	488.
	42″	45″	48 1/2″	7/16″	**DP3L15042CCF**	492.
	48″	51″	48 1/2″	7/16″	**DP3L15048CCF**	637.
57″ High Concealed Post Monolithic Panel Centered Laminate Insert	15″	18″	55 3/8″	7/16″	**DP3L15715CCF**	250.
	18″	21″	55 3/8″	7/16″	**DP3L15718CCF**	298.
	24″	27″	55 3/8″	7/16″	**DP3L15724CCF**	373.
	30″	33″	55 3/8″	7/16″	**DP3L15730CCF**	405.
	36″	39″	55 3/8″	7/16″	**DP3L15736CCF**	493.
	42″	45″	55 3/8″	7/16″	**DP3L15742CCF**	497.
	48″	51″	55 3/8″	7/16″	**DP3L15748CCF**	641.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L15736CCF**
DP3L1 5736	Pattern Number
CC	Center Left, Center Right
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Concealed Post
Monolithic Panel Double with Post Fabric Inserts
Worksurface Height, 28" and 42" High

description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post Monolithic Panel Double with Post Fabric Insert	30″	33″	27 1/4″	7/16″	**DP1SOWH30EPEF**	$139.	$144.	$151.	$153.	$159.	$161.	$163.	$167.
	36″	39″	27 1/4″	7/16″	**DP1SOWH36EPEF**	156.	161.	168.	170.	175.	178.	180.	185.
	48″	51″	27 1/4″	7/16″	**DP1SOWH48EPEF**	170.	175.	183.	186.	193.	196.	199.	204.
	60″	63″	27 1/4″	7/16″	**DP1SOWH60EPEF**	185.	192.	201.	204.	209.	213.	216.	222.
28″ High Concealed Post Monolithic Panel Double with Post Fabric Insert (For 36″h panel frame)	30″	33″	33 13/16″	7/16″	**DP1SO2830EPEF**	110.	112.	118.	122.	124.	127.	128.	131.
	36″	39″	33 13/16″	7/16″	**DP1SO2836EPEF**	149.	152.	161.	164.	168.	171.	173.	177.
	48″	51″	33 13/16″	7/16″	**DP1SO2848EPEF**	186.	193.	202.	206.	211.	215.	218.	224.
	60″	63″	33 13/16″	7/16″	**DP1SO2860EPEF**	226.	232.	244.	248.	255.	260.	264.	270.
42″ High Concealed Post Monolithic Panel Double with Post Fabric Insert	30″	33″	41 3/16″	7/16″	**DP1SO4230EPEF**	136.	140.	147.	151.	153.	157.	159.	163.
	36″	39″	41 3/16″	7/16″	**DP1SO4236EPEF**	173.	178.	186.	192.	195.	199.	202.	207.
	48″	51″	41 3/16″	7/16″	**DP1SO4248EPEF**	209.	215.	226.	230.	236.	240.	244.	250.
	60″	63″	41 3/16″	7/16″	**DP1SO4260EPEF**	246.	253.	265.	270.	277.	282.	287.	295.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO2836EPEF**
DP1SO 2836	Pattern Number
EPE	End, Post, End
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Concealed Post
Monolithic Panel Double with Post Fabric Inserts 50", 57" and 64" High

description	w *	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50″ High Concealed Post Monolithic Panel Double with Post Fabric Insert	30″	33″	48 /12″	7/16″	**DP1SO5030EPEF**	$162.	$165.	$173.	$178.	$181.	$184.	$188.	$194.
	36″	39″	48 1/2″	7/16″	**DP1SO5036EPEF**	196.	201.	210.	215.	220.	224.	229.	235.
	48″	51″	48 1/2″	7/16″	**DP1SO5048EPEF**	229.	236.	247.	252.	259.	263.	268.	274.
	60″	63″	48 1/2″	7/16″	**DP1SO5060EPEF**	263.	271.	284.	289.	298.	302.	308.	315.
57″ High Concealed Post Monolithic Panel Double with Post Fabric Insert	30″	33″	55 3/8″	7/16″	**DP1SO5730EPEF**	186.	193.	202.	206.	211.	213.	218.	224.
	36″	39″	55 3/8″	7/16″	**DP1SO5736EPEF**	218.	225.	236.	241.	247.	250.	255.	262.
	48″	51″	55 3/8″	7/16″	**DP1SO5748EPEF**	249.	256.	269.	274.	282.	286.	291.	299.
	60″	51″	55 3/8″	7/16″	**DP1SO5760EPEF**	281.	289.	303.	309.	319.	324.	330.	338.
64″ High Concealed Post Monolithic Panel Double with Post Fabric Insert	30″	33″	63 1/16″	7/16″	**DP1SO6430EPEF**	238.	244.	256.	261.	268.	272.	278.	284.
	36″	39″	63 1/16″	7/16″	**DP1SO6436EPEF**	253.	261.	274.	279.	287.	291.	297.	304.
	48″	51″	63 1/16″	7/16″	**DP1SO6448EPEF**	269.	278.	291.	297.	305.	310.	315.	324.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Fabric Inserts

1. Pattern Number
2. Fabric

Order Code

Concealed Post Monolithic Panel Fabric Inserts

Example:	**DP1SO5736EPEF**
DP1SO 5736	Pattern Number
EPE	End, Post, End
F	Tile to Floor
W351-3	Foundation Corn Silk Fabric

Included with:

Concealed Post Monolithic Panel Fabric Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Fabric Inserts

Concealed Post
Monolithic Panel Double with Post Laminate Inserts
Worksurface Height, 28″ and 42″ High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post Monolithic Panel Double with Post Laminate Insert	30″	33″	27 1/4″	7/16″	**DP3L1WH30EPEF**	$244.
	36″	39″	27 1/4″	7/16″	**DP3L1WH36EPEF**	291.
	48″	51″	27 1/4″	7/16″	**DP3L1WH48EPEF**	300.
	60″	63″	27 1/4″	7/16″	**DP3L1WH60EPEF**	393.
	72″	75″	27 1/4″	7/16″	**DP3L1WH72EPEF**	402.
	84″	87″	27 1/4″	7/16″	**DP3L1WH84EPEF**	410.
28″ High Concealed Post Monolithic Panel Double with Post Laminate Insert (For 36″h panel frame)	30″	33″	33 13/16″	7/16″	**DP3L12830EPEF**	365.
	36″	39″	33 13/16″	7/16″	**DP3L12836EPEF**	369.
	48″	51″	33 13/16″	7/16″	**DP3L12848EPEF**	390.
	60″	63″	33 13/16″	7/16″	**DP3L12860EPEF**	634.
	72″	75″	33 13/16″	7/16″	**DP3L12872EPEF**	643.
	84″	87″	33 13/16″	7/16″	**DP3L12884EPEF**	650.
42″ High Concealed Post Monolithic Panel Double with Post Laminate Insert	30″	33″	41 3/16″	7/16″	**DP3L14230EPEF**	394.
	36″	39″	41 3/16″	7/16″	**DP3L14236EPEF**	416.
	48″	51″	41 3/16″	7/16″	**DP3L14248EPEF**	430.
	60″	63″	41 3/16″	7/16″	**DP3L14260EPEF**	640.
	72″	75″	41 3/16″	7/16″	**DP3L14272EPEF**	647.
	84″	87″	41 3/16″	7/16″	**DP3L14284EPEF**	655.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L14236EPEF**
DP3L1 4236	Pattern Number
EPE	End, Post, End
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Concealed Post
Monolithic Panel Double with Post Laminate Inserts 50″ and 57″ High

description	w *	w	h	d	pattern no.	list
50″ High Concealed Post Monolithic Panel Double with Post Laminate Insert	30″	33″	48 1/2″	7/16″	**DP3L15030EPEF**	$399.
	36″	39″	48 1/2″	7/16″	**DP3L15036EPEF**	488.
	48″	51″	48 1/2″	7/16″	**DP3L15048EPEF**	637.
	60″	63″	48 1/2″	7/16″	**DP3L15060EPEF**	644.
	72″	75″	48 1/2″	7/16″	**DP3L15072EPEF**	652.
	84″	87″	48 1/2″	7/16″	**DP3L15084EPEF**	660.
57″ High Concealed Post Monolithic Panel Double with Post Laminate Insert	30″	33″	55 3/8″	7/16″	**DP3L15730EPEF**	405.
	36″	39″	55 3/8″	7/16″	**DP3L15736EPEF**	493.
	48″	51″	55 3/8″	7/16″	**DP3L15748EPEF**	641.
	60″	63″	55 3/8″	7/16″	**DP3L15760EPEF**	649.
	72″	75″	55 3/8″	7/16″	**DP3L15772EPEF**	656.
	84″	87″	55 3/8″	7/16″	**DP3L15784EPEF**	665.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Concealed Post Monolithic Panel Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Concealed Post Monolithic Panel Laminate Inserts

Example:	**DP3L15736EPEF**
DP3L1 5736	Pattern Number
EPE	End, Post, End
F	Tile to Floor
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Concealed Post Monolithic Panel Laminate Inserts

- Attachment Clips

Options

Concealed Post Monolithic Panel Laminate Inserts

Finish Options:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Concealed Post
Frameless Add Up
Clear, Powder and Bronze Glass

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25)
Frameless Add Up, 7″ High (For use with concealed post only)	51″	¾″	7″	**DP1AU0751( )G**		$399.	$448.
	57″	¾″	7″	**DP1AU0757( )G**		432.	486.
	63″	¾″	7″	**DP1AU0763( )G**		465.	525.
	69″	¾″	7″	**DP1AU0769( )G**		499.	564.
	75″	¾″	7″	**DP1AU0775( )G**		533.	604.
	81″	¾″	7″	**DP1AU0781( )G**		577.	657.
	87″	¾″	7″	**DP1AU0787( )G**		623.	710.
	93″	¾″	7″	**DP1AU0793( )G**		673.	768.
	99″	¾″	7″	**DP1AU0799( )G**		727.	829.
Shortened Frameless Add Up, 7″ High (For use with concealed post only)	50″	¾″	7″	**DP1AU0750( )G**		399.	448.
	56″	¾″	7″	**DP1AU0756( )G**		432.	486.
	62″	¾″	7″	**DP1AU0762( )G**		465.	525.
	68″	¾″	7″	**DP1AU0768( )G**		499.	564.
	74″	¾″	7″	**DP1AU0774( )G**		533.	604.
	80″	¾″	7″	**DP1AU0780( )G**		527.	657.
	86″	¾″	7″	**DP1AU0786( )G**		623.	710.
	92″	¾″	7″	**DP1AU0792( )G**		673.	768.
	98″	¾″	7″	**DP1AU0798( )G**		727.	829.
Frameless Add Up, 14″ High (For use with concealed post only) 	51″	¾″	14″	**DP1AU1451( )G**		563.	662.
	57″	¾″	14″	**DP1AU1457( )G**		616.	726.
	63″	¾″	14″	**DP1AU1463( )G**		668.	791.
	69″	¾″	14″	**DP1AU1469( )G**		720.	855.
	75″	¾″	14″	**DP1AU1475( )G**		774.	919.
	81″	¾″	14″	**DP1AU1481( )G**		840.	896.
	87″	¾″	14″	**DP1AU1487( )G**		908.	1,078.
	93″	¾″	14″	**DP1AU1493( )G**		981.	1,163.
	99″	¾″	14″	**DP1AU1499( )G**		1,059.	1,255.

Ordering Information

Frameless Add Up with Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Glass

Example:	**DP1AU0757VG**
DP1AU	Frameless Add Up
07	7″ High
57	57″ Wide
V	Full view
G	Glass
117	Frame finish
TEMP	Clear glass finish

Included with:

Frameless Add Up with Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Allignment Clip

Options

Frame Options:
(V)= Full view
(C) = Topway

Glass Options:
(TEMP)= Clear
(GL13) = Powder
(GL25) = Bronze

Concealed Post
Frameless Add Up
Clear, Powder and Bronze Glass

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25)
Shortened Frameless Add Up, 14″ High (For use with concealed post only)	50″	¾″	14″	**DP1AU1450( )G**		$563.	$662.
	56″	¾″	14″	**DP1AU1456( )G**		616.	726.
	62″	¾″	14″	**DP1AU1462( )G**		668.	791.
	68″	¾″	14″	**DP1AU1468( )G**		720.	855.
	74″	¾″	14″	**DP1AU1474( )G**		774.	919.
	80″	¾″	14″	**DP1AU1480( )G**		840.	996.
	86″	¾″	14″	**DP1AU1486( )G**		908.	1,076.
	92″	¾″	14″	**DP1AU1492( )G**		981.	1,163.
	98″	¾″	14″	**DP1AU1498( )G**		1,059.	1,255.



End Cap				**DP1AUECTP**	36.		

Ordering Information

Frameless Add Up with Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Glass

Example:	**DP1AU0757VG**
DP1AU	Frameless Add Up
07	7″ High
57	57″ Wide
V	Full view
G	Glass
117	Frame finish
TEMP	Clear glass finish

Included with:

Frameless Add Up with Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Allignment Clip

Options

Frame Options:
(V)= Full view
(C) = Topway

Glass Options:
(TEMP)= Clear
(GL13) = Powder
(GL25) = Bronze

The 120-degree planning model provides comparable or greater square footage per workstation than typical cubicle layouts (comparisons are illustrated on this page). At the same time, Dividends Horizon 120º allows for a more natural space, creating a more comfortable place to work. Maintaining a consistent 48" module promotes improved asset management and a reduction of reconfiguration costs.



Big House
Sq. Feet = 69.8'
7 Panels



8' x 8'
Sq. Feet = 64'
7 Panels



Full House
Sq. Feet = 42.1'
5 Panels



6' x 7'
Sq. Feet = 42'
7 Panels



Open House
Sq. Feet = 35.5'
4 Panels



6' x 6'
Sq. Feet = 36'
6 Panels

Townhouse
Sq. Feet = 34.1'
3 Panels



6' x 6'
Sq. Feet = 36'
6 Panels



Apartment
Sq. Feet = 32.1'
2 Panels

4' x 6'
Sq. Feet = 24'
4 Panels



8 Open House Stations
Sq. Feet = 284'
19 Panels



8 Station Cluster
Each station 6' x 6'
Sq. Feet = 288'
28 Panels

These worksurfaces are designed specifically for Dividends Horizon 120. The (L/R) suffix at the end of a pattern number indicates a defined pedestal location. If the worksurface has no defined pedestal location, the (L/R) represents the curved side of the top. All tops and tables are available with 2mm edge band or a 1" ergonomic edge.

Worksurface: W3
This worksurface, combined with the T3 Transition top, works best with the "apartment" layout. This application allows for stations on both sides of the spine, and is ideal for high density layouts. Available in extended versions fo placement directly next to another worksurface.

Worksurface: W4
This top works well in the "open house," "full house," and "big house" layouts for call center, professional, and managerial applications.

Worksurface: W5 (L/R)
With transition top T5 and this worksurface, teaming is made easy using the "townhouse" or "open house" layout. The shared space allows for call center, professional, or technical applications.

Worksurface: W6 (L/R)
In the "big house," "full house" or "open house", this worksurface allows for a pedestal on one side (determined by the L/R). Applications for this top include a call center with the "open house," technical applications with the "full house," and managerial layouts with the "big house."

Worksurface: W7 (L/R)
Used in conjunction with a T4 transition top, the W7 worksurface provides a great teaming space when the "townhouse" layout is used. The "open house" layout incorporates the T2 transition top for professional or technical stations with shared space for conferencing. Available in extended versions for placement directly next to another worksurface.

Worksurface: W11 /W1118 (L/R)
This top is a spacious option for a technical station in the "open house" layout. Adding a T2 transition top provides additional teaming space. The W11 surface also fits nicely in a private managerial office or a "full house" professional application.



Worksurface: W3



Worksurface: W6 (L/R)



Worksurface: W4



Worksurface: W7 (L/R)



Worksurface: W5 (L/R)



Worksurface: W11 / W1118 (L/R)

Worksurface: W12 / W1218 (L/R)
This top, with the T5/T518 transition top provides a technical office with shared conferencing space in the “open house” layout. The 18" return allows ample space in the supervisory application of the “full house.”

Worksurface: W13 / W1318 (L/R)
This surface provides a teaming space with the T2/T218 transition in the “open house” layout. The W13/W1318 creates generous worksurface space in the “full house” as well as the management layout of the “big house.”

Transition Tops
Transition tops require columns (not included) for support. Flat brackets (not included) are required to attach transition tops to adjacent worksurfaces.

Application Notes
Dividends Horizon 120 worksurfaces use cantilevers as their main form of support. A cantilever must be used at each post location to support worksurfaces properly. A pedestal may be used for support, where applicable, in conjunction with cantilevers.

Worksurface: W12 / W1218 (L/R)



left right



Worksurface: W13 / W1318 (L/R)



left right



Transition Tops

Transition top: T2



Transition top: T218



Transition top: T3



Transition top: T4

Transition top: T5

Transition top: T518

description	h*	w	d	pattern no.	Black	Metal P1	Metal P2	Metal P3
120°Two-Way Post Assembly	36″	3″	3″	**DP( )120PA362**		$260.	$268.	$277.
	42″	3″	3″	**DP( )120PA422**		260.	268.	277.
	50″	3″	3″	**DP( )120PA502**		272.	281.	289.
	57″	3″	3″	**DP( )120PA572**		301.	311.	320.
	64″	3″	3″	**DP( )120PA642**		301.	311.	320.
	78″	3″	3″	**DP( )120PA782**		383.	400.	413.
120°Three-Way Post Assembly	36″	3″	3″	**DP( )120PA363**		266.	274.	281.
	42″	3″	3″	**DP( )120PA423**		266.	274.	281.
	50″	3″	3″	**DP( )120PA503**		277.	284.	293.
	57″	3″	3″	**DP( )120PA573**		301.	311.	320.
	64″	3″	3″	**DP( )120PA643**		301.	311.	320.
	78″	3″	3″	**DP( )120PA783**		381.	396.	410.
14″ High 120° Stack Panel Posts	14 5/8″	3″	3″	**DP120SPO 14**	80.			
21″ High 120° Stack Panel Posts	21 15/16″	3″	3″	**DP120SPO 21**	81.			
28″ High 120° Stack Panel Posts	29 1/4″	3″	3″	**DP120SPO 28**	92.			

h = nominal height

Ordering Information

Post Assemblies

1. Pattern Number
2. Trim Finish

Order Code

Post Assemblies

Example:	**DP(4)120PA 642, 113**
DP(4)120 PA 642	Pattern Number
113	Dark grey trim finish

Included with:

Post Assemblies

- Post assemblies
- Post top cap
- Post cover
- Connecting hardware

Options

Post assembly trim options

(4) = Metal, Radius
(5) = Metal, Flat

description	type	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Post Covers (Straight) High-Low Connection	36″ - 42″	8″			**DP120PC08S**	$9.	$11.	$11.
	36″ - 50″	14″			**DP120PC14S**	15.	20.	22.
	36″ - 64″	28″			**DP120PC28S**	36.	39.	40.
	36″ - 78″	42″			**DP120PC42SH**	54.	57.	59.
	42″ - 50″	8″			**DP120PC08S**	9.	11.	11.
	42″ - 64″	22″			**DP120PC22S**	23.	24.	25.
	42″ - 78″	36″			**DP120PC36S**	48.	53.	55.
	50″ - 64″	14″			**DP120PC14S**	15.	20.	22.
	50″ - 78″	28″			**DP120PC28S**	36.	39.	40.
	64″ - 78″	14″			**DP120PC14S**	15.	20.	22.
Post Top Caps	One-Way	½″	3″	3″	**DP( )120PT1**	8.	9.	9.
	Three-Way	½″	3″	3″	**DP( )120PT3**	8.	9.	9.
	Two-Way	½″	3″	3″	**DP( )120PT2**	8.	9.	9.
Post Covers (Straight)		36″			**DP120PC36SF**	45.	48.	53.
		42″			**DP120PC42S**	45.	48.	53.
		50″			**DP120PC50S**	46.	50.	54.
		57″			**DP120PC57S**	53.	55.	58.
		64″			**DP120PC64S**	53.	55.	58.
		78″			**DP120PC78S**	58.	64.	66.
Universal Post (Post Only)		36″	3″	3″	**DP120PO36**	195.		
		42″	3″	3″	**DP120PO42**	195.		
		50″	3″	3″	**DP120PO50**	205.		
		57″	3″	3″	**DP120PO57**	222.		
		64″	3″	3″	**DP120PO64**	222.		
		78″	3″	3″	**DP120PO78**	300.		
Inside Panel Shroud for 120° posts		5″			**DP120S**	10.	13.	15.

Ordering Information

Universal Post

1. Pattern Number

Panel Top Cap

1. Pattern Number
2. Trim finish

Post Covers

1. Pattern Number
2. Trim finish

Order Code

Universal Post	
Example:	**DP2A P050**
DP2A P050	Pattern Number
Panel Top Cap	
Example:	**DPV1 PT4, V04**
DPV1 PT4	Pattern Number
V04	Maple trim finish
Post Covers	
Example:	**DP2A PC50S, 117**
DP(2A) PC50S	Pattern Number
117	Soft grey trim finish

Included with:

Universal Post

Connecting hardware

Panel Top Cap

Post Covers

Options

120° Post

Panel Top Cap and Post Covers

(4) = Metal, Radius
(5) = Metal, Flat

This page intentionally left blank

Grain Direction

W3



W4



W5



W6



W7



W11



W12



W13



T3



T4



T5



description	top name	w	return depth	d	pattern no.	2 mm	woodgrain edge	metal edge
Worksurface	W11L	48″	18″L-24″R		**D1WW11481824**	$1,035.	$1,137.	$1,241.
	W11L	48″	24″L-18″R		**D1WW11482418**	1,035.	1,137.	1,241.
	W12L	48″	24″		**D1WW124824L**	1,080.	1,191.	1,298.
	W12R	48″	24″		**D1WW124824R**	1,080.	1,191.	1,298.
	W1318L	48″	24″L-18″R		**D1WW13482418**	1,035.	1,137.	1,241.
	W1318R	48″	18″L-24″R		**D1WW13481824**	1,035.	1,137.	1,241.
	W13L	48″	24″		**D1WW134824L**	1,035.	1,137.	1,241.
	W13R	48″	24″		**D1WW134824R**	1,035.	1,137.	1,241.
	W218L	48″	24″L-18″R		**D1WW12482418**	1,080.	1,191.	1,298.
	W218R	48″	18″L-24″R		**D1WW12481824**	1,080.	1,191.	1,298.
	W3	48″	24″		**D1WW34824**	789.	866.	943.
	W4	48″	24″		**D1WW44824**	811.	892.	973.
	W5L	48″	24″		**D1WW54824L**	652.	718.	786.
	W5R	48″	24″		**D1WW54824R**	652.	718.	786.
	W6L	48″	24″		**D1WW64824L**	877.	964.	1,051.
	W6R	48″	24″		**D1WW64824R**	877.	964.	1,051.
	W7L	48″	24″		**D1WW74824L**	873.	962.	1,048.
	W7R	48″	24″		**D1WW74824R**	873.	962.	1,048.
Transition tops	T2	50″	24″		**D1WT224**	525.	579.	632.
	T218	37½″	18″		**D1WT218**	492.	544.	591.
	T3	26″	24″		**D1WT324**	501.	553.	604.
	T4	26″	24″		**D1WT424**	603.	663.	722.
	T5	50″	24″		**D1WT524**	610.	672.	729.
	T518	37½″	18″		**D1WT518**	547.	600.	653.

Ordering Information

Worksurface

1. Pattern number
2. Finish

Order Code

Example:	**D1WW134824L, 118, 118**
D1W	Dividends 120 w/s 2mm edge
W13	Worksurface #13
4824	Side width/return depth
L	Pedestal on left side
118	Bright White laminate
118	Bright White edge

Included with:

Worksurface

- Worksurface

Worksurface supports must be ordered separately.

For all tops, specify laminate and edge color.

Transition and peninsula tops require a column base for support.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Refer to the worksurface planning page for worksurface drawings and applications.

Note: W3 worksurfaces have a grain direction option. Specify left, right or diagonal. Add $25 to the list price when specifying diagonal.

3+1 Circuit Electrical
The Dividends Horizon 3+1 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring a single isolated circuit is required.

The wire configuration of the 8-wire/4 circuit electrical system is (see chart):

- Hot “A” (black)
- Hot “B” (red)
- Hot “C” (blue)
- Shared neutral “N1” (white/black) for circuits #1, 2 and 3
- Shared ground “G1” (green) for circuits #1, 2 and 3
- Hot “X” (pink)
- Isolated neutral “N2” (white/ red) for circuit 4
- Isolated ground “G2” (green/ yellow) for circuit 4

Circuits 1, 2 and 3 have shared neutral and grounds for convenience power while circuit 4 has a separate ground and neutral for designated/isolated power or to support uninterrupted power supply (UPS).

Compatibility
All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+1 components can be connected to 3+3 wire systems, however only 3+1 will function.

3+1 Duplex Receptacles
Duplex receptacles used in 3+1 electrical systems are:

- Convenience duplex circuit number 1(pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)

Isolated duplex receptacle number 4 has an orange-colored triangle on black background to identify an isolated duplex.

An optional orange-colored isolated duplex is also available. It has the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)

3+1 Electrical System Technical Specifications
The 3+1 electrical system consists of four 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric Code (NEC) limits continuous loads to 80% of capacity or 16 amps.

Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 8-wire (4-circuit) system can supply a cluster of 6 -10 workstations from each infeed.

Surge Suppressors
Dividends Horizon surge suppressors (pattern number DE1SS) plug into any terminal block position to provide surge protection for all duplexes on that circuit.

Note: When connected, surge suppressors take the place of a duplex receptacle resulting in the elimination of one duplex position from the circuit.

Independent Neutral Electrical Systems
Dividends Horizon offers a 2+1 electrical system with independent neutrals as a standard special. It is our belief that independent neutrals are not required. However, if a customer desires an independent neutral electrical system, a Dividends Horizon solution can be provided. For further information, list pricing and schematic drawings, contact Knoll Customer Service.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module
Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.

Power Connector
Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper
Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (3+1)



Electrical Specifications
(2+2) Electrical System

2+2 Electrical System
The Dividends Horizon 2+2 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring two isolated circuits are required.

The wiring configuration of the (2+2) electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Shared neutral "N1" (white/black) for circuits #1 and 2
- Shared ground "G1" (green) for circuits #1 and 2
- Hot "Y" (tan)
- Hot "X" (pink)
- Isolated Shared Neutral "N2" (white/red) for circuits #4 and 5
- Isolated Shared ground "G1" (green/yellow) for circuits #4 and 5

Circuits 1 and 2 share common neutral and ground. Circuits 4 and 5 share a separate common neutral and ground.

Compatibility
All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable.

2+2 Duplex Receptacles
Duplex receptacles used in 8-wire (2+2) electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)

2+2 Electrical System Technical Specifications
The 2+2 electrical system consists of four 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase, and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric

Code (NEC) limits continuous loads up to 80% of capacity or 16 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets.

Surge Suppressors
Dividends Horizon surge suppressors (pattern number DE1 SS) plug into any terminal block position to provide surge protection for all duplexes on that circuit.

Note: When connected, surge suppressors take the place of a duplex receptacle resulting in the elimination of one duplex position from the circuit.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module
Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.

Power Connector
Specify one power connector (with or without post) to connect power modules in adjacent panels.

Power Jumper
Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (2+2)



3+3 Electrical System

The Dividends Horizon 3+3 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring multiple isolated circuits is required.

The wiring configuration of the 3+3 electrical system is (see chart):

- Hot “A” (black)
- Hot “B” (red)
- Hot “C” (blue)
- Shared neutral “N1” (white/black) for circuits #1, 2 and 3
- Shared ground “G1” (green) for circuits #1, 2 and 3
- Hot “Z” (orange)
- Hot “X” (pink)
- Hot “Y” (tan)
- Isolated neutral “N2” (white/ red for circuits 4, 5 and 6
- Isolated ground “G2” (green/yellow) for circuits 4, 5 and 6

Circuits 1, 2 and 3 are for convenience power while circuits 4, 5 and 6 are for designated/ isolated power or for supporting uninterrupted power supply (UPS).

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+3 components can be connected to 3+1 systems, however only 8-wires will function.

3+3 Duplex Receptacles

Duplex receptacles used in 3+3 electrical systems are:

- Convenience duplex circuit number 1(pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)
- Isolated duplex circuit number 6 (pattern number DE1DR6)

Isolated duplex receptacles number 4, 5 and 6 have an orange-colored triangle on black background to signify as an isolated duplex.

Optional orange-colored isolated duplexes are also available. They have the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)
- Isolated orange-colored duplex circuit number 5 (pattern number DE1DOR5)
- Isolated orange-colored duplex circuit number 6 (pattern number DE1DOR6)

3+3 Electrical System Technical Specifications

The 3+3 electrical system consists of six 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric Code (NEC) limits continuous loads to 80% of capacity or 16 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 10-wire (6-circuit) system can supply a cluster of 9 -15 workstations from each infeed.

Surge Suppressors

Dividends Horizon surge suppressors (pattern number DE1SS) plug into any terminal block position to provide surge protection for all duplexes on that circuit.

Note: When connected, surge suppressors take the place of a duplex receptacle resulting in the elimination of one duplex position from the circuit.

Independent Neutral Electrical Systems

Dividends Horizon offers a 10-wire/2+2 electrical system with independent neutrals as a standard special. It is our belief that independent neutrals are not required. However, if a customer desires an independent neutral electrical system, a Dividends Horizon solution can be provided. For further information, list pricing and schematic drawings, contact Knoll Customer Service.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.

Power Connector

Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (3+3)



Base Raceway Electrical
Power Modules, Power Jumpers
Specifications

Base Raceway Electrical

Power can be distributed through the base raceway.

Three systems are available:

- 3 + 1
- 2 + 2
- 3 + 3

Modular components are used to distribute power through the base raceway and consist of:

- Power modules
- Power connectors
- Power jumpers
- Duplex receptacles
- Power infeeds

All electrical components and data cables are field-installed.

CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Power Modules

Power modules are the primary electrical components for distributing electrical within panels. They are also the only components that accept duplex receptacles and power infeeds for access.

Panels 24" and wider can accept power modules. 18" wide panels only accept power jumpers.

Power modules consist of terminal blocks at each end connected by a hard-wired metal conduit. The terminal blocks accept duplex receptacles or power infeeds. Power modules snap into integral channels in base raceways and can be accessed on one or both panel sides.

Power Jumpers

Power jumpers connect between power modules in non-adjacent panels. Power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:

- Single panel power jumpers
- Single panel power jumpers with post
- Multiple panel power jumpers

Single panel power jumpers carry power from a panel with a power module through a single non-electrified panel to an adjacent panel with a power module when a post connector is not involved.

Single panel power jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a power module.

Multiple panel power jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available power module.

Base Raceway Electrical



Power Module



Power Module Connection



Power Jumper



Base Raceway Electrical
3+1, 2+2 and 3+3 Systems Specifications

Power Connectors
Power connectors carry power from power module to power module in adjacent panels.

Two versions are available:
- 12" no post
- 15" with post

12" power connectors connect adjacent power modules in straight configurations when no post connector is involved.

15" power connectors are used in applications involving adjacent power modules separated by post connectors.

Duplex Receptacles
Duplex receptacles provide access to power along the base raceway.

Two duplex receptacles can be installed per panel side in base raceways 24" and wider. 18" wide panels cannot accept duplex receptacles.

Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.

Duplexes are available in (3+1), (2+2) and (3+3) systems. Each system engages a different combination of circuit wiring within the power module. For detailed wiring diagrams, refer to the electrical system required:

- 3 + 1
- 2 + 2
- 3 + 3

3+1, 2+2 and 3+3 Electrical Systems
Each electrical system is designed for different usage.

The (2+2) electrical system is for areas requiring 2 circuits for standard power usage and 2 circuits for isolated power usage.

The (3+1) electrical system is for areas requiring significant power usage and an isolated circuit.

The (3+3) electrical system is for areas with significant power usage and a need for multiple isolated circuits.

Base Power Infeeds
Base power infeeds route power from the building's electrical source to the panel base raceway.

Power infeeds plug into any terminal block position on panel power modules.

Power Connector



Duplex Receptacle



Base Infeed



Legend



Note: Power connectors or power jumpers can only plug into power modules

Power Connectors



Single Panel Power Jumpers



Multiple Panel Power Jumpers



Multiple Panel Power Jumper and Power Connector



Base Raceway Electrical
Power Modules, Connectors and Jumpers (3+1),(2+2) and (3+3)

description	type	pattern no.	E	8	T
Power Module - Double sided for raceway on both sides	24″W Panel	**DE1(E,8,T) PM24**	$108.	$119.	$123.
	30″W Panel	**DE1(E,8,T) PM30**	115.	127.	127.
	36″W Panel	**DE1(E,8,T) PM36**	119.	130.	133.
	42″W Panel	**DE1(E,8,T) PM42**	128.	140.	139.
	48″W Panel	**DE1(E,8,T) PM48**	135.	147.	146.
	60″W Panel	**DE1(E,8,T) PM60**	151.	166.	166.
Power Module - Single sided for raceway on one side	24″W Panel	**DE1(E,8,T) PMS24**	108.	119.	123.
	30″W Panel	**DE1(E,8,T) PMS30**	115.	127.	127.
	36″W Panel	**DE1(E,8,T) PMS36**	119.	130.	133.
	42″W Panel	**DE1(E,8,T) PMS42**	128.	140.	139.
	48″W Panel	**DE1(E,8,T) PMS48**	135.	147.	146.
	60″W Panel	**DE1(E,8,T) PMS60**	151.	166.	166.
Power Connector - (power module-to-power module)	12″ no post	**DE1(E,8,T) PCNP**	70.	76.	85.
	15″ with post	**DE1(E,8,T) PCWP**	72.	78.	92.
Power Jumper	15″ Panel	**DE1(E,8,T) PJ15NP**	81.	94.	119.
	18″ Panel	**DE1(E,8,T) PJ18NP**	81.	94.	119.
	24″ Panel	**DE1(E,8,T) PJ24NP**	93.	99.	125.
	30″ Panel	**DE1(E,8,T) PJ30NP**	96.	104.	129.
	36″ Panel	**DE1(E,8,T) PJ36NP**	99.	109.	136.
	42″ Panel	**DE1(E,8,T) PJ42NP**	104.	116.	140.
	48″ Panel	**DE1(E,8,T) PJ48NP**	111.	124.	146.
Power Jumper (with post)	15″ Panel + Post	**DE1(E,8,T) PJ15WP**	90.	97.	123.
	18″ Panel + Post	**DE1(E,8,T) PJ18WP**	90.	97.	123.
	24″ Panel + Post	**DE1(E,8,T) PJ24WP**	94.	102.	128.
	30″ Panel + Post	**DE1(E,8,T) PJ30WP**	97.	107.	132.
	36″ Panel + Post	**DE1(E,8,T) PJ36WP**	102.	114.	139.
	42″ Panel + Post	**DE1(E,8,T) PJ42WP**	108.	119.	142.
	48″ Panel + Post	**DE1(E,8,T) PJ48WP**	115.	127.	150.

Ordering Information

Power Jumper

1. Pattern Number

Order Code

Power Jumper

Example:	**DE1E PJ42NP**
DE1E	Pattern Number
PJ42NP	

Included with:

Power Jumper

Options

Power Jumper

Options
(E) = 3+1
(8) = 2+2
(T) = 3+3

Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

Base Raceway Electrical
Power Modules, Connectors and Jumpers (3+1),(2+2) and (3+3)

description	type	pattern no.	E	8	T
Multiple Panel Power Jumper (with or without post)	54″ Panel Run	**DE1(E,8,T) PJ54WP**	$121.	$132.	$156.
	60″ Panel Run	**DE1(E,8,T) PJ60WP**	124.	136.	156.
	66″ Panel Run	**DE1(E,8,T) PJ66WP**	130.	142.	167.
	72″ Panel Run	**DE1(E,8,T) PJ72WP**	133.	146.	172.
	78″ Panel Run	**DE1(E,8,T) PJ78WP**	139.	153.	176.
	84″ Panel Run	**DE1(E,8,T) PJ84WP**	144.	161.	180.
	96″ Panel Run	**DE1(E,8,T) PJ96WP**	152.	168.	194.

Ordering Information

Power Jumper

1. Pattern Number

Order Code

Power Jumper

Example:	**DE1E PJ42NP**
DE1E	Pattern Number
PJ42NP	

Included with:

Power Jumper

Options

Power Jumper

Options
(E) = 3+1
(8) = 2+2
(T) = 3+3

Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

This page intentionally left blank

Duplex Receptacles
Duplexes are field-installed into power modules within beltway and base raceways. Duplex receptacles insert into panel power module terminal block positions and attach with a single screw.

Identification of Duplexes
Duplexes are clearly marked to indicate which circuits they access. Convenience duplex receptacles are black in color with the circuit identification in white.

Isolated duplexes are black in color with the circuit identification in white and an orange triangle located in the lower right corner.

Orange isolated duplexes are also available for ease of identification. In orange-colored duplexes the identifying triangle is outlined in black.

Types of Duplex Receptacles
Several types of duplex outlets are available. Each is specific to the circuit it accesses and is listed by power system.

Specify the duplex receptacle related to the power system being used (example: 8-wire) and circuit accessed (example: circuit 4). Black or orange finish.

3+1 Duplex Receptacles
Receptacles in a 3+1 electrical system can access circuits 1, 2 and 3 (convenience power) and circuit 4 (isolated power)

2+2 Duplex Receptacles
Receptacles in a 2+2 electrical system can access circuits 1 and 2 (convenience power) and circuits 4 and 5 (isolated power)

Please note that circuit 3 is not available in a 2+2 electrical system.

3+3 Duplex Receptacles

Receptacles in a 3+3 electrical system can access circuits 1, 2 and 3 (convenience power) and circuits 4, 5 and 6 (isolated power)

Power Capacity
Each duplex circuit has a capacity of 20 amps. The National Electrical Code (NEC) requires that each circuit does not exceed 80% of capacity or 16 amps continuous use on each 20 amp circuit.

Duplex Receptacle Dimensions
- Overall dimensions: 4 $^{5}/_{8}$" wide, 2$^{1}/_{16}$" high, 1" deep
- Face dimensions: 2$^{5}/_{8}$" wide, 1$^{1}/_{4}$" high

Access
Non-electrified panels can accept data ports in any raceway cover knockout. Panels with power modules can only accept data ports in the center knockout due to the location of the terminal block.

Typical Power Requirements of Various Equipment

Equipment	Amp (approx.)
Calculator	.25
Coffee maker*	8.5-15
Desktop copier*	10-15
Fan	1
Fax (plain paper)	5-8
Heater*	8.5-15
Laser printer	6-10
Lighting	.5-1.5
Microwave*	10-20
PC	4-8
Refrigerator*	10-15
Terminal	1-3
Typewriter	1-2
Scanner	.25-.5

*Requires separate circuit

Note: The above amperage chart is based on the estimated average amount of power required and is intended as a general guide only. For precise amperage requirements, refer to the equipment manufacturer's amperage specifications and compare to the available amperage on each circuit.



Base Raceway Covers (knockout locations)



Beltway Covers (knockout locations)



Receptacles
Knockout Replacement Covers

description	type	pattern no.	Single pack list	Ten pack list
Receptacle, (3+1)(Black)	Duplex circuit 1	**DE1DR1 ( )**	$37.	$298.
	Duplex circuit 2	**DE1DR2 ( )**	37.	298.
	Duplex circuit 3	**DE1DR3 ( )**	37.	298.
	Duplex circuit 4	**DE1DR4 ( )**	37.	298.
Receptacle, (2+2)(Black)	Duplex circuit 1	**DE1DR1 ( )**	37.	298.
	Duplex circuit 2	**DE1DR2 ( )**	37.	298.
	Duplex circuit 4	**DE1DR4 ( )**	37.	298.
	Duplex circuit 5	**DE1DR5 ( )**	37.	298.
Receptacle, (3+3)(Black)	Duplex circuit 1	**DE1DR1 ( )**	37.	298.
	Duplex circuit 2	**DE1DR2 ( )**	37.	298.
	Duplex circuit 3	**DE1DR3 ( )**	37.	298.
	Duplex circuit 4	**DE1DR4 ( )**	37.	298.
	Duplex circuit 5	**DE1DR5 ( )**	37.	298.
	Duplex circuit 6	**DE1DR6 ( )**	37.	298.
Receptacle, (Orange)	Duplex circuit 4	**DE1DOR4( )**	37.	298.
	Duplex circuit 5	**DE1DOR5( )**	37.	298.
	Duplex circuit 6	**DE1DOR6( )**	37.	298.
Base Raceway Knockout Replacement Cover (for electrical or data)	Package of 10	**DE1KC**	n/a	40.

Ordering Information	Order Code	Included with:	Options
Receptacle	**Receptacle**	**Receptacle**	**Receptacle**
1. Pattern Number	*Example:* **DE1 DR4**		**Quantity Option:**
	DE1 DR4 Pattern Number		(SP) = Single Pack (TP) = Ten Pack

Vertical Electrical
Power Module, Electrical Receptacle and Trim Plate Specifications

Vertical Power Module
A vertical power module is an alternative to using beltway electrical. The use of a vertical power module allows for electrical access within a panel without having to order a beltway panel. Vertical power modules can be installed below a worksurface, at desk height or even within a panel-mounted overhead cabinet.

A panel's left-hand or right-hand vertical rail (see below) allows for installation of a vertical power module. Vertical power modules may be installed with 1-sided or 2-sided access, allowing users of both panel faces access to an electrical receptacle.

Base Power Jumpers
Base raceway power jumpers are used to connect the adjacent panel's base power module to the vertical power module.

Additional vertical power modules may be "daisy-chained" together with base power jumpers. If one vertical power module is installed, an additional vertical power module may be added within the same panel. A base power jumper connects between the two vertical power modules.

Vertical power modules can also be daisy-chained in adjacent panels. A base power jumper passes through the beltway panel frame opening to connect to the additional vertical power module.

Vertical Electrical Receptacle
Please note that base raceway receptacles are not compatible with vertical power modules.

Vertical electrical receptacles must be ordered separately from the vertical power module. Vertical electrical receptacles consist of one vertical receptacle. One vertical power module can also accommodate back-to-back vertical electrical receptacles.

To provide back-to-back vertical electrical power, two vertical receptacles must be specified. Vertical electrical receptacles must be ordered separately.

Specify the vertical receptacle that relates to the circuit specified.

Desktop Power module
Desktop power modules (DE3WSME) provide two low-profile outlets at worksurface height. The desktop power module also helps meet ADA requirements regarding power access at worksurface height.

A mounting bracket and attachment screw allow the desktop power module to be installed at any point along the rear of a worksurface without tools or the removal of the worksurface. An $8^1/_2$' power cord plugs into any duplex receptacle in the base raceway and accesses the circuit it is connected to. Desktop power module dimensions are $3^3/_4$" wide and $4^1/_2$" high.

Base Raceway Power Jumpers
To specify a base power jumper that connects a desk height vertical power module to an adjacent panel's base power module, specify a 48" base power jumper for panel widths of 36" or less. Use a 54" base power jumper for panel widths of 42" or 48". If a vertical power module is to be installed higher than worksurface height within a 64" high panel, a 66" base power jumper is required and an 84" base power jumper is required for 78" high panels.

To specify a base power jumper to span the width of two vertical power modules within two adjacent panels, identify the base power jumper length by combining the panel widths and height differences between the two vertical power modules.

Note: The base power jumper passes through the panel's beltway opening that is at a height of 33".

The panel's beltway opening (at 33" high) must not be obstructed as to allow for the base power jumper to pass through.

Note: 36" high panel frames do not have beltway openings and do not support horizontal power pass through at 33".

Note: Vertical electrical components can be used with a technology tile or field installed into a fabric tile.



Vertical Electrical Power Jumpers





Vertical Power Module and Electrical Receptacle

Vertical Electrical
Power Module, Electrical Receptacle and Trim Plate Specifications

Communications and Data Distribution
Dividends Horizon panels can accommodate communications and data cables horizontally in three ways:

- Along the top cableway
- Along the beltway (with optional cable tray)
- Along the base raceway (with optional cable tray)

Vertical cable distribution is through the panel's internal panel cavity which is accessed by cable slots located in both the upper and lower horizontal panel frame. Since cables are distributed internally within Dividends Horizon panels, no external cable managers are required.

Raceway cover data knockouts have an opening of $1^{3}/_{8}$" high x $2^{11}/_{16}$" wide. Data port covers are no longer available from Knoll and must be supplied from a communications vendor.

Data Port Access
Non-electrified panels can accept data ports in any raceway cover knockout.

Panels with power modules can only accept data ports in the center knockout due to the location of the terminal blocks.

Single Floating Data Port
Dividends Horizon floating data ports allow data and communications to be mounted in any location on the panel surface.

Floating data ports include front and back mounting plates and attachment screws. All data port kits must be specified separately for floating data ports. Floating data ports involve field-cutting the panel insert for installation.

Includes front and back mounting plates and two mounting screws. Data ports kits or data port components must be specified separately from a communications vendor. Black finish.

Desktop Modules
The desktop data module provides up to two data/communication ports at worksurface height. The desktop power module provides two convenient electrical outlets at worksurface height. The desktop power and data module includes two data/communication ports and two electrical outlets at worksurface height. The thumbscrew on the bracket allows user adjustability if desired. Black finish.

Data modules do not include data jacks. Data jacks need to be purchased separately. This data module has two openings that can accept most standard jack sizes. The data module comes with adapter pieces that can accommodate most standard data jacks.

Topway Panel Cable Routing



Floating Data Port





Data Port Access (Non-Electrified Panels)



Data Port Access (Electrified Panels)

Desktop Data Module



Desktop Power and Data Module



Desktop Power Module



Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate Double and Single Ports

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	3+3
Vertical Power Module	Vertical Power Module	**DE6 VPM**	$195.	n/a			
Vertical Electrical Receptacle (3+1)(Black)	Duplex circuit 1	**DE6 VDR1( )**	37.	298.			
	Duplex circuit 2	**DE6 VDR2( )**	37.	298.			
	Duplex circuit 3	**DE6 VDR3( )**	37.	298.			
	Duplex circuit 4	**DE6 VDR4( )**	37.	298.			
Vertical Electrical Receptacle (2+2)(Black)	Duplex circuit 1	**DE6 VDR1( )**	37.	298.			
	Duplex circuit 2	**DE6 VDR2( )**	37.	298.			
	Duplex circuit 4	**DE6 VDR4( )**	37.	298.			
	Duplex circuit 5	**DE6 VDR5( )**	37.	298.			
Vertical Electrical Receptacle (3+3)(Black)	Duplex circuit 1	**DE6 VDR1( )**	37.	298.			
	Duplex circuit 2	**DE6 VDR2( )**	37.	298.			
	Duplex circuit 3	**DE6 VDR3( )**	37.	298.			
	Duplex circuit 4	**DE6 VDR4( )**	37.	298.			
	Duplex circuit 5	**DE6 VDR5( )**	37.	298.			
	Duplex circuit 6	**DE6 VDR6( )**	37.	298.			

Ordering Information

Vertical Power Module

1. Pattern Number

Base Raceway Power Jumper

1. Pattern Number

Order Code

Vertical Power Module	
Example:	**DE5 VPM**
DE5 VPM	Pattern Number
Base Raceway Power Jumper	
Example:	**DE1(E) BPJ30**
DE1(E) BPJ30	Pattern Number

Included with:

Vertical Power Module

Base Raceway Power Jumper

Options

Vertical Power Module

Base Raceway Power Jumper
Insert appropriate letter for type of wiring required within the parentheses of the pattern number.
(E) = 3+1
(8) = 2+2
(T) = 3+3

Receptacle Quantity Option:
(SP) = Single Pack
(TP) = Ten Pack

Note: Trim plate filler for use with technology tile trim plate only.

Vertical Electrical
Power Module, Electrical Receptacle and Trim Plate Double and Single Ports

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	3+3
Trim Plate Filler 	Package of 10	**DE6 FDPF**	n/a	$39.			
Single Floating Data Port Trim Plate (field install kit) 	Faceplate, backplate and hardward	**DE1 FDP**	46.	n/a			
Technology Tile Trim Plate (field install kit) 	Faceplate, backplate filler and hardware	**DE6 FDP**	50.	n/a			
Base Raceway Power Jumpers	48″ Jumper	**DE1(E,8,T) PJ48WP**			115.	127.	150.
	54″ Jumper	**DE1(E,8,T) PJ54WP**			121.	132.	156.
	60″ Jumper	**DE1(E,8,T) PJ60WP**			124.	136.	156.
	66″ Jumper	**DE1(E,8,T) PJ66WP**			130.	142.	167.
	72″ Jumper	**DE1(E,8,T) PJ72WP**			133.	146.	172.
	78″ Jumper	**DE1(E,8,T) PJ78WP**			139.	153.	176.
	84″ Jumper	**DE1(E,8,T) PJ84WP**			144.	161.	180.

Ordering Information

Vertical Power Module

1. Pattern Number

Base Raceway Power Jumper

1. Pattern Number

Order Code

Vertical Power Module	
Example:	**DE5 VPM**
DE5 VPM	Pattern Number
Base Raceway Power Jumper	
Example:	**DE1(E) BPJ30**
DE1(E) BPJ30	Pattern Number

Included with:

Vertical Power Module

Base Raceway Power Jumper

Options

Vertical Power Module

Base Raceway Power Jumper
Insert appropriate letter for type of wiring required within the parentheses of the pattern number.
(E) = 3+1
(8) = 2+2
(T) = 3+3

Receptacle Quantity Option:
(SP) = Single Pack
(TP) = Ten Pack

Note: Trim plate filler for use with technology tile trim plate only.

description	type	w	d	h	pattern no.	list
Desktop Power Module, clamp mount	With 108″ Cord	3¾″	4½″	2½″	**DE4WSME108**	$135.
	With 72″ Cord	3¾″	4½″	2½″	**DE4WSME72**	109.
Desktop Power + Data Module, clamp mount	With 108″ Cord	6⅛″	4½″	2½″	**DE4WSMED108**	289.
	With 72″ Cord	6⅛″	4½″	2½″	**DE4WSMED72**	262.
Desktop Data Module, clamp mount		3 3/4’	4½″	2½″	**DE4WSMC**	95.

Ordering Information	Order Code	Included with	Options
Desktop Power Module	**Desktop Power Module**		
1. Pattern Number	*Example:* **DE4 WSME108**		

This page intentionally left blank

Beltway Electrical
Power can be distributed through the beltway

Three systems are available:
- 3+1
- 2+2
- 3+3

Modular components are used to distribute power within beltways and consist of:

- Beltway power modules
- Beltway power connectors
- Beltway power jumpers
- Beltway vertical power jumpers
- Duplex receptacles

All electrical components and data cables are field-installed.

WARNING: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTING TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Beltway modules accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway. Another alternative for desk height electrical is a vertical power module.

Depending on the number of desk height receptacles required in each panel, consider the list price of both beltway electrical and vertical power module in each application.

Beltway Power Modules
Power modules are the primary electrical components for distributing power within beltways. Beltway power modules are also components that accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway.

Beltway raceways 30" and wider can accept beltway power modules while 18" and 24" wide panels can accept power jumpers for pass-through power only.

Beltway power modules screw into the vertical channels of panel frames and include a steel horizontal mounting support.

Specify one beltway power module per panel that matches the width of the panel where duplexes are required. Available one- or two-sided.

Just like base raceway power modules, beltway power modules consist of a terminal block at each end connected by a hard-wired metal conduit.

Beltway power modules are one- or two-sided. This allows planning options such as beltway one side and monolithic or tiled inserts on the other, or beltway one side and no inserts on the other for against-the-wall applications. The terminal blocks accept either duplex receptacles or vertical power jumpers.

Beltway Power Connectors
Beltway power connectors carry power from power module to power module in adjacent panels.

Two versions are available:
- no post
- with post.

Beltway power connectors, no post, connect adjacent power modules in straight configurations when a post connector is not involved.

Beltway power connectors, with post, are used in applications involving adjacent power modules separated by post connectors in straight through post configurations only.

Specify one beltway power connector (with or without post) to connect beltway power module or beltway power jumper in adjacent panels. In straight line configurations only.



Beltway Electrical



Beltway Power Module



Beltway Power Connector



Beltway Profiles

Beltway Power Jumpers
Beltway power jumpers connect between power modules in nonadjacent panels. Beltway power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:
- Single panel jumpers
- Single panel jumpers with post
- Multiple panel jumpers

Single panel beltway jumpers carry power from a panel with a beltway power module through a single non-electrified panel to an adjacent panel with a beltway power module when a post is not involved in straight line configurations only.

Single beltway panel jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a beltway power module in straight through post configurations only.

Multiple beltway panel jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available beltway power module in straight line configurations only.

Specify one beltway power jumper per panel that matches the width of the panel for pass-through electrical where duplexes are not required for straight line configurations only.

90° Beltway Power Jumper
A 90° beltway power jumper connects adjacent beltway power modules at a 90° "L" panel connection.

The following illustrations outline the various components required for beltway applications with a post.

Note: A 90° beltway power jumper can only be used with adjacent panels in a "X", "T" or "L" conditions. The 90° jumper cannot be used to span multiple panels.

To specify correct jumper length, determine the largest panel width between the two adjacent corner panels in which jumper is to be installed.

Vertical Power Jumpers
To carry power from the base raceway to the beltway located in the same panel requires a vertical power jumper. Vertical power jumpers function as an extension of the base raceway power system.

Attachment is from any unused outlet position in the base raceway to the end terminal block connection in the beltway power module. The vertical power jumper cable is concealed in the cavity of the panel frame.

Power can also be carried to a beltway run from the base raceway of an adjacent panel with a power module. This is accomplished by using a panel power jumper.

Specify one vertical power jumper per beltway electrical run not to exceed the electrical systems capacity. See the technical specifications for the electrical system being utilized.

Note: Length of power jumper allows for connections with or without post conditions.

Power Infeeds
A ceiling infeed may also be used to bring power directly to the beltway power module without having to go directly to a base raceway power module.

Duplex Receptacles
Duplex receptacles provide access to power along the beltway. Duplexes used in the beltway are the same as the duplexes used in the base raceway.

Two duplex receptacles can be installed per panel side in beltway raceways 30" and wider. 24"W panels will accept beltway power jumpers for pass-through power only.

Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.

Beltway Power Jumper Configurations

Beltway Power Jumper





Beltway Post Connections



Beltway Electrical Components



Legend



Beltway Electrical
Power Modules, Power Connectors and Power Jumpers

description	type	length	pattern no.	3+1	2+2	3+3
Beltway Power Module - 1-Side		30″	**DE1( ) BPM301**	$151.	$167.	$167.
		36″	**DE1( ) BPM361**	159.	174.	170.
		42″	**DE1( ) BPM421**	167.	180.	178.
		48″	**DE1( ) BPM481**	174.	194.	185.
		60″	**DE1( ) BPM601**	197.	202.	202.
Beltway Power Module - 2-Side		30″	**DE1( ) BPM302**	151.	167.	167.
		36″	**DE1( ) BPM362**	159.	174.	170.
		42″	**DE1( ) BPM422**	167.	180.	178.
		48″	**DE1( ) BPM482**	174.	194.	185.
		60″	**DE1( ) BPM602**	197.	202.	202.
Beltway Power Connector	17″ No Post		**DE2( ) BPCNP**	75.	81.	93.
	20″ With Post		**DE2( ) BPCWP**	77.	89.	96.
Beltway Power Jumper (No post)		18″	**DE2( ) BPJ18NP**	93.	99.	125.
		24″	**DE2( ) BPJ24NP**	96.	104.	129.
		30″	**DE2( ) BPJ30NP**	99.	109.	136.
		36″	**DE2( ) BPJ36NP**	104.	116.	140.
		42″	**DE2( ) BPJ42NP**	111.	124.	146.
		48″	**DE2( ) BPJ48NP**	115.	127.	150.
Beltway Power Jumper (With post)		18″	**DE2( ) BPJ18WP**	94.	102.	128.
		24″	**DE2( ) BPJ24WP**	97.	107.	132.
		30″	**DE2( ) BPJ30WP**	102.	114.	139.
		36″	**DE2( ) BPJ36WP**	108.	121.	142.
		42″	**DE2( ) BPJ42WP**	115.	127.	150.
		48″	**DE2( ) BPJ48WP**	124.	129.	152.
Multiple Panel Power Jumper (with or without post)		54″ Panel Run	**DE2( ) BPJ54WP**	124.	136.	156.
		60″ Panel Run	**DE2( ) BPJ60WP**	130.	142.	167.
		66″ Panel Run	**DE2( ) BPJ66WP**	133.	145.	172.
		72″ Panel Run	**DE2( ) BPJ72WP**	139.	152.	176.
		78″ Panel Run	**DE2( ) BPJ78WP**	144.	159.	180.
		84″ Panel Run	**DE2( ) BPJ84WP**	152.	170.	194.
		96″ Panel Run	**DE2( ) BPJ96WP**	164.	177.	201.

Ordering Information

Beltway Power Jumper

1. Pattern Number

Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

Order Code

Beltway Power Jumper

Example: **DE1(E) BPJ30**

DE1(E)	Pattern Number
BPJ30	

Included with:

Beltway Power Jumper

Options

Beltway Power Jumper

Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

- **E**= 3+1
- **8**= 2+2
- **T**= 3+3

description	type	length	pattern no.	3+1	2+2	3+3
90° Beltway Power Jumper		30″ Beltway Panel	**DE1( ) PJ120WP**	$199.	$217.	$249.
		36″ Beltway Panel	**DE1( ) PJ126WP**	205.	226.	259.
		42″ Beltway Panel	**DE1( ) PJ138WP**	214.	236.	268.
		48″ Beltway Panel	**DE1( ) PJ144WP**	221.	244.	278.
Vertical Power Jumper (Within Same Panel)			**DE1( ) VPJ**	170.	185.	176.
Vertical Power Jumper (From Adjacent Panel)		30″ Beltway Panel	**DE1(E,8,T) PJ48WP**	115.	127.	150.
		36″ Beltway Panel	**DE1(E,8,T) PJ54WP**	121.	132.	156.
		42″ Beltway Panel	**DE1(E,8,T) PJ54WP**	121.	132.	156.
		48″ Beltway Panel	**DE1(E,8,T) PJ60WP**	124.	136.	156.

Ordering Information

Beltway Power Jumper

1. Pattern Number

Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

Order Code

Beltway Power Jumper

Example:	**DE1(E) BPJ30**
DE1(E) BPJ30	Pattern Number

Included with:

Beltway Power Jumper

Options

Beltway Power Jumper
Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

- **E**= 3+1
- **8**= 2+2
- **T**= 3+3

Electrical Infeeds and Power Poles
Specifications

Power Infeeds
Power infeeds carry power from the building's electrical source to the panel system's base raceway. Two styles are available:

- Base power infeeds
- Ceiling infeeds

Base Power Infeed
Dividends Horizon base power infeeds route power from floor monuments or electrical boxes to any terminal block duplex position on base raceway power modules. Two screws secure the base power infeed to the power module.

Note: When connected, a base power infeed takes the place of one duplex outlet.

Base power infeeds have a 56" long liquid tight conduit and pigtail for connection to the building's power supply.

Infeeds are specified either right- or left-handed. This allows the conduit to enter the outlet position from either the left or right side.

In addition to right- or left handed base power infeeds is a reversible base power infeed with a 56" long liquid tight conduit. The reversible infeed rotates to provide either a right- or left-hand power entry.

Specify the base infeed that matches the power system accessed and left or right cable entry (example: (3+1), left-hand entry).

Ceiling Infeeds
Raceway-to-ceiling infeeds route power from a ceiling-located power source to the panel system's base raceway. Unlike base infeeds which plug into any terminal block outlet position, ceiling infeeds must plug into the end of a base raceway power module. Ceiling infeeds have a 19 $^{1}/_{2}$' long metal conduit and pigtail. Two components are required for installation:

- Raceway to ceiling infeed
- Power pole

Ceiling infeed may be installed directly into a beltway power module for beltway electrical only.

Specify the ceiling infeed that matches the power system accessed.

Power Poles
Power poles can accommodate one raceway-to-ceiling infeed along with data cables. The power pole can also be used to route data cables only, if required. Cable capacity for power poles with the electrical conduit installed is 30, category 5 cables and without an electrical conduit is 40, category 5 cables.

Power poles integrate within the panel system footprint by mounting atop existing post connectors in "L", "T" or "X" configurations.

Power poles are available in three lengths in order to accommodate all three heights of post connectors. All power poles measure 126" or 144" when added to the height of the post connector. For ceilings less than 126" or 144" high, field-cut the power pole to the required height. Power poles include ceiling trim plate, connecting hardware and post/power pole trim covers.

Legacy Power Pole Construction
Power pole is extruded aluminum powder coated, with four PVC trim covers.

Dividends Horizon DP7 Power Pole Construction
Power pole is extruded aluminum, with removable cover, powder coated in any Knoll Core or Dividends Horizon Legacy finish. One side of the power pole is open, allowing cables to be inserted or removed when the cover is removed.

CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.



Ceiling Connection



Power Pole Connection



Ceiling Infeed Base Raceway Connection

Ceiling Connection





Base Raceway Infeed Connection (right infeed shown)

Ceiling Infeed Connection

Power Infeeds



Base Power Infeed
(right infeed shown)



Reversible Base
Power Infeed

Electrical Infeeds and Power Poles
Base Power and Raceway-to-Ceiling Infeeds

description	type	length	pattern no.	list	P1	P2	P3
Base Power Infeed (specify left or right) (right shown)	2+2	56″	**DE18 BI56(L/R)**	$212.			
	3+1	56″	**DE1E BI56(L/R)**	194.			
	3+3	56″	**DE1T BI56(L/R)**	249.			
Base Power Infeed (reversible)	2+2	56″	**DE18 RBI56**	256.			
	3+1	56″	**DE1E RBI56**	235.			
	3+3	56″	**DE1T RBI56**	308.			
Raceway-to-Ceiling Infeed	2+2	19 1/2’	**DE18 CI144**	311.			
	3+1	19 1/2’	**DE1E CI144**	282.			
	3+3	19 1/2’	**DE1T CI144**	358.			

Ordering Information

Base Power Infeed (L/R)

1. Pattern Number

Power Pole

1. Pattern Number
2. Trim Finish

Note: Power poles mount atop existing post connectors in “L”, “T” and “X” configurations

Order Code

Base Power Infeed (L/R)

Example:	**DE18 BI56(L)**
DE18 BI56(L)	Pattern Number (left entry)
Power Pole	
Example:	**DE(1) PP64S, 117**
DE(1) PP64S	Pattern Number
117	Soft Grey trim finish

Included with:

Base Power Infeed (L/R)

Power Pole

- Power pole
- Ceiling trim plate
- Connecting hardware
- Post/power pole trim cover

Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.

Options

Base Power Infeed (L/R)

- To specify direction of entry, add either an **“L”** or **“R”** suffix to the pattern number.

Legacy Power Pole

- Post cover

(1)= Grooved
(2)= Smooth
Insert appropriate number for post cover option within the parentheses of the pattern number

Dividends Horizon Power Pole

- Post cover

description	type	length	pattern no,	list	P1	P2	P3
Dividends Horizon Power Pole for use with DP7 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 126″ ceiling height	For 36″H DP7 Post	90″	**DP7PP36S**		$400.	$420.	$440.
	For 42″H DP7 Post	84″	**DP7PP42S**		368.	384.	405.
	For 50″H DP7 Post	76″	**DP7PP50S**		339.	354.	372.
	For 57″H DP7 Post	69″	**DP7PP57S**		299.	314.	330.
	For 64″H DP7 Post	62″	**DP7PP64S**		294.	308.	324.
	For 78″H DP7 Post	48″	**DP7PP78S**		294.	308.	324.
Dividends Horizon Power Pole for use with DP7 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 144″ ceiling height	For 36″H DP7 Post	108″	**DP7PP36T**		408.	428.	448.
	For 42″H DP7 Post	102″	**DP7PP42T**		374.	393.	413.
	For 50″H DP7 Post	94″	**DP7PP50T**		339.	354.	372.
	For 57″H DP7 Post	86″	**DP7PP57T**		299.	314.	330.
	For 64″H DP7 Post	80″	**DP7PP64T**		294.	308.	324.
	For 78″H DP7 Post	66″	**DP7PP78T**		294.	308.	324.
Legacy Power Pole for use with Legacy Posts only (does not include Raceway-to-Ceiling Infeed) For 126″ ceiling height	For 36″H Post	90″	**DE2PP36S**	400.			
	For 42″H Post	84″	**DE2PP42S**	368.			
	For 50″H Post	76″	**DE2PP50S**	339.			
	For 64″H Post	62″	**DE2PP64S**	299.			
	For 78″H Post	48″	**DE2PP78S**	294.			
Legacy Power Pole for use with Legacy Posts only (does not include Raceway-to-Ceiling Infeed) For 144″ ceiling height	For 36″H Post	108″	**DE2PP36T**	301.			
	For 42″H Post	102″	**DE2PP42T**	267.			
	For 50″H Post	94″	**DE2PP50T**	346.			
	For 64″H Post	80″	**DE2PP64T**	308.			
	For 78″H Post	66″	**DE2PP78T**	299.			

Ordering Information

Base Power Infeed (L/R)

1. Pattern Number

Power Pole

1. Pattern Number
2. Trim Finish

Order Code

Base Power Infeed (L/R)

Example:	**DE18 BI56(L)**
DE18 BI56(L)	Pattern Number (left entry)

Power Pole

Example:	**DE2 PP64S, 117**
DE2 PP64S	Pattern Number
117	Soft Grey trim finish

Included with:

Base Power Infeed (L/R)

Power Pole

- Power pole
- Ceiling trim plate
- Connecting hardware
- Post/power pole trim cover

Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.

Note: Power poles mount atop existing post connectors in “L”, “T” and “X” configurations

Options

Base Power Infeed (L/R)

- To specify direction of entry, add either an **“L”** or **“R”** suffix to the pattern number.

Legacy Power Pole

- Post cover has a smooth finish

Dividends Horizon Power Pole

This page intentionally left blank

New York City Hardwire Infeeds
The New York City hardwire infeed is comprised of a junction box and a power connector exiting from one side.

New York City infeeds are available in one size which mount within any base raceway 24" or wider.

The New York City infeed takes the place of a power module and prevents the installation of duplex receptacles in the panel housing the infeed. The hardwire infeed's power connector plugs into a power module which must be located in the adjacent panel.

The New York City infeed can be rotated to either the right or left side of the base raceway to provide power to either the adjacent left or right panel.

If power is required in both directions, specify a separate power jumper the length of the panel containing the infeed. The power jumper connects panel power modules located at either side of the panel containing the NYC hardwire infeed and is routed within the same raceway as the NYC hardwire infeed.

The power jumper is then routed in the opposite direction and connects to a power module located in the adjacent panel on the panel's other side (refer to the diagram below).

The panel containing the NYC hardwire infeed must be specified without base raceway cover knockouts.

A template for drilling the base raceway cover to accept the NYC hardwire infeed conduit is included.

Chicago Hardwire
Pre-wired modular electrical systems are not permitted in the City of Chicago. All electrical must be hard-wired by a qualified electrician.

In order to conform to City of Chicago electrical codes, a hardwire receptacle raceway kit(s) must be installed in all panel base raceways that require duplex receptacles. In order to conform to the City of Chicago electrical code for base power infeed, the hardwire infeed raceway kit must be installed within the panel base raceway. Hardwire receptacle raceway kit(s) and hardwire infeed raceway kit(s) mount in the base raceway between the panel feet and are available in 24" to 48" widths.

Hardwire receptacle raceway kits are secured by four screws. In addition, the base raceway covers on both sides of a panel with hardwire receptacle raceway kits must be secured with two screws each. A template for drilling attachment holes in base raceway covers is included with the hardwire receptacle raceway kit.

Optional Chicago base raceway covers can be ordered separately to replace existing covers if pre-drilled covers are desired.

When passing (jumping) hardwired power through panels, panels must be specified without knockouts in the base raceway to conform to the City of Chicago electrical code. All panels containing hardwire receptacle raceway kits must be specified with base raceway knockouts.

Note: Dividends Horizon beltway electrical is not available with Chicago hardwire.

New York Electrical Configurations

NYC Infeeds are reversible and one direction



NYC Infeeds (positioned at left side of raceway)

NYC Infeeds (positioned at right side of raceway)

To provide two direction power

Power Jumper

Power Module

NYC Power Infeed

Power Module

New York Electrical



New York City Infeed

Chicago Electrical



Hardwire Receptacle Raceway Kit (Chicago)

Raceway Cover

Hardwire Infeed Raceway Kit (Chicago)

New York City, San Francisco and Chicago Electrical
Infeeds and Retrofit Kit

description	type	l	pattern no.	list
Hardwire Infeed (NYC) - 1 Direction	2+2		**DE18 B1NY1**	$586.
	3+1		**DE1E B1NY1**	509.
	3+3		**DE1T B1NY1**	655.
Base Power Infeed (San Francisco)	2+2	56″	**DE18 BI56( )SF**	201.
	3+1	56″	**DE1E BI56( )SF**	182.
	3+3	56″	**DE1T BI56( )SF**	237.
Reversible Base Power Infeed (San Francisco)	2+2	56″	**DE18 RBI56SF**	244.
	3+1	56″	**DE1E RBI56SF**	222.
	3+3	56″	**DE1T RBI56SF**	293.
Electrical Retrofit Kit (Chicago) (for electrical on new panel base raceway)			**DP7CERK**	64.

Ordering Information

Hardwire Infeed (NYC)

1. Pattern Number

Order Code

Hardwire Infeed (NYC)

Example:	**DE1E B1NY1**
DE1E B1NY1	**Pattern Number**

Included with:

Hardwire Infeed (NYC)

- Junction box with power connector and infeed
- Ceiling trim plate
- Attachment screws

Options

Hardwire Infeed (NYC)

Power System

- 3+1
- 2+2
- 3+3

San Francisco Infeed direction option
(L) = Left
(R) = Right

Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP7 panel base raceways.

description	type	l	pattern no.	list
Hardwire Infeed Raceway Kit (Chicago) 	Double Sided	24″	**DP7HIRKD24**	$359.
	Double Sided	30″	**DP7HIRKD30**	610.
	Double Sided	36″	**DP7HIRKD36**	616.
	Double Sided	42″	**DP7HIRKD42**	619.
	Double Sided	48″	**DP7HIRKD48**	623.
	Double Sided	60″	**DP7HIRKD60**	634.
	Single Sided	24″	**DP7HIRKS24**	506.
	Single Sided	30″	**DP7HIRKS30**	719.
	Single Sided	36″	**DP7HIRKS36**	724.
	Single Sided	42″	**DP7HIRKS42**	727.
	Single Sided	48″	**DP7HIRKS48**	731.
	Single Sided	60″	**DP7HIRKS60**	744.
Hardwire Receptacle Raceway Kit (Chicago)	Double Sided	24″	**DP7HRRKD24**	277.
	Double Sided	30″	**DP7HRRKD30**	464.
	Double Sided	36″	**DP7HRRKD36**	469.
	Double Sided	42″	**DP7HRRKD42**	472.
	Double Sided	48″	**DP7HRRKD48**	477.
	Double Sided	60″	**DP7HRRKD60**	489.
	Single Sided	24″	**DP7HRRKS24**	320.
	Single Sided	30″	**DP7HRRKS30**	451.
	Single Sided	36″	**DP7HRRKS36**	456.
	Single Sided	42″	**DP7HRRKS42**	456.
	Single Sided	48″	**DP7HRRKS48**	461.
	Single Sided	60″	**DP7HRRKS60**	471.
Pre-Drilled Replacement Covers, Pair (Chicago)	24″ Wide Panel	24″	**DP7RCCH24**	39.
	30″ Wide Panel	30″	**DP7RCCH30**	43.
	36″ Wide Panel	36″	**DP7RCCH36**	46.
	42″ Wide Panel	42″	**DP7RCCH42**	53.
	48″ Wide Panel	48″	**DP7RCCH48**	55.
	60″ Wide Panel	60″	**DP7RCCH60**	64.

Ordering Information

Hardwire Infeed (NYC)

1. Pattern Number

Order Code

Hardwire Infeed (NYC)

Example:	**DE1E B1NY1**
DE1E B1NY1	**Pattern Number**

Included with:

Hardwire Infeed (NYC)

- Junction box with power connector and infeed
- Ceiling trim plate
- Attachment screws

Options

Hardwire Infeed (NYC)

Power System

- 3+1
- 2+2
- 3+3

San Francisco Infeed direction option
(L) = Left
(R) = Right

Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP7 panel base raceways.

This page intentionally left blank

Cable Management
Specifications

Base Raceway Cable Tray
Optional steel cable trays are available for installations requiring the use of data and communications cables within the base raceway. The cable tray mounts between the panel feet.

Cable trays are field-installed and accessible from either side of the base raceway. A single sided base raceway cable tray should be specified when attaching to a tile-to-floor panel base.

Note: Cables should not be installed in base raceways without cable trays.

Beltway Cable Tray
An optional cable tray is available for data and communications cables within the beltway. Beltway cable trays should be used when wires are being routed horizontally from panel-to-panel at the beltway. The cable tray mounts into slots located on the vertical panel frame.

Cable trays are $1^{1}/_{4}$" high, $1^{5}/_{16}$" deep and are field-installed. Construction is 20-gauge steel with black finish.

Note: Beltway cable trays can be installed in monolithic panels to provide additional mid span insert support when required.

Worksurface Cable Management Basket
Constructed of black finished steel wire, the worksurface cable management basket mounts to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable management basket slides forward to a position abutting the panel face to allow the passage of cords and cables.

Specify by width available between worksurface supports. Black finish.

Worksurface cable management baskets are $1^{1}/_{2}$" high, $3^{1}/_{2}$" deep and $19^{1}/_{2}$" to $41^{1}/_{2}$" wide.

Vertical Wire Pathway Grommet
An optional plastic grommet that snaps into the vertical wire pathway on the horizontal panel frame to separate cables from the panel frame. Located in center of topway and base raceway.

Topway Cable Grommet
The primary location for cable management for Dividends Horizon is in the topway. In order to utilize the topway channel effectively, the outside knockouts must be removed by using pliers. When the knockouts are removed the cables can be easily managed in the channel.

If required, a topway knockout grommet may be installed inside of the topway channel. Four grommets would be required per panel topway

Worksurface Cable Management Clip
An optional cable management clip. $^{3}/_{4}$" x $^{1}/_{2}$" (internal dimension) plastic clip manages cables on the underside of worksurfaces.

Data Shield
If separation of cabling and electrical wires is required within the base raceway, a data shield can be attached below a base raceway power module at either end. Data shields are field-installed. The data shield should be used with base raceway panels or tile to floor panels only.



Base Raceway Cable Tray



Beltway Cable Tray



Worksurface Cable Management Basket

Vertical Wire Pathway





Topway Cable Grommet

Worksurface Cable Management Clip





Data Shield

Cable Management
Accessories

description	type	pattern no.	list
Worksurface Cable Management Basket	19½″ wide	**D1WB20**	$40.
	25½″ wide	**D1WB26**	42.
	31½″ wide	**D1WB32**	53.
	35″ wide	**D1WB36**	58.
	41″ wide	**D1WB42**	61.
Vertical Wire Pathway Grommet (optional)	Package of 10	**DP1 VWG**	170.
Topway Cable Grommet	Package of 40	**DP1 TKC**	59.
Worksurface Cable Management Clip	Package of 10	**D1WC**	38.
Data Shield 	1 Pair for use with base raceway	**DE1DATSHD**	30.
	1 Pair for use with tile to floor	**DE1DATSHDF**	30.

Ordering Information

Base Raceway Cable Tray

1. Pattern Number

Order Code

Base Raceway Cable Tray

Example:	**DP1 RCT24**
DP1	Pattern Number
RCT24	

Included with:

Base Raceway Cable Tray

Options

Base Raceway Cable Tray

Note: DP7 cable trays are for use with all DP7 series panels and all panels produced prior to November 2007.

Note: Data Shield is not compatible with open base panels.

description	type	pattern no.	list
Base Raceway Cable Tray - double sided for use with raceway on both sides (optional)	18″ Panel Width	**DP72RCT18**	$24.
	24″ Panel Width	**DP72RCT24**	26.
	30″ Panel Width	**DP72RCT30**	30.
	36″ Panel Width	**DP72RCT36**	32.
	42″ Panel Width	**DP72RCT42**	34.
	48″ Panel Width	**DP72RCT48**	38.
	60″ Panel Width	**DP72RCT60**	41.
Base Raceway Cable Tray - single sided for use with raceway on one side (optional)	18″ Panel Width	**DP71RCT18**	24.
	24″ Panel Width	**DP71RCT24**	26.
	30″ Panel Width	**DP71RCT30**	30.
	36″ Panel Width	**DP71RCT36**	32.
	42″ Panel Width	**DP71RCT42**	34.
	48″ Panel Width	**DP71RCT48**	38.
	60″ Panel Width	**DP71RCT60**	41.
Beltway Cable Tray (optional)	18″ Panel Width	**DP1BCT18**	26.
	24″ Panel Width	**DP1BCT24**	27.
	30″ Panel Width	**DP1BCT30**	31.
	36″ Panel Width	**DP1BCT36**	33.
	42″ Panel Width	**DP1BCT42**	36.
	48″ Panel Width	**DP1BCT48**	39.
	60″ Panel Width	**DP1BCT60**	57.

Ordering Information

Base Raceway Cable Tray

1. Pattern Number

Order Code

Base Raceway Cable Tray

Example: **DP1 RCT24**

DP1	Pattern Number
RCT24	

Included with:

Base Raceway Cable Tray

Options

Base Raceway Cable Tray

Note: DP7 cable trays are for use with all DP7 series panels and all panels produced prior to November 2007.

This page intentionally left blank

Flip-Up Door Overheads
Panel- and Wall-Mounted
Dividends Series 1, Series 2 and Series 3 Overheads - Specifications

Flip-Up Door Overheads
Flip-up overheads mount to the integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Flip-up overhead cabinets consist of a top, shelf, end panels, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.

Series 1 Flip-up Door Overhead
Series 1 flip-up overhead cabinets match the aesthetics of the original Dividends Horizon system. The radiused fronts and molded plastic end trim match the radiused profile trim used on panel topcaps and end trim. Series 1 cabinets are offered with steel doors.

Series 2 Flip-up Door Overhead
Series 2 overhead cabinets offer an alternative aesthetic to the original Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below).The Series 2 overhead offers a painted steel or veneer overhead door front.

Series 3 Flip-up Door Overhead
Series 3 cabinets offer a third aesthetic choice for flip-up overhead cabinets. The series 3 door profile is similar to the rectilinear door of the Series 2 cabinet, but the corners have a sharper radius to complement Dividends Horizon flat profile trim. Series 3 cabinets are offered with steel, laminate or veneer doors.

Note: Horizon Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes
- Height: 15"
- Depth: 14 1/8"
- Widths: 24", 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:
- **Horizontal top and shelf:** 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- **Overhead door:**
  - Steel: 20-gauge painted steel
  - Laminate: 3/4" particle board with high pressure laminate on the outside and a paper backer on the inside. 1mm edgeband.
  - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Overhead door end trim:** Color injected, molded plastic (on Series 1 only)
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Overhead door suspension:** Steel ball bearing

Interior Dimensions
The interior dimensions of overhead cabinets and shelves are:
- Depth: 12"
- Usable interior height: 12 5/8"
- Width: 1/8" shorter than the exterior width

Cabinet Door Clearance
Cabinet doors open over the tops of cabinets. Required clearance is 16 1/4" total height (height of cabinet plus top clearance required).

Touchdown Overhead Cabinets
Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allow the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Task Lights
All Dividends cabinets and shelves will accept task lights. Task lights must be specified separately.

Locks
Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required. When locks are not specified on Series 1 and Series 2 overheads, a plug is located in the lock position. Lock retrofit kits are available for field installation at a later date for Series 1 and Series 2 overheads only.

Note: Horizon Series 3 flip-up overheads are only available in Knoll Core finishes.

Flip-up Door Overhead Configurations



Interior Dimensions



Cabinet Door Clearance



Flip-up Door Overhead Profiles



Flip-Up Door Overheads
Panel- and Wall-Mounted
Dividends Series 1, Series 2 and Horizon Series 3

description	w *	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Dividends Series 1 Flip-Up Overhead w/Steel Door 	24″	23 7/8″	14 1/8″	15″	**DS1O24L**	$369.	$405.	$421.	n/a	n/a	n/a
	30″	29 7/8″	14 1/8″	15″	**DS1O30L**	369.	405.	421.	n/a	n/a	n/a
	36″	35 7/8″	14 1/8″	15″	**DS1O36L**	388.	425.	446.	n/a	n/a	n/a
	42″	41 7/8″	14 1/8″	15″	**DS1O42L**	411.	453.	473.	n/a	n/a	n/a
	48″	47 7/8″	14 1/8″	15″	**DS1O48L**	424.	470.	489.	n/a	n/a	n/a
	54″	53 7/8″	14 1/8″	15″	**DS1O54L**	626.	687.	719.	n/a	n/a	n/a
	60″	59 7/8″	14 1/8″	15″	**DS1O60L**	626.	687.	719.	n/a	n/a	n/a
	66″	65 7/8″	14 1/8″	15″	**DS1O66L**	646.	712.	744.	n/a	n/a	n/a
	72″	71 7/8″	14 1/8″	15″	**DS1O72L**	646.	712.	744.	n/a	n/a	n/a
Series 2 Flip-Up Overhead w/ Steel or Veneer Door 	24″	23 7/8″	14 1/8″	15″	**DS2PM24L**	477.	551.	576.	749.	822.	844.
	30″	29 7/8″	14 1/8″	15″	**DS2PM30L**	477.	551.	576.	749.	822.	844.
	36″	35 7/8″	14 1/8″	15″	**DS2PM36L**	519.	598.	623.	757.	834.	861.
	42″	41 7/8″	14 1/8″	15″	**DS2PM42L**	568.	651.	678.	775.	862.	890.
	48″	47 7/8″	14 1/8″	15″	**DS2PM48L**	623.	716.	749.	832.	925.	958.
	54″	53 7/8″	14 1/8″	15″	**DS2PM54L**	740.	852.	890.	1,185.	1,295.	1,333.
	60″	59 7/8″	14 1/8″	15″	**DS2PM60L**	740.	852.	890.	1,185.	1,295.	1,333.
	66″	65 7/8″	14 1/8″	15″	**DS2PM66L**	825.	949.	990.	1,240.	1,364.	1,406.
	72″	71 7/8″	14 1/8″	15″	**DS2PM72L**	825.	949.	990.	1,240.	1,364.	1,406.
Dividends “touchdown” retro-fit (two kits required for 54″w - 72″w)					**DS1EAKIT**	252.					
Series 3 Flip-Up Overhead w/ Steel Door 	30″	29 7/8″	14 1/2″	15″	**DS3PMS30L**	471.	519.	544.			
	36″	35 7/8″	14 1/2″	15″	**DS3PMS36L**	485.	535.	558.			
	42″	41 7/8″	14 1/2″	15″	**DS3PMS42L**	500.	551.	577.			
	48″	47 7/8″	14 1/2″	15″	**DS3PMS48L**	517.	569.	594.			
	60″	59 7/8″	14 1/2″	15″	**DS3PMS60L**	651.	717.	751.			
	66″	65 7/8″	14 1/2″	15″	**DS3PMS66L**	710.	781.	817.			
	72″	71 7/8″	14 1/2″	15″	**DS3PMS72L**	710.	781.	817.			

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Dividends Series 1 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish
3. Door End Cap Finish

Series 2 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish
3. Door Finish (veneer door only)

Series 3 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish case
3. Door Finish (laminate and veneer door only)
4. Door Edge Finish (laminate door only)

Order Code

Dividends Series 1 Flip-Up Door Overhead

Example:	**DS1O 30L, 113, 113**
DS1O 30L	Pattern Number
113	Dark grey paint finish
113	Dark grey End cap finish

Series 2 Flip-Up Overhead w/ Steel Door

Example:	**DS2PM 30L, 115**
DS2PM 30L	Pattern Number
115	Medium grey paint finish

Included with:

Dividends Series 1 Flip-Up Door Overhead

Series 2 Flip-Up Overhead

Series 3 Flip-Up Overhead

Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads.

Note: Series 3 Horizon overheads are only available in Knoll core finishes.

Wallmount bracket specified separately.

Options

Flip-Up Door Door Overhead
To specify overhead cabinet without locks replace the “L” suffix from the pattern number with “N” Deduct $20. For 54″, 60″, 66″ and 72″ overhead cabinets Deduct $40

To specify Touchdown overhead cabinet, add **“E”** as the 2nd to last digit of the pattern number
Example: **DS3PML48EL**
(Add $157 for cabinet widths of 48″ or less. Add $314 for cabinet widths of 54″ or greater).

Series 2 and Series 3 Flip-Up Door Overhead Finish Option:
Add a “Y” to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Flip-Up Door Overheads
Panel- and Wall-Mounted
Dividends Series 1, Series 2 and Horizon Series 3

description	w *	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Series 3 Flip-Up Overhead w/ Laminate Door 	30″	29 7/8″	14 1/2″	15″	**DS3PML30L**	$712.	$794.	$828.			
	36″	35 7/8″	14 1/2″	15″	**DS3PML36L**	745.	815.	851.			
	42″	41 7/8″	14 1/2″	15″	**DS3PML42L**	766.	839.	877.			
	48″	47 7/8″	14 1/2″	15″	**DS3PML48L**	813.	891.	930.			
	60″	59 7/8″	14 1/2″	15″	**DS3PML60L**	1,216.	1,332.	1,391.			
	66″	65 7/8″	14 1/2″	15″	**DS3PML66L**	1,233.	1,354.	1,424.			
	72″	71 7/8″	14 1/2″	15″	**DS3PML72L**	1,269.	1,396.	1,457.			
Series 3 Flip-Up Overhead w/ Veneer Door 	30″	29 7/8″	14 1/2″	15″	**DS3PMV30L**	984.	1,078.	1,127.			
	36″	35 7/8″	14 1/2″	15″	**DS3PMV36L**	1,006.	1,104.	1,153.			
	42″	41 7/8″	14 1/2″	15″	**DS3PMV42L**	1,030.	1,131.	1,182.			
	48″	47 7/8″	14 1/2″	15″	**DS3PMV48L**	1,075.	1,169.	1,221.			
	60″	59 7/8″	14 1/2″	15″	**DS3PMV60L**	1,733.	1,903.	1,987.			
	66″	65 7/8″	14 1/2″	15″	**DS3PMV66L**	1,780.	1,957.	2,055.			
	72″	71 7/8″	14 1/2″	15″	**DS3PMV72L**	1,795.	1,969.	2,059.			

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Dividends Series 1 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish
3. Door End Cap Finish

Series 2 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish
3. Door Finish (veneer door only)

Series 3 Flip-Up Door Overhead

1. Pattern Number
2. Paint Finish case
3. Door Finish (laminate and veneer door only)
4. Door Edge Finish (laminate door only)

Order Code

Dividends Series 1 Flip-Up Door Overhead

Example:	**DS1O 30L, 113, 113**
DS1O 30L	Pattern Number
113	Dark grey paint finish
113	Dark grey End cap finish

Series 2 Flip-Up Overhead w/ Steel Door

Example:	**DS2PM 30L, 115**
DS2PM 30L	Pattern Number
115	Medium grey paint finish

Included with:

Dividends Series 1 Flip-Up Door Overhead

Series 2 Flip-Up Overhead

Series 3 Flip-Up Overhead

Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads.

Note: Series 3 Horizon overheads are only available in Knoll core finishes.

Wallmount bracket specified separately.

Options

Flip-Up Door Door Overhead
To specify overhead cabinet without locks replace the "L" suffix from the pattern number with "N" Deduct $20. For 54″, 60″, 66″ and 72″ overhead cabinets Deduct $40

To specify Touchdown overhead cabinet, add **"E"** as the 2nd to last digit of the pattern number
Example: **DS3PML48EL**
(Add $157 for cabinet widths of 48″ or less. Add $314 for cabinet widths of 54″ or greater).

Series 2 and Series 3 Flip-Up Door Overhead Finish Option:
Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

This page intentionally left blank

Sliding Door Overheads
Panel-, Center- and Wall-Mounted Specifications

Sliding Door Overheads
Sliding door overheads complement the aesthetic of the Dividends Horizon system. The rectilinear door profile was designed to match Dividends Horizon flat profile trim details.

Dividends Horizon sliding door overhead cabinets mount to integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Sliding door overhead cabinets consist of a top, shelf, mid cabinet septum, end panels and a door with handle. Units are available with or without locks.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.

Note: Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes
- Height: 14" and 21"
- Depth: 13 1/2"
- Widths: 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:
- **Horizontal top and shelf:** 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- **Sliding door**:
  - Steel: 20-gauge painted steel
  - Laminate: 3/4" particle board with high pressure laminate on the outside and a paper backer on the inside. 1mm edgeband.
  - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Fixed shelf**: 16-gauge painted steel
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Sliding door mechanism:** Integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Door handle:** painted aluminum (same color as case)

Interior Dimensions
The interior dimensions of overhead cabinets and shelves are:
- Depth: 12 1/4"
- Usable interior height: 12 5/8"
- Width: 1/8" shorter than the exterior width

Task Lights
All Dividends Horizon cabinets and shelves will accept task lights. Task lights must be ordered separately.

Locks
Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.

Note: Horizon sliding door overheads are only available in Knoll Core finishes.

Sliding Door Overhead Configurations



Interior Dimensions for 14"H Overhead

Front View, Interior Height



Top View, Interior Height



Interior Dimensions for 21"H Overhead

Front View, Interior Height



Top View, Interior Height



Sliding Door Overheads
14″ High Panel-Mounted
Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door	29 7/8″	30″	12 1/2″	14″	**DS3PMNS3014**	$280.	$308.	$323.
	35 7/8″	36″	12 1/2″	14″	**DS3PMNS3614**	291.	321.	337.
	41 7/8″	42″	12 1/2″	14″	**DS3PMNS4214**	300.	331.	346.
	47 7/8″	48″	12 1/2″	14″	**DS3PMNS4814**	311.	343.	356.
	59 7/8″	60″	12 1/2″	14″	**DS3PMNS6014**	354.	390.	409.
	65 7/8″	66″	12 1/2″	14″	**DS3PMNS6614**	367.	402.	420.
	71 7/8″	72″	12 1/2″	14″	**DS3PMNS7214**	376.	414.	432.
Template Panel-Mounted Sliding Door Overhead with Steel Doors	35 7/8″:	36″	15″	14″	**DS3PMTS3614L**	609.	670.	700.
	41 7/8″:	42″	15″	14″	**DS3PMTS4214L**	631.	694.	725.
	47 7/8″:	48″	15″	14″	**DS3PMTS4814L**	650.	715.	748.
	59 7/8″:	60″	15″	14″	**DS3PMTS6014L**	928.	1,022.	1,067.
	71 7/8″:	72″	15″	14″	**DS3PMT7S214L**	983.	1,080.	1,130.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/Steel Door	29 7/8″	30″	13 1/2″	14″	**DS3PMSS3014L**	464.	511.	534.
	35 7/8″	36″	13 1/2″	14″	**DS3PMSS3614L**	476.	524.	550.
	41 7/8″	42″	13 1/2″	14″	**DS3PMSS4214L**	492.	543.	565.
	47 7/8″	48″	13 1/2″	14″	**DS3PMSS4814L**	500.	551.	577.
	59 7/8″	60″	13 1/2″	14″	**DS3PMSS6014L**	565.	623.	650.
	65 7/8″	66″	13 1/2″	14″	**DS3PMSS6614L**	581.	640.	668.
	71 7/8″	72″	13 1/2″	14″	**DS3PMSS7214L**	590.	649.	678.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 7/8″	30″	13 1/2″	14″	**DS3PMSL3014L**	801.	880.	919.
	35 7/8″	36″	13 1/2″	14″	**DS3PMSL3614L**	823.	903.	943.
	41 7/8″	42″	13 1/2″	14″	**DS3PMSL4214L**	847.	928.	971.
	47 7/8″	48″	13 1/2″	14″	**DS3PMSL4814L**	868.	952.	995.
	59 7/8″	60″	13 1/2″	14″	**DS3PMSL6014L**	891.	979.	1,021.
	65 7/8″	66″	13 1/2″	14″	**DS3PMSL6614L**	914.	1,003.	1,046.
	71 7/8″	72″	13 1/2″	14″	**DS3PMSL7214L**	935.	1,026.	1,072.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead w/ Steel Door

Example:	**DS3PMSS3014L /117/117**
DS3PMSS 3014L	Pattern Number
117	Dark grey paint finish case

Included With

Sliding Door Overhead

Note: Sliding door overheads are only available in Knoll core finishes.

Options

Sliding Door Overhead

Lock/No lock
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Sliding Door Overheads
14″ High Panel-Mounted
Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door 	29 7/8″	30″	13 1/2″	14″	**DS3PMSV3014L**	$885.	$971.	$1,015.
	35 7/8″	36″	13 1/2″	14″	**DS3PMSV3614L**	914.	1,002.	1,046.
	41 7/8″	42″	13 1/2″	14″	**DS3PMSV4214L**	940.	1,033.	1,078.
	47 7/8″	48″	13 1/2″	14″	**DS3PMSV4814L**	970.	1,064.	1,111.
	59 7/8″	60″	13 1/2″	14″	**DS3PMSV6014L**	999.	1,096.	1,144.
	65 7/8″	66″	13 1/2″	14″	**DS3PMSV6614L**	1,026.	1,127.	1,177.
	71 7/8″	72″	13 1/2″	14″	**DS3PMSV7214L**	1,055.	1,158.	1,211.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead w/ Steel Door

Example:	**DS3PMSS3014L /117/117**
DS3PMSS 3014L	Pattern Number
117	Dark grey paint finish case

Included With

Sliding Door Overhead

Note: Sliding door overheads are only available in Knoll core finishes.

Options

Sliding Door Overhead

Lock/No lock
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Sliding Door Overheads
21" High Panel-Mounted
Dividends Horizon Full Height Door

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door	29 7/8"	30"	12 1/2"	21"	**DS3PMNS3021**	$387.	$426.	$446.
	35 7/8"	36"	12 1/2"	21"	**DS3PMNS3621**	404.	443.	464.
	41 7/8"	42"	12 1/2"	21"	**DS3PMNS4221**	417.	458.	478.
	47 7/8"	48"	12 1/2"	21"	**DS3PMNS4821**	432.	474.	496.
	59 7/8"	60"	12 1/2"	21"	**DS3PMNS6021**	492.	543.	565.
	65 7/8"	66"	12 1/2"	21"	**DS3PMNS6621**	402.	442.	462.
	71 7/8"	72"	12 1/2"	21"	**DS3PMNS7221**	521.	575.	599.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door	29 7/8"	30"	13 1/2"	21"	**DS3PMSS3021FL**	603.	664.	693.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSS3621FL**	623.	686.	716.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSS4221FL**	644.	707.	740.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSS4821FL**	661.	725.	760.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSS6021FL**	757.	832.	871.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSS6621FL**	778.	855.	894.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSS7221FL**	793.	872.	911.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 7/8"	30"	13 1/2"	21"	**DS3PMSL3021FL**	999.	1,096.	1,143.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSL3621FL**	1,027.	1,128.	1,178.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSL4221FL**	1,058.	1,160.	1,214.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSL4821FL**	1,089.	1,195.	1,246.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSL6021FL**	1,117.	1,227.	1,281.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSL6621FL**	1,146.	1,260.	1,316.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSL7221FL**	1,177.	1,292.	1,349.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door	29 7/8"	30"	13 1/2"	21"	**DS3PMSV3021FL**	1,087.	1,193.	1,245.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSV3621FL**	1,126.	1,237.	1,291.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSV4221FL**	1,168.	1,281.	1,339.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSV4821FL**	1,208.	1,326.	1,386.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSV6021FL**	1,248.	1,371.	1,434.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSV6621FL**	1,289.	1,417.	1,479.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSV7221FL**	1,331.	1,462.	1,526.









w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead w/ Steel Door

Example:	**DS3PMSS3021FL /117/117**
DS3PMSS	Pattern Number
3021FL	
117	Dark grey paint finish case

Included With

Sliding Door Overhead

Note: Sliding door overheads are only available in Knoll core finishes.

Options

Sliding Door Overhead

Lock/No lock
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Sliding Door Overheads
21" High Panel-Mounted
Dividends Horizon Partial Height Door

description	w *	w	d	h	pattern number	P1	P2	P3
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door 	29 7/8"	30"	13 1/2"	21"	**DS3PMSS3021PL**	$599.	$661.	$689.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSS3621PL**	619.	680.	712.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSS4221PL**	639.	701.	731.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSS4821PL**	653.	719.	753.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSS6021PL**	724.	797.	834.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSS6621PL**	748.	820.	857.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSS7221PL**	761.	836.	874.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door 	29 7/8"	30"	13 1/2"	21"	**DS3PMSL3021PL**	990.	1,087.	1,134.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSL3621PL**	1,019.	1,118.	1,168.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSL4221PL**	1,048.	1,149.	1,202.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSL4821PL**	1,077.	1,183.	1,236.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSL6021PL**	1,107.	1,216.	1,269.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSL6621PL**	1,136.	1,247.	1,304.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSL7221PL**	1,165.	1,279.	1,338.
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door 	29 7/8"	30"	13 1/2"	21"	**DS3PMSV3021PL**	1,087.	1,193.	1,244.
	35 7/8"	36"	13 1/2"	21"	**DS3PMSV3621PL**	1,118.	1,228.	1,282.
	41 7/8"	42"	13 1/2"	21"	**DS3PMSV4221PL**	1,151.	1,265.	1,320.
	47 7/8"	48"	13 1/2"	21"	**DS3PMSV4821PL**	1,186.	1,301.	1,359.
	59 7/8"	60"	13 1/2"	21"	**DS3PMSV6021PL**	1,218.	1,338.	1,397.
	65 7/8"	66"	13 1/2"	21"	**DS3PMSV6621PL**	1,249.	1,372.	1,436.
	71 7/8"	72"	13 1/2"	21"	**DS3PMSV7221PL**	1,283.	1,411.	1,473.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead w/ Steel Door

Example:	**DS3PMSS3021PL /117/117**
DS3PMSS	Pattern Number
3021PL	
117	Dark grey paint finish case

Included With

Sliding Door Overhead

Note: Sliding door overheads are only available in Knoll core finishes.

Options

Sliding Door Overhead

Lock/No lock
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Sliding Door Overheads
14" High Wall-Mounted
Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Wall-Mounted Sliding Door Overhead without Door 	35 7/8"	36"	14"	14"	**DS3WMN3614**	$677.	$746.	$779.
	42 7/8"	42"	14"	14"	**DS3WMN4214**	716.	789.	823.
	47 7/8"	48"	14"	14"	**DS3WMN4814**	752.	825.	863.
	59 7/8"	60"	14"	14"	**DS3WMN6014**	1,027.	1,130.	1,182.
	71 7/8"	72"	14"	14"	**DS3WMN7214**	1,113.	1,226.	1,281.
Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Steel Door 	35 7/8"	36"	15"	14"	**DS3WMSS3614L**	851.	935.	979.
	42 7/8"	42"	15"	14"	**DS3WMSS4214L**	893.	984.	1,028.
	47 7/8"	48"	15"	14"	**DS3WMSS4814L**	930.	1,024.	1,069.
	59 7/8"	60"	15"	14"	**DS3WMSS6014L**	1,214.	1,335.	1,397.
	71 7/8"	72"	15"	14"	**DS3WMSS7214L**	1,306.	1,437.	1,502.
Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Laminate Door 	35 7/8"	36"	15"	14"	**DS3WMSL3614L**	n/a	n/a	1,136.
	42 7/8"	42"	15"	14"	**DS3WMSL4214L**	n/a	n/a	1,178.
	47 7/8"	48"	15"	14"	**DS3WMSL4814L**	n/a	n/a	1,218.
	59 7/8"	60"	15"	14"	**DS3WMSL6014L**	n/a	n/a	1,513.
	71 7/8"	72"	15"	14"	**DS3WMSL7214L**	n/a	n/a	1,613.
Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Veneer Door 	35 7/8"	36"	15"	14"	**DS3WMSV3614L**	n/a	n/a	1,318.
	41 7/8"	42"	15"	14"	**DS3WMSV4214L**	n/a	n/a	1,365.
	47 7/8"	48"	15"	14"	**DS3WMSV4814L**	n/a	n/a	1,422.
	59 7/8"	60"	15"	14"	**DS3WMSV6014L**	n/a	n/a	1,721.
	71 7/8"	72"	15"	14"	**DS3WMSV7214L**	n/a	n/a	1,839.

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3WMSS4214N /118/118**
DS3WM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Wall mount cleat
Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Sliding Door Overheads
14″ High Wall-Mounted
Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Template Wall-Mounted Sliding Door Overhead w/Steel Doors	35 7/8″	36″	15″	14″	**DS3WMTS3614L**	$836.	$920.	$963.
	42 7/8″	42″	15″	14″	**DS3WMTS4214L**	883.	971.	1,015.
	47 7/8″	48″	15″	14″	**DS3WMTS4814L**	920.	1,011.	1,058.
	59 7/8″	60″	15″	14″	**DS3WMTS6014L**	1,211.	1,331.	1,393.
	71 7/8″	72″	15″	14″	**DS3WMTS7214L**	1,310.	1,441.	1,507.



Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3WMSS4214N /118/118**
DS3WM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Wall mount cleat
Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Sliding Door Overheads
14″ High Shared Center-Mounted Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Shared Top-Mounted Sliding Door Overhead without Door 	35 7/8″	36″	14″	14″	**DS3SMN3614**	$908.	$1,000.	$1,045.
	42 7/8″	42″	14″	14″	**DS3SMN4214**	947.	1,043.	1,090.
	47 7/8″	48″	14″	14″	**DS3SMN4814**	976.	1,073.	1,122.
	59 7/8″	60″	14″	14″	**DS3SMN6014**	1,155.	1,271.	1,329.
	71 7/8″	72″	14″	14″	**DS3SMN7214**	1,206.	1,326.	1,387.
Template Shared Top-Mounted Sliding Door Overhead with Steel Doors 	35 7/8″	36″	15″	14″	**DS3SMT3614L**	1,074.	1,183.	1,236.
	42 7/8″	42″	15″	14″	**DS3SMT4214L**	1,118.	1,230.	1,285.
	47 7/8″	47″	15″	14″	**DS3SMT4814L**	1,144.	1,260.	1,316.
	59 7/8″	60″	15″	14″	**DS3SMT6014L**	1,335.	1,470.	1,535.
	71 7/8″	72″	15″	14″	**DS3SMT7214L**	1,412.	1,553.	1,623.
Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Steel Door 	35 7/8″	36″	15″	14″	**DS3SMSS3614L**	1,134.	1,247.	1,305.
	42 7/8″	42″	15″	14″	**DS3SMSS4214L**	1,179.	1,297.	1,354.
	47 7/8″	48″	15″	14″	**DS3SMSS4814L**	1,206.	1,326.	1,387.
	59 7/8″	60″	15″	14″	**DS3SMSS6014L**	1,394.	1,533.	1,603.
	71 7/8″	72″	15″	14″	**DS3SMSS7214L**	1,470.	1,616.	1,689.
Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Laminate Door 	35 7/8″	36″	15″	14″	**DS3SMSL3614L**	n/a	n/a	1,740.
	42 7/8″	42″	15″	14″	**DS3SMSL4214L**	n/a	n/a	1,782.
	47 7/8″	48″	15″	14″	**DS3SMSL4814L**	n/a	n/a	1,815.
	59 7/8″	60″	15″	14″	**DS3SMSL6014L**	n/a	n/a	2,007.
	71 7/8″	72″	15″	14″	**DS3SMSL7214L**	n/a	n/a	2,095.

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3SMSS4214N /118/118**
DS3SM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Sliding Door Overheads
14″ High Shared Center-Mounted Dividends Horizon and Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Veneer Door 	35 7/8″	36″	15″	14″	**DS3SMSV3614L**	n/a	n/a	$2,106.
	42 7/8″	42″	15″	14″	**DS3SMSV4214L**	n/a	n/a	2,158.
	47 7/8″	48″	15″	14″	**DS3SMSV4814L**	n/a	n/a	2,220.
	59 7/8″	60″	15″	14″	**DS3SMSV6014L**	n/a	n/a	2,424.
	71 7/8″	72″	15″	14″	**DS3SMSV7214L**	n/a	n/a	2,548.

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish (laminate and veneer door only)
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3SMSS4214N /118/118**
DS3SM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the “L” suffix with a “N” and deduct $20.00 from the list price.

Paint Configuration Option:

Add “Y” at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Sliding Door Overheads
14" High Individual Center-Mounted Dividends Horizon Doors / Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Overhead without Door	35 7/8"	36"	14"	14"	**DS3CMN3614**	$727.	$800.	$836.		
	41 7/8"	42"	14"	14"	**DS3CMN4214**	759.	835.	873.		
	47 7/8"	48"	14"	14"	**DS3CMN4814**	778.	855.	894.		
	59 7/8"	60"	14"	14"	**DS3CMN6014**	1,084.	1,192.	1,245.		
	71 7/8"	72"	14"	14"	**DS3CMN7214**	1,140.	1,256.	1,311.		
Template Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	**DS3CMTS3614L**	870.	958.	1,001.		
	42 7/8"	42"	15"	14"	**DS3CMTS4214L**	907.	999.	1,044.		
	47 7/8"	48"	15"	14"	**DS3CMTS4814L**	930.	1,024.	1,069.		
	59 7/8"	60"	15"	14"	**DS3CMTS6014L**	1,265.	1,393.	1,454.		
	71 7/8"	72"	15"	14"	**DS3CMTS7214L**	1,337.	1,471.	1,537.		
Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	**DS3CMSS4214L**	1,960.	1,056.	1,104.		
	41 7/8"	42"	15"	14"	**DS3CMSS4814L**	987.	1,097.	1,147.		
	47 7/8"	48"	15"	14"	**DS3CMSS6014L**	1,024.	1,126.	1,178.		
	59 7/8"	60"	15"	14"	**DS3CMSS7214L**	1,226.	1,348.	1,410.		







Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3CMTS4214N /118/118**
DS3CM	Pattern Number
T	Template Style Door
S	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Sliding Door Overheads
14" High Individual Center-Mounted Dividends Horizon Doors / Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Laminate Doors 	35 7/8"	36"	15"	14"	**DS3CMSL3614L**				$1,249.	
	35 7/8"	36"	15"	14"	**DS3CMSS3614L**				1,249.	
	41 7/8"	42"	15"	14"	**DS3CMSL4214L**				1,286.	
	47 7/8"	48"	15"	14"	**DS3CMSL4814L**				1,316.	
	59 7/8"	60"	15"	14"	**DS3CMSL6014L**				1,528.	
	71 7/8"	72"	15"	14"	**DS3CMSL7214L**				1,603.	

Sliding Door Overheads
14″ High Individual Center-Mounted Dividends Horizon Doors / Template Doors

description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Veneer Doors	35 7/8″	36″	15″	14″	**DS3CMSV3614L**					$1,431.
	41 7/8″	42″	15″	14″	**DS3CMSV4214L**					1,474.
	47 7/8″	48″	15″	14″	**DS3CMSV4814L**					1,519.
	59 7/8″	60″	15″	14″	**DS3CMSV6014L**					1,734.
	71 7/8″	72″	15″	14″	**DS3CMSV7214L**					1,829.



Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish
4. Door edge finish (laminate door only)

Order Code

Sliding Door Overhead

Example:	**DS3CMTS4214N /118/118**
DS3CM	Pattern Number
T	Template Style Door
S	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct $20.00 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Up Mounted Overheads
Specifications

Panel Up Mounted Overhead Cabinets
Up mounted cabinets mount to 50" or 57" high panels only to provide overhead storage within workstations and are an alternative to overheads panel-mounted on 64" high panels. Up mounted cabinets have full finished backs and require up mount brackets for mounting.

When installed on 50" high panels, up mounted cabinets match up to the overall 64" height of panel-mounted overhead cabinets and freestanding overdesks to provide a consistent height within the facility.

Overhead cabinets consist of a top, shelf, end panels, enclosed back, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Up mounted cabinets are shipped knocked-down.

Up mounted overheads must match the width of single or multiple panels and cannot be mounted off module.

Series 1 Flip-up Overhead Cabinets
Series 1 flip-up overhead cabinets match the aesthetics of the original Dividends Horizon system. The radiused fronts and molded plastic end trim match the radiused profile trim used on panel topcaps and end trim. Series 1 cabinets are offered with steel doors.

Series 2 Flip-up Overhead Cabinets
Series 2 overhead cabinets offer an alternative aesthetic to the Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below). The Series 2 overhead offers a painted steel or veneer overhead door front.

Available Sizes
- Height: 15"
- Depth: 13 1/2"
- Widths: 30", 36", 42", 48", 54", 60", 66" and 72"

Construction:
- Horizontal top and shelf: 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- Overhead door: 20-gauge painted
- Overhead door suspension: Steel ball-bearing
- Overhead door end trim: Color injected, molded plastic (Series 1 only)
- End panels: 16-gauge painted steel with integral mounting hooks
- Up mount brackets: 14-gauge steel

Interior Dimensions
Up mounted cabinet interiors measure:
- Depth 12"
- Usable interior height: 12 5/8"
- Width: 1/8" shorter than the exterior width.

Cabinet Door Clearance
Cabinet doors open over the tops of cabinets. Required clearance is: 16 1/4" total height (height of cabinet plus top clearance required).

Panel Up Mounted Overhead for Stack Frames
Dividends Horizon non-load bearing stacking frames do not allow for panel-mount hanging components. To provide overhead storage, a panel up mounted overhead cabinet with enclosed back can be utilized.

Up mount brackets
Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Touchdown Overhead Cabinets
Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Locks
Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.

When locks are not specified a plug is located in the lock position.

Optional lock retrofit kits are available for field-installation at a later date if required.

Task Lights
All Dividends up mounted cabinets will accept task lights. Task lights must be ordered separately.

Panel Up Mounted Cabinet



Up Mount Brackets



Interior Dimensions



Front View, Interior Height



Top View, Interior Depth

Cabinet Door Clearance



Up Mounted Overheads
Dividends and Series 2

description	w *	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Dividends Overhead Cabinet with Enclosed Back and Lock	30″	29 7/8″	14 1/8″	15″	**DS1E30L**	$489.	$541.	$563.	n/a	n/a	n/a
	36″	35 7/8″	14 1/8″	15″	**DS1E36L**	508.	560.	584.	n/a	n/a	n/a
	42″	41 7/8″	14 1/8″	15″	**DS1E42L**	549.	604.	631.	n/a	n/a	n/a
	48″	47 7/8″	14 1/8″	15″	**DS1E48L**	574.	631.	659.	n/a	n/a	n/a
	54″	53 7/8″	14 1/8″	15″	**DS1E54L**	751.	823.	861.	n/a	n/a	n/a
	60″	59 7/8″	14 1/8″	15″	**DS1E60L**	751.	823.	861.	n/a	n/a	n/a
	66″	65 7/8″	14 1/8″	15″	**DS1E66L**	774.	852.	891.	n/a	n/a	n/a
	72″	71 7/8″	14 1/8″	15″	**DS1E72L**	774.	852.	891.	n/a	n/a	n/a
Series 2 Overhead Cabinet With Enclosed Back and Lock	30″	29 7/8″	14 1/8″	15″	**DS2UM30L**	650.	749.	780.	879.	976.	1,010.
	36″	35 7/8″	14 1/8″	15″	**DS2UM36L**	671.	773.	806.	905.	1,008.	1,043.
	42″	41 7/8″	14 1/8″	15″	**DS2UM42L**	693.	796.	832.	940.	1,046.	1,078.
	48″	47 7/8″	14 1/8″	15″	**DS2UM48L**	706.	812.	846.	991.	1,098.	1,132.
	54″	53 7/8″	14 1/8″	15″	**DS2UM54L**	949.	1,091.	1,137.	1,386.	1,530.	1,574.
	60″	59 7/8″	14 1/8″	15″	**DS2UM60L**	949.	1,091.	1,137.	1,386.	1,530.	1,574.
	66″	65 7/8″	14 1/8″	15″	**DS2UM66L**	991.	1,139.	1,190.	1,447.	1,599.	1,646.
	72″	71 7/8″	14 1/8″	15″	**DS2UM72L**	991.	1,139.	1,190.	1,447.	1,599.	1,646.
Overhead Upmount Brackets (Pair)		7/8″	12 3/16″	11 3/4″	**DB1U18**	71.	77.	82.	n/a	n/a	n/a
Reuter Upmount Brackets (Pair)		7/8″	12 3/16″	11 3/4″	**DB1RU18**	96.	103.	110.	n/a	n/a	n/a

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Upmount Overhead Cabinet

1. Pattern Number
2. Paint Finish
3. Door End Cap Finish

Series 2 Overhead Cabinet

1. Pattern Number
2. Paint Finish

Order Code

Upmount Overhead Cabinet	
Example:	**DS1E 30L, 113, 113**
DS1E 30L	Pattern Number
113	Dark grey paint finish
113	Dark grey end cap finish
Series 2 Overhead Cabinet	
Example:	**DS2UM 30L, 115**
DS2UM 30L	Pattern Number
115	Medium grey paint finish

Included with:

Upmount Overhead Cabinet

Series 2 Overhead Cabinet

Up Mount overheads include an enclosed back.

Up Mount brackets are required and must be ordered separately.

Options

Upmount Overhead Cabinet
To specify overhead cabinet without locks, replace the **"L"** suffix from the pattern number with **"N"** **Deduct $20**For 54″, 60″, 66″ and 72″ overhead cabinets **Deduct $40**

To specify Touchdown overhead cabinet, add **"E"** as the 2nd to last digit of the pattern number *Example:***DS3PML48EL** **(Add $157 for cabinet widths of 48″ or less. Add $314 for cabinet widths of 54″ or greater).**

Series 2 Up Mount Overhead Finish Option:
Add a "Y" to the end of the pattern number to specify a front color that is different than the case color. Use P3 pricing for this dual finish option.

Overhead Bookshelf and Corner Shelf
Specifications

Overhead Book Shelves
Dividends Horizon bookshelves mount to the integral vertical channels on Dividends Horizon panels or to wall mount tracks to provide overhead storage within workstations or private offices.

Bookshelves include a shelf, end panels, open back and required assembly screws.

Shelves must match the width of single or multiple panels and cannot be mounted off-module.

All book shelves are shipped knocked-down.

Available Sizes
- Height: shelf 8"
- Depth: $14\frac{1}{8}$"
- Widths: 24", 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:
- Horizontal shelf: 18-gauge (24" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- End panels: 16-gauge painted steel with integral mounting hooks

Corner Shelf
Dividends Horizon corner shelves mount to the integral vertical channels of Dividends Horizon panels to provide overhead storage in corner applications. Panels supporting the corner shelf must be of the same width. Corner shelf consists of shelf, end panels and rear corner support bracket.

Note: Corner shelves do not accept task lights.

Note: Corner shelves may not be mounted on load bearing stack frames.

Available Sizes
- Height: 8"
- Depth: 12"
- Widths: 36", 42", and 48"

Construction:
- Shelf: $\frac{7}{8}$" wood core construction with laminate on both sides and t-mold edge
- End panels: 16-gauge painted steel with integral mounting hooks

Task Lights
All Dividends Horizon shelves will accept task lights. Task lights must be ordered separately.

Bookshelf



Corner Shelf



Overhead Bookshelf and Corner Shelf
7 1/4" High

description	w *	w	d	h	pattern no.	P1	P2	P3
Overhead Bookshelf	24″	23 7/8″	14 1/8″	7 1/4″	**DS1S 24**	$149.	$165.	$172.
	30″	29 7/8″	14 1/8″	7 1/4″	**DS1S 30**	149.	165.	172.
	36″	35 7/8″	14 1/8″	7 1/4″	**DS1S 36**	157.	165.	173.
	42″	41 7/8″	14 1/8″	7 1/4″	**DS1S 42**	164.	173.	180.
	48″	47 7/8″	14 1/8″	7 1/4″	**DS1S 48**	171.	179.	187.
	54″	53 7/8″	14 1/8″	7 1/4″	**DS1S 54**	183.	195.	204.
	60″	59 7/8″	14 1/8″	7 1/4″	**DS1S 60**	183.	195.	204.
	66″	65 7/8″	14 1/8″	7 1/4″	**DS1S 66**	200.	210.	221.
	72″	71 7/8″	14 1/8″	7 1/4″	**DS1S 72**	200.	210.	221.
Overhead Corner Shelf	36″	35 7/8″	12″	7 1/4″	**DS1CS 36**	386.	409.	424.
	42″	41 7/8″	12″	7 1/4″	**DS1CS 42**	420.	443.	465.
	48″	47 7/8″	12″	7 1/4″	**DS1CS 48**	457.	483.	506.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Overhead Bookshelf

1. Pattern Number
2. Paint Finish

Overhead Corner Shelf

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Order Code

Overhead Bookshelf	
Example:	**DS1S 60, 113**
DS1S 60	Pattern Number
113	Dark Grey Finish
Overhead Corner Shelf	
Example:	**DS1CS36, M42, 117, 117**
DS1CS36	Pattern Number
M42	Soft Grey Laminate
117	Soft Grey Edge Band
117	Soft Grey Paint

Included with:

Overhead Bookshelf

Overhead Corner Shelf

- Rear Corner Support Bracket

Note: An upcharge applies when specifying a Legacy laminate. See Legacy finish page for more information.

Mounting Brackets and Accessories
Backstop, Wall-Mount and Panel Mount Specifications

Optional Overhead Back Stop
Panel-mounted overhead cabinet and bookshelf backs are open and use the panel face as the back. When required, an optional field-installed back stop is available. Attachment can be made to an assembled unit. Construction is dark grey extruded plastic.

Specify the overhead back stop width to match the width of the shelf or overhead cabinet.

Overhead Cabinet Wall-Mount Brackets
Wall-mount brackets allow Dividends Horizon panel-mounted overheads to be wall-mounted to dry-wall construction. Wall-mounting brackets are available in sizes 30", 36", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead cabinet. If cabinet width is 60" or 72" wide, specify two 30" or two 36" wall-mount brackets respectively.

If a 60" cabinet is desired, two (2) 30" wide wall-mount brackets may be installed side-by-side to support the overhead cabinet. When a 72" cabinet is used, two (2) 36" wall-mount brackets may be used.

Shelf Wall-Mount Brackets
Wall-mount brackets allow Dividends Horizon panel-mounted shelves to be wall-mounted to dry-wall construction. Wallmounting brackets are painted black. and are available in sizes 30", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead shelf. Specify paint finish to match the shelf paint finish.

A metal shelf back will ship with the wall-mount bracket, which is painted to match the shelf color. Overhead shelves larger than 48" wide cannot be wall mounted using the Dividends Horizon wall-mount bracket.

NOTE: WALL-MOUNT BRACKETS MUST ONLY BE USED WITH STRUCTURAL WALLS. TO ENSURE PROPER INSTALLATION, PLEASE FOLLOW THE INSTALLATION INSTRUCTIONS ENCLOSED WITH THE BRACKETS.

Up mount brackets
Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Currents Downmount Bracket
This downmount bracket allows for Dividends Horizon or Series 2 panel mounted overhead cabinets to be mounted into Currents spine wall. This downmount bracket can only be used with Currents 64"H spine wall only.

Specify to match the overhead cabinet width. Specify paint finish to match the overhead cabinet finish.

Reuter Panel-Mount Brackets
Reuter panel-mount brackets are available to allow Reuter overheads and shelves to be panel-mounted on Dividends Horizon 57" or 64" high panels. Reuter overhead panel-mount brackets allow overhead sizes up to 72" to be panel-mounted. Reuter shelf panel-mount brackets allow shelves up to 48" to be panel-mounted. Finish black.

Vertical Dividers
Optional vertical dividers attach to the shelves within overhead cabinets and bookshelves to provide inner cabinet organization. Construction is 18-gauge steel with dark grey finish.

Overhead Cabinet Lock Retrofit Kit
The overhead cabinet lock retrofit kit allows non-locking Series 1 and Series 2 flip-up overhead cabinets to be converted to locking overhead cabinets.

Optional Overhead Backstop



Overhead Wall-Mount Bracket



Shelf Wall-Mount Bracket



Upmount Brackets



Reuter Overhead Panel-Mount Brackets



Reuter Shelf Panel-Mount Brackets



Vertical Divider



Mounting Brackets and Accessories
Overhead Backstop, Wall-mount Brackets and Currents Downmount Brackets

description	w *	w	d	h	pattern no.	black	P1	P2	P3
Overhead Back Stop (Dark Grey Only)	24″	23 11/16″	5/8″	1 7/16″	**DS1BS 24**		$4.	n/a	n/a
	30″	29 11/16″	5/8″	1 7/16″	**DS1BS 30**		4.	n/a	n/a
	36″	35 11/16″	5/8″	1 7/16″	**DS1BS 36**		4.	n/a	n/a
	42″	41 11/16″	5/8″	1 7/16″	**DS1BS 42**		7.	n/a	n/a
	48″	47 11/16″	5/8″	1 7/16″	**DS1BS 48**		7.	n/a	n/a
	54″	53 11/16″	5/8″	1 7/16″	**DS1BS 54**		10.	n/a	n/a
	60″	59 11/16″	5/8″	1 7/16″	**DS1BS 60**		10.	n/a	n/a
	66″	65 11/16″	5/8″	1 7/16″	**DS1BS 66**		10.	n/a	n/a
	72″	71 11/16″	5/8″	1 7/16″	**DS1BS 72**		10.	n/a	n/a
14″ H Overhead Wall-Mount Bracket	24″	24″	1/2″	1 4 1/4″	**DS1WM 24**	72.	75.	79.	82.
	30″	30″	1/2″	1 4 1/4″	**DS1WM 30**	72.	75.	79.	82.
	36″	36″	1/2″	1 4 1/4″	**DS1WM 36**	76.	80.	83.	88.
	42″	42″	1/2″	1 4 1/4″	**DS1WM 42**	84.	89.	93.	97.
	48″	48″	1/2″	1 4 1/4″	**DS1WM 48**	91.	96.	100.	104.
Overhead Shelf-Mount Bracket 	30″	30″	1/2″	7″	**DS1SWM 30**		72.	78.	84.
	36″	36″	1/2″	7″	**DS1SWM 36**		76.	85.	89.
	42″	42″	1/2″	7″	**DS1SWM 42**		84.	93.	96.
	48″	48″	1/2″	7″	**DS1SWM 48**		91.	99.	102.
Dividends Series 2 Downmount Brackets (For Currents spine use)	24″				**DSCSWDB24**		238.	n/a	n/a
	30″				**DSCSWDB30**		245.	n/a	n/a
	36″				**DSCSWDB36**		251.	n/a	n/a
	42″				**DSCSWDB42**		259.	n/a	n/a
	48″				**DSCSWDB48**		264.	n/a	n/a

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information	Order Code	Included with:	Options
Overhead Wall-Mount Bracket 1. Pattern Number **Overhead Back Stop** 1. Pattern Number	**Overhead Wall-Mount Bracket** *Example:* **DS1WM 30** **DS1WM** Pattern Number **30** **Overhead Back Stop** *Example:* **DB1BS 30** **DB1BS 30** Pattern Number	**Overhead Wall-Mount Bracket** **Overhead Back Stop**	**Overhead Wall-Mount Bracket** **Overhead Back Stop**

Mounting Brackets and Accessories
Upmount Brackets, Vertical Dividers and Lock Retrofit Kit

description	pattern no.	black	P1	P2	P3
Vertical Dividers Package of 4	**DS1 VD**	$93.	$97.	$102.	$108.
Overhead Cabinet Lock Retrofit Kit	**DS1 OHL**	56.	n/a	n/a	n/a
Overhead Upmount Brackets (Pair)	**DB1U18**	n/a	71.	77.	82.
Reuter Upmount Brackets (Pair)	**DB1RU18**	n/a	96.	103.	110.
Reuter Overhead Panel Bracket (pair)	**RO1 DPB**	55.	n/a	n/a	n/a
Reuter Shelf Panel-Mount Bracket (pair)	**RS1 DPB**	55.	n/a	n/a	n/a

Ordering Information

Vertical Dividers

1. Pattern Number

Reuter Overhead Panel-Mount Bracket

1. Pattern Number

Order Code

Vertical Dividers

Example: **DS1 VD**

Reuter Overhead Panel-Mount Bracket

Example: **RO1 DPB**

Included with:

Vertical Dividers
(4) Vertical dividers

Reuter Overhead Panel-Mount Bracket
Brackets (pair)

Options

Vertical Dividers

Reuter Overhead Panel-Mount Bracket

Overhead cabinet lock retrofit kit is for Dividends Series 1 and Series 2 Flip-up Overhead only.

This page intentionally left blank

Task Lights
Specifications

Task Lights
Dividends Horizon offers T5 and LED task lights. T5 task lights are available in standard and advanced models. Task lights must be ordered separately from shelves, overhead cabinets, and overdesk units.

Task lights are TCLP compliant and meet requirements of California Title 20 and Title 24. T5 advanced task lights are fitted with ballasts and lamps compliant with LEED requirements. All task lights are approved for New York City installations.

T5 Task Lights
T5 task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9 foot grounded cordset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware. T5 task light housings are painted black.

The T5 task light cordset is a center exit. On smaller units the cord exit is off-center, but still not handed, allowing the cordset to be positioned either to the right or left of the task light for easy access to the closest available duplex.

All T5 task lights include mounting hardware for attachment to overhead cabinets, shelves, up mounted cabinets and freestanding overdesks. Specify task lights one size or less than the overall cabinet or overdesk width. T5 task lights have adjustable mounting brackets that lock into integral channels in the underside of the cabinet's lower shelf. The spring steel adjustable mounting brackets flex to install without requiring tools and allow the light to be positioned at any position side-to-side and front-to-back.

City of Chicago T5 task lights have a 9 foot power cord with a resettable circuit breaker built into the plug.

LED Task Lights
LED task lights include LED's, a power supply with 12' cord and mounting hardware. Housings are clear anodized aluminum with grey color end-caps. Cord management clips must be ordered separately. The power supply cord attaches to either end of the fixture, allowing for easier access to the closest available duplex.

LED task lights mount into the recess in the underside of overhead cabinets and shelves at least 5" wider than the task light width..

Cord Management Clips
Cord management clips attach to the integral slotted channels on panel frames to manage task light cordsets. Clips are 3/8" high black molded plastic construction.

Task Light Specifications

Model Number	Fixture Length	Lamp Length	Lamp Part Number	Lamp Watts	Input Watts
T5 Standard Task Lights					
DL3T5E19S	19"	12"	FULHAM F8T5/CW	8	8
DL3T5E25S	25"	21.6"	FULHAM F14T5/41K	14	15
DL3T5E37S	37"	33.4"	FULHAM F21T5/41K	21	24
DL3T5E49S	49"	45.2"	FULHAM F28T5/41K	28	31
T5 Advanced Task Lights					
DL3T5E25A	25"	22.2"	PHILIPS F14T5/841/ALTO	14	18
DL3T5E37A	37"	33.98"	PHILIPS F21T5/841/ALTO	21	24
DL3T5E49A	49"	45.8"	PHILIPS F28T5/841/ALTO	28	31
LED Task Lights					
DL3L193M	19"	18.34"	N/A	4.9	5.58
DL3L196M	19"	18.34"	N/A	9.8	10.95
DL3L199M	19"	18.34"	N/A	14.7	16.3
DL3L376M	37"	36.46"	N/A	9.8	11.1
DL3L3712M	37"	36.46"	N/A	19.6	21.9
DL3L3718M	37"	36.46"	N/A	29.4	32.6

T5 Task Light



LED Task Light



Cord Management Clip Attachment



Task Lights
Cord Management Clip

description	type	w	d	h	pattern no.	list
T5 Standard Task Light	Use with 24″ and wider overhead	19″	4″	1 1/2″	**DL3T5E19S**	$180.
	Use with 30″ and wider overhead	25″	4″	1 1/2″	**DL3T5E25S**	195.
	Use with 42″ and wider overhead	37″	4″	1 1/2″	**DL3T5E37S**	199.
	Use with 60″ and wider overhead	49″	4″	1 1/2″	**DL3T5E49S**	226.
T5 Advanced Task Light	Use with 30″ and wider overhead	25″	4″	1 1/2″	**DL3T5E25A**	456.
	Use with 42″ and wider overhead	37″	4″	1 1/2″	**DL3T5E37A**	480.
	Use with 60″ and wider overhead	49″	4″	1 1/2″	**DL3T5E49A**	499.
LED Task Light	Use with 24″ and wider overheads (3 LED's)	19″	2″	5/8″	**DL3L193M**	301.
	Use with 24″ and wider overheads (6 LED's)	19″	2″	5/8″	**DL3L196M**	380.
	Use with 24″ and wider overheads (9 LED's)	19″	2″	5/8″	**DL3L199M**	517.
	Use with 42″ and wider overheads (6 LED's)	37″	2″	5/8″	**DL3L376M**	607.
	Use with 42″ and wider overheads (12 LED's)	37″	2″	5/8″	**DL3L3712M**	686.
	Use with 42″ and wider overheads (18 LED's)	37″	2″	5/8″	**DL3L3718M**	850.
LED Task Light (for use with corner shelf only)	Use with 24″ and wider overheads (3 LED's)	19″	2″	5/8″	**DL3L193W**	301.
	Use with 24″ and wider overheads (6 LED's)	19″	2″	5/8″	**DL3L196W**	380.
	Use with 24″ and wider overheads (9 LED's)	19″	2″	5/8″	**DL3L199W**	517.
	Use with 42″ and wider overheads (6 LED's)	37″	2″	5/8″	**DL3L376W**	607.
	Use with 42″ and wider overheads (12 LED's)	37″	2″	5/8″	**DL3L3712W**	686.
	Use with 42″ and wider overheads (18 LED's)	37″	2″	5/8″	**DL3L3718W**	850.
Cord management clip	(package of 50)				**DL3TC**	45.

Ordering Information

Task Lights

1. Pattern Number

Cord Management Clip

1. Pattern Number

Order Code

T5 Standard Task Light

Example:	**DL3T5E25S**
DL3	Task Light
T5	T5 lamp
E	Electronic ballast
25	Width
S	Standard

LED Task Light

Example:	**DL3L193M**
DL3	Task Light
L	LED
19	Width
3	# of LED's
M	Metal Overhead Attachment

Included with:

T5 Task Lights:
120v and includes T5 cool white (4100K) fluorescent lamp, electronic ballast, 9′ grounded cordset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware. Housings are black.

LED Task Lights:
Includes LED's, power supply with 12' cord and mounting hardware. Housings are clear anodized aluminum with grey color end-caps.

Cord Management Clips:
Additional clips must be ordered separately.

Options

T5 Task Lights:
Specify suffix -CH and add $45 list for City of Chicago installations. Example: DL3T5E25S-CH

Cordset is center exit. On smaller units cord exit is off-center, but still not handed.

T5 advanced task lights are fitted with ballasts and lamps compliant with LEED requirements, meeting the LEED EB standard for mercury content.

LED Task Lights:
Power cord is able to attach to either end of fixture.

Notes:
All task lights mount into the recess in the underside of overhead cabinets and shelves at least 6″ wider than task light width.

All task lights are TCLP compliant and meet requirements of California Title 20 and Title 24.

Pedestals
Dividends Floorstanding, Doublewide and Mobile Specifications

Floorstanding Pedestals
Dividends Series 1 floorstanding pedestals are used to support worksurfaces in both panel-wrap and freestanding desk applications. No cantilevers or other supports are required at the end of the worksurface supported by a pedestal.

For panel-wrap applications, three depths are available in order to mount beneath 18", 24" and 30" deep worksurfaces.

In floorstanding desks, pedestals can either be specified "Preconfigured" with floorstanding desks or ordered by component for "Build-to-Spec" applications.

Two drawer configurations are available: box/box/file and file/file. Pedestals can be specified with or without locks.

Mobile Pedestals
Dividends Series 1 mobile pedestals provide moveable storage within workstations and tuck beneath worksurfaces when not in use. Available drawer configurations are box/box/file, box/file, and file/file.

Mobile pedestals roll on four corner-mounted swivel casters and one bottom drawer-mounted caster for stability when the lower drawer is in the open position. The front corner casters are locking.

Mobile pedestals may be specified with an optional handle allowing easy mobility. All mobile pedestals include 13-gauge finished tops. All other construction and drawer dimensions are the same as freestanding pedestals.

Mobile pedestals measure $20^{5}/_{8}$" and $26^{5}/_{8}$" high, 15" wide and 18" or 24" deep. All mobile pedestals include locks.

Available Sizes
Depths: 18", 24" and 30"
Width: 15"
Height: $20^{5}/_{8}$" and $26^{7}/_{8}$"

Doublewide Pedestals
The doublewide pedestal incorporates two 12" high drawers in a 30" width (18 $^{3}/_{4}$" depth) and is intended for below worksurface applications only. The doublewide's design allows for side-to-side letter or legal filing and front-to-back letter filing.

Doublewide pedestal can be used below 19", 24", or 36" deep worksurfaces, not 18" deep worksurfaces.

Available Size
Depth: $18^{3}/_{4}$" (floorstanding pedestal only)
Width: 30"
Height: $26^{7}/_{8}$

Construction
Floorstanding mobile and doublewide pedestals match the aesthetics and dimensions of Dividends Horizon panel components.

- Outer wrapper: 20-gauge seamless steel wrapper, includes finished back and full dust pan
- Inner frame: 20-gauge steel uprights and 16-gauge cross rails
- Drawer front: 20-gauge steel, gently radiused (double wide front: 18-gauge)
- Drawer top cap trim: Color injected, molded plastic
- Box drawer suspension (floorstanding ped only): $^{3}/_{4}$" extension, ball-bearing slides
- File drawer suspension: Full extension, ball-bearing slides
- Drawer pulls: Color injected, molded plastic
- Leveling glides: $^{3}/_{8}$" diameter steel stem with $1^{1}/_{2}$"of height adjustment (double wide ped: $^{5}/_{16}$" diameter steel stem with a $1^{9}/_{16}$" of height adjustment

Internal Drawer Dimensions (DS1)
Box drawer
- Internal height: $4^{5}/_{16}$"
- Internal width: $12^{9}/_{16}$"
- Internal depths: 18" = $15^{15}/_{16}$", 24" = $21^{1}/_{4}$", 30" = $27^{1}/_{4}$"

File drawer
- Internal height: $9^{1}/_{4}$"
- Internal width: $12^{1}/_{8}$"
- Internal depths: 18" = $15^{15}/_{16}$", 24" = $21^{1}/_{4}$", 30" = $27^{1}/_{4}$"

File drawer (doublewide ped)
- Internal height: $9^{3}/_{4}$"
- Internal width: $26^{3}/_{4}$"
- Internal depth: $15^{3}/_{4}$"

Locks
Pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field installation of locks at a later date if required.

Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All random keyed locks are factory-installed and have a black finish.

Pedestal Accessories
A hanging file bar for front-to-back or side-to-side filing is included with Series 1 pedestals.



Pedestal Filing Configurations



Doublewide Pedestal Filing Configurations


Doublewide Pedestal


Mobile Pedestal

Pedestals
Dividends Floorstanding, Doublewide and Mobile 18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Floorstanding Pedestals with Locks	12/12	18″	17 1/2″	14 7/8″	26 7/8″	**DS1PF L18B**	$555.	$610.	$639.
	6/6/12	18″	17 1/2″	14 7/8″	26 7/8″	**DS1PF L18A**	578.	634.	664.
	12/12	24″	23 1/2″	14 7/8″	26 7/8″	**DS1PF L24B**	609.	671.	698.
	6/6/12	24″	23 1/2″	14 7/8″	26 7/8″	**DS1PF L24A**	634.	697.	729.
	12/12	30″	29 1/2″	14 7/8″	26 7/8″	**DS1PF L30B**	638.	698.	730.
	6/6/12	30″	29 1/2″	14 7/8″	26 7/8″	**DS1PF L30A**	666.	731.	766.
Mobile Pedestals with Locks	12/12	18″	16 3/4″	14 7/8″	26 3/8″	**DS1PM L18B**	924.	1,018.	1,064.
	6/6/12	18″	16 3/4″	14 7/8″	26 3/8″	**DS1PM L18A**	953.	981.	1,096.
	6/12	18″	17 1/2″	14 7/8″	20 5/8″	**DS1PM L18F**	848.	932.	976.
	6/12	24″	22 3/4″	14 7/8″	20 5/8″	**DS1PM L24F**	918.	1,010.	1,055.
	12/12	24″	22 3/4″	14 7/8″	26 3/8″	**DS1PM L24B**	998.	1,096.	1,146.
	6/6/12	24″	22 3/4″	14 7/8″	26 3/8″	**DS1PM L24A**	1,026.	1,130.	1,181.
Doublewide Pedestals with Locks	12/12	19″	18 3/4″	30″	26 7/8″	**DS1DW 30L**	877.	965.	1,008.

d* = nominal depth
Dimensions listed under d w h are actual to the nearest 1/16″

Ordering Information

Floorstanding Pedestals

1. Pattern Number
2. Paint Finish
3. Pull Finish
4. Drawer Top Cap Finish

Mobile Pedestals

1. Pattern Number
2. Paint Finish
3. Pull Finish
4. Drawer Top Cap Finish

Doublewide Pedestals

1. Pattern Number
2. Paint Finish
3. Pull Finish
4. Drawer Top Cap Finish

Order Code

Floorstanding Pedestals

Example:	**DS1PF L24A, 117, 117, 117**
DS1PF 24A	Pattern Number
117	Soft Grey paint finish
117	Soft Grey pull finish
117	Soft Grey top cap finish

Doublewide Pedestals

Example:	**DS1DW 30L, 117, 117, 117**
DS1DW 30L	Pattern Number
117	Soft Grey paint finish
117	Soft Grey pull finish
117	Soft Grey top cap finish

Mobile Pedestals

Example:	**DS1PM L24A, 117, 117, 117**
DS1PM L24A	Pattern Number
117	Soft Grey paint finish
117	Soft Grey pull finish
117	Soft Grey drawer top cap finish

Included with:

Floorstanding Pedestals

- Hanging file bar (file drawer)

Mobile Pedestals

- Hanging file bar (file drawer)

Doublewide Pedestals

- Hanging file bar (front-to-back)
- Hanging file rail (side-to-side)

Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface

Options

Floorstanding Pedestals

- To specify pedestals without locks, replace the **"L"** (6th character) in the pattern number with an **"N".Deduct $20**

Doublewide Pedestals

- To specify pedestals without locks, replace the **"L"** (6th character) in the pattern number with an **"N".Deduct $20**

Mobile Pedestals
Mobile pedestals are available with lock only.

To specify a Dividends mobile pedestal with a handle, add "P" as the 7th character of the pattern number ie. **DS1PML(P)24 add $53**

Full Extension Drawer Slide Option
To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add $25 to the list price.

Pedestals
Series 2 Floorstanding, Doublewide and Mobile Specifications

Series 2 Floorstanding Pedestals
Series 2 floorstanding pedestals are used to support worksurfaces in both panel wrapped and freestanding applications. No cantilevers or other supports are required at the end of the worksurface supported by a pedestal.

Two drawer configurations are available: box/box/file and file/ file. Mobile pedestals are not available without locks.

The Series 2 24" deep pedestal design offers case without a back. In panel applications or in freestanding desking applications where the desk is against the wall, a back is not necessary.

In desking applications where the back of the case is exposed, an optional back is used to conceal the pedestals contents.

The 18" and 30" deep Series 2 pedestals include a back with each case.

Mobile Pedestals
Series 2 mobile pedestals provide moveable storage within a workstation and tuck beneath worksurfaces when not in use. Available drawer configurations are box/file, box/box/file and file/file.

Mobile pedestals roll on four corner-mounted swivel casters and one bottom drawer-mounted caster for stability when the lower drawer is in the open position. The front corner casters are locking.

Mobile pedestals may be specified with an optional handle allowing easy mobility.



Mobile Pedestal

All mobile pedestals include 13-gauge finished tops. A back is included with all Series 2 mobile pedestals.

Pedestals may be specified without the top for attachment of a pedestal cushion. Pedestal cushion may be ordered through the Knoll Currents product line.

Available Sizes
Depths: 18", 24" and 30" (Floorstanding pedestal only)
Width: 15"
Height: 26 7/8"

Series 2 Doublewide Pedestals
The doublewide pedestal incorporates two 12" high drawers in a 30" or 36" width (18 3/4" depth) and is intended for below worksurface applications only. The doublewide's design allows for side-to-side letter or legal filing and front-to-back letter filing.

Doublewide pedestals can be used below 19", 24", 30" or 36" deep worksurfaces, not 18" deep worksurfaces.

Available Sizes
Depth: 18 3/4" (floorstanding pedestal only)
Width: 30" and 36"
Height: 26 7/8"

Construction:
- Outer wrapper: 20-gauge steel
- Drawer front: 20-gauge steel (double wide front: 18-gauge)
- Pedestal back: 20-gauge
- 3/4 extension ball bearing slides on 6" box drawers
- Full extension ball bearing slides on 12" file drawers
- Leveling glides: 3/8" diameter steel stem with 1 1/2"of height adjustment (double wide ped: 5/16" diameter steel stem with a 1 9/16" of height adjustment

Internal Drawer Dimensions (DS2, 24"d)
Box drawer
- Internal height: 4 5/16"
- Internal width: 12 1/16"
- Internal depths: 18 3/8"

File drawer
- Internal height: 9 1/4"
- Internal width: 12 1/8"
- Internal depths: 18 3/8"

File drawer (doublewide pedestal)
- Internal height: 9 3/4"
- Internal width: 26 3/4" and 32 3/4"
- Internal depth: 15 3/4"

Locks
Series 2 mobile pedestals are available not available without locks. Series 2 doublewide pedestals can be ordered with or without locks.

Locks are randomly keyed unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and have a black finish.

Pedestal Accessories
All Series 2 freestanding pedestal accessories including the hanging file bar must be specified separately. Series 2 double wide pedestals are shipped with hanging file bars.

Interior drawer dimensions for DS2 are 18" deep and 30" deep. Pedestals are the same as DS1 dimensions listed on page 228.

Pedestals
Series 2 Floorstanding, Doublewide and Mobile 18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Series 2 Floorstanding Pedestals with Locks 	12/12 w/back	18″	17½″	14⅞″	26⅞″	**DS2PF L18B**	$559.	$644.	$672.
	6/6/12 w/back	18″	17½″	14⅞″	26⅞″	**DS2PF L18A**	582.	670.	697.
	12/12 no back	24″	23½″	14⅞″	26⅞″	**DS2PF L24B**	472.	545.	567.
	6/6/12 no back	24″	23½″	14⅞″	26⅞″	**DS2PF L24A**	499.	575.	598.
	6/6/12 w/back	30″	24½″	14⅞″	26⅞″	**DS2PF L30A**	672.	773.	810.
	12/12 w/back	30″	29½″	14⅞″	26⅞″	**DS2PF L30B**	643.	736.	769.
Series 2 Floorstanding Case Back (For 24″ deep units only) 				14⅞″	26⅞″	**DS2XPB**	85.	96.	99.
Series 2 Mobile Pedestals with Locks 	6/12	18″	16¾″	14⅞″	20⅝″	**DS2PM L18F**	854.	984.	1,026.
	12/12	18″	16¾″	14⅞″	26⅜″	**DS2PM L18B**	931.	1,072.	1,118.
	6/6/12	18″	16¾″	14⅞″	26⅜″	**DS2PM L18A**	962.	1,104.	1,152.
	6/12	24″	22¾″	14⅞″	20⅝″	**DS2PM L24F**	612.	703.	732.
	6/6/12	24″	22¾″	14⅞″	26⅜″	**DS2PM L24A**	682.	787.	820.
	12/12	24″	22¾″	14⅞″	26⅜″	**DS2PM L24B**	682.	787.	820.

d* = nominal depth
Dimensions listed under d w h are actual to the nearest 1/16″

Ordering Information

Pedestals

1. Pattern Number
2. Paint Finish

Order Code

Floorstanding Pedestals

Example:	**DS2PF L24A, 117**
DS2PF L24A	Pattern Number
117	Soft Grey paint finish

Doublewide Pedestals

Example:	**DS2DW 30L, 113**
DS2DW 30L	Pattern Number
113	Dark grey paint finish

Included with:

Floorstanding Pedestals

- Hanging file bar not included

Note: 24″ deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18″ and 30″ deep floorstanding pedestals have backs.

Mobile Pedestals

- Hanging file bar not included

Doublewide Pedestals

- Hanging File Bar (front-to-back)
- Hanging file rail (side-to-side)

Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.

Options

Floorstanding Pedestals

- To specify pedestals without locks, replace the **"L"**suffix with an **"N". Deduct $15**

Doublewide Pedestals

- To specify pedestals without locks, replace the **"L"**suffix with an **"N". Deduct $20**

Mobile Pedestals

- To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A **Deduct $35**
- Add $53 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A)

Finish Option:
Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Full Extension Drawer Slide Option
To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add $25 to the list price.

Pedestals
Series 2 Floorstanding, Doublewide and Mobile 18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Series 2 Doublewide Pedestals with Locks	12/12	19″	18¾″	30″	26⅞″	**DS2DW 30L**	$883.	$1,016.	$1,059.
	12/12	19″	18¾″	36″	26⅞″	**DS2DW 36L**	932.	1,073.	1,119.

d* = nominal depth
Dimensions listed under d w h are actual to the nearest 1/16″

Ordering Information

Pedestals

1. Pattern Number
2. Paint Finish

Order Code

Floorstanding Pedestals

Example:	**DS2PF L24A, 117**
DS2PF L24A	Pattern Number
117	Soft Grey paint finish

Doublewide Pedestals

Example:	**DS2DW 30L, 113**
DS2DW 30L	Pattern Number
113	Dark grey paint finish

Included with:

Floorstanding Pedestals

- Hanging file bar not included

Note: 24″ deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18″ and 30″ deep floorstanding pedestals have backs.

Mobile Pedestals

- Hanging file bar not included

Doublewide Pedestals

- Hanging File Bar (front-to-back)
- Hanging file rail (side-to-side)

Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.

Options

Floorstanding Pedestals

- To specify pedestals without locks, replace the **"L"**suffix with an **"N". Deduct $15**

Doublewide Pedestals

- To specify pedestals without locks, replace the **"L"**suffix with an **"N". Deduct $20**

Mobile Pedestals

- To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A **Deduct $35**
- Add $53 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A)

Finish Option:
Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Full Extension Drawer Slide Option
To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add $25 to the list price.

This page intentionally left blank

Pencil Tray
Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13 1/4" wide, 5 7/16" deep and 7/8" high. Black or clear finish available.

Hanging File Bar
Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.

A hanging file bar is included with each file drawer when ordering Series 1 desks or pedestals. Hanging file bars are not included with Series 2 pedestals or desks - order separately.

Drawer Dividers
Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.

Stationery Inserts
Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.

Pencil Drawer
For use with freestanding desks or panel-mounted worksurfaces with depths of 24" or more. 24" wide, 17 5/8" deep and 2" high. Black finish.

Attachment: Mounts on underside of worksurface with included mounting hardware

Pedestal Lock Retrofit Kit
Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core and lock rod assembly (must be specified box/box/file or file/file).

Worksurface Edge Grommet
Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.



Pencil Tray



Hanging File Bar



Drawer Divider, Box



Drawer Divider, File Drawer



Stationery Inserts



Pencil Drawer



Worksurface Edge Grommet

Pedestals
Accessories
Drawer Organizers, Grommet Kits and Lock Retrofit Kits

description	type	w	d	h	pattern no.	list
Pencil Tray	Black finish	13 1/4″	5 7/8″	7/8″	**DS2PPTN**	$37.
	Clear finish	13 1/4″	5 7/8″	7/8″	**DS2PPTC**	44.
Hanging File Bar		12 3/16″	2 15/16″	1/2″	**DS1PFS**	32.
Drawer Divider, Box		12 3/8″	3″	3 1/8″	**DS1PBD**	32.
Drawer Divider, File		10	3 5/8″	6 3/8″	**DS1PFD**	32.
Stationary Inserts, box (4 trays)		13	15/16″	8 7/8″	**DS1PST**	170.
Pencil Drawer		24″	17 5/8″	2″	**DS1PCD**	231.
Worksurface Grommet Kit (Dark Grey)		2 3/16″	2 5/16″	1 3/8″	**D1WSG**	23.
Dividends Floorstanding Pedestal Lock Retrofit Kit					**DS1LKKT**	71.
Series 2 Floorstanding Pedestal Lock Retrofit Kit					**DS2LKKT**	58.
Dividends Doublewide Pedestal Lock Retrofit Kit					**DS1DWDPL**	64.
Series 2 Doublewide Pedestal Lock Retrofit Kit		30″			**DS2DWDPL30**	61.
		36″			**DS2DWDPL36**	64.

Ordering Information	**Order Code**	**Included with:**	**Options**
Pencil Tray	**Pencil Tray**	**Pencil Tray**	
1. Pattern Number	*Example:* **DS2PPT**		
	DS2PPT Pattern Number		

Credenzas
Single Depth - Specifications

Single Depth Credenzas
Dividends Horizon single depth credenzas increase planning and design options by blending residential furniture attributes within systems furniture applications. Credenzas offer a practical solution for functional under worksurface storage, while increasing the overall aesthetics of an office.

Credenzas consist of a metal, laminate, or veneer top option with a shelf and binder storage area. Single depth credenzas have four configuration options: sliding door only, drawer only, sliding door and drawer combination, and open shelves without a sliding door or a drawer.

The sliding door is a single steel, laminate, or veneer door with a handle that conceals half the width of the binder storage area. A single drawer may be specified for the location above the shelf. The drawer may be installed in either the right or left location, the drawer location does not need to be specified when ordered. When a drawer is specified along with a sliding door, the drawer front and sliding door finishes are the same. Units that include a drawer have a full back and those without a drawer have a partial back that encloses the binder storage area below the shelf.

Shorter width credenzas, 24, 30, and 36 inches wide, are available with a laminate or veneer top only. 24 inch wide credenzas do not include a center vertical septum and are only available as open shelf units, without a sliding door or drawer. Units are shipped knocked down and may be specified with or without locks. Dividends Horizon credenzas are available in all Knoll Core finishes. Legacy finishes are not available.

Available Sizes
Heights: 24 inches
Depth: 13-5/16 inches
Widths: 24 – 72 inches

Construction

- **Top**:
  - Steel: 16-gauge painted steel
  - Laminate: 1-1/4 inch thick particle board with high pressure laminate on top and a paper backer on the underside with 2mm edgeband
  - Veneer: 1-1/4 inch thick particle board with 0.6mm veneer on top and edge.
- **End Panels:** 16-gauge painted steel
- **Back Panel:** 20-gauge painted steel
- **Door:**
  - Steel: 20-gauge panted steel
  - Laminate: 3/4 inch thick particle board with high pressure laminate on the outside and a paper backer on the inside with 1mm edgeband
  - Veneer 3/4 inch thick particle board with 0.6mm thick veneer on top and edge
- **Fixed Shelf:** 16-gauge painted steel
- **Door Handle:** painted aluminum (same color as case)

Interior Dimensions
Heights: 12-1/2 inches for the lower section, 5-7/8 inches for the upper section
Depth: 12-1/16 inches

Locks
Locks are standard on credenzas with doors and/or drawers and are keyed randomly unless otherwise specified. All locks are factory installed and have a black finish. Credenzas can also be specified without locks if required.

Single Depth Credenza with Open Shelves



Single Depth Credenza with a Drawer



Single Depth Credenza with a Sliding Door



Single Depth Credenza with a Drawer and a Sliding Door



Credenzas
Single Depth with Steel Top
With or Without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza without Door	42″	24″	13 5/16″	**DS4LC1ANS42N**	$640.	$702.	$734.
	48″	24″	13 5/16″	**DS4LC1ANS48N**	655.	720.	754.
	54″	24″	13 5/16″	**DS4LC1ANS54N**	730.	805.	842.
	60″	24″	13 5/16″	**DS4LC1ANS60N**	739.	814.	850.
	66″	24″	13 5/16″	**DS4LC1ANS66N**	761.	836.	874.
	72″	24″	13 5/16″	**DS4LC1ANS72N**	791.	870.	908.
Credenza with Steel Sliding Door	42″	24″	13 5/16″	**DS4LC1BSS42L**	790.	868.	906.
	48″	24″	13 5/16″	**DS4LC1BSS48L**	806.	887.	927.
	54″	24″	13 5/16″	**DS4LC1BSS54L**	896.	987.	1,030.
	60″	24″	13 5/16″	**DS4LC1BSS60L**	901.	993.	1,037.
	66″	24″	13 5/16″	**DS4LC1BSS66L**	929.	1,023.	1,069.
	72″	24″	13 5/16″	**DS4LC1BSS72L**	961.	1,054.	1,103.
Credenza with Laminate Sliding Door	42″	24″	13 5/16″	**DS4LC1BLS42L**	1,282.	1,410.	1,472.
	48″	24″	13 5/16″	**DS4LC1BLS48L**	1,314.	1,443.	1,508.
	54″	24″	13 5/16″	**DS4LC1BLS54L**	1,344.	1,476.	1,542.
	60″	24″	13 5/16″	**DS4LC1BLS60L**	1,374.	1,511.	1,577.
	66″	24″	13 5/16″	**DS4LC1BLS66L**	1,406.	1,544.	1,614.
	72″	24″	13 5/16″	**DS4LC1BLS72L**	1,438.	1,577.	1,649.
Credenza with Veneer Sliding Door	42″	24″	13 5/16″	**DS4LC1BVS42L**	1,367.	1,502.	1,570.
	48″	24″	13 5/16″	**DS4LC1BVS48L**	1,406.	1,544.	1,613.
	54″	24″	13 5/16″	**DS4LC1BVS54L**	1,444.	1,585.	1,657.
	60″	24″	13 5/16″	**DS4LC1BVS60L**	1,482.	1,626.	1,700.
	66″	24″	13 5/16″	**DS4LC1BVS66L**	1,518.	1,669.	1,743.
	72″	24″	13 5/16″	**DS4LC1BVS72L**	1,557.	1,710.	1,787.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with Sliding Door:

1. Pattern number
2. Paint finish
3. Door finish (laminate and veneer only)
4. Door edge finish (laminate only)

Credenza without Sliding Door:

1. Pattern number
2. Paint finish

Order Code

Credenza with Sliding Door:

Example:	**DS4LC1BSS42L /117**
DS4LC1B SS42L	Pattern Number
117	Dark grey paint

Credenza without a Sliding Door:

Example:	**DS4LC1ANS42N /117**
DS4LC1A NS42N	Pattern Number
117	Dark grey paint

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without Sliding Door:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Steel Top Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Drawer	42″	24″	13 5/16″	**DS4LC1CSS42L**	$959.	$1,021.	$1,054.
	48″	24″	13 5/16″	**DS4LC1CSS48L**	974.	1,038.	1,071.
	54″	24″	13 5/16″	**DS4LC1CSS54L**	1,050.	1,123.	1,159.
	60″	24″	13 5/16″	**DS4LC1CSS60L**	1,058.	1,132.	1,169.
	66″	24″	13 5/16″	**DS4LC1CSS66L**	1,078.	1,154.	1,193.
	72″	24″	13 5/16″	**DS4LC1CSS72L**	1,108.	1,189.	1,228.
Credenza with Laminate Drawer	42″	24″	13 5/16″	**DS4LC1CLS42L**	1,136.	1,199.	1,232.
	48″	24″	13 5/16″	**DS4LC1CLS48L**	1,152.	1,217.	1,249.
	54″	24″	13 5/16″	**DS4LC1CLS54L**	1,228.	1,302.	1,338.
	60″	24″	13 5/16″	**DS4LC1CLS60L**	1,236.	1,310.	1,346.
	66″	24″	13 5/16″	**DS4LC1CLS66L**	1,258.	1,332.	1,370.
	72″	24″	13 5/16″	**DS4LC1CLS72L**	1,286.	1,366.	1,406.
Credenza with Veneer Drawer	42″	24″	13 5/16″	**DS4LC1CVS42L**	1,175.	1,237.	1,270.
	48″	24″	13 5/16″	**DS4LC1CVS48L**	1,191.	1,256.	1,288.
	54″	24″	13 5/16″	**DS4LC1CVS54L**	1,266.	1,340.	1,375.
	60″	24″	13 5/16″	**DS4LC1CVS60L**	1,274.	1,348.	1,385.
	66″	24″	13 5/16″	**DS4LC1CVS66L**	1,296.	1,370.	1,409.
	72″	24″	13 5/16″	**DS4LC1CVS72L**	1,325.	1,405.	1,444.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Drawer:

1. Pattern number
2. Paint finish
3. Drawer front finish (laminate and veneer only)
4. Drawer front edge finish (laminate only)

Order Code

Credenza with a Drawer:

Example:	**DS4LC1CLS42L /117/118/118**
DS4LC1C LS42L	Pattern Number
117	Dark grey paint
118	Bright white drawer front
118	Bright white drawer front edge

Included with:

Credenza with a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Steel Top
With a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	42″	24″	13 5/16″	**DS4LC1DSS42L**	$1,107.	$1,188.	$1,226.
	48″	24″	13 5/16″	**DS4LC1DSS48L**	1,125.	1,205.	1,245.
	54″	24″	13 5/16″	**DS4LC1DSS54L**	1,215.	1,305.	1,348.
	60″	24″	13 5/16″	**DS4LC1DSS60L**	1,221.	1,311.	1,355.
	66″	24″	13 5/16″	**DS4LC1DSS66L**	1,247.	1,341.	1,388.
	72″	24″	13 5/16″	**DS4LC1DSS72L**	1,278.	1,371.	1,422.
Credenza with Laminate Sliding Door and Drawer	42″	24″	13 5/16″	**DS4LC1DLS42L**	1,602.	1,728.	1,789.
	48″	24″	13 5/16″	**DS4LC1DLS48L**	1,633.	1,761.	1,826.
	54″	24″	13 5/16″	**DS4LC1DLS54L**	1,662.	1,793.	1,861.
	60″	24″	13 5/16″	**DS4LC1DLS60L**	1,693.	1,829.	1,896.
	66″	24″	13 5/16″	**DS4LC1DLS66L**	1,724.	1,863.	1,932.
	72″	24″	13 5/16″	**DS4LC1DLS72L**	1,755.	1,896.	1,966.
Credenza with Veneer Sliding Door and Drawer	42″	24″	13 5/16″	**DS4LC1DVS42L**	1,686.	1,821.	1,889.
	48″	24″	13 5/16″	**DS4LC1DVS48L**	1,724.	1,863.	1,931.
	54″	24″	13 5/16″	**DS4LC1DVS54L**	1,762.	1,904.	1,976.
	60″	24″	13 5/16″	**DS4LC1DVS60L**	1,799.	1,945.	2,019.
	66″	24″	13 5/16″	**DS4LC1DVS66L**	1,836.	1,987.	2,062.
	72″	24″	13 5/16″	**DS4LC1DVS72L**	1,876.	2,029.	2,106.







Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door and a Drawer:

1. Pattern number
2. Paint finish
3. Drawer/Door finish (laminate and veneer only)
4. Drawer/Door edge finish (laminate only)

Order Code

Credenza with a Sliding Door and a Drawer:

Example:	**DS4LC1DSS42L/117**
DS4LC1D SS42L	Pattern Number
117	Dark grey paint

Included with:

Credenza with a Sliding Door and a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door and a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $40 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Laminate Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza without Door	24″	24″	13 5/16″	**DS4LC1ANL24N**	$860.	$943.	$989.
	30″	24″	13 5/16″	**DS4LC1ANL30N**	860.	943.	989.
	36″	24″	13 5/16″	**DS4LC1ANL36N**	860.	943.	989.
	42″	24″	13 5/16″	**DS4LC1ANL42N**	860.	943.	989.
	48″	24″	13 5/16″	**DS4LC1ANL48N**	884.	972.	1,017.
	54″	24″	13 5/16″	**DS4LC1ANL54N**	952.	1,049.	1,097.
	60″	24″	13 5/16″	**DS4LC1ANL60N**	953.	1,050.	1,098.
	66″	24″	13 5/16″	**DS4LC1ANL66N**	987.	1,086.	1,134.
	72″	24″	13 5/16″	**DS4LC1ANL72N**	1,020.	1,122.	1,172.
Credenza with Steel Sliding Door	30″	24″	13 5/16″	**DS4LC1BSL30L**	1,000.	1,100.	1,149.
	36″	24″	13 5/16″	**DS4LC1BSL36L**	1,000.	1,100.	1,149.
	42″	24″	13 5/16″	**DS4LC1BSL42L**	1,000.	1,100.	1,149.
	48″	24″	13 5/16″	**DS4LC1BSL48L**	1,025.	1,128.	1,179.
	54″	24″	13 5/16″	**DS4LC1BSL54L**	1,112.	1,225.	1,278.
	60″	24″	13 5/16″	**DS4LC1BSL60L**	1,113.	1,226.	1,281.
	66″	24″	13 5/16″	**DS4LC1BSL66L**	1,149.	1,265.	1,321.
	72″	24″	13 5/16″	**DS4LC1BSL72L**	1,182.	1,301.	1,359.
Credenza with Laminate Sliding Door	30″	24″	13 5/16″	**DS4LC1BLL30L**	1,394.	1,531.	1,600.
	36″	24″	13 5/16″	**DS4LC1BLL36L**	1,394.	1,531.	1,600.
	42″	24″	13 5/16″	**DS4LC1BLL42L**	1,394.	1,531.	1,600.
	48″	24″	13 5/16″	**DS4LC1BLL48L**	1,438.	1,577.	1,650.
	54″	24″	13 5/16″	**DS4LC1BLL54L**	1,481.	1,625.	1,698.
	60″	24″	13 5/16″	**DS4LC1BLL60L**	1,524.	1,674.	1,749.
	66″	24″	13 5/16″	**DS4LC1BLL66L**	1,568.	1,722.	1,798.
	72″	24″	13 5/16″	**DS4LC1BLL72L**	1,612.	1,771.	1,850.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Door finish (laminate and veneer only)
6. Door edge finish (laminate only)

Credenza without Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish

Order Code

Credenza with Sliding Door:

Example:	**DS4LC1BLL42L /117/118/117/118/118**
DS4LC1B LL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge
118	Bright white door
118	Bright white door edge

Credenza without a Sliding Door:

Example:	**DS4LC1ANL42N /117**
DS4LC1A NL42N	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without Sliding Door:

Lock/No lock option
For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $20. from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Laminate Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Veneer Sliding Door	30″	24″	13 5/16″	**DS4LC1BVL30L**	$1,481.	$1,625.	$1,700.
	36″	24″	13 5/16″	**DS4LC1BVL36L**	1,481.	1,625.	1,700.
	42″	24″	13 5/16″	**DS4LC1BVL42L**	1,481.	1,625.	1,700.
	48″	24″	13 5/16″	**DS4LC1BVL48L**	1,532.	1,683.	1,757.
	54″	24″	13 5/16″	**DS4LC1BVL54L**	1,581.	1,737.	1,816.
	60″	24″	13 5/16″	**DS4LC1BVL60L**	1,632.	1,792.	1,874.
	66″	24″	13 5/16″	**DS4LC1BVL66L**	1,683.	1,848.	1,932.
	72″	24″	13 5/16″	**DS4LC1BVL72L**	1,732.	1,904.	1,989.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Door finish (laminate and veneer only)
6. Door edge finish (laminate only)

Credenza without Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish

Order Code

Credenza with Sliding Door:

Example:	**DS4LC1BLL42L /117/118/117/118/118**
DS4LC1B LL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge
118	Bright white door
118	Bright white door edge

Credenza without a Sliding Door:

Example:	**DS4LC1ANL42N /117**
DS4LC1A NL42N	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without Sliding Door:

Lock/No lock option
For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $20. from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Laminate Top Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Drawer	30″	24″	13 5/16″	**DS4LC1CSL30L**	$1,179.	$1,263.	$1,307.
	36″	24″	13 5/16″	**DS4LC1CSL36L**	1,179.	1,263.	1,307.
	42″	24″	13 5/16″	**DS4LC1CSL42L**	1,179.	1,263.	1,307.
	48″	24″	13 5/16″	**DS4LC1CSL48L**	1,202.	1,290.	1,334.
	54″	24″	13 5/16″	**DS4LC1CSL54L**	1,271.	1,366.	1,415.
	60″	24″	13 5/16″	**DS4LC1CSL60L**	1,272.	1,367.	1,416.
	66″	24″	13 5/16″	**DS4LC1CSL66L**	1,305.	1,404.	1,452.
	72″	24″	13 5/16″	**DS4LC1CSL72L**	1,338.	1,441.	1,489.
Credenza with Laminate Drawer	30″	24″	13 5/16″	**DS4LC1CLL30L**	1,357.	1,441.	1,485.
	36″	24″	13 5/16″	**DS4LC1CLL36L**	1,357.	1,441.	1,485.
	42″	24″	13 5/16″	**DS4LC1CLL42L**	1,357.	1,441.	1,485.
	48″	24″	13 5/16″	**DS4LC1CLL48L**	1,381.	1,469.	1,513.
	54″	24″	13 5/16″	**DS4LC1CLL54L**	1,449.	1,544.	1,594.
	60″	24″	13 5/16″	**DS4LC1CLL60L**	1,450.	1,545.	1,595.
	66″	24″	13 5/16″	**DS4LC1CLL66L**	1,483.	1,581.	1,630.
	72″	24″	13 5/16″	**DS4LC1CLL72L**	1,516.	1,619.	1,668.
Credenza with Veneer Drawer	30″	24″	13 5/16″	**DS4LC1CVL30L**	1,396.	1,479.	1,523.
	36″	24″	13 5/16″	**DS4LC1CVL36L**	1,396.	1,479.	1,523.
	42″	24″	13 5/16″	**DS4LC1CVL42L**	1,396.	1,479.	1,523.
	48″	24″	13 5/16″	**DS4LC1CVL48L**	1,418.	1,507.	1,551.
	54″	24″	13 5/16″	**DS4LC1CVL54L**	1,487.	1,582.	1,632.
	60″	24″	13 5/16″	**DS4LC1CVL60L**	1,488.	1,583.	1,633.
	66″	24″	13 5/16″	**DS4LC1CVL66L**	1,521.	1,620.	1,669.
	72″	24″	13 5/16″	**DS4LC1CVL72L**	1,554.	1,657.	1,706.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Drawer finish (laminate and veneer only)
6. Drawer edge finish (laminate only)

Order Code

Credenza with a Drawer:

Example:	**DS4LC1CSL42L /117/118/117**
DS4LC1C SL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Laminate Top With a Sliding Door and with a Drawer

description	w	d	h	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer 	30″	13 5/16″	24″	**DS4LC1DSL30L**	$1,317.	$1,418.	$1,469.
	36″	13 5/16″	24″	**DS4LC1DSL36L**	1,317.	1,418.	1,469.
	42″	13 5/16″	24″	**DS4LC1DSL42L**	1,317.	1,418.	1,469.
	48″	13 5/16″	24″	**DS4LC1DSL48L**	1,343.	1,446.	1,497.
	54″	13 5/16″	24″	**DS4LC1DSL54L**	1,432.	1,542.	1,598.
	60″	13 5/16″	24″	**DS4LC1DSL60L**	1,433.	1,543.	1,601.
	66″	13 5/16″	24″	**DS4LC1DSL66L**	1,469.	1,582.	1,641.
	72″	13 5/16″	24″	**DS4LC1DSL72L**	1,500.	1,619.	1,678.
Credenza with Laminate Sliding Door and Drawer 	30″	13 5/16″	24″	**DS4LC1DLL30L**	1,711.	1,850.	1,917.
	36″	13 5/16″	24″	**DS4LC1DLL36L**	1,711.	1,850.	1,917.
	42″	13 5/16″	24″	**DS4LC1DLL42L**	1,711.	1,850.	1,917.
	48″	13 5/16″	24″	**DS4LC1DLL48L**	1,755.	1,896.	1,967.
	54″	13 5/16″	24″	**DS4LC1DLL54L**	1,798.	1,944.	2,018.
	60″	13 5/16″	24″	**DS4LC1DLL60L**	1,843.	1,992.	2,068.
	66″	13 5/16″	24″	**DS4LC1DLL66L**	1,886.	2,040.	2,118.
	72″	13 5/16″	24″	**DS4LC1DLL72L**	1,929.	2,089.	2,167.
Credenza with Veneer Sliding Door and Drawer 	30″	13 5/16″	24″	**DS4LC1DVL30L**	1,798.	1,944.	2,019.
	36″	13 5/16″	24″	**DS4LC1DVL36L**	1,798.	1,944.	2,019.
	42″	13 5/16″	24″	**DS4LC1DVL42L**	1,798.	1,944.	2,019.
	48″	13 5/16″	24″	**DS4LC1DVL48L**	1,851.	2,000.	2,076.
	54″	13 5/16″	24″	**DS4LC1DVL54L**	1,900.	2,055.	2,133.
	60″	13 5/16″	24″	**DS4LC1DVL60L**	1,950.	2,112.	2,192.
	66″	13 5/16″	24″	**DS4LC1DVL66L**	2,000.	2,165.	2,251.
	72″	13 5/16″	24″	**DS4LC1DVL72L**	2,051.	2,222.	2,307.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door and a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Drawer/Door finish (laminate and veneer only)
6. Drawer/Door edge finish (laminate only)

Order Code

Credenza with a Sliding Door and a Drawer:

Example:	**DS4LC1DSL42L /117/118/117**
DS4LC1D SL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Sliding Door and a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door and a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer substitute the "L" suffix with an "N" and deduct $40 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza without Door	24″	24″	13 5/16″	**DS4LC1ANV24N**	$1,316.	$1,448.	$1,514.
	30″	24″	13 5/16″	**DS4LC1ANV30N**	1,316.	1,448.	1,514.
	36″	24″	13 5/16″	**DS4LC1ANV36N**	1,316.	1,448.	1,514.
	42″	24″	13 5/16″	**DS4LC1ANV42N**	1,316.	1,448.	1,514.
	48″	24″	13 5/16″	**DS4LC1ANV48N**	1,347.	1,483.	1,550.
	54″	24″	13 5/16″	**DS4LC1ANV54N**	1,380.	1,517.	1,586.
	60″	24″	13 5/16″	**DS4LC1ANV60N**	1,412.	1,552.	1,622.
	66″	24″	13 5/16″	**DS4LC1ANV66N**	1,443.	1,586.	1,660.
	72″	24″	13 5/16″	**DS4LC1ANV72N**	1,475.	1,621.	1,695.
Credenza with Steel Sliding Door	30″	24″	13 5/16″	**DS4LC1BSV30L**	1,389.	1,525.	1,594.
	36″	24″	13 5/16″	**DS4LC1BSV36L**	1,389.	1,525.	1,594.
	42″	24″	13 5/16″	**DS4LC1BSV42L**	1,389.	1,525.	1,594.
	48″	24″	13 5/16″	**DS4LC1BSV48L**	1,423.	1,563.	1,632.
	54″	24″	13 5/16″	**DS4LC1BSV54L**	1,456.	1,600.	1,671.
	60″	24″	13 5/16″	**DS4LC1BSV60L**	1,489.	1,638.	1,710.
	66″	24″	13 5/16″	**DS4LC1BSV66L**	1,523.	1,673.	1,748.
	72″	24″	13 5/16″	**DS4LC1BSV72L**	1,557.	1,710.	1,787.
Credenza with Laminate Sliding Door	30″	24″	13 5/16″	**DS4LC1BLV30L**	1,687.	1,854.	1,936.
	36″	24″	13 5/16″	**DS4LC1BLV36L**	1,687.	1,854.	1,936.
	42″	24″	13 5/16″	**DS4LC1BLV42L**	1,687.	1,854.	1,936.
	48″	24″	13 5/16″	**DS4LC1BLV48L**	1,721.	1,891.	1,976.
	54″	24″	13 5/16″	**DS4LC1BLV54L**	1,755.	1,928.	2,014.
	60″	24″	13 5/16″	**DS4LC1BLV60L**	1,789.	1,965.	2,055.
	66″	24″	13 5/16″	**DS4LC1BLV66L**	1,823.	2,003.	2,094.
	72″	24″	13 5/16″	**DS4LC1BLV72L**	1,858.	2,041.	2,133.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer)
5. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish

Order Code

Credenza with Sliding Door:

Example:	**DS4LC1BSV42L /117/Y319**
DS4LC1B SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Credenza without a Sliding Door:

Example:	**DS4LC1ANV42N /117/Y319**
DS4LC1A NV42N	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without a Sliding Door:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Veneer Sliding Door	30″	24″	13 5/16″	**DS4LC1BVV30L**	$1,775.	$1,949.	$2,038.
	36″	24″	13 5/16″	**DS4LC1BVV36L**	1,775.	1,949.	2,038.
	42″	24″	13 5/16″	**DS4LC1BVV42L**	1,775.	1,949.	2,038.
	48″	24″	13 5/16″	**DS4LC1BVV48L**	1,816.	1,995.	2,085.
	54″	24″	13 5/16″	**DS4LC1BVV54L**	1,857.	2,040.	2,132.
	60″	24″	13 5/16″	**DS4LC1BVV60L**	1,898.	2,085.	2,178.
	66″	24″	13 5/16″	**DS4LC1BVV66L**	1,938.	2,130.	2,226.
	72″	24″	13 5/16″	**DS4LC1BVV72L**	1,981.	2,174.	2,273.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer)
5. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish

Order Code

Credenza with Sliding Door:

Example:	**DS4LC1BSV42L /117/Y319**
DS4LC1B SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Credenza without a Sliding Door:

Example:	**DS4LC1ANV42N /117/Y319**
DS4LC1A NV42N	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without a Sliding Door:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Veneer Top Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Door	30″	24″	13 5/16″	**DS4LC1CSV30L**	$1,636.	$1,766.	$1,832.
	36″	24″	13 5/16″	**DS4LC1CSV36L**	1,636.	1,766.	1,832.
	42″	24″	13 5/16″	**DS4LC1CSV42L**	1,636.	1,766.	1,832.
	48″	24″	13 5/16″	**DS4LC1CSV48L**	1,666.	1,800.	1,868.
	54″	24″	13 5/16″	**DS4LC1CSV54L**	1,697.	1,835.	1,906.
	60″	24″	13 5/16″	**DS4LC1CSV60L**	1,730.	1,870.	1,941.
	66″	24″	13 5/16″	**DS4LC1CSV66L**	1,761.	1,906.	1,979.
	72″	24″	13 5/16″	**DS4LC1CSV72L**	1,792.	1,939.	2,013.
Credenza with Laminate Door	30″	24″	13 5/16″	**DS4LC1CLV30L**	1,814.	1,945.	2,010.
	36″	24″	13 5/16″	**DS4LC1CLV36L**	1,814.	1,945.	2,010.
	42″	24″	13 5/16″	**DS4LC1CLV42L**	1,814.	1,945.	2,010.
	48″	24″	13 5/16″	**DS4LC1CLV48L**	1,844.	1,980.	2,047.
	54″	24″	13 5/16″	**DS4LC1CLV54L**	1,876.	2,013.	2,084.
	60″	24″	13 5/16″	**DS4LC1CLV60L**	1,909.	2,049.	2,119.
	66″	24″	13 5/16″	**DS4LC1CLV66L**	1,939.	2,084.	2,157.
	72″	24″	13 5/16″	**DS4LC1CLV72L**	1,970.	2,118.	2,192.
Credenza with Veneer Door	30″	24″	13 5/16″	**DS4LC1CVV30L**	1,852.	1,983.	2,049.
	36″	24″	13 5/16″	**DS4LC1CVV36L**	1,852.	1,983.	2,049.
	42″	24″	13 5/16″	**DS4LC1CVV42L**	1,852.	1,983.	2,049.
	48″	24″	13 5/16″	**DS4LC1CVV48L**	1,882.	2,019.	2,085.
	54″	24″	13 5/16″	**DS4LC1CVV54L**	1,914.	2,052.	2,122.
	60″	24″	13 5/16″	**DS4LC1CVV60L**	1,947.	2,087.	2,157.
	66″	24″	13 5/16″	**DS4LC1CVV66L**	1,978.	2,122.	2,195.
	72″	24″	13 5/16″	**DS4LC1CVV72L**	2,009.	2,156.	2,231.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer only)
5. Door edge finish (laminate only)

Order Code

Credenza with a Drawer:

Example:	**DS4LC1CSV42L /117/ Y319**
DS4LC1C SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $20 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Veneer Top
With a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	30″	24″	13 5/16″	**DS4LC1DSV30L**	$1,707.	$1,844.	$1,912.
	36″	24″	13 5/16″	**DS4LC1DSV36L**	1,707.	1,844.	1,912.
	42″	24″	13 5/16″	**DS4LC1DSV42L**	1,707.	1,844.	1,912.
	48″	24″	13 5/16″	**DS4LC1DSV48L**	1,741.	1,881.	1,950.
	54″	24″	13 5/16″	**DS4LC1DSV54L**	1,775.	1,917.	1,989.
	60″	24″	13 5/16″	**DS4LC1DSV60L**	1,809.	1,955.	2,029.
	66″	24″	13 5/16″	**DS4LC1DSV66L**	1,842.	1,991.	2,067.
	72″	24″	13 5/16″	**DS4LC1DSV72L**	1,876.	2,029.	2,106.
Credenza with Laminate Sliding Door and Drawer	30″	24″	13 5/16″	**DS4LC1DLV30L**	2,004.	2,171.	2,255.
	36″	24″	13 5/16″	**DS4LC1DLV36L**	2,004.	2,171.	2,255.
	42″	24″	13 5/16″	**DS4LC1DLV42L**	2,004.	2,171.	2,255.
	48″	24″	13 5/16″	**DS4LC1DLV48L**	2,039.	2,208.	2,294.
	54″	24″	13 5/16″	**DS4LC1DLV54L**	2,074.	2,247.	2,333.
	60″	24″	13 5/16″	**DS4LC1DLV60L**	2,108.	2,285.	2,373.
	66″	24″	13 5/16″	**DS4LC1DLV66L**	2,140.	2,323.	2,412.
	72″	24″	13 5/16″	**DS4LC1DLV72L**	2,175.	2,360.	2,452.
Credenza with Veneer Sliding Door and Drawer	30″	24″	13 5/16″	**DS4LC1DVV30L**	2,093.	2,267.	2,357.
	36″	24″	13 5/16″	**DS4LC1DVV36L**	2,093.	2,267.	2,357.
	42″	24″	13 5/16″	**DS4LC1DVV42L**	2,093.	2,267.	2,357.
	48″	24″	13 5/16″	**DS4LC1DVV48L**	2,133.	2,314.	2,403.
	54″	24″	13 5/16″	**DS4LC1DVV54L**	2,174.	2,359.	2,451.
	60″	24″	13 5/16″	**DS4LC1DVV60L**	2,216.	2,403.	2,498.
	66″	24″	13 5/16″	**DS4LC1DVV66L**	2,257.	2,449.	2,545.
	72″	24″	13 5/16″	**DS4LC1DVV72L**	2,299.	2,494.	2,590.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door and a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Drawer/Door finish (laminate and veneer only)
5. Drawer/Door edge finish (laminate only)

Order Code

Credenza with a Sliding Door and a Drawer:

Example:	**DS4LC1SV42L /117/Y319**
DS4LC1 SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with a Sliding Door and a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door and a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct $40 from the list price.

Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth - Specifications

Double Depth Credenzas
Dividends Horizon double depth credenzas are designed for use in various applications, including personal storage in shared workstations, space division in the open plan, and impromptu collaboration areas. Double depth credenzas offer a more unified aesthetic option, with the seamless top and end panels, when back-to-back credenzas are required.

Double depth credenzas consist of a seamless laminate or veneer top option with a shelf and binder storage area. Credenzas have four configuration options: sliding door only, drawer only, sliding door and drawer combination, and open shelves without a sliding door or a drawer. Double depth credenzas have the same configuration on both sides.

The sliding door is a single steel, laminate, or veneer door with a handle that conceals half the width of the binder storage area. A single drawer may be specified for the location above the shelf. The drawer may be installed in either the right or left location, the drawer location does not need to be specified when ordered. When a drawer is specified along with a sliding door, the drawer front and sliding door finishes are the same. A single full back panel divides the front and back sections of the credenza.

24 inch wide credenzas do not include a center vertical septum and are only available as open shelf units, without a sliding door or drawer. Units are shipped knocked down and may be specified with or without locks. Dividends Horizon credenzas are available in all Knoll Core finishes. Legacy finishes are not available.

Available Sizes
Heights: 24 inches
Depth: 26-5/8 inches
Widths: 24 – 72 inches

Construction

- **Top**:
  - Laminate: 1-1/4 inch thick particle board with high pressure laminate on top and a paper backer on the underside with 2mm edgeband
  - Veneer: 1-1/4 inch thick particle board with 0.6mm veneer on top and edge.
- **End Panels:** 16-gauge painted steel
- **Back Panel:** 20-gauge painted steel
- **Door**:
  - Steel: 20-gauge panted steel
  - Laminate: 3/4 inch thick particle board with high pressure laminate on the outside and a paper backer on the inside with 1mm edgeband
  - Veneer 3/4 inch thick particle board with 0.6mm thick veneer on top and edge
- **Fixed Shelf**: 16-gauge painted steel
- **Door Handle:** painted aluminum (same color as case)

Interior Dimensions
Heights: 12-1/2 inches for the lower section, 5-7/8 inches for the upper section
Depth: 12-1/16 inches

Locks
Locks are standard on credenzas with doors and/or drawers and are keyed randomly unless otherwise specified. All locks are factory installed and have a black finish. Credenzas can also be specified without locks if required.

Double Depth Credenza with Open Shelves



Double Depth Credenza with a Drawer



Double Depth Credenza with a Sliding Door



Double Depth Credenza with a Drawer and a Sliding Door



Credenzas
Double Depth with Laminate Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza without Door	24″	24″	26⅝″	**DS4LC2ANL24N**	$1,721.	$1,889.	$1,978.
	30″	24″	26⅝″	**DS4LC2ANL30N**	1,721.	1,889.	1,978.
	36″	24″	26⅝″	**DS4LC2ANL36N**	1,721.	1,889.	1,978.
	42″	24″	26⅝″	**DS4LC2ANL42N**	1,721.	1,889.	1,978.
	48″	24″	26⅝″	**DS4LC2ANL48N**	1,767.	1,944.	2,033.
	54″	24″	26⅝″	**DS4LC2ANL54N**	1,906.	2,096.	2,194.
	60″	24″	26⅝″	**DS4LC2ANL60N**	1,908.	2,098.	2,196.
	66″	24″	26⅝″	**DS4LC2ANL66N**	1,973.	2,170.	2,268.
	72″	24″	26⅝″	**DS4LC2ANL72N**	2,039.	2,245.	2,342.
Credenza with Steel Sliding Door	30″	24″	26⅝″	**DS4LC2BSL30L**	1,998.	2,200.	2,300.
	36″	24″	26⅝″	**DS4LC2BSL36L**	1,998.	2,200.	2,300.
	42″	24″	26⅝″	**DS4LC2BSL42L**	1,998.	2,200.	2,300.
	48″	24″	26⅝″	**DS4LC2BSL48L**	2,050.	2,256.	2,358.
	54″	24″	26⅝″	**DS4LC2BSL54L**	2,225.	2,449.	2,556.
	60″	24″	26⅝″	**DS4LC2BSL60L**	2,229.	2,451.	2,563.
	66″	24″	26⅝″	**DS4LC2BSL66L**	2,300.	2,530.	2,643.
	72″	24″	26⅝″	**DS4LC2BSL72L**	2,364.	2,601.	2,718.
Credenza with Laminate Sliding Door	30″	24″	26⅝″	**DS4LC2BLL30L**	2,786.	3,061.	3,197.
	36″	24″	26⅝″	**DS4LC2BLL36L**	2,786.	3,061.	3,197.
	42″	24″	26⅝″	**DS4LC2BLL42L**	2,786.	3,061.	3,197.
	48″	24″	26⅝″	**DS4LC2BLL48L**	2,876.	3,155.	3,300.
	54″	24″	26⅝″	**DS4LC2BLL54L**	2,962.	3,251.	3,397.
	60″	24″	26⅝″	**DS4LC2BLL60L**	3,049.	3,349.	3,498.
	66″	24″	26⅝″	**DS4LC2BLL66L**	3,136.	3,443.	3,599.
	72″	24″	26⅝″	**DS4LC2BLL72L**	3,223.	3,541.	3,698.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Door finish (laminate and veneer only)
6. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish

Order Code

Credenza with a Sliding Door:

Example:	**DS4LC2BSL42L /117/118/117**
DS4LC2B LL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Credenza without a Sliding Door:

Example:	**DS4LC2ANL42N /117/118/117**
DS4LC2A NL42N	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Laminate Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Veneer Sliding Door	30″	24″	26⅝″	**DS4LC2BVL30L**	$2,962.	$3,251.	$3,399.
	36″	24″	26⅝″	**DS4LC2BVL36L**	2,962.	3,251.	3,399.
	42″	24″	26⅝″	**DS4LC2BVL42L**	2,962.	3,251.	3,399.
	48″	24″	26⅝″	**DS4LC2BVL48L**	3,063.	3,365.	3,516.
	54″	24″	26⅝″	**DS4LC2BVL54L**	3,164.	3,473.	3,631.
	60″	24″	26⅝″	**DS4LC2BVL60L**	3,263.	3,586.	3,747.
	66″	24″	26⅝″	**DS4LC2BVL66L**	3,365.	3,694.	3,864.
	72″	24″	26⅝″	**DS4LC2BVL72L**	3,465.	3,809.	3,979.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Door finish (laminate and veneer only)
6. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish

Order Code

Credenza with a Sliding Door:

Example:	**DS4LC2BSL42L /117/118/117**
DS4LC2B LL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Credenza without a Sliding Door:

Example:	**DS4LC2ANL42N /117/118/117**
DS4LC2A NL42N	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Laminate Top Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Drawer	30″	24″	26⅝″	**DS4LC2CSL30L**	$2,358.	$2,526.	$2,614.
	36″	24″	26⅝″	**DS4LC2CSL36L**	2,358.	2,526.	2,614.
	42″	24″	26⅝″	**DS4LC2CSL42L**	2,358.	2,526.	2,614.
	48″	24″	26⅝″	**DS4LC2CSL48L**	2,404.	2,580.	2,670.
	54″	24″	26⅝″	**DS4LC2CSL54L**	2,542.	2,733.	2,830.
	60″	24″	26⅝″	**DS4LC2CSL60L**	2,544.	2,735.	2,833.
	66″	24″	26⅝″	**DS4LC2CSL66L**	2,610.	2,807.	2,905.
	72″	24″	26⅝″	**DS4LC2CSL72L**	2,676.	2,882.	2,979.
Credenza with Laminate Drawer	30″	24″	26⅝″	**DS4LC2CLL30L**	2,714.	2,882.	2,971.
	36″	24″	26⅝″	**DS4LC2CLL36L**	2,714.	2,882.	2,971.
	42″	24″	26⅝″	**DS4LC2CLL42L**	2,714.	2,882.	2,971.
	48″	24″	26⅝″	**DS4LC2CLL48L**	2,760.	2,937.	3,025.
	54″	24″	26⅝″	**DS4LC2CLL54L**	2,898.	3,090.	3,187.
	60″	24″	26⅝″	**DS4LC2CLL60L**	2,900.	3,092.	3,189.
	66″	24″	26⅝″	**DS4LC2CLL66L**	2,966.	3,164.	3,261.
	72″	24″	26⅝″	**DS4LC2CLL72L**	3,031.	3,237.	3,336.
Credenza with Veneer Drawer	30″	24″	26⅝″	**DS4LC2CVL30L**	2,790.	2,958.	3,047.
	36″	24″	26⅝″	**DS4LC2CVL36L**	2,790.	2,958.	3,047.
	42″	24″	26⅝″	**DS4LC2CVL42L**	2,790.	2,958.	3,047.
	48″	24″	26⅝″	**DS4LC2CVL48L**	2,837.	3,013.	3,102.
	54″	24″	26⅝″	**DS4LC2CVL54L**	2,975.	3,166.	3,263.
	60″	24″	26⅝″	**DS4LC2CVL60L**	2,977.	3,168.	3,265.
	66″	24″	26⅝″	**DS4LC2CVL66L**	3,043.	3,239.	3,338.
	72″	24″	26⅝″	**DS4LC2CVL72L**	3,109.	3,315.	3,411.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Drawer finish (laminate and veneer only)
6. Drawer edge finish (laminate only)

Order Code

Credenza with a Drawer:

Example:	**DS4LC2CSL42L /117/118/117**
DS4LC2C SL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Laminate Top With a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DSL30L**	$2,635.	$2,837.	$2,937.
	36″	24″	26⅝″	**DS4LC2DSL36L**	2,635.	2,837.	2,937.
	42″	24″	26⅝″	**DS4LC2DSL42L**	2,635.	2,837.	2,937.
	48″	24″	26⅝″	**DS4LC2DSL48L**	2,686.	2,892.	2,994.
	54″	24″	26⅝″	**DS4LC2DSL54L**	2,861.	3,086.	3,193.
	60″	24″	26⅝″	**DS4LC2DSL60L**	2,865.	3,088.	3,199.
	66″	24″	26⅝″	**DS4LC2DSL66L**	2,937.	3,166.	3,280.
	72″	24″	26⅝″	**DS4LC2DSL72L**	3,000.	3,237.	3,355.
Credenza with Laminate Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DLL30L**	3,423.	3,698.	3,834.
	36″	24″	26⅝″	**DS4LC2DLL36L**	3,423.	3,698.	3,834.
	42″	24″	26⅝″	**DS4LC2DLL42L**	3,423.	3,698.	3,834.
	48″	24″	26⅝″	**DS4LC2DLL48L**	3,512.	3,791.	3,937.
	54″	24″	26⅝″	**DS4LC2DLL54L**	3,599.	3,887.	4,033.
	60″	24″	26⅝″	**DS4LC2DLL60L**	3,685.	3,985.	4,134.
	66″	24″	26⅝″	**DS4LC2DLL66L**	3,773.	4,080.	4,235.
	72″	24″	26⅝″	**DS4LC2DLL72L**	3,859.	4,178.	4,334.
Credenza with Veneer Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DVL30L**	3,599.	3,887.	4,036.
	36″	24″	26⅝″	**DS4LC2DVL36L**	3,599.	3,887.	4,036.
	42″	24″	26⅝″	**DS4LC2DVL42L**	3,599.	3,887.	4,036.
	48″	24″	26⅝″	**DS4LC2DVL48L**	3,700.	4,002.	4,153.
	54″	24″	26⅝″	**DS4LC2DVL54L**	3,801.	4,110.	4,267.
	60″	24″	26⅝″	**DS4LC2DVL60L**	3,900.	4,223.	4,384.
	66″	24″	26⅝″	**DS4LC2DVL66L**	4,002.	4,330.	4,500.
	72″	24″	26⅝″	**DS4LC2DVL72L**	4,101.	4,445.	4,615.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door and a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Top edge finish
5. Drawer/Door finish (laminate and veneer only)
6. Drawer/Door edge finish (laminate only)

Order Code

Credenza with a Sliding Door and a Drawer:

Example:	**DS4LC2DSL42L /117/118/117**
DS4LC2D SL42L	Pattern Number
117	Dark grey paint
118	Bright white top
117	Dark grey top edge

Included with:

Credenza with a Sliding Door and a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door and a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $80 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza without Door	24″	24″	26 5/8″	**DS4LC2ANV24N**	$2,633.	$2,896.	$3,027.
	30″	24″	26 5/8″	**DS4LC2ANV30N**	2,633.	2,896.	3,027.
	36″	24″	26 5/8″	**DS4LC2ANV36N**	2,633.	2,896.	3,027.
	42″	24″	26 5/8″	**DS4LC2ANV42N**	2,633.	2,896.	3,027.
	48″	24″	26 5/8″	**DS4LC2ANV48N**	2,696.	2,966.	3,100.
	54″	24″	26 5/8″	**DS4LC2ANV54N**	2,758.	3,034.	3,174.
	60″	24″	26 5/8″	**DS4LC2ANV60N**	2,824.	3,104.	3,243.
	66″	24″	26 5/8″	**DS4LC2ANV66N**	2,886.	3,174.	3,321.
	72″	24″	26 5/8″	**DS4LC2ANV72N**	2,950.	3,241.	3,391.
Credenza with Steel Sliding Door	30″	24″	26 5/8″	**DS4LC2BSV30L**	2,777.	3,051.	3,187.
	36″	24″	26 5/8″	**DS4LC2BSV36L**	2,777.	3,051.	3,187.
	42″	24″	26 5/8″	**DS4LC2BSV42L**	2,777.	3,051.	3,187.
	48″	24″	26 5/8″	**DS4LC2BSV48L**	2,845.	3,126.	3,263.
	54″	24″	26 5/8″	**DS4LC2BSV54L**	2,914.	3,197.	3,342.
	60″	24″	26 5/8″	**DS4LC2BSV60L**	2,979.	3,273.	3,421.
	66″	24″	26 5/8″	**DS4LC2BSV66L**	3,047.	3,346.	3,496.
	72″	24″	26 5/8″	**DS4LC2BSV72L**	3,115.	3,421.	3,575.
Credenza with Laminate Sliding Door	30″	24″	26 5/8″	**DS4LC2BLV30L**	3,374.	3,706.	3,872.
	36″	24″	26 5/8″	**DS4LC2BLV36L**	3,374.	3,706.	3,872.
	42″	24″	26 5/8″	**DS4LC2BLV42L**	3,374.	3,706.	3,872.
	48″	24″	26 5/8″	**DS4LC2BLV48L**	3,441.	3,781.	3,951.
	54″	24″	26 5/8″	**DS4LC2BLV54L**	3,512.	3,857.	4,029.
	60″	24″	26 5/8″	**DS4LC2BLV60L**	3,579.	3,933.	4,110.
	66″	24″	26 5/8″	**DS4LC2BLV66L**	3,645.	4,008.	4,189.
	72″	24″	26 5/16″	**DS4LC2BLV72L**	3,716.	4,082.	4,267.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer)
5. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish

Order Code

Credenza with a Sliding Door:

Example:	**DS4LC2BSV42L /117/Y319**
DS4LC2B SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Credenza without a Sliding Door:

Example:	**DS4LC2ASV42L /117/Y319**
DS4LC2A SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without a Sliding Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Veneer Sliding Door	30″	24″	26⅝″	**DS4LC2BVV30L**	$3,550.	$3,898.	$4,076.
	36″	24″	26⅝″	**DS4LC2BVV36L**	3,550.	3,898.	4,076.
	42″	24″	26⅝″	**DS4LC2BVV42L**	3,550.	3,898.	4,076.
	48″	24″	26⅝″	**DS4LC2BVV48L**	3,631.	3,991.	4,169.
	54″	24″	26⅝″	**DS4LC2BVV54L**	3,714.	4,080.	4,265.
	60″	24″	26⅝″	**DS4LC2BVV60L**	3,796.	4,169.	4,359.
	66″	24″	26⅝″	**DS4LC2BVV66L**	3,876.	4,260.	4,454.
	72″	24″	26⅝″	**DS4LC2BVV72L**	3,961.	4,351.	4,544.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer)
5. Door edge finish (laminate only)

Credenza without a Sliding Door:

1. Pattern number
2. Paint finish
3. Top finish

Order Code

Credenza with a Sliding Door:

Example:	**DS4LC2BSV42L /117/Y319**
DS4LC2B SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Credenza without a Sliding Door:

Example:	**DS4LC2ASV42L /117/Y319**
DS4LC2A SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with or without Sliding Door:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with or without a Sliding Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Veneer Top Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Drawer	30″	24″	26⅝″	**DS4LC2CSV30L**	$3,269.	$3,533.	$3,664.
	36″	24″	26⅝″	**DS4LC2CSV36L**	3,269.	3,533.	3,664.
	42″	24″	26⅝″	**DS4LC2CSV42L**	3,269.	3,533.	3,664.
	48″	24″	26⅝″	**DS4LC2CSV48L**	3,332.	3,603.	3,737.
	54″	24″	26⅝″	**DS4LC2CSV54L**	3,395.	3,671.	3,811.
	60″	24″	26⅝″	**DS4LC2CSV60L**	3,461.	3,741.	3,880.
	66″	24″	26⅝″	**DS4LC2CSV66L**	3,523.	3,811.	3,957.
	72″	24″	26⅝″	**DS4LC2CSV72L**	3,586.	3,878.	4,027.
Credenza with Laminate Drawer	30″	24″	26⅝″	**DS4LC2CLV30L**	3,626.	3,889.	4,021.
	36″	24″	26⅝″	**DS4LC2CLV36L**	3,626.	3,889.	4,021.
	42″	24″	26⅝″	**DS4LC2CLV42L**	3,626.	3,889.	4,021.
	48″	24″	26⅝″	**DS4LC2CLV48L**	3,687.	3,959.	4,092.
	54″	24″	26⅝″	**DS4LC2CLV54L**	3,751.	4,027.	4,167.
	60″	24″	26⅝″	**DS4LC2CLV60L**	3,817.	4,097.	4,237.
	66″	24″	26⅝″	**DS4LC2CLV66L**	3,878.	4,167.	4,314.
	72″	24″	26⅝″	**DS4LC2CLV72L**	3,943.	4,235.	4,384.
Credenza with Veneer Drawer	30″	24″	26⅝″	**DS4LC2CVV30L**	3,702.	3,966.	4,097.
	36″	24″	26⅝″	**DS4LC2CVV36L**	3,702.	3,966.	4,097.
	42″	24″	26⅝″	**DS4LC2CVV42L**	3,702.	3,966.	4,097.
	48″	24″	26⅝″	**DS4LC2CVV48L**	3,765.	4,036.	4,169.
	54″	24″	26⅝″	**DS4LC2CVV54L**	3,827.	4,104.	4,244.
	60″	24″	26⅝″	**DS4LC2CVV60L**	3,893.	4,174.	4,314.
	66″	24″	26⅝″	**DS4LC2CVV66L**	3,955.	4,244.	4,390.
	72″	24″	26⅝″	**DS4LC2CVV72L**	4,019.	4,312.	4,460.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Door finish (laminate and veneer only)
5. Door edge finish (laminate only)

Order Code

Credenza with a Drawer:

Example:	**DS4LC2CSV42L /117/Y319**
DS4LC2C SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $40 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Double Depth with Veneer Top With a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DSV30L**	$3,413.	$3,687.	$3,823.
	36″	24″	26⅝″	**DS4LC2DSV36L**	3,413.	3,687.	3,823.
	42″	24″	26⅝″	**DS4LC2DSV42L**	3,413.	3,687.	3,823.
	48″	24″	26⅝″	**DS4LC2DSV48L**	3,481.	3,763.	3,900.
	54″	24″	26⅝″	**DS4LC2DSV54L**	3,550.	3,834.	3,979.
	60″	24″	26⅝″	**DS4LC2DSV60L**	3,615.	3,910.	4,057.
	66″	24″	26⅝″	**DS4LC2DSV66L**	3,683.	3,983.	4,132.
	72″	24″	26⅝″	**DS4LC2DSV72L**	3,751.	4,057.	4,212.
Credenza with Laminate Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DLV30L**	4,011.	4,342.	4,508.
	36″	24″	26⅝″	**DS4LC2DLV36L**	4,011.	4,342.	4,508.
	42″	24″	26⅝″	**DS4LC2DLV42L**	4,011.	4,342.	4,508.
	48″	24″	26⅝″	**DS4LC2DLV48L**	4,078.	4,418.	4,588.
	54″	24″	26⅝″	**DS4LC2DLV54L**	4,149.	4,494.	4,666.
	60″	24″	26⅝″	**DS4LC2DLV60L**	4,216.	4,569.	4,746.
	66″	24″	26⅝″	**DS4LC2DLV66L**	4,282.	4,644.	4,826.
	72″	24″	26⅝″	**DS4LC2DLV72L**	4,353.	4,718.	4,904.
Credenza with Veneer Sliding Door and Drawer	30″	24″	26⅝″	**DS4LC2DVV30L**	4,187.	4,534.	4,712.
	36″	24″	26⅝″	**DS4LC2DVV36L**	4,187.	4,534.	4,712.
	42″	24″	26⅝″	**DS4LC2DVV42L**	4,187.	4,534.	4,712.
	48″	24″	26⅝″	**DS4LC2DVV48L**	4,267.	4,628.	4,806.
	54″	24″	26⅝″	**DS4LC2DVV54L**	4,351.	4,716.	4,902.
	60″	24″	26⅝″	**DS4LC2DVV60L**	4,432.	4,806.	4,996.
	66″	24″	26⅝″	**DS4LC2DVV66L**	4,512.	4,897.	5,090.
	72″	24″	26⅝″	**DS4LC2DVV72L**	4,598.	4,987.	5,181.

Dimensions listed under w h d are actual to the nearest 1/16″

Ordering Information

Credenza with a Sliding Door and a Drawer:

1. Pattern number
2. Paint finish
3. Top finish
4. Drawer/Door finish (laminate and veneer only)
5. Drawer/Door edge finish (laminate only)

Order Code

Credenza with a Sliding Door and a Drawer:

Example:	**DS4LC2SV42L /117/Y319**
DS4LC2D SV42L	Pattern Number
117	Dark grey paint
Y319	Cherry Techwood top

Included with:

Credenza with a Sliding Door and a Drawer:

Note: Credenzas are only available in Knoll core finishes.

Options

Credenza with a Sliding Door and a Drawer:

Lock/No lock option
For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct $80 from the list price.

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

This page intentionally left blank

Flip-up Door Overdesk and Tackboards
Specifications

Flip-up Door Overdesk Units
Series 1 and Series 2 freestanding flip-up door overdesk units mount atop freestanding desks to provide overhead storage.

Pass-through communications or visual privacy can be obtained with a removeable privacy screen. When installed on freestanding desks, overdesks match up to 64" high panels to provide a consistent height within the facility.

Flip-up door overdesk units consist of an overhead cabinet with or without lock and enclosed back along with desk-mount stanchions. Tackable privacy screens are optional and mount between the stanchions. Overdesks 30" to 48" wide have single overhead doors while units 60" and 72" wide have double doors.

Available Sizes
- Height: 37 1/2"
- Depth: 13 1/2"
- Widths: 36", 42", 48", 54", 60", 66" and 72"

Flip-up Door Overdesk Attachment
Flip-up door overdesks can be mounted to both single and double pedestal desks. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper floorstanding worksurface support is used.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Construction
- Outer cabinet: 20-gauge steel
- Cabinet top and lower shelf: 18-gauge for 36", 42" and 48" widths and 16-gauge for 60" and 72" widths
- Overhead doors: 20-gauge painted steel
- Door end trim: Color injected, molded plastic
- Overhead door suspension: Steel ball-bearing
- Outer stanchions: 14-gauge steel
- Inner stanchions: 20-gauge steel

Wire Management
Vertical wire management channels for task light wires are located inside stanchions and are concealed by the inner stanchion.

Locks
Locks are standard on overdesks and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores (K001-K250). All locks are factory-installed and are black finish. Overdesks can also be specified without locks if required.

Optional lock retrofit kits are available for field installation in flip-up door overdesks without locks at a later date if required.

Tackable Privacy Screen
Flip-up door overdesk privacy screen provides visual privacy and a tackable surface. Privacy screens mount between flip-up door overdesk stanchions and are available in all overdesk widths.

Privacy screen construction is similar to the fabric insert used on Dividends panel frames. Two fabric wrapped inserts sandwich a honeycomb core providing both tackable and acoustic features.

Note: Tackable privacy screens are for use with Series 1 and Series 2 flip-up door overdesks only. They are not compatible with sliding door overdesks.

"Touchdown" Overhead Cabinets
Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up door overdesk.

Task Lights
Series 1 and 2 flip-up door overdesks will accept task lights. Task lights must be ordered separately.

Flip-Up Door Overdesk Applications



Overdesk units can span a single worksurface or two worksurfaces in "L" configuration.

Flip-Up Door Overdesk Unit Components



Flip-Up Door Overdesk Size Configurations



Flip-up Door Overdesk and Tackboards
Dividends and Series 2

description	w	d	h	pattern no.	black	P1	P2	P3	V1-P1	V1-P2	V1-P3
Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions) 	36″	13 ½″	15″	**DD2OD 36L**	n/a	$755.	$835.	$874.	n/a	n/a	n/a
	42″	13 ½″	15″	**DD2OD 42L**	n/a	795.	877.	919.	n/a	n/a	n/a
	48″	13 ½″	15″	**DD2OD 48L**	n/a	819.	903.	948.	n/a	n/a	n/a
	54″	13 ½″	15″	**DD2OD 54L**	n/a	1,000.	1,099.	1,155.	n/a	n/a	n/a
	60″	13 ½″	15″	**DD2OD 60L**	n/a	1,000.	1,099.	1,155.	n/a	n/a	n/a
	66″	13 ½″	15″	**DD2OD 66L**	n/a	1,026.	1,129.	1,187.	n/a	n/a	n/a
	72″	13 ½″	15″	**DD2OD 72L**	n/a	1,026.	1,129.	1,187.	n/a	n/a	n/a
Series 2 Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions) 	36″	13 ½″	15″	**DS2OD 36L**	n/a	1,070.	1,231.	1,285.	1,306.	1,470.	1,521.
	42″	13 ½″	15″	**DS2OD 42L**	n/a	1,092.	1,256.	1,310.	1,342.	1,504.	1,560.
	48″	13 ½″	15″	**DS2OD 48L**	n/a	1,106.	1,271.	1,325.	1,391.	1,558.	1,610.
	54″	13 ½″	15″	**DS2OD 54L**	n/a	1,347.	1,549.	1,619.	1,785.	1,989.	2,055.
	60″	13 ½″	15″	**DS2OD 60L**	n/a	1,347.	1,549.	1,619.	1,785.	1,989.	2,055.
	66″	13 ½″	15″	**DS2OD 66L**	n/a	1,391.	1,601.	1,668.	1,848.	2,057.	2,125.
	72″	13 ½″	15″	**DS2OD 72L**	n/a	1,391.	1,601.	1,668.	1,848.	2,057.	2,125.
Vertical Dividers Package of 4				**DS1 VD**	93.	97.	102.	108.			

Ordering Information

Overdesk Cabinet

1. Pattern Number
2. Paint Finish
3. Door End Cap Finish

Order Code

Overdesk Cabinet

Example:	**DD2OD 48L, 613, 113**
DD2OD 48L	Pattern Number
613	Silver paint finish
113	Dark grey door end cap finish

Included with:

Overdesk Cabinet

Stanchion mount overdesk cabinets include an enclosed back.

Options

Overdesk Cabinet
To specify overhead cabinet without locks, replace the **"L"** suffix from the pattern number with **"N"**. For 30″ to 48″ wide overdesk units, **Deduct $20** For 54″, 60″, 66″ and 72″ wide overdesk units, **Deduct $40**

To specify Touchdown overhead cabinet, add **"E"** as the 2nd to last digit of the pattern number *Example:***DS3PML48EL (Add $157 for cabinet widths of 48″ or less. Add $314 for cabinet widths of 54″ or greater).**

Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Flip-up Door Overdesk and Tackboards
Dividends and Series 2 Tackboard

description	w	d	h	pattern no.	grade 10	15	20	25	30	35	40	45
Flip-Up Door Overdesk Tackable Privacy Screen (for Dividends and Series 2 Overdesks)	36″	18″	20″	**DD3 PS36**	$269.	$277.	$291.	$296.	$303.	$308.	$314.	$323.
	42″	24″	20″	**DD3 PS42**	281.	291.	304.	309.	320.	325.	330.	339.
	48″	30″	20″	**DD3 PS48**	293.	301.	314.	322.	330.	337.	342.	350.
	54″	36″	20″	**DD3 PS54**	313.	323.	339.	345.	353.	358.	368.	375.
	60″	42″	20″	**DD3 PS60**	313.	323.	339.	345.	353.	358.	368.	375.
	66″	42″	20″	**DD3 PS66**	339.	347.	366.	371.	381.	387.	397.	405.
	72″	48″	20″	**DD3 PS72**	339.	347.	366.	371.	381.	387.	397.	405.

Ordering Information

Overdesk Tackable Privacy Screen

1. Pattern Number
2. Fabric

Order Code

Overdesk Tackable Privacy Screen

Example:	**DD3 PS48, W351-3**
DD3 PS48	Pattern Number
W351-3	Foundation Corn Silk

Included with:

Overdesk Tackable Privacy Screen

Options

Note: Flip-up Door overdesk tackable privacy screen is for use with Dividends and Series 2 Flip-up door overheads.

This page intentionally left blank

Sliding Door Overdesks
Specifications

Sliding Door Overdesks
The rectilinear door profile of the sliding door overdesk was designed to complement the flat profile trim details of the Dividends Horizon system. Sliding door overdesks can be used in paneled workstation configurations or freestanding office applications.

Sliding door overdesks mount atop worksurfaces to provide overhead storage. When installed on a worksurface, sliding door overdesks match up to 57" and 64" high panels to provide a consistent height within the facility. 14" or 21" high sliding door overdesks consist of a top, shelf, mid cabinet septum, end panels/stanchions, and a door with a handle.

14" high cabinets and 21" high cabinets with full doors are standard with fully enclosed backs behind the stoarge area. No door units and 21" high cabinets with partial doors have a partial or full back option available. Partial backs cover the upper storage section of the cabinet. Full backs enclose both the upper and lower storage section of the cabinet.

21" high cabinets are able to be specified with a full or partial door. A partial door covers the upper section of the cabinet. A full door covers both the upper and lower section of the cabinet.

Available Sizes
- Height: 14" and 21"
- Depth: 13-1/2"
- Widths: 30", 36", 42", 48", 60", 66", and 72"

Construction
- **Horizontal top and shelf:** 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted steel
- **Sliding door:**
  - Steel: 20-gauge painted steel
  - Laminate: 3/4" particle board with high pressure laminate on the outside and a paper backer on the inside. 1mm edgeband.
  - Veneer: 3/4" thick partcle board with 0.6mm thick veneer on top and edge.
- **End panels/stanchions:** 16-gauge painted steel
- **Sliding door mechanism:** integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Fixed Shelf:** 16-gauge painted steel
- **Door handle:** painted aluminum (same color as case)
- **Back panel:** 20-gauge painted steel

Interior Dimensions
The interior dimensions of sliding door overdesks are:
- Depth: 12 1/4"
- Usable interior height: 12-1/2"high for 14"H cabinets and upper portion of 21"H cabinets; 6-1/8"H for lower portion of 21"H cabinets.
- Width: 1" shorter than exterior width

Overdesk Attachment
Overdesks can be mounted to both single and double pedestal desks as well as panel hung worksurfaces. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper worksurface support is used.

Dividends Horizon Series 3 Overdesk units are sized to the nominal dimension, and are designed for use on the width dimension of Dividends Horizon rectangular worksurfaces.

Series 3 overheads are not compatible with use on extended corner worksurfaces, or a combination of other worksurfaces that are less than the nominal dimension.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Task Lights
Sliding door overdesks will accept task lights. Task lights must be ordered separately.

Locks
Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are a black finish. Overdesks can also be specified without locks if required.

Note: Sliding door overdesks are only available in Knoll Core finishes.

Sliding Door Overdesks



Interior Dimensions for 14"H Overhead

Front View, Interior Height



Top View, Interior Height



Interior Dimensions for 21"H Overhead

Front View, Interior Height



Top View, Interior Height



Sliding Door Overdesks
57″ High Cabinet with 14″ High Storage, 14″ High Door

description	w	pattern no.	P1	P2	P3
57″h Overdesk without Door with 14″ Tall Cabinet	30″	**DS3ODNS1573014**	$898.	$989.	$1,031.
	36″	**DS3ODNS1573614**	916.	1,008.	1,053.
	42″	**DS3ODNS1574214**	933.	1,026.	1,073.
	48″	**DS3ODNS1574814**	967.	1,061.	1,110.
	60″	**DS3ODNS1576014**	1,049.	1,153.	1,205.
	66″	**DS3ODNS1576614**	1,073.	1,182.	1,235.
	72″	**DS3ODNS1577214**	1,090.	1,199.	1,252.
57″h Overdesk with Steel Sliding Door and 14″ Tall Cabinet	30″	**DS3ODSS1573014L**	971.	1,066.	1,112.
	36″	**DS3ODSS1573614L**	993.	1,090.	1,138.
	42″	**DS3ODSS1574214L**	1,016.	1,113.	1,163.
	48″	**DS3ODSS1574814L**	1,048.	1,149.	1,201.
	60″	**DS3ODSS1576014L**	1,145.	1,260.	1,315.
	66″	**DS3ODSS1576614L**	1,175.	1,290.	1,348.
	72″	**DS3ODSS1577214L**	1,191.	1,307.	1,364.
57″h Overdesk with Laminate Sliding Door and 14″ Tall Cabinet	30″	**DS3ODSL1573014L**	1,282.	1,408.	1,472.
	36″	**DS3ODSL1573614L**	1,316.	1,446.	1,511.
	42″	**DS3ODSL1574214L**	1,349.	1,483.	1,549.
	48″	**DS3ODSL1574814L**	1,385.	1,519.	1,587.
	60″	**DS3ODSL1576014L**	1,418.	1,558.	1,626.
	66″	**DS3ODSL1576614L**	1,451.	1,595.	1,667.
	72″	**DS3ODSL1577214L**	1,485.	1,632.	1,706.
57″h Overdesk with Veneer Sliding Door and 14″ Tall Cabinet	30″	**DS3ODSV1573014L**	1,350.	1,484.	1,550.
	36″	**DS3ODSV1573614L**	1,392.	1,527.	1,597.
	42″	**DS3ODSV1574214L**	1,432.	1,571.	1,643.
	48″	**DS3ODSV1574814L**	1,471.	1,615.	1,688.
	60″	**DS3ODSV1576014L**	1,511.	1,660.	1,733.
	66″	**DS3ODSV1576614L**	1,550.	1,703.	1,780.
	72″	**DS3ODSV1577214L**	1,589.	1,746.	1,825.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
57" High Cabinet with 21" High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
57″h without Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODNS( )573021**	$968.	$1,065.	$1,112.
	36″	**DS3ODNS( )573621**	991.	1,090.	1,139.
	42″	**DS3ODNS( )574221**	1,015.	1,114.	1,164.
	48″	**DS3ODNS( )574821**	1,053.	1,159.	1,213.
	60″	**DS3ODNS( )576021**	1,152.	1,268.	1,326.
	66″	**DS3ODNS( )576621**	1,183.	1,302.	1,360.
	72″	**DS3ODNS( )577221**	1,202.	1,321.	1,384.
57″h Steel Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSS2573021FL**	1,105.	1,215.	1,268.
	36″	**DS3ODSS2573621FL**	1,127.	1,238.	1,292.
	42″	**DS3ODSS2574221FL**	1,159.	1,272.	1,329.
	48″	**DS3ODSS2574821FL**	1,223.	1,342.	1,402.
	60″	**DS3ODSS2576021FL**	1,343.	1,475.	1,541.
	66″	**DS3ODSS2576621FL**	1,387.	1,521.	1,592.
	72″	**DS3ODSS2577221FL**	1,416.	1,553.	1,623.
57″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSL2573021FL**	1,449.	1,592.	1,663.
	36″	**DS3ODSL2573621FL**	1,498.	1,647.	1,720.
	42″	**DS3ODSL2574221FL**	1,547.	1,700.	1,776.
	48″	**DS3ODSL2574821FL**	1,597.	1,754.	1,832.
	60″	**DS3ODSL2576021FL**	1,646.	1,809.	1,890.
	66″	**DS3ODSL2576621FL**	1,694.	1,863.	1,945.
	72″	**DS3ODSL2577221FL**	1,743.	1,916.	2,002.
57″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSV2573021FL**	1,523.	1,673.	1,748.
	36″	**DS3ODSV2573621FL**	1,582.	1,739.	1,818.
	42″	**DS3ODSV2574221FL**	1,644.	1,807.	1,886.
	48″	**DS3ODSV2574821FL**	1,702.	1,870.	1,954.
	60″	**DS3ODSV2576021FL**	1,763.	1,936.	2,024.
	66″	**DS3ODSV2576621FL**	1,822.	2,002.	2,092.
	72″	**DS3ODSV2577221FL**	1,882.	2,068.	2,161.









Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021FL, 613**

DS3ODSS	Pattern Number
2573021FL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
57" High Cabinet with 21" High Storage (Partial Height Door)

description	w	pattern no.	P1	P2	P3
57″h Steel Sliding Door Overdesk with 21″ Tall Cabinet 	30″	**DS3ODSS( )573021PL**	$1,105.	$1,215.	$1,268.
	36″	**DS3ODSS( )573621PL**	1,127.	1,238.	1,292.
	42″	**DS3ODSS( )574221PL**	1,159.	1,272.	1,329.
	48″	**DS3ODSS( )574821PL**	1,223.	1,342.	1,402.
	60″	**DS3ODSS( )576021PL**	1,343.	1,475.	1,541.
	66″	**DS3ODSS( )576621PL**	1,387.	1,521.	1,592.
	72″	**DS3ODSS( )577221PL**	1,416.	1,553.	1,623.
57″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet 	30″	**DS3ODSL( )573021PL**	1,441.	1,582.	1,653.
	36″	**DS3ODSL( )573621PL**	1,489.	1,638.	1,709.
	42″	**DS3ODSL( )574221PL**	1,538.	1,689.	1,765.
	48″	**DS3ODSL( )574821PL**	1,585.	1,742.	1,821.
	60″	**DS3ODSL( )576021PL**	1,637.	1,795.	1,877.
	66″	**DS3ODSL( )576621PL**	1,684.	1,850.	1,933.
	72″	**DS3ODSL( )577221PL**	1,732.	1,903.	1,989.
57″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet 	30″	**DS3ODSV( )573021PL**	1,512.	1,661.	1,735.
	36″	**DS3ODSV( )573621PL**	1,566.	1,720.	1,796.
	42″	**DS3ODSV( )574221PL**	1,620.	1,781.	1,861.
	48″	**DS3ODSV( )574821PL**	1,675.	1,841.	1,923.
	60″	**DS3ODSV( )576021PL**	1,730.	1,900.	1,987.
	66″	**DS3ODSV( )576621PL**	1,785.	1,960.	2,049.
	72″	**DS3ODSV( )577221PL**	1,839.	2,022.	2,113.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example:	**DS3ODSS 2573021PL, 613**
DS3ODSS	Pattern Number
2573021PL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract $20.

Back option
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
64″ High Cabinet with 14″ High Storage

description	w	pattern no.	P1	P2	P3
64″h without Sliding Door Overdesk with 14″ Tall Cabinet 	30″	**DS3ODNS1643014**	$930.	$1,022.	$1,067.
	36″	**DS3ODNS1643614**	938.	1,030.	1,076.
	42″	**DS3ODNS1644214**	968.	1,061.	1,108.
	48″	**DS3ODNS1644814**	1,052.	1,154.	1,205.
	60″	**DS3ODNS1646014**	1,084.	1,190.	1,242.
	66″	**DS3ODNS1646614**	1,108.	1,217.	1,271.
	72″	**DS3ODNS1647214**	1,123.	1,233.	1,286.
64″h Steel Sliding Door Overdesk with 14″ Tall Cabinet 	30″	**DS3ODSS1643014L**	981.	1,075.	1,123.
	36″	**DS3ODSS1643614L**	1,002.	1,100.	1,147.
	42″	**DS3ODSS1644214L**	1,024.	1,123.	1,173.
	48″	**DS3ODSS1644814L**	1,056.	1,160.	1,213.
	60″	**DS3ODSS1646014L**	1,155.	1,269.	1,326.
	66″	**DS3ODSS1646614L**	1,187.	1,302.	1,360.
	72″	**DS3ODSS1647214L**	1,199.	1,316.	1,373.
64″h Laminate Sliding Door Overdesk with 14″ Tall Cabinet 	30″	**DS3ODSL1643014L**	1,292.	1,419.	1,483.
	36″	**DS3ODSL1643614L**	1,327.	1,457.	1,521.
	42″	**DS3ODSL1644214L**	1,362.	1,495.	1,563.
	48″	**DS3ODSL1644814L**	1,396.	1,534.	1,603.
	60″	**DS3ODSL1646014L**	1,432.	1,571.	1,643.
	66″	**DS3ODSL1646614L**	1,466.	1,610.	1,683.
	72″	**DS3ODSL1647214L**	1,499.	1,648.	1,721.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example:	**DS3ODSS 2643014FL, 613**
DS3ODSS	Pattern Number
2643014FL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
64″ High Cabinet with 14″ High Storage

description	w	pattern no.	P1	P2	P3
64″h Veneer Sliding Door Overdesk with 14″ Tall Cabinet	30″	**DS3ODSV1643014L**	$1,362.	$1,496.	$1,564.
	36″	**DS3ODSV1643614L**	1,402.	1,541.	1,610.
	42″	**DS3ODSV1644214L**	1,444.	1,585.	1,657.
	48″	**DS3ODSV1644814L**	1,484.	1,629.	1,703.
	60″	**DS3ODSV1646014L**	1,525.	1,674.	1,750.
	66″	**DS3ODSV1646614L**	1,566.	1,719.	1,796.
	72″	**DS3ODSV1647214L**	1,607.	1,763.	1,844.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FL, 613**

DS3ODSS Pattern Number
2643014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
64″ High Cabinet with 21″ High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
64″h without Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODNS( )643021**	$989.	$1,088.	$1,136.
	36″	**DS3ODNS( )643621**	1,005.	1,105.	1,155.
	42″	**DS3ODNS( )644221**	1,030.	1,135.	1,188.
	48″	**DS3ODNS( )644821**	1,097.	1,205.	1,261.
	60″	**DS3ODNS( )646021**	1,203.	1,323.	1,385.
	66″	**DS3ODNS( )646621**	1,242.	1,365.	1,429.
	72″	**DS3ODNS( )647221**	1,270.	1,398.	1,461.
64″h Steel Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSS2643021FL**	1,112.	1,222.	1,275.
	36″	**DS3ODSS2643621FL**	1,135.	1,245.	1,302.
	42″	**DS3ODSS2644221FL**	1,165.	1,279.	1,338.
	48″	**DS3ODSS2644821FL**	1,229.	1,349.	1,411.
	60″	**DS3ODSS2646021FL**	1,349.	1,483.	1,549.
	66″	**DS3ODSS2646621FL**	1,394.	1,532.	1,600.
	72″	**DS3ODSS2647221FL**	1,423.	1,563.	1,632.
64″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSL2643021FL**	1,463.	1,608.	1,680.
	36″	**DS3ODSL2643621FL**	1,512.	1,661.	1,735.
	42″	**DS3ODSL2644221FL**	1,561.	1,714.	1,791.
	48″	**DS3ODSL2644821FL**	1,610.	1,769.	1,848.
	60″	**DS3ODSL2646021FL**	1,659.	1,823.	1,906.
	66″	**DS3ODSL2646621FL**	1,708.	1,877.	1,960.
	72″	**DS3ODSL2647221FL**	1,757.	1,931.	2,019.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example:	**DS3ODSS 2643021FL, 613**
DS3ODSS	Pattern Number
2643021FL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
64″ High Cabinet with 21″ High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
64″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSV2643021FL**	$1,537.	$1,688.	$1,764.
	36″	**DS3ODSV2643621FL**	1,597.	1,754.	1,832.
	42″	**DS3ODSV2644221FL**	1,657.	1,820.	1,901.
	48″	**DS3ODSV2644821FL**	1,715.	1,886.	1,968.
	60″	**DS3ODSV2646021FL**	1,776.	1,950.	2,039.
	66″	**DS3ODSV2646621FL**	1,835.	2,018.	2,108.
	72″	**DS3ODSV2647221FL**	1,895.	2,083.	2,174.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example:	**DS3ODSS 2643021FL, 613**
DS3ODSS	Pattern Number
2643021FL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks
64″ High Cabinet with 21″ High Storage (Partial Height Door)

description	w	pattern no.	P1	P2	P3
64″h Steel Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSS( )643021PL**	$1,112.	$1,222.	$1,275.
	36″	**DS3ODSS( )643621PL**	1,135.	1,245.	1,302.
	42″	**DS3ODSS( )644221PL**	1,165.	1,279.	1,338.
	48″	**DS3ODSS( )644821PL**	1,229.	1,349.	1,411.
	60″	**DS3ODSS( )646021PL**	1,349.	1,483.	1,549.
	66″	**DS3ODSS( )646621PL**	1,394.	1,532.	1,600.
	72″	**DS3ODSS( )647221PL**	1,423.	1,563.	1,632.
64″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSL( )643021PL**	1,453.	1,598.	1,669.
	36″	**DS3ODSL( )643621PL**	1,502.	1,651.	1,724.
	42″	**DS3ODSL( )644221PL**	1,551.	1,705.	1,781.
	48″	**DS3ODSL( )644821PL**	1,600.	1,757.	1,836.
	60″	**DS3ODSL( )646021PL**	1,649.	1,812.	1,893.
	66″	**DS3ODSL( )646621PL**	1,696.	1,865.	1,948.
	72″	**DS3ODSL( )647221PL**	1,745.	1,918.	2,004.
64″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet	30″	**DS3ODSV( )643021PL**	1,525.	1,675.	1,750.
	36″	**DS3ODSV( )643621PL**	1,578.	1,736.	1,814.
	42″	**DS3ODSV( )644221PL**	1,635.	1,794.	1,876.
	48″	**DS3ODSV( )644821PL**	1,689.	1,856.	1,938.
	60″	**DS3ODSV( )646021PL**	1,743.	1,916.	2,000.
	66″	**DS3ODSV( )646621PL**	1,797.	1,976.	2,065.
	72″	**DS3ODSV( )647221PL**	1,852.	2,036.	2,128.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example:	**DS3ODSS 2643021PL, 613**
DS3ODSS	Pattern Number
2643021PL	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
57″ High Cabinet with 14″ High Storage, 14″ High Door

description	w	pattern no.	P1	P2	P3
57″h Overdesk without Door with 14″ Tall Cabinet with tackboard 	30″	**DS3ODNS1573014T**	$1,185.	$1,276.	$1,318.
	36″	**DS3ODNS1573614T**	1,210.	1,302.	1,347.
	42″	**DS3ODNS1574214T**	1,244.	1,337.	1,384.
	48″	**DS3ODNS1574814T**	1,287.	1,381.	1,430.
	60″	**DS3ODNS1576014T**	1,392.	1,496.	1,548.
	66″	**DS3ODNS1576614T**	1,416.	1,525.	1,578.
	72″	**DS3ODNS1577214T**	1,460.	1,569.	1,622.
57″h Overdesk with Steel Sliding Door and 14″ Tall Cabinet with tackboard 	30″	**DS3ODSS1573014LT**	1,258.	1,353.	1,399.
	36″	**DS3ODSS1573614LT**	1,287.	1,384.	1,432.
	42″	**DS3ODSS1574214LT**	1,327.	1,424.	1,474.
	48″	**DS3ODSS1574814LT**	1,368.	1,469.	1,521.
	60″	**DS3ODSS1576014LT**	1,488.	1,603.	1,658.
	66″	**DS3ODSS1576614LT**	1,518.	1,633.	1,691.
	72″	**DS3ODSS1577214LT**	1,561.	1,677.	1,734.
57″h Overdesk with Laminate Sliding Door and 14″ Tall Cabinet with tackboard 	30″	**DS3ODSL1573014LT**	1,569.	1,695.	1,759.
	36″	**DS3ODSL1573614LT**	1,610.	1,739.	1,805.
	42″	**DS3ODSL1574214LT**	1,660.	1,794.	1,860.
	48″	**DS3ODSL1574814LT**	1,705.	1,839.	1,907.
	60″	**DS3ODSL1576014LT**	1,761.	1,901.	1,969.
	66″	**DS3ODSL1576614LT**	1,794.	1,938.	2,010.
	72″	**DS3ODSL1577214LT**	1,855.	2,002.	2,076.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
57″ High Cabinet with 14″ High Storage, 14″ High Door

description	w	pattern no.	P1	P2	P3
57″h Overdesk with Veneer Sliding Door and 14″ Tall Cabinet with tackboard	30″	**DS3ODSV1573014LT**	$1,637.	$1,771.	$1,837.
	36″	**DS3ODSV1573614LT**	1,686.	1,821.	1,891.
	42″	**DS3ODSV1574214LT**	1,743.	1,882.	1,954.
	48″	**DS3ODSV1574814LT**	1,791.	1,935.	2,008.
	60″	**DS3ODSV1576014LT**	1,854.	2,003.	2,076.
	66″	**DS3ODSV1576614LT**	1,893.	2,046.	2,123.
	72″	**DS3ODSV1577214LT**	1,959.	2,116.	2,195.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option: Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
57" High Cabinet with 21" High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
57"h without Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	**DS3ODNS( )573021T**	$1,168.	$1,265.	$1,312.
	36"	**DS3ODNS( )573621T**	1,198.	1,297.	1,346.
	42"	**DS3ODNS( )574221T**	1,239.	1,338.	1,388.
	48"	**DS3ODNS( )574821T**	1,286.	1,392.	1,446.
	60"	**DS3ODNS( )576021T**	1,408.	1,524.	1,582.
	66"	**DS3ODNS( )576621T**	1,439.	1,558.	1,616.
	72"	**DS3ODNS( )577221T**	1,485.	1,604.	1,667.
57"h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	**DS3ODSS2573021FLT**	1,305.	1,415.	1,468.
	36"	**DS3ODSS2573621FLT**	1,334.	1,445.	1,499.
	42"	**DS3ODSS2574221FLT**	1,383.	1,496.	1,553.
	48"	**DS3ODSS2574821FLT**	1,456.	1,575.	1,635.
	60"	**DS3ODSS2576021FLT**	1,599.	1,731.	1,797.
	66"	**DS3ODSS2576621FLT**	1,643.	1,777.	1,848.
	72"	**DS3ODSS2577221FLT**	1,699.	1,836.	1,906.
57"h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	**DS3ODSL2573021FLT**	1,649.	1,792.	1,863.
	36"	**DS3ODSL2573621FLT**	1,705.	1,854.	1,927.
	42"	**DS3ODSL2574221FLT**	1,771.	1,924.	2,000.
	48"	**DS3ODSL2574821FLT**	1,830.	1,987.	2,065.
	60"	**DS3ODSL2576021FLT**	1,902.	2,065.	2,146.
	66"	**DS3ODSL2576621FLT**	1,950.	2,119.	2,201.
	72"	**DS3ODSL2577221FLT**	2,026.	2,199.	2,285.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabrics

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021FLT, 613**

DS3ODSS Pattern Number
2573021FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
57" High Cabinet with 21" High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
57″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODSV2573021FLT**	$1,723.	$1,873.	$1,948.
	36″	**DS3ODSV2573621FLT**	1,789.	1,946.	2,025.
	42″	**DS3ODSV2574221FLT**	1,868.	2,031.	2,110.
	48″	**DS3ODSV2574821FLT**	1,935.	2,103.	2,187.
	60″	**DS3ODSV2576021FLT**	2,019.	2,192.	2,280.
	66″	**DS3ODSV2576621FLT**	2,078.	2,258.	2,348.
	72″	**DS3ODSV2577221FLT**	2,165.	2,351.	2,444.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabrics

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021FLT, 613**

DS3ODSS Pattern Number **2573021FLT**

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
57" High Cabinet with 21" High Storage (Partial Height Door)

description	w	pattern no.	P1	P2	P3
57"h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	36"	**DS3ODSS( )573021PLT**	$1,334.	$1,445.	$1,499.
	36"	**DS3ODSS( )573621PLT**	1,334.	1,445.	1,499.
	42"	**DS3ODSS( )574221PLT**	1,383.	1,496.	1,553.
	48"	**DS3ODSS( )574821PLT**	1,456.	1,575.	1,635.
	60"	**DS3ODSS( )576021PLT**	1,599.	1,731.	1,797.
	66"	**DS3ODSS( )576621PLT**	1,643.	1,777.	1,848.
	72"	**DS3ODSS( )577221PLT**	1,699.	1,836.	1,906.
57"h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	**DS3ODSL( )573021PLT**	1,641.	1,782.	1,853.
	36"	**DS3ODSL( )573621PLT**	1,696.	1,845.	1,916.
	42"	**DS3ODSL( )574221PLT**	1,762.	1,913.	1,989.
	48"	**DS3ODSL( )574821PLT**	1,818.	1,975.	2,054.
	60"	**DS3ODSL( )576021PLT**	1,893.	2,051.	2,133.
	66"	**DS3ODSL( )576621PLT**	1,940.	2,106.	2,189.
	72"	**DS3ODSL( )577221PLT**	2,015.	2,186.	2,272.
57"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	**DS3ODSV( )573021PLT**	1,712.	1,861.	1,935.
	36"	**DS3ODSV( )573621PLT**	1,773.	1,927.	2,003.
	42"	**DS3ODSV( )574221PLT**	1,844.	2,005.	2,085.
	48"	**DS3ODSV( )574821PLT**	1,908.	2,074.	2,156.
	60"	**DS3ODSV( )576021PLT**	1,986.	2,156.	2,243.
	66"	**DS3ODSV( )576621PLT**	2,041.	2,216.	2,305.
	72"	**DS3ODSV( )577221PLT**	2,122.	2,305.	2,396.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021PLF, 613**

DS3ODSS Pattern Number
2573021PLF

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
64″ High Cabinet with 14″ High Storage

description	w	pattern no.	P1	P2	P3
64″h without Sliding Door Overdesk with 14″ Tall Cabinet with tackboard 	30″	**DS3ODNS1643014T**	$1,246.	$1,338.	$1,383.
	36″	**DS3ODNS1643614T**	1,261.	1,353.	1,399.
	42″	**DS3ODNS1644214T**	1,310.	1,403.	1,450.
	48″	**DS3ODNS1644814T**	1,404.	1,506.	1,557.
	60″	**DS3ODNS1646014T**	1,461.	1,567.	1,619.
	66″	**DS3ODNS1646614T**	1,485.	1,594.	1,648.
	72″	**DS3ODNS1647214T**	1,530.	1,640.	1,693.
64″h Steel Sliding Door Overdesk with 14″ Tall Cabinet with tackboard 	30″	**DS3ODSS1643014LT**	1,297.	1,391.	1,439.
	36″	**DS3ODSS1643614LT**	1,325.	1,423.	1,470.
	42″	**DS3ODSS1644214LT**	1,366.	1,465.	1,515.
	48″	**DS3ODSS1644814LT**	1,408.	1,512.	1,565.
	60″	**DS3ODSS1646014LT**	1,532.	1,646.	1,703.
	66″	**DS3ODSS1646614LT**	1,564.	1,679.	1,737.
	72″	**DS3ODSS1647214LT**	1,606.	1,723.	1,780.
64″h Laminate Sliding Door Overdesk with 14″ Tall Cabinet with tackboard 	30″	**DS3ODSL1643014LT**	1,608.	1,735.	1,799.
	36″	**DS3ODSL1643614LT**	1,650.	1,780.	1,844.
	42″	**DS3ODSL1644214LT**	1,704.	1,837.	1,905.
	48″	**DS3ODSL1644814LT**	1,748.	1,886.	1,955.
	60″	**DS3ODSL1646014LT**	1,809.	1,948.	2,020.
	66″	**DS3ODSL1646614LT**	1,843.	1,987.	2,060.
	72″	**DS3ODSL1647214LT**	1,906.	2,055.	2,128.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FLT, 613**

DS3ODSS Pattern Number
2643014FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
64″ High Cabinet with 14″ High Storage

description	w	pattern no.	P1	P2	P3
64″h Veneer Sliding Door Overdesk with 14″ Tall Cabinet with tackboard	30″	**DS3ODSV1643014LT**	$1,678.	$1,812.	$1,880.
	36″	**DS3ODSV1643614LT**	1,725.	1,864.	1,933.
	42″	**DS3ODSV1644214LT**	1,786.	1,927.	1,999.
	48″	**DS3ODSV1644814LT**	1,836.	1,981.	2,055.
	60″	**DS3ODSV1646014LT**	1,902.	2,051.	2,127.
	66″	**DS3ODSV1646614LT**	1,943.	2,096.	2,173.
	72″	**DS3ODSV1647214LT**	2,014.	2,170.	2,251.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FLT, 613**

DS3ODSS Pattern Number **2643014FLT**

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Paint Configuration Option: Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
64″ High Cabinet with 21″ High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
64″h without Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODNS( )643021T**	$1,276.	$1,375.	$1,423.
	36″	**DS3ODNS( )643621T**	1,299.	1,399.	1,449.
	42″	**DS3ODNS( )644221T**	1,341.	1,446.	1,499.
	48″	**DS3ODNS( )644821T**	1,417.	1,525.	1,581.
	60″	**DS3ODNS( )646021T**	1,546.	1,666.	1,728.
	66″	**DS3ODNS( )646621T**	1,585.	1,708.	1,772.
	72″	**DS3ODNS( )647221T**	1,640.	1,768.	1,831.
64″h Steel Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODSS2643021FLT**	1,399.	1,509.	1,562.
	36″	**DS3ODSS2643621FLT**	1,429.	1,539.	1,596.
	42″	**DS3ODSS2644221FLT**	1,476.	1,590.	1,649.
	48″	**DS3ODSS2644821FLT**	1,549.	1,669.	1,731.
	60″	**DS3ODSS2646021FLT**	1,692.	1,826.	1,892.
	66″	**DS3ODSS2646621FLT**	1,737.	1,875.	1,943.
	72″	**DS3ODSS2647221FLT**	1,793.	1,933.	2,002.
64″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODSL2643021FLT**	1,750.	1,895.	1,967.
	36″	**DS3ODSL2643621FLT**	1,806.	1,955.	2,029.
	42″	**DS3ODSL2644221FLT**	1,872.	2,025.	2,102.
	48″	**DS3ODSL2644821FLT**	1,930.	2,089.	2,168.
	60″	**DS3ODSL2646021FLT**	2,002.	2,166.	2,249.
	66″	**DS3ODSL2646621FLT**	2,051.	2,220.	2,303.
	72″	**DS3ODSL2647221FLT**	2,127.	2,301.	2,389.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021FLT, 613**

DS3ODSS	Pattern Number
2643021FLT	
613	Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
64″ High Cabinet with 21″ High Storage (Full Height Door)

description	w	pattern no.	P1	P2	P3
64″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODSV2643021FLT**	$1,824.	$1,975.	$2,051.
	36″	**DS3ODSV2643621FLT**	1,891.	2,048.	2,126.
	42″	**DS3ODSV2644221FLT**	1,968.	2,131.	2,212.
	48″	**DS3ODSV2644821FLT**	2,035.	2,206.	2,288.
	60″	**DS3ODSV2646021FLT**	2,119.	2,293.	2,382.
	66″	**DS3ODSV2646621FLT**	2,178.	2,361.	2,451.
	72″	**DS3ODSV2647221FLT**	2,265.	2,453.	2,544.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021FLT, 613**

DS3ODSS Pattern Number **2643021FLT**

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard
64″ High Cabinet with 21″ High Storage (Partial Height Door)

description	w	pattern no.	P1	P2	P3
64″h Steel Sliding Door Overdesk with 21″ Tall Cabinet with tackboard 	30″	**DS3ODSS( )643021PLT**	$1,399.	$1,509.	$1,562.
	36″	**DS3ODSS( )643621PLT**	1,429.	1,539.	1,596.
	42″	**DS3ODSS( )644221PLT**	1,476.	1,590.	1,649.
	48″	**DS3ODSS( )644821PLT**	1,549.	1,669.	1,731.
	60″	**DS3ODSS( )646021PLT**	1,692.	1,826.	1,892.
	66″	**DS3ODSS( )646621PLT**	1,737.	1,875.	1,943.
	72″	**DS3ODSS( )647221PLT**	1,793.	1,933.	2,002.
64″h Laminate Sliding Door Overdesk with 21″ Tall Cabinet with tackboard 	30″	**DS3ODSL( )643021PLT**	1,740.	1,885.	1,956.
	36″	**DS3ODSL( )643621PLT**	1,796.	1,945.	2,018.
	42″	**DS3ODSL( )644221PLT**	1,862.	2,016.	2,092.
	48″	**DS3ODSL( )644821PLT**	1,920.	2,077.	2,156.
	60″	**DS3ODSL( )646021PLT**	1,992.	2,155.	2,236.
	66″	**DS3ODSL( )646621PLT**	2,039.	2,208.	2,291.
	72″	**DS3ODSL( )647221PLT**	2,115.	2,288.	2,374.
64″h Veneer Sliding Door Overdesk with 21″ Tall Cabinet with tackboard	30″	**DS3ODSV( )643021PLT**	1,812.	1,962.	2,037.
	36″	**DS3ODSV( )643621PLT**	1,872.	2,030.	2,108.
	42″	**DS3ODSV( )644221PLT**	1,946.	2,105.	2,187.
	48″	**DS3ODSV( )644821PLT**	2,009.	2,176.	2,258.
	60″	**DS3ODSV( )646021PLT**	2,086.	2,259.	2,343.
	66″	**DS3ODSV( )646621PLT**	2,140.	2,319.	2,408.
	72″	**DS3ODSV( )647221PLT**	2,222.	2,406.	2,498.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021PLT, 613**

DS3ODSS Pattern Number
2643021PLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard coves from top of worksurface to bottom of lower shelf.

Options

No lock - substitute “N” for “L” at the end of pattern number, subtract $20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:
Add “Y” at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

This page intentionally left blank

Available Worksurface Styles
- Rectangular
- Rectilinear corner
- Split top corner
- Curvilinear corner
- Trapezoid
- Smooth wave
- Curvilinear wave end
- Half-round
- Quarter-round
- Blended “D” shape
- “D” shape peninsula
- “P” and “9” shape peninsula
- Counter Worksurfaces
- Transition

Universal Applications
The undersides of worksurfaces are pre-drilled to accept various panel-hung and freestanding supports. Cascade edge worksurfaces do not have pre-drilled holes.

All supports must be ordered separately.

In panel-hung applications, worksurfaces are supported by:

- Cantilevers
- Pedestals
- Panel-to-worksurface brackets
- Flat brackets
- Panel-mounted C-leg support
- Open support legs

In peninsula applications, worksurfaces are supported by panels on one end and the other end is supported by:

- Support column
- A leg
- T support base

For freestanding applications, worksurface support is provided by:

- Pedestals
- End units
- Flat brackets

Construction

Laminate
- Surface material: .028 high-pressure laminate on top surface with a paper backer on under side
- Edge material: 2mm ABS on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

Techwood
- Surface material: 0.6mm veneer
- Edge material: 0.6mm veneer on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

For available sizes, refer to the individual worksurface categories within this section.

Optional Edge Grommets
Edge grommets are optional and can be specified factory-installed centered along the rear edge of rectangular, rectilinear corner, curvilinear wave end, and curvilinear corner worksurfaces. Grommets can also be retrofitted to worksurfaces by ordering an edge grommet kit (pattern number D1WSG). The edge grommet kit allows grommets to be field-installed in any location along the rear edge of worksurfaces.

Note: Edge grommets on 'D', '9', and 'P' peninsula worksurfaces are located on the panel hung side.

Cable Management
A 1/2" reveal is provided between the worksurface and panel for cable management. When edge grommets are specified, the grommet works in conjunction with the 1/2" reveal to allow plugs to be inserted through the grommet and cables to be positioned anywhere along the rear edge of the worksurface.

Loading Capacities
Maximum weight allowed for worksurfaces:

- 24"-42" wide: 200 lbs.
- 48" wide: 216 lbs.
- 54" wide: 243 lbs.
- 60" wide: 270 lbs.
- 66" wide: 297 lbs.
- 72" wide: 324 lbs.
- 78" wide: 351 lbs.
- 84" wide: 378 lbs.
- 90" wide: 405 lbs:
- 96" wide: 432 lbs.

Note: Installations which violate these requirements will not be covered by the Knoll, Inc. warranty.



Worksurfaces and Supports, Panel Application



Worksurfaces and Supports, Freestanding Application



2mm ABS Edge Detail







Worksurface Cable Management

Laminate Worksurface Grain Direction

The standard grain direction for wood grain or brushed laminates for each worksurface shape is shown below.

When wood grain or brushed laminates are specified on Dividends Horizon corner worksurfaces, a left, right or diagonal grain direction option must be specified as shown below. Insert the desired grain direction option (L, R or D) after the laminate finish code. The diagonal option is an upcharge. This option applies only to corner worksurfaces with the same dimension on each rear side.

Techwood Worksurface Grain Direction

The standard grain direction for Techwood worksurfaces for each worksurface shape is shown below.

Techwood corner worksurfaces with the same dimension on each rear side have a diagonal grain direction.

Laminate Worksurface Grain Direction



Techwood Worksurface Grain Direction



Panel-Hung Worksurface Support
All worksurfaces require support every 48" in width. In panel-hung applications, mid-span support must be provided by cantilevers, panel-mounted C-legs or open support legs.

When worksurfaces are mounted perpendicular to panels, the worksurface depth must equal the width of the panel when using panel-to-worksurface brackets.

Cantilevers are available in three depths to match worksurface depths.

- 18" deep worksurfaces are supported by 18" deep cantilevers.
- 24" deep worksurfaces are supported by 24" deep cantilevers.
- 30" deep worksurfaces are not recommended to be supported by cantilevers. 30" deep cantilevers are used for mid-span support.
- 36" deep worksurfaces cannot be supported by cantilevers.

Panel-mounted C-leg supports are available to support 24" and 30" worksurface depths in heavier worksurface load applications. Open support legs are available to support 18", 24" and 30" worksurfaces depths.

Freestanding Worksurface Support
For freestanding desk applications, specify freestanding pedestals, end units and/or intermediate support every 48" in width.

- 18" deep worksurfaces can be supported by 18" deep pedestals and end units only
- 24" deep worksurfaces can be supported by either 18" or 24" deep pedestals or end units
- 30" deep worksurfaces can be supported by either 24" or 30" deep pedestals or end units
- 36" deep worksurfaces can only be supported by 30" deep pedestals or end units and provide a 6" front overhang for desk applications.

Maximum Width Between Panel-Hung Worksurface Supports



Maximum Width Between Freestanding Worksurface Supports



Worksurface Reinforcement
Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.

Notes:
- Whenever using pedestals they should be connected to panels with panel-to-worksurface brackets
- Panel runs must be floor-supported every 8 feet (i.e., pedestal with panel-to-worksurface brackets or panel-mounted C-leg)
- When a panel mounted C-leg is used, unsupported worksurface span is not to exceed 48".

Legend



Worksurface Reinforcement
Panel Hung Application



Worksurface Reinforcement
Freestanding Desk Application



Rectangular Worksurfaces
18" and 24" Deep Specifications

Rectangular Worksurfaces
Dividends Horizon rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes
- Depths: 18" and 24"
- Widths: 24" to 96"

Panel-Hung Applications
When a worksurface spans multiple panels a cantilever or freestanding support is required every 48" of width.

Freestanding Applications
Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.

The most common freestanding applications involve desks, returns and bridge units in “L” and “U” configurations.



24"D Rectangular Worksurface



18"D Rectangular Worksurface



Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support





Freestanding Desk Applications

Rectangular Worksurfaces
18″ and 24″ Deep

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
18″ Deep Rectangular No Grommets	24″	23 13/16″	17 1/2″	1 1/4″	**D1R 2418N**	$157.	$173.	$188.	$386.
	30″	29 13/16″	17 1/2″	1 1/4″	**D1R 3018N**	166.	183.	200.	407.
	36″	35 13/16″	17 1/2″	1 1/4″	**D1R 3618N**	185.	205.	224.	426.
	42″	41 13/16″	17 1/2″	1 1/4″	**D1R 4218N**	215.	236.	256.	447.
	48″	47 13/16″	17 1/2″	1 1/4″	**D1R 4818N**	239.	263.	288.	466.
	54″	53 13/16″	17 1/2″	1 1/4″	**D1R 5418N**	254.	280.	306.	482.
	60″	59 13/16″	17 1/2″	1 1/4″	**D1R 6018N**	277.	304.	332.	501.
	66″	65 13/16″	17 1/2″	1 1/4″	**D1R 6618N**	298.	328.	357.	519.
	72″	71 13/16″	17 1/2″	1 1/4″	**D1R 7218N**	314.	346.	377.	539.
	78″	77 13/16″	17 1/2″	1 1/4″	**D1R 7818N**	338.	371.	405.	560.
	84″	83 13/16″	17 1/2″	1 1/4″	**D1R 8418N**	355.	390.	425.	582.
	90″	89 13/16″	17 1/2″	1 1/4″	**D1R 9018N**	396.	436.	472.	604.
	96″	95 13/16″	17 1/2″	1 1/4″	**D1R 9618N**	438.	480.	524.	626.
24″ Deep Rectangular No Grommets	24″	23 13/16″	23 1/2″	1 1/4″	**D1R 2424N**	167.	184.	202.	399.
	30″	29 13/16″	23 1/2″	1 1/4″	**D1R 3024N**	193.	210.	229.	422.
	36″	35 13/16″	23 1/2″	1 1/4″	**D1R 3624N**	213.	234.	254.	444.
	42″	41 13/16″	23 1/2″	1 1/4″	**D1R 4224N**	244.	267.	295.	468.
	48″	47 13/16″	23 1/2″	1 1/4″	**D1R 4824N**	272.	301.	329.	490.
	54″	53 13/16″	23 1/2″	1 1/4″	**D1R 5424N**	296.	325.	354.	516.
	60″	59 13/16″	23 1/2″	1 1/4″	**D1R 6024N**	320.	350.	382.	542.
	66″	65 13/16″	23 1/2″	1 1/4″	**D1R 6624N**	345.	379.	414.	565.
	72″	71 13/16″	23 1/2″	1 1/4″	**D1R 7224N**	359.	397.	432.	590.
	78″	77 13/16″	23 1/2″	1 1/4″	**D1R 7824N**	386.	424.	462.	618.
	84″	83 13/16″	23 1/2″	1 1/4″	**D1R 8424N**	409.	452.	491.	645.
	90″	89 13/16″	23 1/2″	1 1/4″	**D1R 9024N**	461.	506.	553.	672.
	96″	95 13/16″	23 1/2″	1 1/4″	**D1R 9624N**	502.	554.	605.	697.

w* = nominal width
Dimensions listed under w d t are actual to the nearest 1/16″

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1R 4818N, 114, 114**
D1R 4818N	Pattern Number
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the **"N"** suffix from the pattern number with **"G".**
Add $18.

Rectangular Worksurfaces
19" Deep Specifications

Rectangular Worksurfaces
The 19" deep rectangular worksurface aligns with the depth of a doublewide pedestal. Dividends Horizon worksurfaces provide a 1/2" reveal between the worksurface and panel for cable management.

Dividends Horizon 19" deep rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes
- Depths: 19"
- Widths: 24" to 96"

Panel-Hung Applications
When a worksurface spans multiple panels, a cantilever or freestanding support is required every 48" of width.

Freestanding Applications
Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.

The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.



19"D Rectangular Worksurface



Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support



19" Deep Worksurface Application

Rectangular Worksurfaces
19″ Deep

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
19″ Deep Rectangular - No Grommets (for use with doublewide pedestals)	24″	23 13/16″	18 3/4″	1 1/4″	**D1R2419N**	$159.	$175.	$192.	$388.
	30″	29 13/16″	18 3/4″	1 1/4″	**D1R3019N**	171.	187.	204.	409.
	36″	35 13/16″	18 3/4″	1 1/4″	**D1R3619N**	192.	209.	228.	430.
	42″	41 13/16″	18 3/4″	1 1/4″	**D1R4219N**	219.	242.	263.	450.
	48″	47 13/16″	18 3/4″	1 1/4″	**D1R4819N**	244.	268.	294.	470.
	54″	53 13/16″	18 3/4″	1 1/4″	**D1R5419N**	262.	288.	314.	489.
	60″	59 13/16″	18 3/4″	1 1/4″	**D1R6019N**	284.	312.	342.	508.
	66″	65 13/16″	18 3/4″	1 1/4″	**D1R6619N**	305.	337.	368.	526.
	72″	71 13/16″	18 3/4″	1 1/4″	**D1R7219N**	323.	354.	387.	547.
	78″	77 13/16″	18 3/4″	1 1/4″	**D1R7819N**	345.	379.	415.	570.
	84″	83 13/16″	18 3/4″	1 1/4″	**D1R8419N**	366.	402.	438.	592.
	90″	89 13/16″	18 3/4″	1 1/4″	**D1R9019N**	407.	447.	488.	616.
	96″	95 13/16″	18 3/4″	1 1/4″	**D1R9619N**	449.	493.	540.	639.

w* = nominal width
Dimensions listed under w d t are actual to the nearest 1/16″

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1R 4819N, 114, 114**
D1R 4819N	Pattern Number
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the **"N"** suffix from the pattern number with **"G".**
Add $18.

Rectangular Worksurfaces
30″ and 36″ Deep Specifications

Rectangular Worksurfaces
Dividends Horizon rectangular worksurfaces are universal and can be used in:

- Panel-hung applications
- Freestanding applications

See page 166 for the following:

- Worksurface construction
- Optional edge grommets
- Loading capacities

Available Sizes
- Depths: 30" and 36"
- Widths: 24" to 96" (30"D), 60" to 72" (36"D)

Panel-Hung Applications
When a worksurface spans multiple panels a cantilever or freestanding floor support is required every 48". 36" deep worksurfaces cannot be supported by cantilevers. Worksurfaces over 48" W require mid-span support

Freestanding Applications
Refer to the freestanding desk section for "preconfigured" applications. Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.

The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.

Overhang Desks
Overhang desks can be ordered by component by specifying desk supports and worksurfaces separately. To specify, select either a 30" or 36" deep worksurface in 60", 66" or 72" widths. Back panels should be specified to match the worksurface width while supports (pedestals or end units) should be one size smaller than the worksurface depth to provide a 6" front overhang. Example: 36" deep worksurface with 30" deep pedestals or end units.



30"D Rectangular Worksurface



36"D Rectangular Worksurface



Worksurfaces over 48"W require mid-span support





Freestanding Desk Applications

Rectangular Worksurfaces
30″ and 36″ Deep

description	w	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
30″ Deep Rectangular No Grommets	24″	23 13/16″	29 1/2″	1 1/4″	**D1R 2430N**	$214.	$235.	$255.	$414.
	30″	29 13/16″	29 1/2″	1 1/4″	**D1R 3030N**	239.	263.	288.	446.
	36″	35 13/16″	29 1/2″	1 1/4″	**D1R 3630N**	264.	291.	319.	476.
	42″	41 13/16″	29 1/2″	1 1/4″	**D1R 4230N**	288.	316.	344.	508.
	48″	47 13/16″	29 1/2″	1 1/4″	**D1R 4830N**	320.	350.	382.	541.
	54″	53 13/16″	29 1/2″	1 1/4″	**D1R 5430N**	363.	398.	434.	563.
	60″	59 13/16″	29 1/2″	1 1/4″	**D1R 6030N**	399.	439.	477.	587.
	66″	65 13/16″	29 1/2″	1 1/4″	**D1R 6630N**	443.	488.	534.	610.
	72″	71 13/16″	29 1/2″	1 1/4″	**D1R 7230N**	461.	506.	553.	632.
	78″	77 13/16″	29 1/2″	1 1/4″	**D1R 7830N**	492.	544.	592.	662.
	84″	83 13/16″	29 1/2″	1 1/4″	**D1R 8430N**	522.	575.	628.	690.
	90″	89 13/16″	29 1/2″	1 1/4″	**D1R 9030N**	562.	618.	675.	719.
	96″	95 13/16″	29 1/2″	1 1/4″	**D1R 9630N**	603.	663.	723.	749.
36″ Deep Rectangular No Grommets	60″	59 13/16″	35 1/2″	1 1/4″	**D1R 6036N**	511.	561.	612.	696.
	66″	65 13/16″	35 1/2″	1 1/4″	**D1R 6636N**	564.	622.	677.	720.
	72″	71 13/16″	35 1/2″	1 1/4″	**D1R 7236N**	622.	685.	747.	748.
	78″	77 13/16″	35 1/2″	1 1/4″	**D1R 7836N**	662.	705.	752.	755.
	84″	83 13/16″	35 1/2″	1 1/4″	**D1R 8436N**	702.	722.	758.	763.
	90″	89 13/16″	35 1/2″	1 1/4″	**D1R 9036N**	755.	778.	808.	821.
	96″	95 13/16″	35 1/2″	1 1/4″	**D1R 9636N**	809.	832.	855.	879.

w* = nominal width
Dimensions listed under w h t are actual to the nearest 1/16″

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1R 6030N, 114, 114**
D1R 6030N	Pattern Number
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the **"N"** suffix from the pattern number with **"G".**
Add $18.

Curvilinear Wave End Worksurfaces
Specifications

Curvilinear Wave End Worksurfaces
Dividends Horizon curvilinear wave end worksurfaces are primarily used in panel-hung applications.

Available Sizes
Curvilinear wave end worksurfaces are handed with one side deeper than the other.

- Depths: 24"/30", 18"/30", 24"/36"
- Widths: 36" to 72"

Curvilinear Wave End Applications
36" to 48" wide wave ends are generally used as worksurface returns attached to curvilinear corners.

72" wide wave ends are used as primary worksurfaces with returns attached at the deep end.

Note: Only 18" and 24" deep returns can be attached to 72" wide wave end worksurfaces.

Curvilinear Wave End Support
In applications where worksurface ends are mounted perpendicular to panels, panel-to-worksurface brackets or a cantilever and a panel-to-worksurface bracket can be used as shown below.

72" wide curvilinear wave ends always require mid-span cantilever support including applications involving pedestal support at one end.

Pedestal Support Applications
Pedestals can be used as supports in the following locations:

- The deep end of all curvilinear wave ends
- The shallow end of all 48" and 72" wide curvilinear wave end worksurfaces

Recommended Pedestal Depths
- 18" deep wave ends require 18" deep pedestals
- 24" deep wave ends can use either a 18" or 24" deep pedestal
- 30" deep wave ends can use either a 24" or 30" deep pedestal
- 36" deep wave ends require a 30" deep pedestal

Note: When the pedestal depth is less than the worksurface depth, a panel-to-worksurface bracket must be used in the rear corner of the worksurface to the panel.

Freestanding Applications
Curvilinear wave end worksurfaces can be used to create unique freestanding workstations supported by pedestals and end units. The most common application is a 72" wide wave end worksurface with a single pedestal and end unit attached to a freestanding return.

Curvilinear Wave End Worksurface



Curvilinear Wave End Worksurface Sizes



Curvilinear Wave End Applications



** Requires a return panel, panel-mounted C-leg support, open support leg, or a pedestal with a panel-to-worksurface bracket for support.

Pedestal Support Applications



Pedestal on deep end of curvilinear wave ends





Pedestal on shallow end of curvilinear wave ends

Curvilinear Wave End Worksurfaces
Mixed Depths

description	w *	1	2	3	A	B	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Wave End Left No Grommets	36″	35 13/16″	23 1/2″	29 1/2″	14 15/16″	2 15/16″	1 1/4″	**D1W 363024N**	$450.	$493.	$542.	$862.
	42″	41 13/16″	23 1/2″	29 1/2″	14 15/16″	8 15/16″	1 1/4″	**D1W 423024N**	471.	520.	565.	888.
	48″	47 13/16″	23 1/2″	29 1/2″	14 15/16″	14 15/16″	1 1/4″	**D1W 483024N**	503.	555.	606.	913.
	72″	71 13/16″	17 1/2″	29 1/2″	23 7/16″	14 15/16″	1 1/4″	**D1W 723018N**	624.	686.	749.	937.
	72″	71 13/16″	23 1/2″	29 1/2″	23 7/16″	30 7/16″	1 1/4″	**D1W 723024N**	643.	706.	773.	964.
	72″	71 13/16″	23 1/2″	35 1/2″	23 7/16″	14 15/16″	1 1/4″	**D1W 723624N**	664.	728.	796.	989.
Curvilinear Wave End Right No Grommets	36″	35 13/16″	29 1/2″	23 1/2″	2 15/16″	14 15/16″	1 1/4″	**D1W 362430N**	450.	493.	542.	862.
	42″	41 13/16″	29 1/2″	23 1/2″	8 15/16″	14 15/16″	1 1/4″	**D1W 422430N**	471.	520.	565.	888.
	48″	47 13/16″	29 1/2″	23 1/2″	14 15/16″	14 15/16″	1 1/4″	**D1W 482430N**	503.	555.	606.	913.
	72″	71 13/16″	29 1/2″	17 1/2″	14 15/16″	23 7/16″	1 1/4″	**D1W 721830N**	624.	686.	749.	937.
	72″	71 13/16″	29 1/2″	23 1/2″	30 7/16″	23 7/16″	1 1/4″	**D1W 722430N**	643.	706.	773.	964.
	72″	71 13/16″	35 1/2″	23 1/2″	14 15/16″	23 7/16″	1 1/4″	**D1W 722436N**	664.	728.	796.	989.

w* = nominal width
A and B = straight edge length
Dimensions listed under 1, 2 and 3 are actual to nearest 1/16″

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1R 6030N, 114, 114**
D1R 6030N	Pattern Number
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the **"N"** suffix from the pattern number with **"G".**
Add $18.

description	w*	w	depth left	depth right	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Smooth Wave	48″	47 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S481824N**	$503.	$555.	$606.	$878.
	48″	47 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S481830N**	503.	555.	606.	881.
	48″	47 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S482418N**	503.	555.	606.	886.
	48″	47 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S482430N**	503.	555.	606.	889.
	48″	47 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S483018N**	503.	555.	606.	893.
	48″	47 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S483024N**	503.	555.	606.	896.
	60″	59 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S601824N**	584.	643.	700.	900.
	60″	59 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S601830N**	584.	643.	700.	903.
	60″	59 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S602418N**	584.	643.	700.	908.
	60″	59 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S602430N**	584.	643.	700.	913.
	60″	59 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S603018N**	584.	643.	700.	917.
	60″	59 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S603024N**	584.	643.	700.	920.
	66″	65 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S661824N**	624.	687.	750.	924.
	66″	65 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S661830N**	624.	687.	750.	927.
	66″	65 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S662418N**	624.	687.	750.	931.
	66″	65 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S662430N**	624.	687.	750.	935.
	66″	65 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S663018N**	624.	687.	750.	939.
	66″	65 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S663024N**	624.	687.	750.	942.
	72″	71 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S721824N**	664.	728.	796.	947.
	72″	71 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S721830N**	664.	728.	796.	950.
	72″	71 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S722418N**	664.	728.	796.	956.
	72″	71 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S722430N**	664.	728.	796.	961.
	72″	71 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S723018N**	664.	728.	796.	965.
	72″	71 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S723024N**	664.	728.	796.	968.
	78″	77 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S781824N**	702.	774.	844.	972.
	78″	77 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S781830N**	702.	774.	844.	974.
	78″	77 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S782418N**	702.	774.	844.	975.
	78″	77 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S782430N**	702.	774.	844.	980.
	78″	77 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S783018N**	702.	774.	844.	984.
	78″	77 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S783024N**	702.	774.	844.	988.
	84″	83 13/16″	17 1/2″	23 1/2″	1 1/4″	**D1W S841824N**	745.	817.	892.	991.
	84″	83 13/16″	17 1/2″	29 1/2″	1 1/4″	**D1W S841830N**	745.	817.	892.	995.
	84″	83 13/16″	23 1/2″	17 1/2″	1 1/4″	**D1W S842418N**	745.	817.	892.	999.
	84″	83 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W S842430N**	745.	817.	892.	1,003.
	84″	83 13/16″	29 1/2″	17 1/2″	1 1/4″	**D1W S843018N**	745.	817.	892.	1,006.
	84″	83 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W S843024N**	745.	817.	892.	1,011.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1R 6030N, 114, 114**
D1W	Dividends Worksurface
S	Smooth Wave Shape
72	Overall width in inches
30	Nominal depth at user's left side
24	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets, replace the **"N"** suffix from the pattern number with a **"G".**
Add $28

Trapezoidal Worksurfaces

description	w*	w	depth left	depth right	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Trapezoidal 	48″	47 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W T482430N**	$503.	$555.	$606.	$628.
	48″	47 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W T483024N**	503.	555.	606.	628.
	60″	59 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W T602430N**	584.	643.	700.	664.
	60″	59 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W T603024N**	584.	643.	700.	664.
	66″	65 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W T662430N**	624.	687.	750.	698.
	66″	65 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W T663024N**	624.	687.	750.	698.
	72″	71 13/16″	23 1/2″	29 1/2″	1 1/4″	**D1W T722430N**	664.	728.	796.	734.
	72″	71 13/16″	29 1/2″	23 1/2″	1 1/4″	**D1W T723024N**	664.	728.	796.	734.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1W T482430N**
D1W	Dividends Worksurface
T	Trapezoidal Shape
48	Overall Width, inches
24	Nominal depth at user's left side
30	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurface

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets replace the **"N"** suffix from the pattern number with a **"G".**
Add $28

Corner Worksurfaces
Rectilinear and Split Top Corner Specifications

Rectilinear Corner Worksurfaces
Dividends Horizon rectilinear corner worksurfaces are used in panel-hung and freestanding applications.

Split Top Corner Worksurfaces
Split top corner worksurfaces allow for height and angle adjustment on the front worksurface.

The depth of the front keyboard worksurface is 10 5/8". The front surface adjusts from a - 5 3/4" below the worksurface to a + 7" above. The mechanism has a tilt feature of ±10 degrees.

Included with the split top worksurface is the back corner worksurface, the front corner worksurface, the split top mechanism, one rear corner panel-to-worksurface bracket and two flat brackets for attachment to return worksurfaces. Cantilevers must be ordered separately and are specified to the size return worksurface depth (i.e 24" cantilevers for 24" deep return worksurfaces). Panel-mounted C-leg or Open Leg worksurface supports may be used in place of cantilevers.

Available Sizes
- Widths: 36", 42" and 48"
- Returns: 18", 24" and 30"
- Thickness: 1 1/4"

Corner Worksurface Support
Corner worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or Open Leg worksurface supports may be used instead of cantilevers for corner worksurface support. Cantilevers and panel-mounted C-leg or Open Leg supports are ordered separately. Panel-to-worksurface bracket is included.

Corner Worksurface Applications
Corner worksurfaces attach to adjacent worksurfaces with cantilevers and flat brackets. Suggested applications are illustrated below.

Note: All dimensions are nominal except for front edge dimension.

Note: Series 3 overdesk units are not compatible with corner worksurfaces.

Rectilinear Corner Worksurface



Rectilinear Split-Top Corner Worksurface



Rectilinear and Split Top Corner Worksurface Sizes Available



Corner Worksurface Support



Corner Worksurface Applications



** Requires a return panel, panel-mounted C-leg or Open Leg support or a pedestal with a panel-to-worksurface bracket for support.

Corner Worksurfaces
Rectilinear and Split Top Corner
Mixed Depths

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Rectilinear Corner Worksurface No Grommets	36″	36″	18″	18″	1 1/4″	**D1C 3618N**	$384.	$423.	$461.	$781.
	36″	36″	24″	24″	1 1/4″	**D1C 3624N**	391.	432.	470.	854.
	42″	42″	24″	24″	1 1/4″	**D1C 4224N**	441.	485.	528.	926.
	48″	48″	24″	24″	1 1/4″	**D1C 4824N**	504.	556.	607.	1,000.
	48″	48″	30″	30″	1 1/4″	**D1C 4830N**	520.	572.	624.	1,073.
Rectilinear Corner Worksurface. 24″ Deep Return Left 30″ Deep Return Right No Grommets 	42″	42″	24″	30″	1 1/4″	**D1C 422430N**	462.	508.	555.	1,006.
	48″	48″	24″	30″	1 1/4″	**D1C 482430N**	524.	578.	631.	1,073.
Rectilinear Corner Worksurface. 30″ Deep Return Left 24″ Deep Return Right No Grommets 	42″	42″	30″	24″	1 1/4″	**D1C 423024N**	462.	508.	555.	1,006.
	48″	48″	30″	24″	1 1/4″	**D1C 483024N**	524.	578.	631.	1,073.
Split Top Corner Worksurface No Grommets 	42″	42″	24″	24″	1 1/4″	**D1CS 4224N**	1,568.	1,724.	1,883.	2,666.
	48″	48″	24″	24″	1 1/4″	**D1CS 4824N**	1,616.	1,775.	1,937.	2,755.
	48″	48″	30″	30″	1 1/4″	**D1CS 4830N**	1,626.	1,788.	1,953.	2,844.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2″ less than shown above.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Split Top Corner Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example:	**D1C 423024N, 117, 115**
D1C 423024N	Pattern Number
117	Soft Grey Laminate
115	Medium Grey Edge Band

Split Top Corner Worksurfaces

Example:	**D1CS 4224N, 117, 117**
D1CS 4224N	Pattern Number
117	Soft Grey Laminate
117	Soft Grey Edge Band

Included with:

Worksurfaces

- Worksurface
- Panel-to-Worksurface Bracket

Split Top Corner Worksurfaces

- Front Worksurface
- Back Worksurface
- Split Top Mechanism
- Flat Brackets
- Panel-to-Worksurface Bracket

Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add $25 to the list price for diagonal grain (D) selection.

Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 2 Center-Located Edge Grommets
- Woodgrain PVC edge
- Metal edge
- Techwood edge

To specify edge grommets, replace the **"N"** suffix from the pattern number with a **"G".**
Add $28

Split Top Corner Worksurfaces

- 2 Center-Located Edge Grommets
- Woodgrain PVC edge
- Metal edge
- Techwood edge

Note: Overdesk units are not compatible with corner worksurfaces.

Corner Worksurfaces
Curvilinear Corner "L" Shape - 24" Depths Specifications

Curvilinear Corner L Shape Worksurfaces
Dividends Horizon curvilinear corner "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support
Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support.

Cantilevers, panel-mounted c-leg and open support legs are ordered separately. A panel-to-worksurface bracket is included.

Note: Worksurfaces greater than 48" wide require an additional mid-span cantilever support along the 60" or 72" side.

Note: A pedestal, panel-mounted C-leg or Open Leg Support can be substituted for a cantilever in the following locations:

- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces

Note: Series 3 overdesk units are not compatible with corner worksurfaces.

Curvilinear Corner Worksurface



Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Support Options







Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Support Leg with panel-to-worksurface bracket for support

Corner Worksurfaces
Curvilinear Corner "L" Shape - 24" Depths
24" Depths

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Corner "L" Shape Worksurface 24" Deep Returns Left and Right	36"	36"	24"	24"	1¼"	**D1L 3636SSN**	$418.	$458.	$500.	$962.
	42"	42"	24"	24"	1¼"	**D1L 4242SSN**	502.	554.	605.	1,021.
	42"	60"	24"	24"	1¼"	**D1L 4260SSN**	692.	762.	830.	1,140.
	42"	66"	24"	24"	1¼"	**D1L 4266SSN**	711.	787.	855.	1,170.
	42"	72"	24"	24"	1¼"	**D1L 4272SSN**	737.	812.	887.	1,228.
	42"	78"	24"	24"	1¼"	**D1L 4278SSN**	747.	821.	895.	1,285.
	48"	48"	24"	24"	1¼"	**D1L 4848SSN**	565.	624.	678.	1,079.
	48"	60"	24"	24"	1¼"	**D1L 4860SSN**	700.	770.	839.	1,199.
	48"	66"	24"	24"	1¼"	**D1L 4866SSN**	725.	798.	870.	1,258.
	48"	72"	24"	24"	1¼"	**D1L 4872SSN**	753.	826.	899.	1,315.
	48"	78"	24"	24"	1¼"	**D1L 4878SSN**	830.	913.	995.	1,344.
	48"	84"	24"	24"	1¼"	**D1L 4884SSN**	931.	1,025.	1,118.	1,372.
	60"	42"	24"	24"	1¼"	**D1L 6042SSN**	692.	762.	830.	1,140.
	60"	48"	24"	24"	1¼"	**D1L 6048SSN**	700.	770.	839.	1,199.
	66"	42"	24"	24"	1¼"	**D1L 6642SSN**	711.	787.	855.	1,170.
	66"	48"	24"	24"	1¼"	**D1L 6648SSN**	725.	798.	870.	1,258.
	72"	42"	24"	24"	1¼"	**D1L 7242SSN**	737.	812.	887.	1,228.
	72"	48"	24"	24"	1¼"	**D1L 7248SSN**	753.	826.	899.	1,315.
	78"	42"	24"	24"	1¼"	**D1L 7842SSN**	747.	821.	895.	1,285.
	78"	48"	24"	24"	1¼"	**D1L 7848SSN**	830.	913.	995.	1,344.
	84"	48"	24"	24"	1¼"	**D1L 8448SSN**	931.	1,025.	1,118.	1,372.





Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are ½" less than shown above.

Ordering Information

1. **Worksurfaces**
2. Pattern Number
3. Top Finish Type
4. Edge Finish

Order Code

Worksurfaces

Example:	**D1L 4860SSN, 117, 117**
D1L 4860SSN	Pattern Number
117	Soft Grey laminate
117	Soft Grey Edge Band

Included with:

Worksurfaces

- Worksurface
- Panel-to-Worksurface Bracket

Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add $25 to the list price for diagonal grain (D) selection.

Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 2 center-located edge grommets
- Woodgrain ABS edge
- Metal edge
- Techwood

To specify edge grommets, replace the **"N"** suffix from the pattern number with **"G"**
Add $28

Note: Overdesk units are not compatible with corner worksurfaces.

Corner Worksurfaces
Curvilinear Corner "L" shape-Mixed Depths Specifications

Curvilinear Corner ''L'' Shape Worksurfaces
Dividends Horizon curvilinear corner, "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support
Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support. Cantilevers and panel-mounted C-leg or open leg supports are ordered separately. A panel-to-worksurface bracket is included.

Note: 60" and 72" wide curvilinear corners require an additional mid-span cantilever support along the 60" or 72" side.

Note: A pedestal or panel-mounted C-leg can be substituted for a cantilever in the following locations:

- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces

Curvilinear Corner Worksurface Applications
Curvilinear "L" shape corner worksurfaces are primarily used with wave end and rectangular worksurface returns.

Curvilinear Corner Worksurface



Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Support Options







Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Leg Support with panel-to-worksurface bracket for support

Corner Worksurfaces
Curvilinear Corner "L" shape-Mixed Depths
Mixed Depths

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Corner "L" Shape Worksurface. 30″ Deep Returns Left and Right	48″	48″	30″	30″	1¼″	**D1L 4848DDN**	$610.	$672.	$730.	$1,092.
Curvilinear Corner "L" Shape Worksurface 24″ Deep Return Left 30″ Deep Return Right 	48″	48″	24″	30″	1¼″	**D1L 4848SDN**	603.	663.	723.	1,092.
	48″	60″	24″	30″	1¼″	**D1L 4860SDN**	688.	758.	823.	1,120.
	48″	66″	24″	30″	1¼″	**D1L 4866SDN**	722.	794.	866.	1,148.
	48″	72″	24″	30″	1¼″	**D1L 4872SDN**	758.	832.	906.	1,178.
	60″	48″	24″	30″	1¼″	**D1L 6048SDN**	675.	741.	810.	1,208.
	66″	48″	24″	30″	1¼″	**D1L 6648SDN**	708.	779.	853.	1,237.
	72″	48″	24″	30″	1¼″	**D1L 7248SDN**	745.	819.	893.	1,266.
Curvilinear Corner "L" Shape Worksurface 30″ Deep Return Left 24″ Deep Return Right 	48″	48″	30″	24″	1¼″	**D1L 4848DSN**	603.	663.	723.	1,092.
	48″	60″	30″	24″	1¼″	**D1L 4860DSN**	675.	741.	810.	1,120.
	48″	66″	30″	24″	1¼″	**D1L 4866DSN**	708.	779.	853.	1,148.
	48″	72″	30″	24″	1¼″	**D1L 4872DSN**	745.	819.	893.	1,178.
	60″	48″	30″	24″	1¼″	**D1L 6048DSN**	688.	758.	823.	1,208.
	66″	48″	30″	24″	1¼″	**D1L 6648DSN**	722.	794.	866.	1,237.
	72″	48″	30″	24″	1¼″	**D1L 7248DSN**	758.	832.	906.	1,266.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are ½″ less than shown above.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Band Finish

Order Code

Worksurfaces

Example:	**D1L 4860SDN, 117, 117**
D1L 4860SDN	Pattern Number
117	Soft Grey Laminate
117	Soft Grey edge band

Included with:

Worksurfaces

- Worksurface
- Panel-to-worksurface bracket

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 2 center-located edge grommets
- Woodgrain ABS edge
- Metal edge
- Techwood

To specify edge grommets, replace the **"N"** suffix from the pattern number with **"G"**
Add $28

Note: An overdesk unit will not align with the width of a corner worksurface due to the ½″ wire drop gap. The overdesk will be ½″ too wide.

Peninsula Worsurfaces
“D”, “P”, “9” and Blended “D” Specifications

“D”, Blended “D”, Conferencing, “P” and “9” Shape Peninsula Worksurfaces

Dividends Horizon peninsula worksurfaces mount perpendicular to panels of the same width to provide conferencing area within a workstation.

“D”, “P” and “9” tops are supported by panel-to-worksurface brackets on the flat end and a support column, T leg or A leg support at the free end. Adjacent worksurfaces can attach to peninsula tops with flat brackets.

All brackets and supports are ordered separately. “D”, “P” and “9” shape peninsula worksurfaces may be used in freestanding applications.

“D” Shaped Peninsula

Available Sizes
- Depths: 24", 30" and 36"
- Widths: 48", 60", 66" and 72"
- Thickness: 1 1/4"

"P" and "9" Shaped Peninsula
Available Sizes
- Depth: 30" panel depth
- Widths: 66", 72" and 78"
- Conferencing diameter: 36" and 42"
- Thickness: 1 1/4"

Blended “D” Peninsula

Available Sizes
- Depths: 48"
- Widths: 72" and 66"
- Thickness: 1 1/4

Conferencing Worksurfaces
- Depth: 48"
- Width: 60"
- Thickness: 1 1/4"

“D” and “P” Shape Peninsula Worksurfaces



Blended "D" Shape Peninsula Worksurface



(Left hand shown)

Conferencing Worksurface Dimensions



Peninsula Worsurfaces
"D", "P", "9" and Blended "D" Mixed Depths

description	type	w *	w	d	dia.	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
"D" Peninsula Worksurface Laminate No Grommets		48″	47 13/16″	23 13/16″		1 1/4″	**D1D 4824N**	$414.	$456.	$496.	$1,026.
		48″	47 13/16″	29 13/16″		1 1/4″	**D1D 4830N**	456.	500.	548.	1,060.
		60″	59 13/16″	29 13/16″		1 1/4″	**D1D 6030N**	582.	641.	698.	1,094.
		66″	65 13/16″	29 13/16″		1 1/4″	**D1D 6630N**	636.	697.	762.	1,128.
		72″	71 13/16″	29 13/16″		1 1/4″	**D1D 7230N**	668.	734.	802.	1,161.
		72″	71 13/16″	35 13/16″		1 1/4″	**D1D 7236N**	730.	804.	878.	1,196.
Blended "D" Peninsula Worksurface (Left hand shown)	LH w/ 24″ return depth	66″	65 13/16″	47 13/16″		1 1/4″	**D1BD6648SL**	676.	745.	811.	2,394.
		72″	71 13/16″	47 13/16″		1 1/4″	**D1BD7248SL**	690.	761.	828.	2,416.
	LH w/ 30″ return depth	66″	65 13/16″	47 13/16″		1 1/4″	**D1BD6648DL**	711.	787.	855.	2,394.
		72″	71 13/16″	47 13/16″		1 1/4″	**D1BD7248DL**	736.	811.	886.	2,416.
	RH w/ 24″ return depth	66″	65 13/16″	47 13/16″		1 1/4″	**D1BD6648SR**	676.	745.	811.	2,394.
		72″	71 13/16″	47 13/16″		1 1/4″	**D1BD7248SR**	690.	761.	828.	2,416.
	RH w/ 30″ return depth	66″	65 13/16″	47 13/16″		1 1/4″	**D1BD6648DR**	711.	787.	855.	2,394.
		72″	71 13/16″	47 13/16″		1 1/4″	**D1BD7248DR**	736.	811.	886.	2,416.
Conferencing worksurface (left hand shown)		60″	59 13/16″	48″	24″	1 1/4″	**DB1BD48SL**	930.	1,024.	1,117.	2,370.
		60″	59 13/16″	48″	24″	1 1/4″	**DB1BD48SR**	930.	1,024.	1,117.	2,370.
Peninsula Worksurface-Laminate No Grommets (9-shaped shown)	P-shaped	66″	65 13/16″	29 13/16″	36″	1 1/4″	**D1P 6630N**	664.	728.	796.	1,533.
		72″	71 13/16″	29 13/16″	42″	1 1/4″	**D1P 7230N**	677.	746.	812.	1,576.
		78″	77 13/16″	29 13/16″	42″	1 1/4″	**D1P 7830N**	760.	834.	908.	1,621.
	9-shaped	66″	65 13/16″	29 13/16″	36″	1 1/4″	**D19 6630N**	664.	728.	796.	1,533.
		72″	71 13/16″	29 13/16″	42″	1 1/4″	**D19 7230N**	677.	746.	812.	1,576.
		78″	77 13/16″	29 13/16″	42″	1 1/4″	**D19 7830N**	760.	834.	908.	1,621.

w* = nominal width
Dimensions listed under w d t are actual to the nearest 1/16″

Ordering Information

"D" Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

"D" Worksurface

Example:	**D1H 6030, 114, 114**
D1H 6030	Pattern Number
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurface

Note: Support column and panel-to-worksurface brackets must be ordered separately.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify an edge grommet, replace **"N"** suffix from pattern number with **"G".**
Add $18.

Curvilinear Half- and Corner-Round Worksurfaces
Specifications

Curvilinear Half-Round Worksurfaces
Curvilinear half-round worksurfaces are sized to match up to the width of two back-to-back 24" deep or two back-to-back 30" deep freestanding desks.

Panel-supported half-round worksurfaces are notched along the flat end to accommodate the panel end trim.

Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the half-round worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes
- Depths: 18" and 24"
- Widths: 48" and 63"
- Thickness: 1 1/4

Note: All Dividends Horizon worksurfaces include a 1/2" wire drop at the rear edge. When used back to back with Half-Round worksurface, these two 1/2" wire drops will meet to form a 1" space between worksurfaces.

Transition Worksurfaces
Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the transition worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes
- Depths: 24", 36", 48"
- Widths: 48"
- Thickness: 1 1/4

Corner Round Worksurfaces
Corner-round worksurfaces are designed to "finish" a run of panel-mounted worksurfaces. Corner-round may be specified in two ways.

In a 90° "L" configuration, a notched corner-round worksurface is used to wrap around the panels. Two cantilevers and flat brackets (must be ordered separately) support the corner-round worksurface.

In an end run configuration, the corner-round worksurface is handed and must be specified as a left-hand or a right-hand top. One cantilever with a flat bracket and one panel-to-worksurface bracket (must be ordered separately) support the corner-round top.

Available Sizes
- Depth: 24"
- Width: 24"
- Thickness: 1 1/4"

Optional Edge Grommets
Grommets are not available for worksurfaces on this page.

Curvilinear Half-Round Worksurfaces (without panels)



Curvilinear Half-Round Worksurfaces (with panels)



Corner-Round Worksurface

Notched Corner Worksurfae

Corner-Round Applications



Corner-Round - Notched
"L" Configuration



Corner-Round - End Run
Configuration (right-hand shown)
Quarter-round Surface

Curvilinear Half- and Corner-Round Worksurfaces
Mixed Depths

description	type	w	return depth	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Half-Round Worksurface	w/o panels	48″	18″	1¼″	**D1H4818**	$359.	$397.	$432.	$987.
	w/o panels	60″	24″	1¼″	**D1H6024**	495.	546.	595.	1,073.
	w/panels	51″	18″	1¼″	**D1H5118P**	367.	404.	439.	1,029.
	w/panels	63″	24″	1¼″	**D1H6324P**	501.	553.	604.	1,117.
Transition Worksurface	w panels	51″	24″	1¼″	**D2H5124P**	441.	485.	528.	1,146.
	w panels	51″	36″	1¼″	**D2H5136P**	450.	493.	542.	1,186.
	w panels	51″	48″	1¼″	**D2H5148P**	458.	503.	551.	1,222.
	w/o panels	48″	24″	1¼″	**D2H4824**	436.	477.	521.	1,036.
	w/o panels	48″	36″	1¼″	**D2H4836**	442.	486.	533.	1,073.
	w/o panels	48″	48″	1¼″	**D2H4848**	453.	496.	544.	1,110.
Corner Round Worksurface	left	23 13/16″	23 1/2″	1¼″	**D1CRL24**	193.	210.	229.	840.
	notched	23 1/2″	23 1/2″	1¼″	**D1CRN24**	193.	210.	229.	840.
	right	23 13/16″	23 1/2″	1¼″	**D1CRR24**	193.	210.	229.	840.

Ordering Information

Half-Round Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Transition Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Corner-Round Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Half-Round Worksurface

Example:	**D1H 5118P, 118, 118**
D1H 5118P	Pattern Number
118	Bright White Laminate
118	Bright White Edge Band

Transition Worksurface

Example:	**D2H 5136P, 117, 117**
D2H 5136P	Pattern Number
117	Soft Grey Laminate
117	Soft Grey Edge Band

Included with:

Half-Round Worksurface

- Worksurface
- 2 flat brackets

Note: Support column must be ordered separately.

Transition Worksurface

- Worksurface
- 2 flat brackets

Note: Support column must be ordered separately.

Corner Round Worksurface

- Worksurface

Note: 2 cantilevers must be ordered separately.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Half-Round Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Transition Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Corner-Round Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Curvilinear Half-Round and Transition Worksurface Option

Add an 'F' suffix to the pattern number when using with flat profile panel trim.

Transaction Counter Worksurfaces
15" Deep
Specifications

15"D Counter Worksurfaces
Dividends Horizon 15"D counter worksurfaces attach to the tops of 42" high panels to provide a transaction area within workstations. Three types are available:

- Straight
- Square corner
- Quarter-round corner

Available Sizes
- Depth: 15"
- Widths: 24" to 96"
- Thickness: 1 1/4"

Straight Counter Worksurface Support
Straight counter worksurfaces can span single or multiple panels. Counter worksurfaces are supported by four counter worksurface brackets which are included with the straight counter worksurfaces. Counter worksurface brackets are required at panel or post junctions for proper support.

Note: High-low panel end trim must be field cut when using countertops in a high-low straight panel run application.

Note: Counter worksurfaces may NOT be used with on any screens or 36H panels.

Square and Quarter-Round Corner Counter Worksurfaces
Square corners allow rectilinear "L", "T" and "X" configurations while quarter-round corners allow radiused "L" configurations. When using corner counter worksurfaces, all adjoining straight counter worksurfaces must be 6" less than panel(s) width dimension. Square and quarter-round counter worksurfaces are supported by flat brackets which are included with corner worksurfaces. Additional support is provided by counter worksurface brackets from the adjoining straight counter worksurfaces.

Square-corner counter worksurfaces include three flat brackets while quarter-round counters include two flat brackets. Flat brackets are dark grey finish.

Counter Worksurface Corner Applications
Suggested applications and configurations are illustrated below.

Note: When connecting a 15" deep counter worksurface with either corner counter worksurface, specify 6" shorter than the required width to accommodate the width of the corner counter worksurface.

Counter Worksurface Supports
Straight counter worksurfaces 24" to 48" wide include four counter worksurface brackets while straight counters 54" to 96" wide include six counter worksurface brackets.

15"D Counter Worksurface



15"D Square-Shape Counter Worksurface

15"D Quarter Round Counter Worksurface

15"D Counter Worksurface Sizes Available



15"D Counter Worksurface Applications



Transaction Counter Worksurfaces
Rectangular, Square Corner and Quarter-round Corner
15″ Deep

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
15″ Deep Quarter-Round Shape Corner Counter Worksurface	15″	14 13/16″	15″	1 1/4″	**D1R 1515C**	$190.	$210.	$230.	$769.
15″ Deep Square-Shape Corner Counter Worksurface	15″	14 13/16″	15″	1 1/4″	**D1R 1515S**	174.	194.	210.	482.
15″ Deep Rectangular Counter Worksurface	24″	23 13/16″	15″	1 1/4″	**D1R 2415**	218.	240.	262.	497.
	30″	29 13/16″	15″	1 1/4″	**D1R 3015**	236.	260.	282.	519.
	36″	35 13/16″	15″	1 1/4″	**D1R 3615**	242.	266.	290.	544.
	42″	41 13/16″	15″	1 1/4″	**D1R 4215**	243.	267.	291.	565.
	48″	47 13/16″	15″	1 1/4″	**D1R 4815**	243.	267.	291.	588.
	54″	54 13/16″	15″	1 1/4″	**D1R 5415**	252.	277.	305.	609.
	60″	59 13/16″	15″	1 1/4″	**D1R 6015**	267.	295.	322.	632.
	66″	65 13/16″	15″	1 1/4″	**D1R 6615**	277.	306.	334.	654.
	72″	71 13/16″	15″	1 1/4″	**D1R 7215**	304.	334.	364.	677.
	78″	77 13/16″	15″	1 1/4″	**D1R 7815**	322.	353.	386.	698.
	84″	83 13/16″	15″	1 1/4″	**D1R 8415**	338.	373.	406.	721.
	90″	89 13/16″	15″	1 1/4″	**D1R 9015**	355.	391.	425.	745.
	96″	95 13/16″	15″	1 1/4″	**D1R 9615**	373.	410.	446.	766.

w* = nominal width
Dimensions listed under w d are actual to the nearest 1/16″

Ordering Information

15″D Counter Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish
4. Counter Worksurface Bracket Finish

Square-Shape Corner Counter Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Quarter-Round Shape Counter Worksurface

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

15″D Counter Worksurface

Example:	**D1R 3615, 117, 117, 117**
D1R 3615	Pattern Number
117	Soft Grey Laminate
117	Soft Grey Edge Band
117	Soft Grey Bracket Finish

Square-Shape Counter Worksurface

Example:	**D1R 1515S, 117, 117**
D1R 1515S	Pattern Number
117	Soft Grey Laminate
117	Soft Grey Edge Band

Quarter-Round Shape Counter Worksurface

Example:	**D1R 1515C, 117, 117**
D1R 1515C	Pattern Number
117	Soft Grey Laminate
117	Soft Grey Edge Band

Included with:

15″D Counter Worksurface

- Four counter worksurface brackets
- Attachment hardware

Square-Shape Counter Worksurface

- Three counter worksurface flat brackets
- Attachment hardware

Quarter-Round Shape Counter Worksurface

- Two counter worksurface flat brackets
- Attachment hardware

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

15″D Counter Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Square-Shape Counter Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Quarter-Round Shape Counter Worksurface

- Woodgrain ABS edge
- Metal edge
- Techwood edge

Rectangular with Cascade Edge
24″ and 30″ Deep

description	w	d	t	pattern no.	Solid	Woodgrain
24″ D Rectangular	24″	24″	1 ¼″	**DCE1R2424N**	$213.	$245.
	30″	24″	1 ¼″	**DCE1R3024N**	245.	282.
	36″	24″	1 ¼″	**DCE1R3624N**	270.	312.
	42″	24″	1 ¼″	**DCE1R4224N**	312.	359.
	48″	24″	1 ¼″	**DCE1R4824N**	350.	403.
	54″	24″	1 ¼″	**DCE1R5424N**	376.	432.
	60″	24″	1 ¼″	**DCE1R6024N**	408.	469.
	66″	24″	1 ¼″	**DCE1R6624N**	441.	506.
	72″	24″	1 ¼″	**DCE1R7224N**	461.	530.
	78″	24″	1 ¼″	**DCE1R7824N**	495.	568.
	84″	24″	1 ¼″	**DCE1R8424N**	523.	601.
	90″	24″	1 ¼″	**DCE1R9024N**	590.	677.
	96″	24″	1 ¼″	**DCE1R9624N**	644.	740.
30″ D Rectangular	24″	30″	1 ¼″	**DCE1R2430N**	271.	313.
	30″	30″	1 ¼″	**DCE1R3030N**	305.	350.
	36″	30″	1 ¼″	**DCE1R3630N**	339.	390.
	42″	30″	1 ¼″	**DCE1R4230N**	368.	422.
	48″	30″	1 ¼″	**DCE1R4830N**	408.	469.
	54″	30″	1 ¼″	**DCE1R5430N**	462.	531.
	60″	30″	1 ¼″	**DCE1R6030N**	508.	583.
	66″	30″	1 ¼″	**DCE1R6630N**	566.	651.
	72″	30″	1 ¼″	**DCE1R7230N**	590.	677.
	78″	30″	1 ¼″	**DCE1R7830N**	629.	723.
	84″	30″	1 ¼″	**DCE1R8430N**	669.	769.
	90″	30″	1 ¼″	**DCE1R9030N**	719.	827.
	96″	30″	1 ¼″	**DCE1R9630N**	769.	884.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example:	DCE1R4824N, 118
DCE1	Dividends Cascade Edge Worksurface
R	Rectangular
48	Width
24	Depth
N	No Grommet
118	Bright White finish

Included with:

Specify worksurface supports separately.

Available Colors:

Solid:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Woodgrain:

124 Medium Cherry
125 Natural Maple
126 Natural Cherry
127 Walnut

Options

Worksurfaces

- Center-Located Edge Grommet
  To specify, replace the **"N"** suffix from the pattern number with **"G".**
  Add $21.

Shaded area on worksurface drawings represents cascade edge detail.

Blended “D” and Curvilinear Corner with Cascade Edge

description	A	B	C	pattern no.	Solid	Woodgrain
Blended “D”	66″	48″	24″	**DCE1BD6648S(L/R)**	$863.	$992.
	66″	48″	30″	**DCE1BD6648D(L/R)**	907.	1,044.
	72″	48″	24″	**DCE1BD7248S(L/R)**	882.	1,016.
	72″	48″	30″	**DCE1BD7248D(L/R)**	940.	1,082.
	78″	48″	24″	**DCE1BD7848S(L/R)**	1,019.	1,172.
	78″	48″	30″	**DCE1BD7848D(L/R)**	1,054.	1,211.
right hand shown	84″	48″	24″	**DCE1BD8448S(L/R)**	1,047.	1,204.
	84″	48″	30″	**DCE1BD8448D(L/R)**	1,113.	1,279.
Blended “L”	36″	24″	24″	**DCE1L3636SSN**	533.	614.
	42″	24″	24″	**DCE1L4242SSN**	644.	740.
	42″	24″	30″	**DCE1L4242SDN**	765.	878.
	42″	30″	24″	**DCE1L4242DSN**	765.	878.
	48″	24″	24″	**DCE1L4848SSN**	723.	832.
	48″	24″	30″	**DCE1L4848SDN**	866.	996.
	48″	30″	24″	**DCE1L4848DSN**	866.	996.
	48″	30″	30″	**DCE1L4848DDN**	777.	894.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example:	**DCE1BD7248SL, 118**
DCE1	Dividends Cascade Edge worksurface
BD	Blended “D”
72	Width
48	Depth
S	24″d return
L	Extended Left
118	Bright White

Included with:

Available Colors:

Solid:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Woodgrain:

124 Medium Cherry
125 Natural Maple
126 Natural Cherry
127 Walnut

Options

Worksurfaces

- Center-Located Edge Grommet (Blended “L” only)To specify, replace the **“N”** suffix from the pattern number with **“G”. Add $42.**

Note: Support column and panel-to-worksurface brackets must be ordered separately.

Shaded area on worksurface drawings represents cascade edge detail.

Note: When wood grain or brushed laminates are specified on Cascade corner worksurfaces with two “A” sides of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add $25 to the list price for diagonal grain (D) selection.

Blended “L” with Cascade Edge

description	Width B	Width C	Width A	Width D	t	pattern no.	Solid	Woodgrain
Blended “L” 	42″	60″	24″	24″	1¼″	**DCE1L4260SSN**	$884.	$1,017.
	42″	66″	24″	24″	1¼″	**DCE1L4266SSN**	907.	1,044.
	42″	72″	24″	24″	1¼″	**DCE1L4272SSN**	941.	1,084.
	42″	78″	24″	24″	1¼″	**DCE1L4278SSN**	953.	1,094.
	48″	60″	24″	24″	1¼″	**DCE1L4860SSN**	896.	1,029.
	48″	60″	24″	30″	1¼″	**DCE1L4860SDN**	878.	1,012.
	48″	60″	30″	24″	1¼″	**DCE1L4860DSN**	878.	1,012.
	48″	66″	24″	24″	1¼″	**DCE1L4866SSN**	928.	1,066.
	48″	66″	24″	30″	1¼″	**DCE1L4866SDN**	924.	1,063.
	48″	66″	30″	24″	1¼″	**DCE1L4866DSN**	924.	1,063.
	48″	72″	24″	24″	1¼″	**DCE1L4872SSN**	962.	1,106.
	48″	72″	24″	30″	1¼″	**DCE1L4872SDN**	967.	1,113.
	48″	72″	30″	24″	1¼″	**DCE1L4872DSN**	967.	1,113.
	48″	78″	24″	24″	1¼″	**DCE1L4878SSN**	1,060.	1,219.
	48″	84″	24″	24″	1¼″	**DCE1L4884SSN**	1,191.	1,371.
	60″	42″	24″	24″	1¼″	**DCE1L6042SSN**	884.	1,017.
	60″	48″	24″	24″	1¼″	**DCE1L6048SSN**	896.	1,029.
	60″	48″	24″	30″	1¼″	**DCE1L6048SDN**	878.	1,012.
	60″	48″	30″	24″	1¼″	**DCE1L6048DSN**	878.	1,012.
	66″	42″	24″	24″	1¼″	**DCE1L6642SSN**	907.	1,044.
	66″	48″	24″	24″	1¼″	**DCE1L6648SSN**	928.	1,066.
	66″	48″	24″	30″	1¼″	**DCE1L6648SDN**	924.	1,063.
	66″	48″	30″	24″	1¼″	**DCE1L6648DSN**	924.	1,063.
	72″	42″	24″	24″	1¼″	**DCE1L7242SSN**	941.	1,084.
	72″	48″	24″	24″	1¼″	**DCE1L7248SSN**	962.	1,106.
	72″	48″	24″	30″	1¼″	**DCE1L7248SDN**	967.	1,113.
	72″	48″	30″	24″	1¼″	**DCE1L7248DSN**	967.	1,113.
	78″	42″	24″	24″	1¼″	**DCE1L7842SSN**	953.	1,094.
	78″	48″	24″	24″	1¼″	**DCE1L7848SSN**	1,060.	1,219.
	84″	48″	24″	24″	1¼″	**DCE1L8448SSN**	1,191.	1,371.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example:	DCE1L4872SDG,114
DCE1	Dividends Cascade Edge worksurface
L	Blended “L”
48	Width
72	Depth
S	24″d, left side
D	30″d, right side
G	Grommet
114	Folkstone Grey

Included with:

Available Colors:

Solid:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Woodgrain:

124 Medium Cherry
125 Natural Maple
126 Natural Cherry
127 Walnut

Options

Worksurfaces

- Center-Located Edge Grommet
  To specify, replace the **“N”** suffix from the pattern number with **“G”**.
  Add $42.

Note: Specify the panel-to-worksurface brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

Half Round and Corner Round with Cascade Edge

description	w	d	t	pattern no.	Solid	Woodgrain
Half Round	48″	18″	1¼″	**DCE1H4818**	$461.	$530.
	48″	18″	1¼″	**DCE1H4818P**	461.	530.
	60″	24″	1¼″	**DCE1H6024**	634.	731.
	60″	24″	1¼″	**DCE1H6024P**	634.	731.
LH Corner Round	24″	24″	1¼″	**DCE1CR24L**	245.	282.
RH Corner Round	24″	24″	1¼″	**DCE1CR24R**	245.	282.
Notched Corner Round	24″	24″	1¼″	**DCE1CR24N**	245.	282.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example:	DCE1H4818P,117
DCE1	Dividends Cascade Edge worksurface
H	Half Round
48	Width
18	Depth
P	Notched for panel
117	Soft Grey

Included with:

Available Colors:

Solid:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Woodgrain:

124 Medium Cherry
125 Natural Maple
126 Natural Cherry
127 Walnut

Options

P= Notched for panel

Note: Specify all support brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

Wave End with Cascade Edge

description	1	2	3	A	B	t	pattern no.	Solid	Woodgrain
Wave End, RH	36″	30″	24″	3″	15″	1¼″	**DCE1W362430N**	$573.	$659.
	42″	30″	24″	9″	15″	1¼″	**DCE1W422430N**	602.	693.
	48″	30″	24″	15″	15″	1¼″	**DCE1W482430N**	645.	742.
	72″	30″	24″	30½″	23½″	1¼″	**DCE1W722430N**	821.	942.



shown with grommet

Wave End, LH	36″	24″	30″	15″	3″	1¼″	**DCE1W363024N**	573.	659.
	42″	24″	30″	15″	9″	1¼″	**DCE1W423024N**	602.	693.
	48″	24″	30″	15″	15″	1¼″	**DCE1W483024N**	645.	742.
	72″	24″	30″	23½″	30½″	1¼″	**DCE1W723024N**	821.	942.



Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example:	DCE1W483024N,118
DCE1	Dividends Cascade Edge worksurface
W	Wave End
48	Width
30	30″d, left side
24	24″d, right side
N	No grommet
118	Bright White

Included with:

Available Colors:

Solid:

114 Folkstone Grey
117 Soft Grey
118 Bright White
119 Pumice

Woodgrain:

124 Medium Cherry
125 Natural Maple
126 Natural Cherry
127 Walnut

Options

Worksurfaces

- Center-Located Edge Grommet
  To specify, replace the **"N"** suffix from the pattern number with **"G".**
  Add $21.

Note: Specify all support brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

This page intentionally left blank

Panel Mounted Worksurface Brackets
Specifications

Worksurface Supports
Worksurfaces are shipped without supports which must be ordered separately.

A variety of worksurface supports are available. They include:
- Cantilevers
- Flat brackets
- Panel-to-worksurface brackets

In addition, freestanding pedestals and end units can also be used for worksurface support.

Cantilevers and panel-to-worksurface brackets are used strictly in panel-mount applications while flat brackets, pedestals and end units can be used in both panel-mounted and freestanding applications.

Cantilevers
Cantilevers provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary cantilever applications include:

- Corner worksurfaces
- Worksurface mid-span support
- 18" and 24" deep rectangular worksurface support in moderate load situations

Note: For heavy load applications, panel-to-worksurface brackets, freestanding pedestal, panel-mount C-leg, or open support leg is recommended. In applications involving 30" deep worksurfaces, cantilevers are only recommended for mid-span support.

Cantilevers are left- and right-handed and are available in three depths (18", 24" and 30") to support 18", 24" and 30" deep worksurfaces.

Note: 36" deep worksurfaces cannot be supported by cantilevers.

- **Attachment**: Cantilevers lock into the panel's slotted standard and adjust vertically in 1 $^1/_2$" increments. Cantilevers are left- or right-handed
- **Construction**: 14-gauge, black painted steel

Flat Brackets
Flat brackets are used to join a primary worksurface with an adjacent return or bridge unit worksurface at the same height.

Flat brackets are available in three depths to support 18", 24" and 30" deep worksurface returns.

- **Attachment**: Flat brackets attach to pre-drilled positions on the undersides of worksur-faces with provided screws
- **Construction**: 14-gauge painted steel

Shared Cantilevers
Adjacent worksurfaces can share a single cantilever if the appropriate flat bracket is used in conjunction with the appropriate cantilever (i.e. 18" cantilever with 18" flat bracket).

Panel-to-Worksurface Brackets, Worksurface Support

Panel-to-worksurface brackets are used to:
- Mount worksurfaces perpendicular to panels
- Anchor the rear corner of corner worksurfaces to panels
- Secure a panel to a pedestal

Panel-to-worksurface brackets provide the most secure panel-hung support for heavily loaded worksurfaces.

Panel worksurface brackets are handed left or right.

Note: The panel width must match the worksurface depth for panel-to-worksurface brackets to connect worksurfaces perpendicular to panels.

- **Attachment**: Panel-to-worksurface brackets lock into the panel's slotted standard and adjust vertically in 1 $^1/_2$" increments
- **Construction**: 14-gauge painted steel

Panel-to-Worksurface Brackets, Stabilizing Support
Panel-to-worksurface brackets are also used in conjunction with pedestals to stabilize panel runs.

In applications where the worksurface is "wrapped" with a return panel and a pedestal is installed below the worksurface at the "wrapped" end, a panel-to-worksurface bracket is used at the front corner of the worksurface. In pedestal applications, the panel-to-worksurface bracket connects the pedestal at the rear corner of the pedestal to the panel (as shown in the illustration below) or front corner of the pedestal to the panel when a return wing panel is used.

Panel-to-Worksurface Brackets, Off-Module Support
For applications where the width of the panel exceeds the depth of the worksurface, specify off-module panel-to-worksurface brackets which allow off module worksurface support.

Worksurface Reinforcement
Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.

Panel Mounted Worksurface Bracket Application



Flat Bracket Application



Shared Cantilever Application



Stabilizing Support



Off-Module Support



Worksurface Reinforcement Panel Hung Application



Panel Mounted Worksurface Brackets
Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets

description	type	w	d	h	pattern no.	black	P1	P2	P3
Cantilever Bracket Left or Right (Left Shown) (package of 10)	For 18″D WS	1 5/16″	12 3/16″	11 13/16″	**DB1C 18 (L or R) 10**	$378.	$397.	$416.	$434.
	For 24″D WS	1 5/16″	20 5/8″	10 1/2″	**DB1C 24 (L or R) 10**	471.	494.	517.	543.
	For 30″D WS	1 5/16″	26 15/16″	10 1/2″	**DB1C 30 (L or R) 10**	673.	707.	739.	774.
Cantilever Brackets, Left or Right (Left Shown) (single pack)	For 18″D WS	1 5/16″	12 3/16″	11 13/16″	**DB1C 18 (L or R)**	38.	40.	42.	43.
	For 24″D WS	1 5/16″	20 5/8″	10 1/2″	**DB1C 24 (L or R)**	49.	52.	55.	57.
	For 30″D WS	1 5/16″	26 15/16″	10 1/2″	**DB1C 30 (L or R)**	69.	72.	76.	79.
Cantilever Brackets for 120° Planning (Left Shown)(single pack)		20 5/8″″		1 5/16″	**DB120C (L or R)**	49.	52.	55.	57.
Flat Bracket (single pack)	For 18″D WS	3 3/4″	8 5/16″		**DB1F18SP**	15.	n/a	n/a	n/a
	For 24″D WS	3 3/4″	14 5/8″		**DB1F24SP**	27.	n/a	n/a	n/a
	For 30″D WS	3 3/4″	20 15/16″		**DB1F30SP**	31.	n/a	n/a	n/a
Flat Bracket (package of 10)	For 18″D WS	3 3/4″	8 5/16″		**DB1F18TP**	128.	n/a	n/a	n/a
	For 24″D WS	3 3/4″	14 5/16″		**DB1F24TP**	212.	n/a	n/a	n/a
	For 30″D WS	3 3/4″	20 5/16″		**DB1F30TP**	244.	n/a	n/a	n/a
Worksurface Reinforcement 		54″	4″		**DB1WR54**	61.	n/a	n/a	n/a
		60″	4″		**DB1WR60**	62.	n/a	n/a	n/a
		66″	4″		**DB1WR66**	65.	n/a	n/a	n/a
		72″	4″		**DB1WR72**	67.	n/a	n/a	n/a

Ordering Information

Panel-to-Worksurface Bracket, Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket, Off Module

Example:	**DB1P WS36, 113**
DB1P WS36	Pattern Number
113	Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket, Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket, Off Module

Panel Mounted Worksurface Brackets
Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets

description	type	w	d	h	pattern no.	black	P1	P2	P3
Panel-to-Worksurface Brackets	Left (Shown)	3″	3″	4 11/16″	**DB1PWSL**	$7.	$7.	$8.	$9.
	Pair	3″	3″	4 11/16″	**DB1PWSP**	14.	14.	16.	18.
	Right	3″	3″	4 11/16″	**DB1PWSR**	7.	7.	8.	9.
Panel-to-Worksurface Brackets for use with Worksurface Height Panels ONLY	Left	3″	3″	4 11/16″	**DB1PWSLWH**	22.	24.	26.	28.
	Pair	3″	3″	4 11/16″	**DB1PWSPWH**	44.	48.	52.	56.
	Right	3″	3″	4 11/16″	**DB1PWSRWH**	22.	24.	26.	28.
Panel-to-Worksurface Brackets (Off Module) 	For 24″ Wide Panel				**DB1PWS24**	n/a	65.	70.	72.
	For 30″ Wide Panel				**DB1PWS30**	n/a	68.	74.	78.
	For 36″ Wide Panel				**DB1PWS36**	n/a	71.	78.	82.
	For 42″ Wide Panel				**DB1PWS42**	n/a	76.	85.	91.
	For 48″ Wide Panel				**DB1PWS48**	n/a	82.	91.	94.

Ordering Information

Panel-to-Worksurface Bracket, Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket, Off Module

Example:	**DB1P WS36, 113**
DB1P WS36	Pattern Number
113	Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket, Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket, Off Module

This page intentionally left blank

Screen-to-Worksurface Brackets
Specifications

Screen-to-Worksurface Brackets, Worksurface Support

Screen-to-worksurface brackets are used to:

- Mount worksurfaces perpendicular to screens
- Anchor the rear corner of corner worksurfaces to screens

Screen-to-worksurface brackets provide the most secure screen-hung support for heavily loaded worksurfaces.

Screen worksurface brackets are handed left or right.

Note: The screen width must match the worksurface depth for screen-to-worksurface brackets to connect worksurfaces perpendicular to screens.

- **Attachment**: Screen-to-worksurface brackets lock into the screen's slotted standard and adjust vertically in 1 $^{1}/_{2}$" increments
- **Construction**: 14-gauge painted steel

Screen-to-Worksurface Support Application



Screen-to-Worksurface Brackets



Screen-to-Worksurface Brackets
Screen mid-span worksurface support

description	type	w	d	h	pattern no.	P1	P2	P3
Screen-to-Worksurface Brackets (Individual)	Left				**DB1SWSL**	$7.	$9.	$12.
	Right				**DB1SWSR**	7.	9.	12.
Screen-to-Worksurface Brackets (Pair)	Left/Right				**DB1SWSP**	14.	18.	24.
Screen Mid-Span Worksurface Support	left hand				**DBSMLH**	24.	25.	26.
	right hand				**DBSMRH**	24.	25.	26.

Ordering Information

Panel-to-Worksurface Bracket, Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket, Off Module

Example:	**DB1P WS36, 113**
DB1P WS36	Pattern Number
113	Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket, Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket, Off Module

Panel Mounted Worksurface Supports
Specifications

Panel-Mounted C-Legs, Open Support Legs, and Worksurface End Panels
Panel-mounted C-legs, open support legs, and worksurface end panels provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary panel-mounted support applications include:
- Rectangular worksurface end support for 24" and 30" depth worksurfaces
- Mid span worksurface support for 24" and 30" depth worksurfaces
- Corner and split top corner worksurface support
- Support for heavier worksurface load applications
- Shared support between two adjacent worksurfaces

Note: 18" deep and 36" worksurface may not be used with panel-mounted C-leg worksurface support.

Construction
C-leg support:
- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: $^{3}/_{16}$" steel plate

Open Support Leg:
- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: $^{3}/_{16}$" steel plate

Worksurface End Panel:
- Panel: 20 gauge steel
- Mounting brackets: 14 gauge steel

Note: Open support legs and worksurface end panels are only available in Knoll Core finishes

Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used on the end of a panel run.

Note: Worksurface end panels are for use with panels only and are non-handed.

Panel-Mounted C-Leg Support



Panel-Mounted C-Leg Support (radiused foot)



Open Support Leg



Worksurface End Panel



Panel Mounted Worksurface Supports
Open Support Leg, C-Leg and Worksurface End Panel

description	type	w	d	h	pattern no.	P1	P2	P3
Panel Mounted C-Leg Worksurface Support (Left-hand shown)	Left-hand C-Leg			26⅞″	**DB1CL24L**	$327.	$358.	$375.
	Right-hand C-Leg			26⅞″	**DB1CL 24R**	327.	358.	375.
	Shared C-Leg			26⅞″	**DB1CL24S**	346.	380.	399.
Panel Mounted C-Leg Worksurface Support Radiused Foot (Right-hand shown)	LH Shared Worksurface C-Leg			26⅞″	**DB2CL24LS**	410.	453.	471.
	LH Single Worksurface C-Leg			26⅞″	**DB2CL24L**	388.	426.	447.
	RH Shared Worksurface C-Leg			26⅞″	**DB2CL24RS**	410.	453.	471.
	RH Single Worksurface C-Leg			26⅞″	**DB2CL24R**	388.	426.	447.
Open Support Leg Panel Attachment 		3″	15″	26⅞″	**DB1LSP15( )**	312.	331.	345.
		3″	18″	26⅞″	**DB1LSP18( )**	312.	331.	345.
		3″	24″	26⅞″	**DB1LSP24( )**	308.	325.	341.
		3″	30″	26⅞″	**DB1LSP30( )**	323.	338.	355.
		3″	36″	26⅞″	**DB1LSP36( )**	342.	358.	375.
Open Support Leg Screen Attachment 		3″	15″	26⅞″	**DB1LSS15( )**	312.	331.	345.
		3″	18″	26⅞″	**DB1LSS18( )**	312.	331.	345.
		3″	24″	26⅞″	**DB1LSS24( )**	308.	325.	341.
		3″	30″	26⅞″	**DB1LSS30( )**	323.	338.	355.
		3″	36″	26⅞″	**DB1LSS36( )**	342.	358.	375.
Worksurface End Panel Panel Attachment		1¼″	15″	26⅞″	**DB1PSP15**	284.	311.	328.
		1¼″	18″	26⅞″	**DB1PSP18**	296.	327.	341.
		1¼″	24″	26⅞″	**DB1PSP24**	325.	357.	374.
		1¼″	30″	26⅞″	**DB1PSP30**	349.	384.	402.
		1¼″	36″	26⅞″	**DB1PSP36**	373.	410.	427.

Ordering Information

Panel-Mounted C-Leg Worksurface Support

1. Pattern Number
2. Paint Finish

Worksurface End Panel

1. Pattern Number
2. Paint Finish

Open Support Leg

1. Pattern Number
2. Paint Finish

Order Code

Panel Mounted C-Leg Worksurface Support

Example:	**DB1 CL24R, 117**
DB1 CL24R	Pattern Number
117	Soft Grey finish

Worksurface End Panel

Example:	**DB1 PSP 24**
DB1 PSP 24	Pattern Number
117	Soft Grey finish

Included with:

Panel-Mounted C-Leg Worksurface Support

- C-leg foot
- C-leg column
- Panel attachment bracket
- C-leg flat bracket
- Leveling glides

Worksurface End Panel

- Panel attachment bracket
- Leveling glides

Note: Open Support Legs are only available in Knoll core finishes.

Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used at the end of a panel run.

Options

Open Support Leg Option
(R) = Right-hand leg
(L) = Left-hand leg
(S) = Shared leg

Note: Worksurface end panels are for use with panels only.

Peninsula Worksurface Supports
Specifications

Round Support Column
4" diameter round column may be used to support the rounded end of panel-mounted curvilinear half-round, “D”, “P”, “9”, and blended “D” peninsula tops. Column is available in all Knoll core paint finishes

Construction
- Material: 4" diameter steel tube
- Mounting bracket: heavy gauge steel plate, 6 x 6

T-Support Column
The T-support column may be used to support the rounded end of a panel-mounted curvilinear half-round, “D”, “P”, “9”, and blended “D” peninsula tops. The T-support column is recommended for use with “D” peninsula worksurfaces used in freestanding applications. The T-support column is available in all Dividends paint finishes.

Construction
T-support column specifications:
- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: heavy gauge steel plate

T-End Unit
The T-end unit is used on the end of a freestanding “D” peninsula worksurface top. The T-end is available in a depth of 24" and 30" for use with “D”, “P” and “9” top depths of 24" and 30".

Construction
- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel

A Leg
An A leg may be used to support panel mounted curvilinear half-round, "D", "P", "9" and blended "D" peninsula tops. A legs are available in any Knoll Core paint finish.

Construction
- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: 14 gauge steel

Note: A legs are only available in Knoll Core finishes

Round Column with Panel “D” Worksurface



T-Support Base with Panel “D” Worksurface



T-End Unit with Freestanding “D” Worksurface



A-Leg with Panel "D" Worksurface



Peninsula Worksurface Supports
Round Support Column, T-Support Base and A Leg

description	w	d	h	pattern no.	Black (NA)	P1	P2	P3
T-End Unit	21 13/16″	12″	26 7/8″	**DD1TEU24**		$308.	$340.	$355.
	27 13/16″	12″	26 7/8″	**DD1TEU30**		338.	371.	387.
T-Support Base	23 1/2″	12″	26 7/8″	**DB1TB**		290.	320.	333.
Round Support Column	4″	4″	26 7/8″	**DB1S CR**	228.	250.	262.	281.
A Leg	3″	15″	26 7/8″	**DB1LS15A**		330.	363.	377.
	3″	18″	26 7/8″	**DB1LS18A**		341.	375.	389.
	3″	24″	26 7/8″	**DB1LS24A**		351.	386.	402.
	3″	30″	26 7/8″	**DB1LS30A**		364.	399.	415.
	3″	36″	26 7/8″	**DB1LS36A**		373.	410.	425.

Dimensions listed under w d t are actual to the nearest 1/16″

Ordering Information

T-End Unit
1. Pattern Number
2. Paint Finish

T-Support Base
1. Pattern Number
2. Paint Finish

A Leg
1. Pattern Number
2. Paint Finish

Round Support Column
1. Pattern Number
2. Paint Finish

Order Code

T-End Unit

Example:	**DD1TEU24, 115**
DD1TEU24	Pattern Number
115	Medium Grey Paint Finish

T-Support Base

Example:	**DB1TB, 115**
DB1TB	Pattern Number
115	Medium Grey Paint Finish

Round Support Column

Example:	**DB1SCR,118**
DB1SCR	Pattern Number
118	Bright White Paint Finish

Included with:

T-End Unit
- Worksurface

T-Support Base

Note: The A leg is for use in peninsula worksurface applications only. It is not to be used in freestanding applications.

Note: A Legs are only available in Knoll core finishes.

Options

T-End Unit

T-Support Base

A Leg

Round Support Column

Y Leg Tables
Freestanding and Credenza Supported Specifications

Dividends Horizon Tables
The design details of Dividends Horizon tables are consistent with the scale and visual language of the Dividends Horizon system. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon Y Leg tables are available in two versions:
- Freestanding Y Leg
- Credenza Supported Y Leg

Freestanding Y Leg Tables
Freestanding Y Leg tables include a worksurface and base assembly. All freestanding table sizes are available with two Y legs and a horizontal stretcher connecting the two columns.

In addition, 24 and 30 inch deep tables are available without a stretcher. Tables without stretcher include an integral worksurface support plate. 36 and 42 inch deep tables are available only with a stretcher.

Available Sizes
- Width: 60-96 inches
- Depth: 24-42 inches
- Height: 28-1/2 inches

Credenza Supported Y Leg Tables
The unique Dividends Horizon Credenza Supported Y Leg tables are designed to be used in concert with Dividends Horizon low credenzas, specified separately.

Credenza Supported Tables include one Y Leg, credenza support spacer, and aworksurface with integral stiffening plate.

Note: Credenza supported tables may be used with laminate or veneer top credenzas only, and are not compatible with steel top credenzas.

Available Sizes
- Width: 60-96 inches
- Depth: 24-36 inches
- Height: 28-1/2 inches

Optional Edge Grommet
Edge grommets are optional and can be factory installed centered along the rear edge of rectangular or racetrack freestanding or credenza supported Y Leg tables.

Construction
- Worksurface:
  - Material: 0.028 inch thick high pressure laminate or 0.6mm thick veneer on 1-1/8" particle board core
  - Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16 inch thick Techwood edge
- Bases:
  - Stretcher: extruded aluminum
  - Stiffening plate: 4 inch deep 12 gauge steel plate (length varies)
  - Foot: die cast aluminum
  - Column: extruded aluminum with 3/16 inch thick structural plate
  - Credenza support spacer: 2-15/16 inches high x 9-5/8 inches wide x 1-9/16 inches deep steel box with a flat bracket on top

Note: Dividends Horizon tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: The stiffening plate on tables without a stretcher prevents the field installation of a grommet or plexus box. (see illustration below)

24" Deep Freestanding Racetrack Y Leg Table with Stretcher

24" Deep Credenza Supported Racetrack Y Leg Table



24" Deep Freestanding Racetrack Y Leg Table without Stretcher



Y Leg Tables
Freestanding Rectangular Table Top 24″ and 30″ Deep

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24″ Deep Rectangular with (2) Y-Legs, No Grommet	60″	59 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY6024NS**	$1,546.	$1,702.	$1,770.	$1,772.	$1,949.	$2,028.
	66″	65 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY6624NS**	1,564.	1,721.	1,788.	1,799.	1,982.	2,061.
	72″	71 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY7224NS**	1,580.	1,739.	1,810.	1,830.	2,013.	2,094.
	78″	77 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY7824NS**	1,599.	1,757.	1,828.	1,860.	2,047.	2,128.
	84″	83 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY8424NS**	1,627.	1,789.	1,862.	1,890.	2,079.	2,162.
	90″	89 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY9024NS**	1,656.	1,823.	1,895.	1,918.	2,112.	2,195.
	96″	95 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ARY9624NS**	1,686.	1,855.	1,928.	1,948.	2,143.	2,230.

(with stretcher shown)

30″ Deep Rectangular with (2) Y-Legs, No Grommet	60″	59 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY6030NS**	1,585.	1,745.	1,816.	1,811.	1,991.	2,071.
	66″	65 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY6630NS**	1,609.	1,770.	1,841.	1,845.	2,029.	2,110.
	72″	71 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY7230NS**	1,629.	1,792.	1,865.	1,879.	2,067.	2,150.
	78″	77 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY7830NS**	1,652.	1,818.	1,891.	1,914.	2,105.	2,189.
	84″	83 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY8430NS**	1,684.	1,853.	1,926.	1,948.	2,143.	2,230.
	90″	89 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY9030NS**	1,714.	1,886.	1,961.	1,983.	2,179.	2,268.
	96″	95 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ARY9630NS**	1,746.	1,921.	1,997.	2,018.	2,218.	2,307.

(with stretcher shown)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Freestanding Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Freestanding Y Leg Table:

Example:	**DT1ARY6024NS, 114, 114, 114**
DT1	Dividends Horizon Table
A	2 Leg table assembly
R	Rectangular shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
S	Stretcher
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Freestanding Y Leg Table:

- (2) Y Legs
- Hardware kit
- Table top
- Stretcher or stiffening plate

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the “N” suffix from the pattern number with an “E” and add $17.

Stretcher Option:

- A stretcher is optional on 24″ and 30″ deep tables ONLY. To specify a table without a stretcher replace the “S” suffix from the pattern number with an “N”. Stretchers are required on 36″ and 42″ depths.

Y Leg Tables
Freestanding Rectangular Table Top 36″ and 42″ Deep

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36″ Deep Rectangular with (2) Y-Legs, No Grommet	60″	59 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY6036N**	$1,639.	$1,800.	$1,874.	$1,891.	$2,080.	$2,162.
	66″	65 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY6636N**	1,667.	1,833.	1,907.	1,927.	2,121.	2,204.
	72″	71 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY7236N**	1,695.	1,865.	1,941.	1,964.	2,161.	2,247.
	78″	77 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY7836N**	1,724.	1,897.	1,973.	2,001.	2,202.	2,290.
	84″	83 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY8436N**	1,752.	1,928.	2,005.	2,039.	2,243.	2,332.
	90″	89 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY9036N**	1,781.	1,959.	2,038.	2,076.	2,285.	2,374.
	96″	95 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY9636N**	1,811.	1,991.	2,071.	2,114.	2,325.	2,416.
42″ Deep Rectangular with (2) Y-Legs, No Grommet	84″	83 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ARY8442N**	1,797.	1,979.	2,059.	2,282.	2,510.	2,611.
	90″	89 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ARY9042N**	1,836.	2,021.	2,101.	2,314.	2,545.	2,646.
	96″	95 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ARY9642N**	1,864.	2,051.	2,132.	2,344.	2,579.	2,682.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Freestanding Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Freestanding Y Leg Table:

Example:	**DT1ARY6024NS, 114, 114, 114**
DT1	Dividends Horizon Table
A	2 Leg table assembly
R	Rectangular shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
S	Stretcher
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Freestanding Y Leg Table:

- (2) Y Legs
- Hardware kit
- Table top
- Stretcher or stiffening plate

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the “N” suffix from the pattern number with an “E” and add $17.

Stretcher Option:

- A stretcher is optional on 24″ and 30″ deep tables ONLY. To specify a table without a stretcher replace the “S” suffix from the pattern number with an “N”. Stretchers are required on 36″ and 42″ depths.

Y Leg Tables
Freestanding Racetrack Table Top 24″and 30″ Deep

description	w *	w	d	t	h	pattern number	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24″ Deep Racetrack with (2) Y-Legs, No Grommet	60″	59 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY6024NS**	$1,545.	$1,701.	$1,769.	$2,758.	$3,035.	$3,157.
	66″	65 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY6624NS**	1,594.	1,752.	1,823.	2,784.	3,062.	3,186.
	72″	71 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY7224NS**	1,641.	1,806.	1,877.	2,809.	3,092.	3,216.
	78″	77 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY7824NS**	1,688.	1,857.	1,931.	2,835.	3,120.	3,243.
	84″	83 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY8424NS**	1,717.	1,889.	1,964.	2,859.	3,147.	3,272.
	90″	89 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY9024NS**	1,746.	1,921.	1,997.	2,886.	3,175.	3,303.
	96″	95 13/16″	23 1/2″	1 1/4″	28 1/2″	**DT1ATY9624NS**	1,776.	1,953.	2,032.	2,912.	3,202.	3,332.

(with stretcher shown)

30″ Deep Racetrack with (2) Y-Legs, No Grommet	60″	59 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY6030NS**	1,607.	1,766.	1,838.	2,800.	3,081.	3,204.
	66″	65 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY6630NS**	1,651.	1,817.	1,889.	2,827.	3,111.	3,235.
	72″	71 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY7230NS**	1,696.	1,865.	1,941.	2,854.	3,140.	3,266.
	78″	77 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY7830NS**	1,741.	1,915.	1,991.	2,883.	3,171.	3,299.
	84″	83 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY8430NS**	1,774.	1,951.	2,029.	2,911.	3,201.	3,330.
	90″	89 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY9030NS**	1,807.	1,986.	2,066.	2,938.	3,231.	3,361.
	96″	95 13/16″	29 1/2″	1 1/4″	28 1/2″	**DT1ATY9630NS**	1,839.	2,023.	2,103.	2,965.	3,262.	3,393.

(with stretcher shown)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Freestanding Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Freestanding Y Leg Table:

Example:	**DT1ATY6024NS, 114, 114, 114**
DT1	Dividends Horizon Table
A	2 Leg table assembly
T	Racetrack shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
S	Stretcher
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Freestanding Y Leg Table:

- (2) Y Legs
- Hardware kit
- Table top
- Stretcher or stiffening plate

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the “N” suffix from the pattern number with an “E” and add $17.

Stretcher Option:

- A stretcher is optional on 24″ and 30″ deep tables ONLY. To specify a table without a stretcher replace the “S” suffix from pattern number with an “N”. Stretchers are required on 36″ and 42″ depths.

Y Leg Tables
Freestanding Racetrack Table Top
36″ and 42″ Deep

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36″ Deep Racetrack with (2) Y-Legs, No Grommet	60″	59 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY6036N**	$1,661.	$1,828.	$1,901.	$2,841.	$3,125.	$3,251.
	66″	65 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY6636N**	1,713.	1,884.	1,959.	2,872.	3,157.	3,284.
	72″	71 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY7236N**	1,764.	1,942.	2,020.	2,900.	3,190.	3,319.
	78″	77 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY7836N**	1,817.	1,997.	2,078.	2,930.	3,223.	3,353.
	84″	83 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY8436N**	1,845.	2,030.	2,110.	2,960.	3,256.	3,387.
	90″	89 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY9036N**	1,875.	2,062.	2,144.	2,989.	3,290.	3,421.
	96″	95 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY9636N**	1,903.	2,093.	2,176.	3,019.	3,322.	3,454.
42″ Deep Racetrack with (2) Y-Legs, No Grommet	84″	83 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ATY8442N**	1,889.	2,078.	2,160.	3,012.	3,314.	3,445.
	90″	89 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ATY9042N**	1,925.	2,119.	2,203.	3,044.	3,349.	3,481.
	96″	95 13/16″	42 1/2″	1 1/4″	28 1/2″	**DT1ATY9642N**	1,959.	2,156.	2,242.	3,074.	3,383.	3,518.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Freestanding Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Freestanding Y Leg Table:

Example:	**DT1ATY6024NS, 114, 114, 114**
DT1	Dividends Horizon Table
A	2 Leg table assembly
T	Racetrack shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
S	Stretcher
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Freestanding Y Leg Table:

- (2) Y Legs
- Hardware kit
- Table top
- Stretcher or stiffening plate

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the “N” suffix from the pattern number with an “E” and add $17.

Stretcher Option:

- A stretcher is optional on 24″ and 30″ deep tables ONLY. To specify a table without a stretcher replace the “S” suffix from pattern number with an “N”. Stretchers are required on 36″ and 42″ depths.

Y Leg Tables
Credenza Supported Rectangular Table Top
24", 30" and 36" Deep

description	w *	w	d	t	h	pattern no"	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY6024N**	$1,292.	$1,422.	$1,479.	$1,515.	$1,666.	$1,732.
	66"	65 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY6624N**	1,309.	1,440.	1,498.	1,543.	1,698.	1,765.
	72"	71 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY7224N**	1,325.	1,458.	1,517.	1,573.	1,730.	1,798.
	78"	77 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY7824N**	1,342.	1,477.	1,536.	1,604.	1,763.	1,833.
	84"	83 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY8424N**	1,371.	1,510.	1,570.	1,633.	1,794.	1,867.
	90"	89 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY9024N**	1,402.	1,541.	1,604.	1,661.	1,828.	1,900.
	96"	95 13/16"	23 1/2"	1 1/4"	28 1/2"	**DT1CRY9624N**	1,432.	1,574.	1,638.	1,691.	1,860.	1,934.
30" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY6030N**	1,329.	1,462.	1,520.	1,554.	1,709.	1,777.
	66"	65 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY6630N**	1,351.	1,486.	1,545.	1,587.	1,747.	1,817.
	72"	71 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY7230N**	1,372.	1,511.	1,571.	1,622.	1,784.	1,856.
	78"	77 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY7830N**	1,396.	1,535.	1,598.	1,656.	1,823.	1,895.
	84"	83 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY8430N**	1,428.	1,570.	1,633.	1,691.	1,860.	1,934.
	90"	89 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY9030N**	1,458.	1,606.	1,670.	1,725.	1,898.	1,973.
	96"	95 13/16"	29 1/2"	1 1/4"	28 1/2"	**DT1CRY9630N**	1,490.	1,641.	1,706.	1,758.	1,935.	2,012.
36" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY6036N**	1,410.	1,551.	1,613.	1,660.	1,827.	1,900.
	66"	65 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY6636N**	1,437.	1,579.	1,644.	1,695.	1,865.	1,939.
	72"	71 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY7236N**	1,463.	1,610.	1,673.	1,729.	1,902.	1,979.
	78"	77 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY7836N**	1,489.	1,639.	1,704.	1,764.	1,941.	2,019.
	84"	83 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY8436N**	1,526.	1,680.	1,746.	1,797.	1,978.	2,057.
	90"	89 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY9036N**	1,564.	1,720.	1,788.	1,833.	2,017.	2,096.
	96"	95 13/16"	35 1/2"	1 1/4"	28 1/2"	**DT1CRY9636N**	1,602.	1,761.	1,831.	1,867.	2,053.	2,135.



(credenza not included)



(credenza not included)



(credenza not included)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information

Credenza Supported Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Credenza Supported Y Leg Table:

Example:	**DT1CRY6024N, 114, 114, 114**
DT1	Dividends Horizon Table
C	Credenza support assembly
R	Rectangular shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Credenza Supported Y leg Table:

- (1) Y Leg
- (1) Credenza support spacer
- Hardware kit
- Table top
- Stiffening plate

Credenza must be specified separately

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add $17.

Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.

Y Leg Tables
Credenza Supported Racetrack Table Top
24", 30" and 36" Deep

description	w *	w	d	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24″ Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60″	59 13/16″	23 1/2″	28 1/2″	**DT1CTY6024N**	$1,290.	$1,419.	$1,477.	$2,526.	$2,778.	$2,853.
	66″	65 13/16″	23 1/2″	28 1/2″	**DT1CTY6624N**	1,338.	1,472.	1,531.	2,539.	2,794.	2,877.
	72″	71 13/16″	23 1/2″	28 1/2″	**DT1CTY7224N**	1,386.	1,524.	1,584.	2,553.	2,809.	2,897.
	78″	77 13/16″	23 1/2″	28 1/2″	**DT1CTY7824N**	1,434.	1,576.	1,640.	2,568.	2,825.	2,920.
	84″	83 13/16″	23 1/2″	28 1/2″	**DT1CTY8424N**	1,449.	1,594.	1,657.	2,581.	2,841.	2,942.
	90″	89 13/16″	23 1/2″	28 1/2″	**DT1CTY9024N**	1,465.	1,612.	1,675.	2,596.	2,855.	2,963.
	96″	95 13/16″	23 1/2″	28 1/2″	**DT1CTY9624N**	1,480.	1,628.	1,693.	2,610.	2,873.	2,985.
30″ Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60″	59 13/16″	29 1/2″	28 1/2″	**DT1CTY6030N**	1,351.	1,486.	1,545.	2,541.	2,795.	2,889.
	66″	65 13/16″	29 1/2″	28 1/2″	**DT1CTY6630N**	1,397.	1,536.	1,599.	2,570.	2,826.	2,924.
	72″	71 13/16″	29 1/2″	28 1/2″	**DT1CTY7230N**	1,442.	1,584.	1,649.	2,597.	2,857.	2,960.
	78″	77 13/16″	29 1/2″	28 1/2″	**DT1CTY7830N**	1,486.	1,636.	1,701.	2,625.	2,889.	2,995.
	84″	83 13/16″	29 1/2″	28 1/2″	**DT1CTY8430N**	1,518.	1,670.	1,738.	2,655.	2,920.	3,029.
	90″	89 13/16″	29 1/2″	28 1/2″	**DT1CTY9030N**	1,551.	1,706.	1,774.	2,682.	2,952.	3,065.
	96″	95 13/16″	29 1/2″	28 1/2″	**DT1CTY9630N**	1,582.	1,741.	1,812.	2,711.	2,982.	3,101.
36″ Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60″	59 13/16″	35 1/2″	28 1/2″	**DT1CTY6036N**	1,431.	1,573.	1,637.	2,556.	2,812.	2,924.
	66″	65 13/16″	35 1/2″	28 1/2″	**DT1CTY6636N**	1,480.	1,628.	1,693.	2,599.	2,858.	2,973.
	72″	71 13/16″	35 1/2″	28 1/2″	**DT1CTY7236N**	1,531.	1,684.	1,751.	2,641.	2,906.	3,021.
	78″	77 13/16″	35 1/2″	28 1/2″	**DT1CTY7836N**	1,580.	1,739.	1,810.	2,684.	2,953.	3,069.
	84″	83 13/16″	35 1/2″	28 1/2″	**DT1CTY8436N**	1,617.	1,779.	1,851.	2,726.	2,999.	3,120.
	90″	89 13/16″	35 1/2″	28 1/2″	**DT1CTY9036N**	1,654.	1,819.	1,892.	2,769.	3,046.	3,168.
	96″	95 13/16″	35 1/2″	28 1/2″	**DT1CTY9636N**	1,690.	1,859.	1,933.	2,811.	3,093.	3,217.



(credenza not included)



(credenza not included)



(credenza not included)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Credenza Supported Y Leg Table:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Credenza Supported Y Leg Table:

Example:	**DT1CTY6024N, 114, 114, 114**
DT1	Dividends Horizon Table
C	Credenza support assembly
T	Racetrack shape
Y	Y Leg Base
60	Overall width in inches
24	Overall depth in inches
N	No grommet
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Credenza Supported Y Leg Table:

- (1) Y Leg
- (1) Credenza support spacer
- Hardware kit
- Table top
- Stiffening plate

Credenza must be specified separately

Note: Y Leg tables are finished with textured paint, including 613 Silver.

Note: Y Leg Tables are only available in Knoll core finishes.

Options

Grommet Option:

- To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add $17.

Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.

This page intentionally left blank

X Base Tables
Table Supports
Specifications

X Base Tables
Dividends Horizon X base tables are designed to be used along with the Dividends Horizon system to create a consistent aesthetic throughout the entire office. With various height and width options, X base tables can be used in a multitude of applications, including collaboration areas in the open plan, break rooms, and lounge areas.

Available with a round, square or rounded square top shape with either a laminate or veneer finish, a Dividends Horizon X base table is appropriate for use in a vast array of applications from the private office to the open plan and even to lounge areas. The five height options allow for the same table base to be used in various applications while maintaining visual consistency throughout the space.

X base tables include a top, support column, and X base.

Available Sizes
- Width: 30 - 48 inches
- Depth:30 - 48 inches
- Heights: 17, 21, 28-1/2, 36, and 42 inches

Construction
- **Worksurface**:
  - Material: 0.028" thick high pressure laminate or 0.6mm thick veneer on 1-1/8" particle board core
  - Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge.
- **Base**:
  - Foot: die cast aluminum
  - Column: extruded aluminum with 3/16" thick structural plate

Table Supports
X bases may be specified separately for use with an alternative table top. The appropriate X base size must be selected according to the width of the table top being used. X bases are available in five heights and may be used with table tops that are 30 to 48 inches wide.

Available Sizes
Heights: 17, 21, 28-1/2, 36, and 42 inches

Construction
- **Base**:
  - Foot: die cast aluminum
  - Column: extruded aluminum with 3/16" thick structural plate

Note: Dividends Horizon tables are only available in Knoll Core paint and laminate finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Square X Base Table



Round X Base Table

Rounded Square X Base Table

X Base Tables
Square Table Tops
17", 21", 28", 36" and 42" High

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
17″ High Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	17″	**DT1ASX303017**	$940.	$1,037.	$1,079.	$1,389.	$1,535.	$1,597.
	36″	35 13/16″	35 13/16″	1 1/4″	17″	**DT1ASX363617**	982.	1,083.	1,127.	1,468.	1,616.	1,682.
	42″	41 13/16″	41 13/16″	1 1/4″	17″	**DT1ASX424217**	1,089.	1,200.	1,248.	1,553.	1,710.	1,779.
	48″	47 13/16″	47 13/16″	1 1/4″	17″	**DT1ASX484817**	1,142.	1,260.	1,310.	1,615.	1,778.	1,851.
21″ High Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	21″	**DT1ASX303021**	940.	1,037.	1,079.	1,389.	1,535.	1,597.
	36″	35 13/16″	35 13/16″	1 1/4″	21″	**DT1ASX363621**	982.	1,083.	1,127.	1,468.	1,616.	1,682.
	42″	41 13/16″	41 13/16″	1 1/4″	21″	**DT1ASX424221**	1,089.	1,200.	1,248.	1,553.	1,710.	1,779.
	48″	47 13/16″	47 13/16″	1 1/4″	21″	**DT1ASX484821**	1,142.	1,260.	1,310.	1,615.	1,778.	1,851.
28″ High Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	28 1/2″	**DT1ASX3030**	963.	1,059.	1,101.	1,410.	1,556.	1,617.
	36″	35 13/16″	35 13/16″	1 1/4″	28 1/2″	**DT1ASX3636**	1,003.	1,103.	1,147.	1,488.	1,638.	1,703.
	42″	41 13/16″	41 13/16″	1 1/4″	28 1/2″	**DT1ASX4242**	1,109.	1,222.	1,270.	1,574.	1,731.	1,799.
	48″	47 13/16″	47 13/16″	1 1/4″	28 1/2″	**DT1ASX4848**	1,163.	1,280.	1,331.	1,637.	1,798.	1,872.
36″ High Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	36″	**DT1ASX303036**	1,016.	1,111.	1,154.	1,463.	1,610.	1,670.
	36″	35 13/16″	35 13/16″	1 1/4″	36″	**DT1ASX363636**	1,056.	1,156.	1,201.	1,541.	1,690.	1,755.
	42″	41 13/16″	41 13/16″	1 1/4″	36″	**DT1ASX424236**	1,162.	1,274.	1,323.	1,627.	1,784.	1,854.
	48″	47 13/16″	47 13/16″	1 1/4″	36″	**DT1ASX484836**	1,217.	1,333.	1,385.	1,689.	1,853.	1,924.
42″ High Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	42″	**DT1ASX303042**	1,036.	1,133.	1,176.	1,484.	1,630.	1,691.
	36″	35 13/16″	35 13/16″	1 1/4″	42″	**DT1ASX363642**	1,076.	1,178.	1,223.	1,563.	1,711.	1,777.
	42″	41 13/16″	41 13/16″	1 1/4″	42″	**DT1ASX424242**	1,185.	1,296.	1,344.	1,649.	1,807.	1,875.
	48″	47 13/16″	47 13/16″	1 1/4″	42″	**DT1ASX484842**	1,238.	1,354.	1,406.	1,710.	1,874.	1,946.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

Example:	**DT1ASX3030, 114, 114, 114**
DT1	Dividends Horizon Table
A	Table assembly
S	Square shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.

Options

X Base Tables
Round Table Tops
17", 21", 28", 36" and 42" High

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
17″ High Round X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	17″	**DT1ACX3017**	$950.	$1,049.	$1,091.	$2,122.	$2,334.	$2,429.
	36″	35 13/16″	35 13/16″	1 1/4″	17″	**DT1ACX3617**	989.	1,090.	1,134.	2,205.	2,428.	2,527.
	42″	41 13/16″	41 13/16″	1 1/4″	17″	**DT1ACX4217**	1,094.	1,205.	1,255.	2,311.	2,545.	2,647.
	48″	47 13/16″	47 13/16″	1 1/4″	17″	**DT1ACX4817**	1,147.	1,265.	1,315.	2,374.	2,614.	2,719.
21″ High Round X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	21″	**DT1ACX3021**	950.	1,049.	1,091.	2,122.	2,334.	2,429.
	36″	35 13/16″	35 13/16″	1 1/4″	21″	**DT1ACX3621**	989.	1,090.	1,134.	2,205.	2,428.	2,527.
	42″	41 13/16″	41 13/16″	1 1/4″	21″	**DT1ACX4221**	1,094.	1,205.	1,255.	2,311.	2,545.	2,647.
	48″	47 13/16″	47 13/16″	1 1/4″	21″	**DT1ACX4821**	1,147.	1,265.	1,315.	2,374.	2,614.	2,719.
28″ High Round X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	28 1/2″	**DT1ACX30**	972.	1,069.	1,111.	2,143.	2,356.	2,451.
	36″	35 13/16″	35 13/16″	1 1/4″	28 1/2″	**DT1ACX36**	1,010.	1,110.	1,155.	2,226.	2,450.	2,547.
	42″	41 13/16″	41 13/16″	1 1/4″	28 1/2″	**DT1ACX42**	1,114.	1,227.	1,275.	2,333.	2,566.	2,670.
	48″	47 13/16″	47 13/16″	1 1/4″	28 1/2″	**DT1ACX48**	1,170.	1,285.	1,337.	2,395.	2,635.	2,741.
36″ High Round X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	36″	**DT1ACX3036**	1,025.	1,122.	1,164.	2,196.	2,408.	2,504.
	36″	35 13/16″	35 13/16″	1 1/4″	36″	**DT1ACX3636**	1,063.	1,163.	1,208.	2,280.	2,503.	2,600.
	42″	41 13/16″	41 13/16″	1 1/4″	36″	**DT1ACX4236**	1,169.	1,279.	1,328.	2,385.	2,619.	2,722.
	48″	47 13/16″	47 13/16″	1 1/4″	36″	**DT1ACX4836**	1,223.	1,339.	1,391.	2,449.	2,688.	2,793.
42″ High Round X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	42″	**DT1ACX3042**	1,046.	1,143.	1,187.	2,217.	2,429.	2,526.
	36″	35 13/16″	35 13/16″	1 1/4″	42″	**DT1ACX3642**	1,085.	1,186.	1,230.	2,301.	2,524.	2,621.
	42″	41 13/16″	41 13/16″	1 1/4″	42″	**DT1ACX4242**	1,190.	1,301.	1,349.	2,407.	2,640.	2,744.
	48″	47 13/16″	47 13/16″	1 1/4″	42″	**DT1ACX4842**	1,243.	1,360.	1,411.	2,470.	2,710.	2,814.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

Example:	**DT1ACX3030, 114, 114, 114**
DT1	Dividends Horizon Table
A	Table assembly
C	Round shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.

Options

X Base Tables
Rounded Square Table Tops
17", 21", 28", 36" and 42" High

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
17″ High Rounded Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	17″	**DT1ADX303017**	$950.	$1,049.	$1,091.	$2,122.	$2,334.	$2,429.
	36″	35 13/16″	35 13/16″	1 1/4″	17″	**DT1ADX363617**	989.	1,090.	1,134.	2,205.	2,428.	2,527.
	42″	41 13/16″	41 13/16″	1 1/4″	17″	**DT1ADX424217**	1,094.	1,205.	1,255.	2,311.	2,545.	2,647.
	48″	47 13/16″	47 13/16″	1 1/4″	17″	**DT1ADX484817**	1,147.	1,265.	1,315.	2,374.	2,614.	2,719.
21″ High Rounded Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	21″	**DT1ADX303021**	950.	1,049.	1,091.	2,122.	2,334.	2,429.
	36″	35 13/16″	35 13/16″	1 1/4″	21″	**DT1ADX363621**	989.	1,090.	1,134.	2,205.	2,428.	2,527.
	42″	41 13/16″	41 13/16″	1 1/4″	21″	**DT1ADX424221**	1,094.	1,205.	1,255.	2,311.	2,545.	2,647.
	48″	47 13/16″	47 13/16″	1 1/4″	21″	**DT1ADX484821**	1,147.	1,265.	1,315.	2,374.	2,614.	2,719
28″ High Rounded Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	28 1/2″	**DT1ADX3030**	972.	1,069.	1,111.	2,143.	2,356.	2,451
	36″	35 13/16″	35 13/16″	1 1/4″	28 1/2″	**DT1ADX3636**	1,010.	1,110.	1,155.	2,226.	2,450.	2,547
	42″	41 13/16″	41 13/16″	1 1/4″	28 1/2″	**DT1ADX4242**	1,114.	1,227.	1,275.	2,333.	2,566.	2,670
	48″	47 13/16″	47 13/16″	1 1/4″	28 1/2″	**DT1ADX4848**	1,170.	1,285.	1,337.	2,395.	2,635.	2,741
36″ High Rounded Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	36″	**DT1ADX303036**	1,025.	1,122.	1,164.	2,196.	2,408.	2,504.
	36″	35 13/16″	35 13/16″	1 1/4″	36″	**DT1ADX363636**	1,063.	1,163.	1,208.	2,280.	2,503.	2,600.
	42″	41 13/16″	41 13/16″	1 1/4″	36″	**DT1ADX424236**	1,169.	1,279.	1,328.	2,385.	2,619.	2,722.
	48″	47 13/16″	47 13/16″	1 1/4″	36″	**DT1ADX484836**	1,223.	1,339.	1,391.	2,449.	2,688.	2,793.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

Example:	**DT1ADX3030, 114, 114, 114**
DT1	Dividends Horizon Table
A	Table assembly
D	Rounded Square shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.

Options

X Base Tables
Rounded Square Table Tops
17″, 21″, 28″, 36″ and 42″ High

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
42″ High Rounded Square X Base Table	30″	29 13/16″	29 13/16″	1 1/4″	42″	**DT1ADX303042**	$1,046.	$1,143.	$1,187.	$2,217.	$2,429.	$2,526.
	36″	35 13/16″	35 13/16″	1 1/4″	42″	**DT1ADX363642**	1,085.	1,186.	1,230.	2,301.	2,524.	2,621.
	42″	41 13/16″	41 13/16″	1 1/4″	42″	**DT1ADX424242**	1,190.	1,301.	1,349.	2,407.	2,640.	2,744.
	48″	47 13/16″	47 13/16″	1 1/4″	42″	**DT1ADX484842**	1,243.	1,360.	1,411.	2,470.	2,710.	2,814.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

Example:	**DT1ADX3030, 114, 114, 114**
DT1	Dividends Horizon Table
A	Table assembly
D	Rounded Square shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.

Options

Table Supports
X Bases
Credenza Support Spacer

description	w	h	d	pattern no.	P1	P2	P3
Small X-Base, for use with 30″ or 36″ wide round, square or rounded square table tops		17″		**DT1BXS17**	$505.	$558.	$582.
		21″		**DT1BXS21**	505.	558.	582.
		28″		**DT1BXS**	525.	580.	603.
		36″		**DT1BXS36**	580.	632.	655.
		42″		**DT1BXS42**	600.	653.	677.
Large X Base, for use with 42″ or 48″ wide round, square or rounded square table tops		17″		**DT1BXL17**	557.	616.	641.
		21″		**DT1BXL21**	557.	616.	641.
		28″		**DT1BXL**	579.	637.	662.
		36″		**DT1BXL36**	631.	689.	715.
		42″		**DT1BXL42**	652.	711.	735.
Credenza Support Spacer For use with Dividends Horizon Credenza	9 5/8″	2 15/16″	1 9/16″	**DT1S**	140.	155.	161.
Small T-Base, for use with 24″ or 30″ deep tops		28″		**DT1BTS**	525.	580.	603.
Largel T-Base, for use with 24″ or 30″ deep tops		28″		**DT1BTL**	579.	637.	662.

Ordering Information

Table Supports:

1. Pattern number
2. Paint Finish

Order Code

X Base:

Example:	**DT1BXS, 114**
DT1	Dividends Horizon Table
B	Base
S	X Shape
114	Paint finish

Credenza Support Spacer:

Example:	**DT1S, 114**
DT1	Dividends Horizon Table
S	Support Spacer
114	Paint finish

Included with:

X Base:

- X Base
- Hardware kit

T Base:

- T Base
- Hardware kit

Credenza Support spacer:

- Support spacer
- Hardware Kit

Note: X and T bases are painted with textured paint, including 613 Silver.

Note: Table supports are only available in Knoll core finishes.

Options

Casters are designed for use on X- and Y-bases only.

Tables with casters may not exceed 28″h, 84″w or 42″d.

Table Supports
X Bases
Credenza Support Spacer

description	w	h	d	pattern no.	P1	P2	P3
Caster Kit (set of 4) black only		1″		**DT1CK4**	$36.		

Ordering Information

Table Supports:

1. Pattern number
2. Paint Finish

Order Code

X Base:

Example:	**DT1BXS, 114**
DT1	Dividends Horizon Table
B	Base
S	X Shape
114	Paint finish

Credenza Support Spacer:

Example:	**DT1S, 114**
DT1	Dividends Horizon Table
S	Support Spacer
114	Paint finish

Included with:

X Base:

- X Base
- Hardware kit

T Base:

- T Base
- Hardware kit

Credenza Support spacer:

- Support spacer
- Hardware Kit

Note: X and T bases are painted with textured paint, including 613 Silver.

Note: Table supports are only available in Knoll core finishes.

Options

Casters are designed for use on X- and Y-bases only.

Tables with casters may not exceed 28″h, 84″w or 42″d.

This page intentionally left blank

Conference Tables
Specifications

Dividends Horizon Conference Tables
Dividends Horizon conference tables are designed with a scale and visual language consistent with the full scope of Dividends Horizon products. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon conference tables are available in racetrack, rectangular, or boat shape and in all standard Dividends Horizon finishes.

Conference tables include a table top and base assembly. A conference table base assembly includes two Y legs, one center support T base, and two horizontal stretchers that connect the three bases. Top sizes up to 120 inches are produced in one piece, while tops longer than 120 inches are produced in two pieces.

Available Sizes
Width: 102- 144 inches
Depth: 36- 48 inches
Height: 28-1/2 inches

Construction
Worksurface:
- Material: 0.028 inch thick high pressure laminate or 0.6mm thick veneer on 1-1/8 inch thick particle board core
- Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge

Base:
- Stretcher: extruded aluminum
- Foot: die cast aluminum
- Column: extruded aluminum with 3/16 inch thick structural plate

Note: Dividends Horizon conference tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: Grain patterns on woodgrain laminate and veneer tops will not match at the seam in the middle of tables longer than 120 inches.

Rectangular Conference Table



Racetrack Conference Table



Boat Shape Conference Table



Conference Tables
Rectangular Table Top
36", 42" and 48" Deep

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36″ Deep Rectangular Conference Table	102″	101 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY10236N**	$2,229.	$2,281.	$2,334.	$2,546.	$2,653.	$2,865.
	108″	107 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ARY10836N**	2,281.	2,334.	2,387.	2,599.	2,858.	2,974.
42″ Deep Rectangular Conference Table	102″	101 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ARY10242N**	2,281.	2,334.	2,387.	2,599.	2,706.	2,918.
	108″	107 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ARY10842N**	2,334.	2,387.	2,441.	2,625.	2,918.	3,062.
	120″	119 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ARY12042N**	2,496.	2,548.	2,601.	2,727.	3,000.	3,121.
	132″	131 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ARY13242N**	2,601.	2,655.	2,708.	3,171.	3,488.	3,629.
	144″	143 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ARY14442N**	2,708.	2,760.	2,813.	3,614.	3,977.	4,134.
48″ Deep Rectangular Conference Table	102″	101 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ARY10248N**	2,334.	2,387.	2,441.	2,653.	2,811.	3,023.
	108″	107 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ARY10848N**	2,387.	2,441.	2,494.	2,732.	2,997.	3,130.
	120″	119 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ARY12048N**	2,555.	2,608.	2,663.	2,807.	3,089.	3,212.
	132″	131 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ARY13248N**	2,663.	2,715.	2,768.	3,259.	3,584.	3,729.
	144″	143 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ARY14448N**	2,768.	2,820.	2,875.	3,709.	4,081.	4,245.





w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Conference Tables:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Conference Table:

Example:	**DT1ARY10836N**
DT1	Dividends Horizon Table
A	Table Assembly
R	Rectangular shape
Y	Y Leg Base
108	Overall width in inches
36	Overall depth in inches
N	No grommet
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Conference Table:

- (2) Y Legs
- (1) T leg
- (2) Stretchers
- Table Top
- Hardware Kit

Options

Conference Tables

Conference Tables
Racetrack Table Top
36", 42" and 48" Deep

description	w	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36″ Deep Racetrack Conference Table	102″	101 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY10236N**	$2,229.	$2,281.	$2,334.	$3,290.	$3,607.	$3,714.
	108″	107 13/16″	35 1/2″	1 1/4″	28 1/2″	**DT1ATY10836N**	2,281.	2,334.	2,387.	3,337.	3,671.	3,817.
42″ Deep Racetrack Conference Table	102″	101 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ATY10242N**	2,281.	2,334.	2,387.	3,316.	3,660.	3,819.
	108″	107 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ATY10842N**	2,334.	2,387.	2,441.	3,395.	3,714.	3,872.
	120″	119 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ATY12042N**	2,496.	2,548.	2,601.	3,465.	3,812.	3,964.
	132″	131 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ATY13242N**	2,601.	2,655.	2,708.	3,979.	4,376.	4,551.
	144″	143 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ATY14442N**	2,708.	2,760.	2,813.	4,491.	4,939.	5,137.
48″ Deep Racetrack Conference Table	102″	101 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ATY10248N**	2,334.	2,387.	2,441.	3,395.	3,686.	3,846.
	108″	107 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ATY10848N**	2,387.	2,441.	2,494.	3,502.	3,767.	3,926.
	120″	119 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ATY12048N**	2,555.	2,608.	2,663.	3,542.	3,896.	4,053.
	132″	131 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ATY13248N**	2,663.	2,715.	2,768.	4,064.	4,470.	4,650.
	144″	143 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ATY14448N**	2,768.	2,820.	2,875.	4,587.	5,045.	5,247.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Conference Tables:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Conference Table:

Example:	**DT1ARY10836N**
DT1	Dividends Horizon Table
A	Table Assembly
R	Rectangular shape
Y	Y Leg Base
108	Overall width in inches
36	Overall depth in inches
N	No grommet
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Conference Table:

- (2) Y Legs
- (1) T leg
- (2) Stretchers
- Table Top
- Hardware Kit

Options

Conference Tables

Conference Tables
Boat Shape Table Top
42″ and 48″ Deep

description	w *	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
42″ Deep Boat Shape Conference Table	102″	101 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ABY10242N**	$2,281.	$2,334.	$2,387.	$3,316.	$3,660.	$3,819.
	108″	107 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ABY10842N**	2,334.	2,387.	2,441.	3,395.	3,714.	3,872.
	120″	119 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ABY12042N**	2,496.	2,548.	2,601.	3,465.	3,812.	3,964.
	132″	131 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ABY13242N**	2,601.	2,655.	2,708.	3,979.	4,376.	4,551.
	144″	143 13/16″	41 1/2″	1 1/4″	28 1/2″	**DT1ABY14442N**	2,708.	2,760.	2,813.	4,491.	4,939.	5,137.
48″ Deep Boat Shape Conference Table	102″	101 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ABY10248N**	2,334.	2,387.	2,441.	3,395.	3,686.	3,846.
	108″	107 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ABY10848N**	2,387.	2,441.	2,494.	3,502.	3,767.	3,926.
	120″	119 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ABY12048N**	2,555.	2,608.	2,663.	3,542.	3,896.	4,053.
	132″	131 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ABY13248N**	2,663.	2,715.	2,768.	4,064.	4,470.	4,650.
	144″	143 13/16″	47 1/2″	1 1/4″	28 1/2″	**DT1ABY14448N**	2,768.	2,820.	2,875.	4,587.	5,045.	5,247.

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16″

Ordering Information

Conference Tables:

1. Pattern number
2. Base/Stretcher Paint Finish
3. Top Finish
4. Edge Finish

Order Code

Conference Table:

Example:	**DT1ARY10836N**
DT1	Dividends Horizon Table
A	Table Assembly
R	Rectangular shape
Y	Y Leg Base
108	Overall width in inches
36	Overall depth in inches
N	No grommet
114	Base/ stretcher paint finish
114	Laminate top finish
114	Edgeband finish

Included with:

Conference Table:

- (2) Y Legs
- (1) T leg
- (2) Stretchers
- Table Top
- Hardware Kit

Options

Conference Tables

Preconfigured Desks
Series 2 Single and Double Pedestal Specifications

Series 2 Single and Double Pedestal Desks
Series 2 freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer configuration is required, or when back panels are not needed.

"Preconfigured" single pedestal desks consist of a worksurface, Series 2 box/box/file pedestal, "L" shaped end panel and full height back panel.

"Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and full height back panel.

Available Sizes
- Height: 28 1/2"
- Depths: 24", 30" and 36" (double pedestal desk only)
- Widths: 60", 66" and 72"
- Worksurface thickness: 1 1/4"

''Build-to-Spec'' Desks
For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction
All freestanding desks match the aesthetics and dimensions of Dividends Horizon panel components.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 desks include full-height modesty panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

Optional Edge Grommets
Edge grommets are optional for all desks except overhang desks and can be specified factory-installed, centered along the rear edge of worksurfaces. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.When grommets are specified, a reveal of 1/2" is provided between the rear of the worksurface and the back panel for repositioning cables anywhere along the back panel.

Locks
Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250.

All locks are factory-installed and have a black finish.

Desk Accessory
All Series 2 pedestal accessories including the hanging file bar must be specified separately.

Series 2 Single Pedestal Desk



Series 2 Double Pedestal Desk



Series 2 Desk Components



Optional Edge Grommet



Series 2 Freestanding Desk Configurations



Preconfigured Desks
Series 2 Single and Double Pedestal
24", 30" and 36" Deep

description	w *	w	d	h	pattern no.	P1	P2	P3
Single Pedestal Desk with Locks	60″	59 13/16″	23 1/2″	28 1/2″	**DD2S L6024N**	$1,544.	$1,668.	$1,727.
	60″	59 13/16″	29 1/2″	28 1/2″	**DD2S L6030N**	1,693.	1,821.	1,885.
	66″	65 13/16″	23 1/2″	28 1/2″	**DD2S L6624N**	1,582.	1,706.	1,767.
	66″	65 13/16″	29 1/2″	28 1/2″	**DD2S L6630N**	1,749.	1,880.	1,944.
	72″	71 13/16″	23 1/2″	28 1/2″	**DD2S L7224N**	1,609.	1,733.	1,795.
	72″	71 13/16″	29 1/2″	28 1/2″	**DD2S L7230N**	1,777.	1,910.	1,975.
Double Pedestal Desk with Locks	60″	59 13/16″	23 1/2″	28 1/2″	**DD2D L6024N**	1,776.	1,922.	1,995.
	60″	59 13/16″	29 1/2″	28 1/2″	**DD2D L6030N**	1,917.	2,068.	2,143.
	66″	65 13/16″	23 1/2″	28 1/2″	**DD2D L6624N**	1,815.	1,960.	2,035.
	66″	65 13/16″	29 1/2″	28 1/2″	**DD2D L6630N**	1,975.	2,127.	2,203.
	72″	71 13/16″	23 1/2″	28 1/2″	**DD2D L7224N**	1,840.	1,988.	2,063.
	72″	71 13/16″	29 1/2″	28 1/2″	**DD2D L7230N**	2,003.	2,155.	2,235.
Double Pedestal Desk with Locks and 6″ Front Overhang	60″	59 13/16″	35 1/2″	28 1/2″	**DD2O L6036N**	2,033.	2,182.	2,259.
	66″	65 13/16″	35 1/2″	28 1/2″	**DD2O L6636N**	2,098.	2,251.	2,327.
	72″	71 13/16″	35 1/2″	28 1/2″	**DD2O L7236N**	2,168.	2,322.	2,395.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Single Pedestal Desk

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Double Pedestal Desk

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Order Code

Single Pedestal Desk

Example:	**DD2S L7230N, 117, 117, 117**
DD2S L7230N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish

Double Pedestal Desk

Example:	**DD2D L7230N, 117, 117, 117**
DD2D L7230N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish

Included with:

Single Pedestal Desk

Double Pedestal Desk

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Single Pedestal Desk

- To specify desk with center located edge grommet, replace the suffix letter **"N"** with a **"G".**

Add $18
(Grommets not available for overhang desks)

- To specify pedestals without locks, replace the fifth character **"L"** with an **"N".**

Deduct $21

Double Pedestal Desk

- To specify desk with center located edge grommet, replace the suffix letter **"N"** with a **"G".**

Add $18
(Grommets not available for overhang desks)

- To specify pedestals without locks, replace the fifth character **"L"** with an **"N".**

Deduct $42

Preconfigured Desks
Single and Double Pedestal Specifications

Single and Double Pedestal Desks
Dividends freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer configuration is required, or when back panels are not needed. "Preconfigured" single pedestal desks consist of a worksurface, box/box/file pedestal, "L" shaped end panel and half-height back panel.

"Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and half-height back panel.

Available Sizes
- Height: 28 1/2"
- Depths: 24", 30" and 36" (Double pedestal desk only
- Widths: 60", 66" and 72"
- Worksurface thickness: 1 1/4"

"Build-to-Spec" Desks
For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction
All freestanding desks match the aesthetics and dimensions of Dividends panel components.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset 3/4" from the pedestal backs and match the softly-radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

Locks
Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250 All locks are factory-installed and have a black finish.

Accessory
Hanging file bars for front-to-back or side-to-side filing are included with pedestals.

Single Pedestal Desk



Double Pedestal Desk



Desk Components



Optional Edge Grommet



Freestanding Desk Configurations



Preconfigured Desks
Single and Double Pedestal
24″, 30″ and 36″ Deep

description	w *	w	d	h	pattern no.	P1	P2	P3
Single Pedestal Desk with Locks	60″	59 13/16″	23 1/2″	28 1/2″	**DD1S L6024N**	$1,544.	$1,668.	$1,727.
	60″	59 13/16″	29 1/2″	28 1/2″	**DD1S L6030N**	1,693.	1,821.	1,885.
	66″	65 13/16″	23 1/2″	28 1/2″	**DD1S L6624N**	1,582.	1,706.	1,767.
	66″	65 13/16″	29 1/2″	28 1/2″	**DD1S L6630N**	1,749.	1,880.	1,944.
	72″	71 13/16″	23 1/2″	28 1/2″	**DD1S L7224N**	1,609.	1,733.	1,795.
	72″	71 13/16″	29 1/2″	28 1/2″	**DD1S L7230N**	1,777.	1,910.	1,975.
Double Pedestal Desk with Locks	60″	59 13/16″	23 1/2″	28 1/2″	**DD1D L6024N**	1,776.	1,922.	1,995.
	60″	59 13/16″	29 1/2″	28 1/2″	**DD1D L6030N**	1,917.	2,068.	2,143.
	66″	65 13/16″	23 1/2″	28 1/2″	**DD1D L6624N**	1,815.	1,960.	2,035.
	66″	65 13/16″	29 1/2″	28 1/2″	**DD1D L6630N**	1,975.	2,127.	2,203.
	72″	71 13/16″	23 1/2″	28 1/2″	**DD1D L7224N**	1,840.	1,988.	2,063.
	72″	71 13/16″	29 1/2″	28 1/2″	**DD1D L7230N**	2,003.	2,155.	2,235.
Double Pedestal Desk with Locks and 6″ Front Overhang	60″	59 13/16″	35 1/2″	28 1/2″	**DD1O L6036N**	2,033.	2,182.	2,259.
	66″	65 13/16″	35 1/2″	28 1/2″	**DD1O L6636N**	2,098.	2,251.	2,327.
	72″	71 13/16″	35 1/2″	28 1/2″	**DD1O L7236N**	2,168.	2,322.	2,395.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Single Pedestal Desk

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish
5. Pull Finish
6. Drawer Top Cap Finish

Double Pedestal Desk

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish
5. Pull Finish
6. Drawer Top Cap Finish

Order Code

Single Pedestal Desk

Example:	**DD1S L7230N, 117, 117, 117, 117, 117**
DD1S L7230N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish
117	Soft Grey pull finish
Y3	Dark Grey top cap finish

Double Pedestal Desk

Example:	**DD1D L7230N, 117, 117, 117, 117, 117**
DD1D L7230N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish
117	Soft Grey pull finish
117	Soft Grey top cap finish

Included with:

Single Pedestal Desk

Double Pedestal Desk

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Single Pedestal Desk

- To specify desk with center located edge grommet, replace the suffix letter **"N"** with a **"G".**

Add $18
(Grommets not available for overhang desks)

- To specify pedestals without locks, replace the fifth character **"L"** with an **"N".**

Deduct $21

Double Pedestal Desk

- To specify desk with center located edge grommet, replace the suffix letter **"N"** with a **"G".**

Add $18
(Grommets not available for overhang desks)

- To specify pedestals without locks, replace the fifth character **"L"** with an **"N".**

Deduct $42

Preconfigured Desks
Series 2 Freestanding Corner Unit Specifications

Series 2 Freestanding Corner Units (Assembly)
Dividends Horizon Series 2 freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications.

"Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two full height back panels.

Available Sizes
- Height: 28½"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit:
- Worksurface: 1¼" thick, 45 lb. density particle board core with high pressure laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel
- Series 2 Freestanding Corner Units include full height back panels

Rear Corner End Unit
- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ⅜" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit
- Outer skin: 21-guage
- Inner frame: 20-gauge
- Leveling glide: ⅜" 16-gauge steel with 1½" of height adjustment
- Attachment bracket:11-gauge steel

Freestanding Corner End Units (Components)
Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.

Optional Edge Grommets
Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.

Series 2 Freestanding Corner Unit Components



Edge Grommet Locations



Series 2 Freestanding Corner Unit Attached to Return to Form a "L" Shaped Workstation



Preconfigured Desks
Series 2 Freestanding Corner Unit
24″ Deep

description	type	w *	w	d	h	pattern no.	P1	P2	P3
Freestanding Corner Unit (Assembly)		36″	35 1/2″	23 1/2″	28 1/2″	**DD2VD 3624 N**	$1,305.	$1,437.	$1,502.
		42″	41 1/2″	23 1/2″	28 1/2″	**DD2VD 4224 N**	1,349.	1,484.	1,551.
		48″	47 1/2″	23 1/2″	28 1/2″	**DD2VD 4824 N**	1,416.	1,556.	1,627.
Freestanding Curved Corner Unit (Assembly)		36″	35 1/2″	23 1/2″	28 1/2″	**DD2VL 3624 N**	1,333.	1,467.	1,535.
		42″	41 1/2″	23 1/2″	28 1/2″	**DD2VL 4224 N**	1,415.	1,555.	1,626.
		48″	47 1/2″	23 1/2″	28 1/2″	**DD2VL 4824 N**	1,477.	1,626.	1,698.
Freestanding Corner End Unit (Component)			6 9/16″	6 9/16″	26 7/8″	**DD1R CU6**	274.	303.	316.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Freestanding Corner

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Freestanding Corner End Unit

1. Pattern Number
2. Paint Finish

Order Code

Freestanding Corner

Example:	**DD2VD 3624 N, 117, 117, 117**
DD2VD 3624	Pattern Number
N	No Grommets
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish

Freestanding Corner End Unit

Example:	**DD1RCU6, 117**
DD1RCU6	Pattern Number
117	Soft Grey paint finish

Included with:

Freestanding Corner

- Corner supports (3)
- Back panels (2)
- Corner worksurface
- Connecting hardware

Freestanding Corner End Unit

Note: Series 2 freestanding corner units have full height modesty panels.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Freestanding Corner

- To specify two center-mounted edge grommets, replace the suffix letter **"N"** with a **"G".**

Add $28.

Freestanding Corner End Unit

Preconfigured Desks
Freestanding Corner Unit Specifications

Freestanding Corner Units (Assembly)
Dividends freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications. "Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two 11" high back panels.

Available Sizes
- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit Specifications
- Worksurface: 1 1/4" thick, 45 lb. density particle board core with high pressure laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel

Rear Corner End Unit
- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: 3/8" 16-gauge steel with 1 1/2" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit
- Outer skin: 21-guage
- Inner frame: 20-gauge
- Leveling glide: 3/8" 16-gauge steel
- Attachment bracket:11-gauge steel

Freestanding Corner End Units (Components)
Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.

Optional Edge Grommets
Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.

Freestanding Corner Unit Components



Edge Grommet Locations



Freestanding Corner Unit attached to returns to form an "L" shaped workstation



Preconfigured Desks
Freestanding Corner Unit
24″ Deep

description	type	w *	w	d	h	pattern no.	P1	P2	P3
Freestanding Corner Unit (Assembly)		36″	35 1/2″	23 1/2″	28 1/2″	**DD1VD 3624 N**	$1,305.	$1,437.	$1,502.
		42″	41 1/2″	23 1/2″	28 1/2″	**DD1VD 4224 N**	1,349.	1,484.	1,551.
		48″	47 1/2″	23 1/2″	28 1/2″	**DD1VD 4824 N**	1,416.	1,556.	1,627.
Freestanding Curved Corner Unit (Assembly)		36″	35 1/2″	23 1/2″	28 1/2″	**DD1VL 3624 N**	1,333.	1,467.	1,535.
		42″	41 1/2″	23 1/2″	28 1/2″	**DD1VL 4224 N**	1,415.	1,555.	1,626.
		48″	47 1/2″	23 1/2″	28 1/2″	**DD1VL 4824 N**	1,477.	1,626.	1,698.
Freestanding Corner End Unit (Component)			6 9/16″	6 9/16″	26 7/8″	**DD1R CU6**	274.	303.	316.
Freestanding Corner Unit (Component)			6 9/16″	12 9/16″	26 7/8″	**DD1S CU12**	323.	354.	372.
Back Panels for Freestanding Corner Unit (Component)	full height	36″	20 15/16″	26 5/8″		**DD1 FBPV36**	195.	212.	222.
	full height	42″	26 15/16″	26 5/8″		**DD1 FBPV42**	197.	215.	226.
	full height	48″	32 15/16″	26 5/8″		**DD1 FBPV48**	200.	219.	229.
	half height	36″	20 15/16″	11″		**DD1 BPV36**	163.	178.	185.
	half height	42″	26 15/16″	11″		**DD1 BPV42**	171.	188.	197.
	half height	48″	32 15/16″	11″		**DD1 BPV48**	179.	199.	207.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Freestanding Corner

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Freestanding Corner End Unit

1. Pattern Number
2. Paint Finish

Freestanding Corner Back Panel

1. Pattern Number
2. Paint Finish

Order Code

Freestanding Corner	
Example:	**DD1VD 3624 N, 117, 117, 117**
DD1VD 3624	Pattern Number
N	No Grommets
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish
Freestanding Corner End Unit	
Example:	**DD1R CU6, 117**
DD1R CU6	Pattern Number
117	Soft Grey paint finish
Freestanding Corner Back Panel	
Example:	**DD1 BPV42, 115**
DD1 BPV42	Pattern Number
115	Medium grey paint finish

Included with:

Freestanding Corner

- Corner supports (3)
- Back panels (2)
- Corner worksurface
- Connecting hardware

Freestanding Corner End Unit

Freestanding Corner Back Panel

Note: Series 1 freestanding corner units have a curved half modesty panel.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Freestanding Corner

- To specify two center-mounted edge grommets, replace the suffix letter **"N"** with a **"G".**

Add $28.

Freestanding Corner End Unit

Freestanding Corner Back Panel

Preconfigured Desks
Series 2 Returns and Bridge Units
Specifications

Series 2 End Panel and Pedestal Returns
Dividends Horizon freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and full-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and full height back panel.

Available Sizes
- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment
Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction
All freestanding returns match the aesthetics of the Dividends Horizon panel system.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 Desk components include full-height back panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges
For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory
Hanging file bars for front-to-back or side-to-side filing are included with pedestals.

Bridge Units
Bridge units are used to form freestanding "U" shaped workstations.

Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.

Available Sizes
- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"



Series 2 Return Sizes Available



Series 2 Bridge Unit Sizes Available



Series 2 Desk Configurations



Preconfigured Desks
Series 2 Returns and Bridge Units
18″ and 24″ Deep

description	w *	w	d	h	pattern no.	P1	P2	P3
End Panel Return	36″	35 13/16″	17 1/2″	28 1/2″	**DD2E 3618N**	$720.	$775.	$796.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD2E 3624N**	787.	842.	871.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD2E 4218N**	758.	812.	839.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD2E 4224N**	824.	882.	911.
Pedestal Return	36″	35 13/16″	17 1/2″	28 1/2″	**DD2P (L)3618N**	931.	1,006.	1,042.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD2P (L)3624N**	1,018.	1,095.	1,134.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD2P (L)4218N**	972.	1,045.	1,080.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD2P (L)4224N**	1,058.	1,137.	1,176.
	48″	47 13/16″	17 1/2″	28 1/2″	**DD2P (L)4818N**	1,008.	1,080.	1,118.
	48″	47 13/16″	23 1/2″	28 1/2″	**DD2P (L)4824N**	1,099.	1,179.	1,220.
Bridge Unit	30″	29 13/16″	17 1/2″	28 1/2″	**DD2B 3018N**	351.	368.	374.
	36″	35 13/16″	17 1/2″	28 1/2″	**DD2B 3618N**	387.	405.	414.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD2B 3624N**	416.	432.	440.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD2B 4218N**	420.	438.	447.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD2B 4224N**	455.	473.	481.
	48″	47 13/16″	17 1/2″	28 1/2″	**DD2B 4818N**	455.	473.	481.
	48″	47 13/16″	23 1/2″	28 1/2″	**DD2B 4824N**	496.	515.	523.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Pedestal Return

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

End Panel Return or Bridge Unit

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Order Code

Pedestal Return

Example:	**DD2P L4824N, 117, 117, 117**
DP2P L4824N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish

End Panel Return or Bridge Unit

Example:	**DD2B 4224N, 117, 117, 117**
DD2B 4424	Pattern Number
117	Soft Grey laminate
117	Soft Grey finish
117	Soft Grey finish

Included with:

Pedestal Return

- Worksurface
- Pedestal
- Back panel
- Half height flat bracket (1)
- Connecting hardware

End Panel Return or Bridge Unit

- Worksurface
- Back panel
- Half height flat brackets (2)
- Connecting hardware

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Pedestal Return

- To specify center-mounted edge grommet, replace the **"N"** suffix from the pattern number with **"G". Add $18**
- To specify pedestal without locks, replace the 5th digit **"L"**from the pattern number with **"N". Deduct $21**

End Panel Return or Bridge Unit

- To specify center-mounted edge grommet, replace the **"N"** suffix from the pattern number with **"G". Add $18**

Preconfigured Desks
Returns and Bridge Units
Specifications

End Panel and Pedestal Returns
Dividends freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and half-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and half-height back panel.

Available Sizes
- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment
Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction
All freestanding returns match the aesthetics of the Dividends panel system.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset 3/4" from the pedestal backs and match the softly radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges
For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory
Hanging file bars for front-to-back or side-to-side filing are included with pedestals.

Bridge Units
Bridge units are used to form freestanding "U" shaped workstations.

Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.

Available Sizes
- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"

Pedestal Return



End Panel Return



Bridge Unit



Return Sizes Available



Bridge Unit Sizes Available



Freestanding Configuration





Preconfigured Desks
Returns and Bridge Units
18″ and 24″ Deep

description	w *	w	d	h	pattern no.	P1	P2	P3
End Panel Return	36″	35 13/16″	17 1/2″	28 1/2″	**DD1E 3618N**	$720.	$775.	$796.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD1E 3624N**	787.	842.	871.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD1E 4218N**	758.	812.	839.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD1E 4224N**	824.	882.	911.
Pedestal Return	36″	35 13/16″	17 1/2″	28 1/2″	**DD1P (L)3618N**	931.	1,006.	1,042.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD1P (L)3624N**	1,018.	1,095.	1,134.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD1P (L)4218N**	972.	1,045.	1,080.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD1P (L)4224N**	1,058.	1,137.	1,176.
	48″	47 13/16″	17 1/2″	28 1/2″	**DD1P (L)4818N**	1,008.	1,080.	1,118.
	48″	47 13/16″	23 1/2″	28 1/2″	**DD1P (L)4824N**	1,099.	1,179.	1,220.
Bridge Unit	30″	29 13/16″	17 1/2″	28 1/2″	**DD1B 3018N**	351.	368.	374.
	36″	35 13/16″	17 1/2″	28 1/2″	**DD1B 3618N**	387.	405.	414.
	36″	35 13/16″	23 1/2″	28 1/2″	**DD1B 3624N**	416.	432.	440.
	42″	41 13/16″	17 1/2″	28 1/2″	**DD1B 4218N**	420.	438.	447.
	42″	41 13/16″	23 1/2″	28 1/2″	**DD1B 4224N**	455.	473.	481.
	48″	47 13/16″	17 1/2″	28 1/2″	**DD1B 4818N**	455.	473.	481.
	48″	47 13/16″	23 1/2″	28 1/2″	**DD1B 4824N**	496.	515.	523.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16″

Ordering Information

Pedestal Return

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish
5. Pull Finish
6. Drawer Top Cap Finish

End Panel Return or Bridge Unit

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Order Code

Pedestal Return

Example:	**DD1P L4824N, 117, 117, 117, 117, 117**
DP1P L4824N	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge finish
117	Soft Grey paint finish
117	Soft Grey pull finish
117	Soft Grey top cap finish

End Panel Return or Bridge Unit

Example:	**DD1B 4224N, 117, 117, 117**
DD1B 4424	Pattern Number
117	Soft Grey laminate
117	Soft Grey edge band
117	Soft Grey finish

Included with:

Pedestal Return

- Worksurface
- Pedestal
- Back panel
- Half height flat bracket (1)
- Connecting hardware

End Panel Return or Bridge Unit

- Worksurface
- Back panel
- Half height flat brackets (2)
- Connecting hardware

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Pedestal Return

- To specify center-mounted edge grommet, replace the **"N"** suffix from the pattern number with **"G". Add $18**
- To specify pedestal without locks, replace the 5th digit **"L"**from the pattern number with **"N". Deduct $21**

End Panel Return or Bridge Unit

- To specify center-mounted edge grommet, replace the **"N"** suffix from the pattern number with **"G". Add $18**

Desk Components
End Units
Planning Guidelines

Desk End Units
Dividends desk end units are an "L" shaped, non-handed design that can be used on either end of a worksurface in freestanding and panel applications. Desk end units have the same footprint (outside dimension) as pedestals and can be interchanged with pedestals.

End units are used in "Preconfigured" single pedestal desks and end panel returns. They can also be specified by component for "Build-to-Spec" applications.

These include when an end panel is required on one end and a desk integration unit is required on the other, or when an end unit is required on both ends of the worksurface.

Available Sizes
Depths: 18", 24" and 30"
Width: 15"
Height: $26^{7}/_{8}$"

Desk End Unit Attachment
Desk end units have mounting brackets that allow attachment to worksurfaces with supplied screws. Dividends worksurfaces are pre-drilled for end unit attachment.

Construction
End unit specifications:
- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glides: $^{3}/_{8}$" 16-gauge steel with $1^{1}/_{2}$" of height adjustment
- Attachment bracket: 11-gauge steel

Desk Integration End Units
If a back panel (modesty) is required in a systems application, a desk integration end unit can be used in place of an end unit.

Panel-to-worksurface brackets are included and make the connection between the worksurface and Dividends Horizon panels. Desk integration end units are 15" wide.

Note: The desk integration end unit is a non-structural support. Panel-to-work surface brackets provide the actual support for the worksurface.

Note: Panel width must match the depth of the connecting worksurface.

Construction
Desk integration end unit specifications:
- Outer skin: 20-gauge steel
- Panel-to-worksurface brackets: 14-gauge steel

Intermediate End Units
Intermediate end units are freestanding "T" shaped end units used to support two desks in an in-line configuration.

Units attach to 18", 24" and 30" deep worksurfaces in place of desk end units. Mounting brackets and a front worksurface alignment plate are included with intermediate end units.

Available Size
- Depth: 14"
- Width: 30"
- Height: $26^{7}/_{8}$"

Construction
Intermediate end unit specifications:
- Outer skin: 20-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel

Desk End Unit



Intermediate End Unit



Desk End Unit Available Sizes



Desk Integration End Unit (Non-structural)



End Unit Configurations



Desk Integration End Unit

Intermediate End Unit

Desk Components
End Units
Desk End, Desk Integration and Intermediate

description	d *	d	w	h	pattern no.	P1	P2	P3
Desk End Unit	18″	16 5/8″	14 7/8″	26 7/8″	**DD1 EU18**	$345.	$379.	$398.
	24″	22 5/8″	14 7/8″	26 7/8″	**DD1 EU24**	380.	418.	437.
	30″	28 5/8″	14 7/8″	26 7/8″	**DD1 EU30**	415.	454.	476.
Desk Integration End Unit (Non-structural)	1 1/2″	1 1/2″	14 7/8″	26 7/8″	**DD1 DIEU**	192.	208.	217.
Intermediate End Unit	14″	12″	31 9/16″	26 7/8″	**DD1 IE30**	345.	379.	398.

d* = nominal depth
Dimensions listed under d w h are actual to the nearest 1/16″

Ordering Information

Desk End Unit
1. Pattern Number
2. Paint Finish

Desk Integration End Unit
1. Pattern Number
2. Paint Finish

Intermediate End Unit
1. Pattern Number
2. Paint Finish

Order Code

Desk End Unit	
Example:	**DD1 EU18, 117**
DD1 EU18	Pattern Number
117	Soft Grey Paint Finish
Desk Integration End Unit	
Example:	**DD1 DIEU, 117**
DD1 DIEU	Pattern Number
117	Soft Grey Paint Finish
Intermediate End Unit	
Example:	**DD1 IE30, 117**
DD1 IE30	Pattern Number
117	Soft Grey Paint Finish

Included with:

Desk End Unit

Desk Integration End Unit
- Panel-to-Worksurface Brackets (2)

Intermediate End Unit

Options

Desk End Unit

Desk Integration End Unit

Intermediate End Unit

Desk Components
Half Height Back Panels
Planning Guidelines

Half Height Back Panels
Dividends back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units. Back panels are softly-radiused to match the aesthetics of the Dividends Horizon system and extend 11" down from the worksurface to provide a half-height modesty.

Back panels are used in "Preconfigured" desks or can be specified separately by component for "Build-to-Spec" applications.

Available Sizes
- Widths: $19\frac{5}{8}$" to $48\frac{1}{4}$" see compatibility chart (below)
- Height: 11"

Back Panel Attachment
Back panels attach to the undersides of worksurfaces with mounting brackets and do not require attachment to adjacent pedestals or end units. Dividends Horizon worksurfaces are pre-drilled for back panel attachment.

Construction
Back panel specifications:
- Outer skin: 22-gauge steel
- Mounting Brace: 16-gauge

Back Panel Compatibility
The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management
When installed, back panels provide a $\frac{1}{2}$" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations





Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	$23\frac{7}{8}$"	DD1 BPD54	2
	60	$29\frac{7}{8}$	DD1 BPD60	2
	66	$35\frac{7}{8}$	DD1 BPD66	2
	72	$41\frac{7}{8}$	DD1 BPD72	2
Returns	36	$21\frac{5}{8}$	DD1 BPR36	1
	42	$27\frac{5}{8}$	DD1 BPR42	1
	48	$33\frac{5}{8}$	DD1 BPR48	1
	60	$45\frac{5}{8}$	DD1 BPR60	1
Bridge Units	30	$31\ 3/8$	DD1 BPB30	0
	36	$37\ 3/8$	DD1 BPB36	0
	42	$43\ 3/8$	DD1 BPB42	0
	48	$49\ 3/8$	DD1 BPB48	0
"U" Credenza w/2 peds	72	$26\frac{15}{16}$	DD1 BPU72	3
Freestanding Corner Unit (needs two back panels)	36	$20\frac{15}{16}$	DD1 BPV36	3
	42	$26\frac{15}{16}$	DD1 BPV42	3
	48	$32\frac{15}{16}$	DD1 BPV48	3

Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

Desk Components
Half Height Back Panels
For Desks, Returns, Bridges and 2 Pedestal Configuration

description	top width	w *	h	pattern no.	P1	P2	P3
Half Height Back panels for Desks	54″	29 7/8″	11″	**DD1 BPD54**	$193.	$209.	$219.
	60″	29 7/8″	11″	**DD1 BPD60**	202.	222.	231.
	66″	35 7/8″	11″	**DD1 BPD66**	212.	234.	243.
	72″	41 7/8″	11″	**DD1 BPD72**	224.	244.	258.
Half Height Back panels for Returns	36″	21 5/8″	11″	**DD1 BPR36**	171.	188.	197.
	42″	27 5/8″	11″	**DD1 BPR42**	178.	197.	206.
	48″	33 5/8″	11″	**DD1 BPR48**	192.	208.	217.
	60″	45 5/8″	11″	**DD1 BPR60**	212.	234.	243.
Half Height Back panels for Bridges	30″	31 3/8″	11″	**DD1 BPB30**	151.	166.	175.
	36″	37 3/8″	11″	**DD1 BPB36**	163.	178.	185.
	42″	43 3/8″	11″	**DD1 BPB42**	171.	188.	197.
	48″	49 3/8″	11″	**DD1 BPB48**	181.	200.	208.
Half Height Back panels for 2 Pedestal “U” Credenza	72″	26 15/16″	11″	**DD1 BPU72**	171.	188.	197.

Dimensions listed under w h are actual to the nearest 1/16″

Ordering Information

Back Panels for Bridges

1. Pattern Number
2. Paint Finish

Order Code

Back Panels for Bridges

Example:	**DD1 BPB36 , 117**
DD1 BPB36	Pattern Number
117	Soft Grey Paint Finish

Included with:

Back Panels for Bridges

- Attachment Hardware

Options

Back Panels for Bridges

Desk Components
Full Back Panels
Planning Guidelines

Full Back Panels
Dividends full back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units.

Full back panels are specified separately by component for "Build-to-Spec" applications.

Available Sizes
- Widths: 19 5/8" to 48 1/4" see compatibility chart (above)
- Height: 26 5/8

Full Back Panel Attachment
Back panels attach to the undersides of pedestals or end units with mounting brackets.

Construction
Back panel specifications:
- Outer skin: 20-gauge steel
- Mounting Brace: 16-gauge

Back Panel Compatibility
The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management
When installed, back panels provide a 1/2" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations





Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	23 7/8"	DD1 FFBPD54	2
	60	29 7/8	DD1 FFBPD60	2
	66	35 7/8	DD1 FBPD66	2
	72	41 7/8	DD1 FBPD72	2
Returns	36	21 5/8	DD1 FBPR36	1
	42	27 5/8	DD1 FBPR42	1
	48	33 5/8	DD1 FBPR48	1
	60	45 5/8	DD1 FBPR60	1
Bridge Units	30	31 5/8	DD1 FBPB30	0
	36	37 5/8	DD1 FBPB36	0
	42	43 5/8	DD1 FBPB42	0
	48	49 5/8	DD1 FBPB48	0
"U" Credenza w/2 peds	72	26 15/16	DD1 FBPU72	3
Freestanding Corner Unit (needs two back panels)	36	20 15/16	DD1 FBPV36	3
	42	26 15/16	DD1 FBPV42	3
	48	32 15/16	DD1 FBPV48	3

Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

Desk Components
Full Back Panels
For Desks, Returns, Bridges and 2 Pedestal Configuration

description	top width	w *	h	pattern no.	P1	P2	P3
Full Back panels for Desks	54″	23 7/8″	26 5/8″	**DD1 FBPD54**	$228.	$250.	$262.
	60″	29 7/8″	26 5/8″	**DD1 FBPD60**	232.	255.	268.
	66″	35 7/8″	26 5/8″	**DD1 FBPD66**	239.	263.	272.
	72″	41 7/8″	26 5/8″	**DD1 FBPD72**	246.	270.	283.
Full Back panels for Returns	36″	21 5/8″	26 5/8″	**DD1 FBPR36**	214.	235.	246.
	42″	27 5/8″	26 5/8″	**DD1 FBPR42**	219.	241.	251.
	48″	33 5/8″	26 5/8″	**DD1 FBPR48**	229.	251.	263.
	60″	45 5/8″	26 5/8″	**DD1 FBPR60**	250.	273.	289.
Full Back panels for Bridges	30″	31 3/8″	26 5/8″	**DD1 FBPB30**	201.	220.	230.
	36″	37 3/8″	26 5/8″	**DD1 FBPB36**	210.	232.	242.
	42″	43 3/8″	26 5/8″	**DD1 FBPB42**	229.	251.	263.
	48″	49 3/8″	26 5/8″	**DD1 FBPB48**	235.	259.	270.
Full Back panels for 2 Pedestal “U” Credenza	72″	26 15/16″	26 5/8″	**DD1 FBPU72**	219.	241.	251.

Dimensions listed under w h are actual to the nearest 1/16″

Ordering Information

Back Panels for Bridges

1. Pattern Number
2. Paint Finish

Order Code

Back Panels for Bridges

Example:	**DD1 FBPB36 , 117**
DD1 FBPB36	Pattern Number
117	Soft Grey Paint Finish

Included with:

Back Panels for Bridges

- Attachment Hardware

Options

Back Panels for Bridges

Pencil Tray
Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13 1/4 wide, 5 7/16 deep and 7/8 high. Black or clear finish available.

Hanging File Bar
Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.

Note: A hanging file bar is included with each file drawer when ordering desks or pedestals.

Drawer Dividers
Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.

Stationery Inserts
Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.

Pencil Drawer
For use with freestanding desks or panel-mounted worksurfaces with depths of 24 or more. 24 wide, 17 5/8 deep and 2 high. Black finish.

Attachment: Mounts on underside of worksurface with included mounting hardware

Pedestal Lock Retrofit Kit
Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core (keyed randomly unless specified keyed alike) and lock rod assembly (must be specified box/box/file or file/file).

Flat Brackets
Allow same-height worksurfaces to be joined in perpendicular configurations. All flat brackets are 3 3/4 wide. Black finish.

Three sizes available to support the following worksurface depths:

- 18 deep worksurfaces
- 24 deep worksurfaces
- 30 deep worksurfaces
- Construction: 14-gauge steel
- Attachment: Mounts on underside of worksurfaces in pre-drilled locations with included mounting hardware

Worksurface Cable Management Clips
Self-adhesive, injection-molded clips adhere to any flat, nonporous surface to route cables along and beneath worksurfaces. 3/4 x 1/2 internal dimension.

Worksurface Cable Management Basket
Steel wire basket attaches to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable basket slides forward to a position abutting the panel face to allow the passage of cords and cables. Black finish.

Worksurface Edge Grommet
Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.

Worksurface Reinforcement
Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.



Pencil Tray



Pencil Drawer



Stationery Inserts



Worksurface Cable Management Clip



Hanging File Bar



Drawer Divider, File Drawer



Flat Bracket



Worksurface Cable Management Basket



Drawer Divider, Box Drawer



Worksurface Reinforcement Panel Hung Application



Worksurface Edge Grommet

Desk Accessories
Drawer Organizers, Cable Management and Grommet Kits

description	type	w	d	h	pattern no.	list
Pencil Tray	Black finish	13 1/4″	5 7/8″	7/8″	**DS2PPTN**	$37.
	Clear finish	13 1/4″	5 7/8″	7/8″	**DS2PPTC**	44.
Hanging File Bar		12 3/16″	2 15/16″	1/2″	**DS1PFS**	32.
Drawer Divider, Box		12 3/8″	3″	3 1/8″	**DS1PBD**	32.
Drawer Divider, File		10	3 5/8″	6 3/8″	**DS1PFD**	32.
Stationary Inserts, box (4 trays)		13	15/16″	8 7/8″	**DS1PST**	170.
Pencil Drawer		24″	17 5/8″	2″	**DS1PCD**	231.
Worksurface Cable Management Clip	Package of 10	3/4″	1/2″		**D1WC**	38.
Worksurface Cable Management Basket	19 1/2″ wide	16 1/2″	3 1/2″	1 1/2″	**D1WB20**	40.
	25 1/2″ wide	25 1/2″	3 1/2″	1 1/2″	**D1WB26**	42.
	31 1/2″ wide	31 1/2″	3 1/2″	1 1/2″	**D1WB32**	53.
	35″ wide	35″	3 1/2″	1 1/2″	**D1WB36**	58.
	41″ wide	41″	3 1/2″	1 1/2″	**D1WB42**	61.
Worksurface Grommet Kit (Dark Grey)		2 3/16″	2 5/16″	1 3/8″	**D1WSG**	23.

Ordering Information	Order Code	Included with:	Options
Pencil Tray 1. Pattern Number	**Pencil Tray** *Example:* **DS1 PPT** **DS1 PPT** Pattern Number	**Pencil Tray**	

Desk Accessories
Flat Brackets and Worksurface Reinforcements

description	w	d	pattern no.	list
Flat Bracket (single pack)	3 3/4″	8 5/16″	**DB1F18SP**	$15.
	3 3/4″	14 5/8″	**DB1F24SP**	27.
	3 3/4″	20 15/16″	**DB1F30SP**	31.
Flat Bracket (package of 10)	3 3/4″	8 5/16″	**DB1F18TP**	128.
	3 3/4″	14 5/16″	**DB1F24TP**	212.
	3 3/4″	20 5/16″	**DB1F30TP**	244.
Worksurface Reinforcement	54″	4″	**DB1WR54**	61.
	60″	4″	**DB1WR60**	62.
	66″	4″	**DB1WR66**	65.
	72″	4″	**DB1WR72**	67.

Ordering Information	**Order Code**	**Included with:**	**Options**
Flat Bracket 1. Pattern Number	**Flat Bracket** *Example:* **DB1PWSP** **DB1PWSP** Pattern Number	**Flat Bracket**	**Flat Bracket**

Wall Mounting Suggestions

The following information is provided only as a guide, and represents minimum recommendations only. Knoll does not accept responsibility for the attachment of any Knoll product to a Customer's site wall. Wall specification/construction is the responsibility of the Customer and its structural engineer/architect. Failure to properly attach Knoll products to adequate wall structures can lead to property damage and/or personal injury.

You should consult your own structural engineers and/or architects and must not rely on the information provided herein.

It is the responsibility of the Customer and its structural engineers/architects to verify that the permanent structural walls (studs, blocks, solid masonry, etc.) on which the Knoll products are intended to be mounted are designed appropriately to support the product weight, PLUS 3 lbs. per linear inch for each useable shelf length

NOTE: A cabinet's top is considered a "useable shelf" and MUST be included in the calculation of the total load for an overhead cabinet.

It is the responsibility of the Customer and its structural engineer/architects to specify the fasteners and method for attaching the Knoll supplied wall mounting cleat, bracket, frame, etc. to the supporting wall and to confirm that the installers have adhered to these specifications. For all local building standards and codes, and additional requirements (including, but not limited to, seismic conditions) the Customer should always consult local code agencies.

		EXISTING CONSTRUCTION				
	NEW CONSTRUCTION	**Cinder Block or Poured Concrete Masonry Wall**	**Wood Stud Wall, the studs being FULL HEIGHT to the roof/floor above**	**Wood Stud Wall, the studs being only Ceiling Height**	**Steel Stud Wall, the studs being FULL HEIGHT to the roof/floor above**	**Steel Stud Wall, the studs being only Ceiling Height**
Stud Specification	Wood studs, grade #2 or better, 3 1/2" minimum width, **OR** Metal studs, minimum 25 gage thickness, 3 5/8" minimum width	The wall must be a minimum of 6" thick, and must be full height to the roof/ floor structure above	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width
Stud Centers	Metal and wood studs must be spaced at 16" c/c maximum	N/A	Wood studs must be spaced at 16" c/c maximum	Wood studs must be spaced at 16"" c/c maximum"	Metal studs must be spaced at 16" c/c maximum	Metal studs must be spaced at 16" c/c maximum
Stud Height	Metal and wood studs must extend upwards, and be securely attached to the roof/ floor structure above			Wood studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix #2 grade 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof/ floor structure above		Metal studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix metal bracing 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof / floor structure above
Mounting the Knoll Supplied Cleat, Bracket, Frame, etc*	Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the studs to accommodate the full width of the cabinet, **and beyond to the next stud.** Fasten the wood block to each stud using three screws at the ends of each block. (Fasten the Danback™ as directed by the manufacturer) Fasten the Knoll supplied wall mounting cleat, bracket, frame, etc directly to each wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	Fasten the Knoll supplied cabinet wall mounting cleat, bracket, frame, etc. directly to the masonry wall every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wall every 6", and fasten the lower horizontal element to the wall every 16"	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, **and beyond to the next stud.** Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, **and beyond to the next stud.** Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, **and beyond to the next stud.** Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, **and beyond to the next stud.** Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.
***Graham Wall Hung Shelf**	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	Fasten the Knoll supplied wall mounting brackets directly to the masonry wall, using the holes provided in each bracket	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above
Fasten the Knoll supplied wall cleat with...	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	3/16" x 3 1/2" Tapcon Masonry Screws or equiv. @ 6" c/c with 1-1/4" embedment, screwed directly into the masonry wall	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking

Alpha-Numeric Index

pattern no.	page
D19 6630N	311
D19 7230N	311
D19 7830N	311
D1BD6648DL	311
D1BD6648DR	311
D1BD6648SL	311
D1BD6648SR	311
D1BD7248DL	311
D1BD7248DR	311
D1BD7248SL	311
D1BD7248SR	311
D1C 3618N	305
D1C 3624N	305
D1C 422430N	305
D1C 4224N	305
D1C 423024N	305
D1C 482430N	305
D1C 4824N	305
D1C 483024N	305
D1C 4830N	305
D1CRL24	313
D1CRN24	313
D1CRR24	313
D1CS 4224N	305
D1CS 4824N	305
D1CS 4830N	305
D1D 4824N	311
D1D 4830N	311
D1D 6030N	311
D1D 6630N	311
D1D 7230N	311
D1D 7236N	311
D1H4818	313
D1H5118P	313
D1H6024	313
D1H6324P	313
D1L 3636SSN	307
D1L 4242SSN	307
D1L 4260SSN	307
D1L 4266SSN	307
D1L 4272SSN	307
D1L 4278SSN	307
D1L 4848DDN	309
D1L 4848DSN	309
D1L 4848SDN	309
D1L 4848SSN	307
D1L 4860DSN	309
D1L 4860SDN	309
D1L 4860SSN	307
D1L 4866DSN	309
D1L 4866SDN	309
D1L 4866SSN	307
D1L 4872DSN	309
D1L 4872SDN	309
D1L 4872SSN	307
D1L 4878SSN	307
D1L 4884SSN	307
D1L 6042SSN	307
D1L 6048DSN	309
D1L 6048SDN	309
D1L 6048SSN	307
D1L 6642SSN	307
D1L 6648DSN	309
D1L 6648SDN	309
D1L 6648SSN	307
D1L 7242SSN	307
D1L 7248DSN	309
D1L 7248SDN	309
D1L 7248SSN	307
D1L 7842SSN	307
D1L 7848SSN	307
D1L 8448SSN	307
D1P 6630N	311
D1P 7230N	311
D1P 7830N	311
D1R 1515C	315
D1R 1515S	315
D1R 2415	315
D1R 2418N	295
D1R 2424N	295
D1R 2430N	299
D1R 3015	315
D1R 3018N	295
D1R 3024N	295
D1R 3030N	299
D1R 3615	315
D1R 3618N	295
D1R 3624N	295
D1R 3630N	299
D1R 4215	315
D1R 4218N	295
D1R 4224N	295
D1R 4230N	299
D1R 4815	315
D1R 4818N	295
D1R 4824N	295
D1R 4830N	299
D1R 5415	315
D1R 5418N	295
D1R 5424N	295
D1R 5430N	299
D1R 6015	315
D1R 6018N	295
D1R 6024N	295
D1R 6030N	299
D1R 6036N	299
D1R 6615	315
D1R 6618N	295
D1R 6624N	295
D1R 6630N	299
D1R 6636N	299
D1R 7215	315
D1R 7218N	295
D1R 7224N	295
D1R 7230N	299
D1R 7236N	299
D1R 7815	315
D1R 7818N	295
D1R 7824N	295
D1R 7830N	299
D1R 7836N	299
D1R 8415	315
D1R 8418N	295
D1R 8424N	295
D1R 8430N	299
D1R 8436N	299
D1R 9015	315
D1R 9018N	295
D1R 9024N	295
D1R 9030N	299
D1R 9036N	299
D1R 9615	315
D1R 9618N	295
D1R 9624N	295
D1R 9630N	299
D1R 9636N	299
D1R2419N	297
D1R3019N	297
D1R3619N	297
D1R4219N	297
D1R4819N	297
D1R5419N	297
D1R6019N	297
D1R6619N	297
D1R7219N	297
D1R7819N	297
D1R8419N	297
D1R9019N	297
D1R9619N	297
D1W 362430N	301
D1W 363024N	301
D1W 422430N	301
D1W 423024N	301
D1W 482430N	301
D1W 483024N	301
D1W 721830N	301
D1W 722430N	301
D1W 722436N	301
D1W 723018N	301
D1W 723024N	301
D1W 723624N	301
D1W S481824N	302
D1W S481830N	302
D1W S482418N	302
D1W S482430N	302
D1W S483018N	302
D1W S483024N	302
D1W S601824N	302
D1W S601830N	302
D1W S602418N	302
D1W S602430N	302
D1W S603018N	302
D1W S603024N	302
D1W S661824N	302
D1W S661830N	302
D1W S662418N	302
D1W S662430N	302
D1W S663018N	302
D1W S663024N	302
D1W S721824N	302
D1W S721830N	302
D1W S722418N	302
D1W S722430N	302
D1W S723018N	302
D1W S723024N	302
D1W S781824N	302
D1W S781830N	302
D1W S782418N	302
D1W S782430N	302
D1W S783018N	302
D1W S783024N	302
D1W S841824N	302
D1W S841830N	302
D1W S842418N	302
D1W S842430N	302
D1W S843018N	302
D1W S843024N	302
D1W T482430N	303
D1W T483024N	303
D1W T602430N	303
D1W T603024N	303
D1W T662430N	303
D1W T663024N	303
D1W T722430N	303
D1W T723024N	303
D1WB20	207, 371
D1WB26	207, 371
D1WB32	207, 371
D1WB36	207, 371
D1WB42	207, 371
D1WC	207, 371
D1WSG	243, 371
D1WT218	177
D1WT224	177
D1WT324	177
D1WT424	177
D1WT518	177
D1WT524	177
D1WW11481824	177
D1WW11482418	177
D1WW12481824	177
D1WW12482418	177
D1WW124824L	177
D1WW124824R	177
D1WW13481824	177
D1WW13482418	177
D1WW134824L	177
D1WW134824R	177
D1WW34824	177
D1WW44824	177
D1WW54824L	177
D1WW54824R	177
D1WW64824L	177
D1WW64824R	177
D1WW74824L	177
D1WW74824R	177
D2H4824	313
D2H4836	313
D2H4848	313
D2H5124P	313
D2H5136P	313
D2H5148P	313
D2P1	81
DB120C (L or R)	323

pattern no.	*page*
DB1BD48SL	311
DB1BD48SR	311
DB1C 18 (L or R)	323
DB1C 18 (L or R) 10	323
DB1C 24 (L or R)	323
DB1C 24 (L or R) 10	323
DB1C 30 (L or R)	323
DB1C 30 (L or R) 10	323
DB1CL 24R	329
DB1CL24L	329
DB1CL24S	329
DB1F18SP	323, 372
DB1F18TP	323, 372
DB1F24SP	323, 372
DB1F24TP	323, 372
DB1F30SP	323, 372
DB1F30TP	323, 372
DB1LS15A	331
DB1LS18A	331
DB1LS24A	331
DB1LS30A	331
DB1LS36A	331
DB1LSP15	329
DB1LSP18	329
DB1LSP24	329
DB1LSP30	329
DB1LSP36	329
DB1LSS15	329
DB1LSS18	329
DB1LSS24	329
DB1LSS30	329
DB1LSS36	329
DB1PSP15	329
DB1PSP18	329
DB1PSP24	329
DB1PSP30	329
DB1PSP36	329
DB1PWS24	324
DB1PWS30	324
DB1PWS36	324
DB1PWS42	324
DB1PWS48	324
DB1PWSL	324
DB1PWSLWH	324
DB1PWSP	324
DB1PWSPWH	324
DB1PWSR	324
DB1PWSRWH	324
DB1RU18	227, 232
DB1S CR	331
DB1SWSL	327
DB1SWSP	327
DB1SWSR	327
DB1TB	331
DB1U18	227, 232
DB1WR54	323, 372
DB1WR60	323, 372
DB1WR66	323, 372
DB1WR72	323, 372
DB2CL24L	329
DB2CL24LS	329
DB2CL24R	329
DB2CL24RS	329
DBSMLH	327
DBSMRH	327

pattern no.	*page*
DCE1BD6648D(L/R)	317
DCE1BD6648S(L/R)	317
DCE1BD7248D(L/R)	317
DCE1BD7248S(L/R)	317
DCE1BD7848D(L/R)	317
DCE1BD7848S(L/R)	317
DCE1BD8448D(L/R)	317
DCE1BD8448S(L/R)	317
DCE1CR24L	319
DCE1CR24N	319
DCE1CR24R	319
DCE1H4818	319
DCE1H4818P	319
DCE1H6024	319
DCE1H6024P	319
DCE1L3636SSN	317
DCE1L4242DSN	317
DCE1L4242SDN	317
DCE1L4242SSN	317
DCE1L4260SSN	318
DCE1L4266SSN	318
DCE1L4272SSN	318
DCE1L4278SSN	318
DCE1L4848DDN	317
DCE1L4848DSN	317
DCE1L4848SDN	317
DCE1L4848SSN	317
DCE1L4860DSN	318
DCE1L4860SDN	318
DCE1L4860SSN	318
DCE1L4866DSN	318
DCE1L4866SDN	318
DCE1L4866SSN	318
DCE1L4872DSN	318
DCE1L4872SDN	318
DCE1L4872SSN	318
DCE1L4878SSN	318
DCE1L4884SSN	318
DCE1L6042SSN	318
DCE1L6048DSN	318
DCE1L6048SDN	318
DCE1L6048SSN	318
DCE1L6642SSN	318
DCE1L6648DSN	318
DCE1L6648SDN	318
DCE1L6648SSN	318
DCE1L7242SSN	318
DCE1L7248DSN	318
DCE1L7248SDN	318
DCE1L7248SSN	318
DCE1L7842SSN	318
DCE1L7848SSN	318
DCE1L8448SSN	318
DCE1R2424N	316
DCE1R2430N	316
DCE1R3024N	316
DCE1R3030N	316
DCE1R3624N	316
DCE1R3630N	316
DCE1R4224N	316
DCE1R4230N	316
DCE1R4824N	316
DCE1R4830N	316
DCE1R5424N	316
DCE1R5430N	316

pattern no.	*page*
DCE1R6024N	316
DCE1R6030N	316
DCE1R6624N	316
DCE1R6630N	316
DCE1R7224N	316
DCE1R7230N	316
DCE1R7824N	316
DCE1R7830N	316
DCE1R8424N	316
DCE1R8430N	316
DCE1R9024N	316
DCE1R9030N	316
DCE1R9624N	316
DCE1R9630N	316
DCE1W362430N	320
DCE1W363024N	320
DCE1W422430N	320
DCE1W423024N	320
DCE1W482430N	320
DCE1W483024N	320
DCE1W722430N	320
DCE1W723024N	320
DD1 BPB30	367
DD1 BPB36	367
DD1 BPB42	367
DD1 BPB48	367
DD1 BPD54	367
DD1 BPD60	367
DD1 BPD66	367
DD1 BPD72	367
DD1 BPR36	367
DD1 BPR42	367
DD1 BPR48	367
DD1 BPR60	367
DD1 BPU72	367
DD1 BPV36	359
DD1 BPV42	359
DD1 BPV48	359
DD1 DIEU	365
DD1 EU18	365
DD1 EU24	365
DD1 EU30	365
DD1 FBPB30	369
DD1 FBPB36	369
DD1 FBPB42	369
DD1 FBPB48	369
DD1 FBPD54	369
DD1 FBPD60	369
DD1 FBPD66	369
DD1 FBPD72	369
DD1 FBPR36	369
DD1 FBPR42	369
DD1 FBPR48	369
DD1 FBPR60	369
DD1 FBPU72	369
DD1 FBPV36	359
DD1 FBPV42	359
DD1 FBPV48	359
DD1 IE30	365
DD1B 3018N	363
DD1B 3618N	363
DD1B 3624N	363
DD1B 4218N	363
DD1B 4224N	363
DD1B 4818N	363

pattern no.	*page*
DD1B 4824N	363
DD1D L6024N	355
DD1D L6030N	355
DD1D L6624N	355
DD1D L6630N	355
DD1D L7224N	355
DD1D L7230N	355
DD1E 3618N	363
DD1E 3624N	363
DD1E 4218N	363
DD1E 4224N	363
DD1O L6036N	355
DD1O L6636N	355
DD1O L7236N	355
DD1P (L)3618N	363
DD1P (L)3624N	363
DD1P (L)4218N	363
DD1P (L)4224N	363
DD1P (L)4818N	363
DD1P (L)4824N	363
DD1R CU6	357, 359
DD1S CU12	359
DD1S L6024N	355
DD1S L6030N	355
DD1S L6624N	355
DD1S L6630N	355
DD1S L7224N	355
DD1S L7230N	355
DD1TEU24	331
DD1TEU30	331
DD1VD 3624 N	359
DD1VD 4224 N	359
DD1VD 4824 N	359
DD1VL 3624 N	359
DD1VL 4224 N	359
DD1VL 4824 N	359
DD2B 3018N	361
DD2B 3618N	361
DD2B 3624N	361
DD2B 4218N	361
DD2B 4224N	361
DD2B 4818N	361
DD2B 4824N	361
DD2D L6024N	353
DD2D L6030N	353
DD2D L6624N	353
DD2D L6630N	353
DD2D L7224N	353
DD2D L7230N	353
DD2E 3618N	361
DD2E 3624N	361
DD2E 4218N	361
DD2E 4224N	361
DD2O L6036N	353
DD2O L6636N	353
DD2O L7236N	353
DD2OD 36L	267
DD2OD 42L	267
DD2OD 48L	267
DD2OD 54L	267
DD2OD 60L	267
DD2OD 66L	267
DD2OD 72L	267
DD2P (L)3618N	361
DD2P (L)3624N	361

pattern no.	*page*
DD2P (L)4218N	361
DD2P (L)4224N	361
DD2P (L)4818N	361
DD2P (L)4824N	361
DD2S L6024N	353
DD2S L6030N	353
DD2S L6624N	353
DD2S L6630N	353
DD2S L7224N	353
DD2S L7230N	353
DD2VD 3624 N	357
DD2VD 4224 N	357
DD2VD 4824 N	357
DD2VL 3624 N	357
DD2VL 4224 N	357
DD2VL 4824 N	357
DD3 PS36	268
DD3 PS42	268
DD3 PS48	268
DD3 PS54	268
DD3 PS60	268
DD3 PS66	268
DD3 PS72	268
DE1	196, 197
DE1 FDP	191
DE1 KCBW	75
DE18 B1NY1	203
DE18 BI56	203
DE18 BI56(L/R)	199
DE18 CI144	199
DE18 RBI56	199
DE18 RBI56SF	203
DE1DATSHD	207
DE1DATSHDF	207
DE1DOR4	187
DE1DOR5	187
DE1DOR6	187
DE1DR1	187
DE1DR2	187
DE1DR3	187
DE1DR4	187
DE1DR5	187
DE1DR6	187
DE1E B1NY1	203
DE1E BI56	203
DE1E BI56(L/R)	199
DE1E CI144	199
DE1E RBI56	199
DE1E RBI56SF	203
DE1(E,8,T) PCNP	183
DE1(E,8,T) PCWP	183
DE1(E,8,T) PJ15NP	183
DE1(E,8,T) PJ15WP	183
DE1(E,8,T) PJ18NP	183
DE1(E,8,T) PJ18WP	183
DE1(E,8,T) PJ24NP	183
DE1(E,8,T) PJ24WP	183
DE1(E,8,T) PJ30NP	183
DE1(E,8,T) PJ30WP	183
DE1(E,8,T) PJ36NP	183
DE1(E,8,T) PJ36WP	183
DE1(E,8,T) PJ42NP	183
DE1(E,8,T) PJ42WP	183
DE1(E,8,T) PJ48NP	183
DE1(E,8,T) PJ48WP	183, 191, 197
DE1(E,8,T) PJ54WP	184, 191, 197
DE1(E,8,T) PJ60WP	184, 191, 197
DE1(E,8,T) PJ66WP	184, 191
DE1(E,8,T) PJ72WP	184, 191
DE1(E,8,T) PJ78WP	184, 191
DE1(E,8,T) PJ84WP	184, 191
DE1(E,8,T) PJ96WP	184
DE1(E,8,T) PM24	183
DE1(E,8,T) PM30	183
DE1(E,8,T) PM36	183
DE1(E,8,T) PM42	183
DE1(E,8,T) PM48	183
DE1(E,8,T) PM60	183
DE1(E,8,T) PMS24	183
DE1(E,8,T) PMS30	183
DE1(E,8,T) PMS36	183
DE1(E,8,T) PMS42	183
DE1(E,8,T) PMS48	183
DE1(E,8,T) PMS60	183
DE1KC	187
DE1T B1NY1	203
DE1T BI56	203
DE1T BI56(L/R)	199
DE1T CI144	199
DE1T RBI56	199
DE1T RBI56SF	203
DE2	196
DE2PP36S	200
DE2PP36T	200
DE2PP42S	200
DE2PP42T	200
DE2PP50S	200
DE2PP50T	200
DE2PP64S	200
DE2PP64T	200
DE2PP78S	200
DE2PP78T	200
DE4WSMC	192
DE4WSME108	192
DE4WSME72	192
DE4WSMED108	192
DE4WSMED72	192
DE6 FDP	191
DE6 FDPF	191
DE6 VDR1	190
DE6 VDR2	190
DE6 VDR3	190
DE6 VDR4	190
DE6 VDR5	190
DE6 VDR6	190
DE6 VPM	190
DL3L193M	235
DL3L193W	235
DL3L196M	235
DL3L196W	235
DL3L199M	235
DL3L199W	235
DL3L3712M	235
DL3L3712W	235
DL3L3718M	235
DL3L3718W	235
DL3L376M	235
DL3L376W	235
DL3T5E19S	235
DL3T5E25A	235
DL3T5E25S	235
DL3T5E37A	235
DL3T5E37S	235
DL3T5E49A	235
DL3T5E49S	235
DL3TC	235
DP	101, 129, 131, 135, 137, 138, 141, 153, 173, 174
DP1	79
DP1 CG	147
DP1 CHB	147
DP1 CHP	147
DP1 TKC	207
DP1 VWG	207
DP120PC08S	174
DP120PC14S	174
DP120PC22S	174
DP120PC28S	174
DP120PC36S	174
DP120PC36SF	174
DP120PC42S	174
DP120PC42SH	174
DP120PC50S	174
DP120PC57S	174
DP120PC64S	174
DP120PC78S	174
DP120PO36	174
DP120PO42	174
DP120PO50	174
DP120PO57	174
DP120PO64	174
DP120PO78	174
DP120S	174
DP120SPO 14	173
DP120SPO 21	173
DP120SPO 28	173
DP1AU0714	117
DP1AU0715	117
DP1AU0717	117
DP1AU0718	117
DP1AU0723	117
DP1AU0724	117
DP1AU0729	117
DP1AU0730	117
DP1AU0735	117
DP1AU0736	117
DP1AU0741	117
DP1AU0742	117
DP1AU0747	117
DP1AU0748	117
DP1AU0750	168
DP1AU0751	168
DP1AU0753	117
DP1AU0754	117
DP1AU0756	168
DP1AU0757	168
DP1AU0759	117
DP1AU0760	117
DP1AU0762	168
DP1AU0763	168
DP1AU0765	117
DP1AU0766	117
DP1AU0768	168
DP1AU0769	168
DP1AU0771	117
DP1AU0772	117
DP1AU0774	168
DP1AU0775	168
DP1AU0777	117
DP1AU0778	117
DP1AU0780	168
DP1AU0781	168
DP1AU0783	117
DP1AU0784	117
DP1AU0786	168
DP1AU0787	168
DP1AU0789	117
DP1AU0790	117
DP1AU0792	168
DP1AU0793	168
DP1AU0795	117
DP1AU0796	117
DP1AU0798	168
DP1AU0799	168
DP1AU1414	118
DP1AU1415	118
DP1AU1417	118
DP1AU1418	118
DP1AU1423	118
DP1AU1424	118
DP1AU1429	118
DP1AU1430	118
DP1AU1435	118
DP1AU1436	118
DP1AU1441	118
DP1AU1442	118
DP1AU1447	118
DP1AU1448	118
DP1AU1450	169
DP1AU1451	168
DP1AU1453	118
DP1AU1454	118
DP1AU1456	169
DP1AU1457	168
DP1AU1459	118
DP1AU1460	118
DP1AU1462	169
DP1AU1463	168
DP1AU1465	118
DP1AU1466	118
DP1AU1468	169
DP1AU1469	168
DP1AU1471	118
DP1AU1472	118
DP1AU1474	169
DP1AU1475	168
DP1AU1477	118
DP1AU1478	118
DP1AU1480	169
DP1AU1481	168
DP1AU1483	118
DP1AU1484	118
DP1AU1486	169
DP1AU1487	168
DP1AU1489	118
DP1AU1490	118
DP1AU1492	169
DP1AU1493	168
DP1AU1495	118
DP1AU1496	118
DP1AU1498	169

pattern no.	*page*
DP1AU1499	168
DP1AUECTP	118, 169
DP1BCT18	208
DP1BCT24	208
DP1BCT30	208
DP1BCT36	208
DP1BCT42	208
DP1BCT48	208
DP1BCT60	208
DP1FPRBL	147
DP1FPRBS	147
DP1FPRBT	147
DP1FPRBX	147
DP1MBT24	85
DP1MBT30	85
DP1MBT36	85
DP1MBT42	85
DP1MBT48	85
DP1PRBL	147
DP1PRBS	147
DP1PRBT	147
DP1PRBX	147
DP1PRFN15	148
DP1PRFN250	148
DP1PRFN70	148
DP1PT3	141
DP1PT4	141
DP1SO1015	67
DP1SO1018	67
DP1SO1024	67
DP1SO1030	67
DP1SO1036	67
DP1SO1042	67
DP1SO1048	67
DP1SO1060	67
DP1SO1415	67
DP1SO1418	67
DP1SO1424	67
DP1SO1430	67
DP1SO1436	67
DP1SO1442	67
DP1SO1448	67
DP1SO1460	67
DP1SO2115	68
DP1SO2118	68
DP1SO2124	68
DP1SO2130	68
DP1SO2136	68
DP1SO2142	68
DP1SO2148	68
DP1SO2160	68
DP1SO2418	75
DP1SO2424	75
DP1SO2430	75
DP1SO2436	75
DP1SO2442	75
DP1SO2448	75
DP1SO2460	75
DP1SO2815	57, 68, 156
DP1SO2815CCF	160
DP1SO2818	57, 68, 156
DP1SO2818CCF	160
DP1SO2824	57, 68, 156
DP1SO2824CCF	160
DP1SO2830	57, 68, 156
DP1SO2830CCF	160
DP1SO2830EPEF	164
DP1SO2836	57, 68, 156
DP1SO2836CCF	160
DP1SO2836EPEF	164
DP1SO2842	57, 68, 156
DP1SO2842CCF	160
DP1SO2848	57, 68, 156
DP1SO2848CCF	160
DP1SO2848EPEF	164
DP1SO2860	57, 68, 156
DP1SO2860CCF	160
DP1SO2860EPEF	164
DP1SO4215	57, 156
DP1SO4215CCF	160
DP1SO4218	57, 156
DP1SO4218CCF	160
DP1SO4224	57, 156
DP1SO4224CCF	160
DP1SO4230	57, 156
DP1SO4230CCF	160
DP1SO4230EPEF	164
DP1SO4236	57, 156
DP1SO4236CCF	160
DP1SO4236EPEF	164
DP1SO4242	57, 156
DP1SO4242CCF	160
DP1SO4248	57, 156
DP1SO4248CCF	160
DP1SO4248EPEF	164
DP1SO4260	57, 156
DP1SO4260CCF	160
DP1SO4260EPEF	164
DP1SO5015	57, 157
DP1SO5015CCF	161
DP1SO5018	57, 157
DP1SO5018CCF	161
DP1SO5024	57, 157
DP1SO5024CCF	161
DP1SO5030	57, 157
DP1SO5030CCF	161
DP1SO5030EPEF	165
DP1SO5036	57, 157
DP1SO5036CCF	161
DP1SO5036EPEF	165
DP1SO5042	57, 157
DP1SO5042CCF	161
DP1SO5048	57, 157
DP1SO5048CCF	161
DP1SO5048EPEF	165
DP1SO5060	57, 157
DP1SO5060CCF	161
DP1SO5060EPEF	165
DP1SO5715	58, 157
DP1SO5715CCF	161
DP1SO5718	58, 157
DP1SO5718CCF	161
DP1SO5724	58, 157
DP1SO5724CCF	161
DP1SO5730	58, 157
DP1SO5730CCF	161
DP1SO5730EPEF	165
DP1SO5736	58, 157
DP1SO5736CCF	161
DP1SO5736EPEF	165
DP1SO5742	58, 157
DP1SO5742CCF	161
DP1SO5748	58, 157
DP1SO5748CCF	161
DP1SO5748EPEF	165
DP1SO5760	58, 157
DP1SO5760CCF	161
DP1SO5760EPEF	165
DP1SO6415	58, 157
DP1SO6415CCF	161
DP1SO6418	58, 157
DP1SO6418CCF	161
DP1SO6424	58, 157
DP1SO6424CCF	161
DP1SO6430	58, 157
DP1SO6430CCF	161
DP1SO6430EPEF	165
DP1SO6436	58, 157
DP1SO6436CCF	161
DP1SO6436EPEF	165
DP1SO6442	58, 157
DP1SO6442CCF	161
DP1SO6448	58, 157
DP1SO6448CCF	161
DP1SO6448EPEF	165
DP1SO6460	58, 157
DP1SO6460CCF	161
DP1SO715	67
DP1SO718	67
DP1SO724	67
DP1SO730	67
DP1SO736	67
DP1SO742	67
DP1SO748	67
DP1SO760	67
DP1SO7815	58
DP1SO7818	58
DP1SO7824	58
DP1SO7830	58
DP1SO7836	58
DP1SO7842	58
DP1SO7848	58
DP1SOS15	69
DP1SOS18	69
DP1SOS24	69
DP1SOS30	69
DP1SOS36	69
DP1SOS42	69
DP1SOS48	69
DP1SOS60	69
DP1SOWH15	57, 156
DP1SOWH15CCF	160
DP1SOWH18	57, 156
DP1SOWH18CCF	160
DP1SOWH24	57, 156
DP1SOWH24CCF	160
DP1SOWH30	57, 156
DP1SOWH30CCF	160
DP1SOWH30EPEF	164
DP1SOWH36	57, 156
DP1SOWH36CCF	160
DP1SOWH36EPEF	164
DP1SOWH42	57, 156
DP1SOWH42CCF	160
DP1SOWH48	57, 156
DP1SOWH48CCF	160
DP1SOWH48EPEF	164
DP1SOWH60	57, 156
DP1SOWH60CCF	160
DP1SOWH60EPEF	164
DP1SW0724	95
DP1SW0730	95
DP1SW0736	95
DP1SW0742	95
DP1SW0748	95
DP1SW1424	95
DP1SW1430	95
DP1SW1436	95
DP1SW1442	95
DP1SW1448	95
DP1SW2124	95
DP1SW2130	95
DP1SW2136	95
DP1SW2142	95
DP1SW2148	95
DP1SW2824	95
DP1SW2830	95
DP1SW2836	95
DP1SW2842	95
DP1SW2848	95
DP1WT57	144
DP1WT64	144
DP1WT71	144
DP1WT78	144
DP1WTBTC15	144
DP1WTBTC18	144
DP1WTBTC24	144
DP1WTBTC30	144
DP1WTBTC36	144
DP1WTBTC42	144
DP1WTBTC48	144
DP1WTET57	144
DP1WTET64	144
DP1WTET71	144
DP1WTET78	144
DP1WTTC15	144
DP1WTTC18	144
DP1WTTC24	144
DP1WTTC30	144
DP1WTTC36	144
DP1WTTC42	144
DP1WTTC48	144
DP1WTTC54	144
DP1WTTC60	144
DP1WTTC66	144
DP1WTTC72	144
DP1WTTC78	144
DP1WTTC84	144
DP1WTTC90	144
DP1WTTC96	144
DP1WTTSB	145
DP2 STFL1418	53
DP2 STFL1424	53
DP2 STFL1430	53
DP2 STFL1436	53
DP2 STFL1442	53
DP2 STFL1448	53
DP2APO36	131
DP2APO42	131
DP2APO50	131

pattern no.	*page*
DP2APO57	131
DP2APO64	131
DP2APO78	131
DP2ASPO 14	132
DP2ASPO 21	132
DP2ASPO 28	132
DP2BC18K	75
DP2BC24K	75
DP2BC30K	75
DP2BC36K	75
DP2BC42K	75
DP2BC48K	75
DP2BC60K	75
DP2CHTP	147
DP2PMS36	141
DP2PMS42	141
DP2PMS50	141
DP2PMS57	141
DP2PMS64	141
DP2PMS78	141
DP2PRFIC15	148
DP2PRFIC70	148
DP2PRFN15	148
DP2PRFN70	148
DP2PRFW15	148
DP2PRFW70	148
DP2PS	90
DP2SOS15	69
DP2SOS18	69
DP2SOS24	69
DP2SOS30	69
DP2SOS36	69
DP2SOS42	69
DP2SOS48	69
DP2SOS60	69
DP2SOSC	69
DP2STF 2118	53
DP2STF 2124	53
DP2STF 2130	53
DP2STF 2136	53
DP2STF 2142	53
DP2STF 2148	53
DP2S(T/N)F 1418	53
DP2S(T/N)F 1424	53
DP2S(T/N)F 1430	53
DP2S(T/N)F 1436	53
DP2S(T/N)F 1442	53
DP2S(T/N)F 1448	53
DP2S(T/N)F 2818	53
DP2S(T/N)F 2824	53
DP2S(T/N)F 2830	53
DP2S(T/N)F 2836	53
DP2S(T/N)F 2842	53
DP2S(T/N)F 2848	53
DP3ESB	76, 91, 92
DP3L10715	71
DP3L10718	71
DP3L10724	71
DP3L10730	71
DP3L10736	71
DP3L10742	71
DP3L10748	71
DP3L11015	71
DP3L11018	71
DP3L11024	71
DP3L11030	71
DP3L11036	71
DP3L11042	71
DP3L11048	71
DP3L11415	71
DP3L11415F	72
DP3L11418	71
DP3L11418F	72
DP3L11424	71
DP3L11424F	72
DP3L11430	71
DP3L11430F	72
DP3L11436	71
DP3L11436F	72
DP3L11442	71
DP3L11442F	72
DP3L11448	71
DP3L11448F	72
DP3L12115	71
DP3L12118	71
DP3L12124	71
DP3L12130	71
DP3L12136	71
DP3L12142	71
DP3L12148	71
DP3L12415	77
DP3L12415F	77
DP3L12418	77
DP3L12418F	77
DP3L12424	77
DP3L12424F	77
DP3L12430	77
DP3L12430F	77
DP3L12436	77
DP3L12436F	77
DP3L12442	77
DP3L12442F	77
DP3L12448	77
DP3L12448F	77
DP3L12815	61, 71, 158
DP3L12815CCF	162
DP3L12815F	62, 72
DP3L12818	61, 71, 158
DP3L12818CCF	162
DP3L12818F	62, 72
DP3L12824	61, 71, 158
DP3L12824CCF	162
DP3L12824F	62, 72
DP3L12830	61, 71, 158
DP3L12830CCF	162
DP3L12830EPEF	166
DP3L12830F	62, 72
DP3L12836	61, 71, 158
DP3L12836CCF	162
DP3L12836EPEF	166
DP3L12836F	62, 72
DP3L12842	61, 71, 158
DP3L12842CCF	162
DP3L12842F	62, 72
DP3L12848	61, 71, 158
DP3L12848CCF	162
DP3L12848EPEF	166
DP3L12848F	62, 72
DP3L12860EPEF	166
DP3L12872EPEF	166
DP3L12884EPEF	166
DP3L14215	61, 158
DP3L14215CCF	162
DP3L14215F	62
DP3L14218	61, 158
DP3L14218CCF	162
DP3L14218F	62
DP3L14224	61, 158
DP3L14224CCF	162
DP3L14224F	62
DP3L14230	61, 158
DP3L14230CCF	162
DP3L14230EPEF	166
DP3L14230F	62
DP3L14236	61, 158
DP3L14236CCF	162
DP3L14236EPEF	166
DP3L14236F	62
DP3L14242	61, 158
DP3L14242CCF	162
DP3L14242F	62
DP3L14248	61, 158
DP3L14248CCF	162
DP3L14248EPEF	166
DP3L14248F	62
DP3L14260EPEF	166
DP3L14272EPEF	166
DP3L14284EPEF	166
DP3L15015	63, 159
DP3L15015CCF	163
DP3L15015F	64
DP3L15018	63, 159
DP3L15018CCF	163
DP3L15018F	64
DP3L15024	63, 159
DP3L15024CCF	163
DP3L15024F	64
DP3L15030	63, 159
DP3L15030CCF	163
DP3L15030EPEF	167
DP3L15030F	64
DP3L15036	63, 159
DP3L15036CCF	163
DP3L15036EPEF	167
DP3L15036F	64
DP3L15042	63, 159
DP3L15042CCF	163
DP3L15042F	64
DP3L15048	63, 159
DP3L15048CCF	163
DP3L15048EPEF	167
DP3L15048F	64
DP3L15060EPEF	167
DP3L15072EPEF	167
DP3L15084EPEF	167
DP3L15715	63, 159
DP3L15715CCF	163
DP3L15715F	64
DP3L15718	63, 159
DP3L15718CCF	163
DP3L15718F	64
DP3L15724	63, 159
DP3L15724CCF	163
DP3L15724F	64
DP3L15730	63, 159
DP3L15730CCF	163
DP3L15730EPEF	167
DP3L15730F	64
DP3L15736	63, 159
DP3L15736CCF	163
DP3L15736EPEF	167
DP3L15736F	64
DP3L15742	63, 159
DP3L15742CCF	163
DP3L15742F	64
DP3L15748	63, 159
DP3L15748CCF	163
DP3L15748EPEF	167
DP3L15748F	64
DP3L15760EPEF	167
DP3L15772EPEF	167
DP3L15784EPEF	167
DP3L1WH15	61, 158
DP3L1WH15CCF	162
DP3L1WH15F	62
DP3L1WH18	61, 158
DP3L1WH18CCF	162
DP3L1WH18F	62
DP3L1WH24	61, 158
DP3L1WH24CCF	162
DP3L1WH24F	62
DP3L1WH30	61, 158
DP3L1WH30CCF	162
DP3L1WH30EPEF	166
DP3L1WH30F	62
DP3L1WH36	61, 158
DP3L1WH36CCF	162
DP3L1WH36EPEF	166
DP3L1WH36F	62
DP3L1WH42	61, 158
DP3L1WH42CCF	162
DP3L1WH42F	62
DP3L1WH48	61, 158
DP3L1WH48CCF	162
DP3L1WH48EPEF	166
DP3L1WH48F	62
DP3L1WH60EPEF	166
DP3L1WH72EPEF	166
DP3L1WH84EPEF	166
DP3MB	84, 85
DP3PSB	76, 89, 90
DP3PWS36	141
DP3PWS42	141
DP3PWS50	141
DP3PWS57	141
DP3PWS64	141
DP3PWS78	141
DP3SS	76, 87, 88
DP6PE08	136
DP6PE14	136
DP6PE22	136
DP6PE28	136
DP6PE36	136
DP6PE36F	136
DP6PE42	136
DP6PE42H	136
DP6PE50	136
DP6PE57	136
DP6PE64	136
DP6PE78	136

pattern no.	*page*
DP6PEWH	136
DP6PEWH36	136
DP6PEWH42	136
DP6PEWH50	136
DP6PEWH57	136
DP6PEWH64	136
DP6PEWH78	136
DP6PEWHS14	136
DP6PEWHS21	136
DP6PEWHS28	136
DP6TF	97
DP6TS	98
DP7	48, 49, 50
DP71RCT18	208
DP71RCT24	208
DP71RCT30	208
DP71RCT36	208
DP71RCT42	208
DP71RCT48	208
DP71RCT60	208
DP72RCT18	208
DP72RCT24	208
DP72RCT30	208
DP72RCT36	208
DP72RCT42	208
DP72RCT48	208
DP72RCT60	208
DP7BF	124
DP7CBBFR4218	43
DP7CBBFR4224	43
DP7CBBFR4230	43
DP7CBBFR4236	43
DP7CBBFR4242	43
DP7CBBFR4248	43
DP7CBBFR4260	43
DP7CBBFR5018	43
DP7CBBFR5024	43
DP7CBBFR5030	43
DP7CBBFR5036	43
DP7CBBFR5042	43
DP7CBBFR5048	43
DP7CBBFR5060	43
DP7CBBFR5718	44
DP7CBBFR5724	44
DP7CBBFR5730	44
DP7CBBFR5736	44
DP7CBBFR5742	44
DP7CBBFR5748	44
DP7CBBFR5760	44
DP7CBBFR6418	44
DP7CBBFR6424	44
DP7CBBFR6430	44
DP7CBBFR6436	44
DP7CBBFR6442	44
DP7CBBFR6448	44
DP7CBBFR6460	44
DP7CBBFR7818	45
DP7CBBFR7824	45
DP7CBBFR7830	45
DP7CBBFR7836	45
DP7CBBFR7842	45
DP7CBBFR7848	45
DP7CBBRR4218	41
DP7CBBRR4224	41
DP7CBBRR4230	41
DP7CBBRR4236	41
DP7CBBRR4242	41
DP7CBBRR4248	41
DP7CBBRR4260	41
DP7CBBRR5018	41
DP7CBBRR5024	41
DP7CBBRR5030	41
DP7CBBRR5036	41
DP7CBBRR5042	41
DP7CBBRR5048	41
DP7CBBRR5060	41
DP7CBBRR5718	42
DP7CBBRR5724	42
DP7CBBRR5730	42
DP7CBBRR5736	42
DP7CBBRR5742	42
DP7CBBRR5748	42
DP7CBBRR5760	42
DP7CBBRR6418	42
DP7CBBRR6424	42
DP7CBBRR6430	42
DP7CBBRR6436	42
DP7CBBRR6442	42
DP7CBBRR6448	42
DP7CBBRR6460	42
DP7CBBRR7818	42
DP7CBBRR7824	42
DP7CBBRR7830	42
DP7CBBRR7836	42
DP7CBBRR7842	42
DP7CBBRR7848	42
DP7CERK	203
DP7CMMFR3615	19
DP7CMMFR3618	19
DP7CMMFR3624	19
DP7CMMFR3630	19
DP7CMMFR3636	19
DP7CMMFR3642	19
DP7CMMFR3648	19
DP7CMMFR3660	19
DP7CMMFR4215	19
DP7CMMFR4218	19
DP7CMMFR4224	19
DP7CMMFR4230	19
DP7CMMFR4236	19
DP7CMMFR4242	19
DP7CMMFR4248	19
DP7CMMFR4260	19
DP7CMMFR5015	20
DP7CMMFR5018	20
DP7CMMFR5024	20
DP7CMMFR5030	20
DP7CMMFR5036	20
DP7CMMFR5042	20
DP7CMMFR5048	20
DP7CMMFR5060	20
DP7CMMFR5715	20
DP7CMMFR5718	20
DP7CMMFR5724	20
DP7CMMFR5730	20
DP7CMMFR5736	20
DP7CMMFR5742	20
DP7CMMFR5748	20
DP7CMMFR5760	20
DP7CMMFR6415	20
DP7CMMFR6418	20
DP7CMMFR6424	20
DP7CMMFR6430	20
DP7CMMFR6436	20
DP7CMMFR6442	20
DP7CMMFR6448	20
DP7CMMFR6460	20
DP7CMMFR7815	21
DP7CMMFR7818	21
DP7CMMFR7824	21
DP7CMMFR7830	21
DP7CMMFR7836	21
DP7CMMFR7842	21
DP7CMMFR7848	21
DP7CMMFRWH15	19
DP7CMMFRWH18	19
DP7CMMFRWH24	19
DP7CMMFRWH30	19
DP7CMMFRWH36	19
DP7CMMFRWH42	19
DP7CMMFRWH48	19
DP7CMMFRWH60	19
DP7CMMLL3618	17
DP7CMMLL3624	17
DP7CMMLL3630	17
DP7CMMLL3636	17
DP7CMMLL3642	17
DP7CMMLL3648	17
DP7CMMLL3660	17
DP7CMMLL4218	17
DP7CMMLL4224	17
DP7CMMLL4230	17
DP7CMMLL4236	17
DP7CMMLL4242	17
DP7CMMLL4248	17
DP7CMMLL4260	17
DP7CMMLL5018	17
DP7CMMLL5024	17
DP7CMMLL5030	17
DP7CMMLL5036	17
DP7CMMLL5042	17
DP7CMMLL5048	17
DP7CMMLL5060	17
DP7CMMLL5718	18
DP7CMMLL5724	18
DP7CMMLL5730	18
DP7CMMLL5736	18
DP7CMMLL5742	18
DP7CMMLL5748	18
DP7CMMLL5760	18
DP7CMMLL6418	18
DP7CMMLL6424	18
DP7CMMLL6430	18
DP7CMMLL6436	18
DP7CMMLL6442	18
DP7CMMLL6448	18
DP7CMMLL6460	18
DP7CMMLL7818	18
DP7CMMLL7824	18
DP7CMMLL7830	18
DP7CMMLL7836	18
DP7CMMLL7842	18
DP7CMMLL7848	18
DP7CMMLLWH18	17
DP7CMMLLWH24	17
DP7CMMLLWH30	17
DP7CMMLLWH36	17
DP7CMMLLWH42	17
DP7CMMLLWH48	17
DP7CMMLLWH60	17
DP7CMMRR3615	15
DP7CMMRR3618	15
DP7CMMRR3624	15
DP7CMMRR3630	15
DP7CMMRR3636	15
DP7CMMRR3642	15
DP7CMMRR3648	15
DP7CMMRR3660	15
DP7CMMRR4215	15
DP7CMMRR4218	15
DP7CMMRR4224	15
DP7CMMRR4230	15
DP7CMMRR4236	15
DP7CMMRR4242	15
DP7CMMRR4248	15
DP7CMMRR4260	15
DP7CMMRR5015	15
DP7CMMRR5018	15
DP7CMMRR5024	15
DP7CMMRR5030	15
DP7CMMRR5036	15
DP7CMMRR5042	15
DP7CMMRR5048	15
DP7CMMRR5060	15
DP7CMMRR5715	16
DP7CMMRR5718	16
DP7CMMRR5724	16
DP7CMMRR5730	16
DP7CMMRR5736	16
DP7CMMRR5742	16
DP7CMMRR5748	16
DP7CMMRR5760	16
DP7CMMRR6415	16
DP7CMMRR6418	16
DP7CMMRR6424	16
DP7CMMRR6430	16
DP7CMMRR6436	16
DP7CMMRR6442	16
DP7CMMRR6448	16
DP7CMMRR6460	16
DP7CMMRR7815	16
DP7CMMRR7818	16
DP7CMMRR7824	16
DP7CMMRR7830	16
DP7CMMRR7836	16
DP7CMMRR7842	16
DP7CMMRR7848	16
DP7CMMRRWH15	15
DP7CMMRRWH18	15
DP7CMMRRWH24	15
DP7CMMRRWH30	15
DP7CMMRRWH36	15
DP7CMMRRWH42	15
DP7CMMRRWH48	15
DP7CMMRRWH60	15
DP7CPPFR4215	37
DP7CPPFR4218	37
DP7CPPFR4224	37
DP7CPPFR4230	37
DP7CPPFR4236	37

pattern no.	*page*
DP7CPPFR4242	37
DP7CPPFR4248	37
DP7CPPFR4260	37
DP7CPPFR5015	37
DP7CPPFR5018	37
DP7CPPFR5024	37
DP7CPPFR5030	37
DP7CPPFR5036	37
DP7CPPFR5042	37
DP7CPPFR5048	37
DP7CPPFR5060	37
DP7CPPFR5715	38
DP7CPPFR5718	38
DP7CPPFR5724	38
DP7CPPFR5730	38
DP7CPPFR5736	38
DP7CPPFR5742	38
DP7CPPFR5748	38
DP7CPPFR5760	38
DP7CPPFR6415	38
DP7CPPFR6418	38
DP7CPPFR6424	38
DP7CPPFR6430	38
DP7CPPFR6436	38
DP7CPPFR6442	38
DP7CPPFR6448	38
DP7CPPFR6460	38
DP7CPPFR7815	39
DP7CPPFR7818	39
DP7CPPFR7824	39
DP7CPPFR7830	39
DP7CPPFR7836	39
DP7CPPFR7842	39
DP7CPPFR7848	39
DP7CPPLL4218	34
DP7CPPLL4224	34
DP7CPPLL4230	34
DP7CPPLL4236	34
DP7CPPLL4242	34
DP7CPPLL4248	34
DP7CPPLL4260	34
DP7CPPLL5018	34
DP7CPPLL5024	34
DP7CPPLL5030	34
DP7CPPLL5036	34
DP7CPPLL5042	34
DP7CPPLL5048	34
DP7CPPLL5060	34
DP7CPPLL5718	35
DP7CPPLL5724	35
DP7CPPLL5730	35
DP7CPPLL5736	35
DP7CPPLL5742	35
DP7CPPLL5748	35
DP7CPPLL5760	35
DP7CPPLL6418	35
DP7CPPLL6424	35
DP7CPPLL6430	35
DP7CPPLL6436	35
DP7CPPLL6442	35
DP7CPPLL6448	35
DP7CPPLL6460	35
DP7CPPLL7818	36
DP7CPPLL7824	36
DP7CPPLL7830	36
DP7CPPLL7836	36
DP7CPPLL7842	36
DP7CPPLL7848	36
DP7CPPRR4215	31
DP7CPPRR4218	31
DP7CPPRR4224	31
DP7CPPRR4230	31
DP7CPPRR4236	31
DP7CPPRR4242	31
DP7CPPRR4248	31
DP7CPPRR4260	31
DP7CPPRR5015	31
DP7CPPRR5018	31
DP7CPPRR5024	31
DP7CPPRR5030	31
DP7CPPRR5036	31
DP7CPPRR5042	31
DP7CPPRR5048	31
DP7CPPRR5060	31
DP7CPPRR5715	32
DP7CPPRR5718	32
DP7CPPRR5724	32
DP7CPPRR5730	32
DP7CPPRR5736	32
DP7CPPRR5742	32
DP7CPPRR5748	32
DP7CPPRR5760	32
DP7CPPRR6415	32
DP7CPPRR6418	32
DP7CPPRR6424	32
DP7CPPRR6430	32
DP7CPPRR6436	32
DP7CPPRR6442	32
DP7CPPRR6448	32
DP7CPPRR6460	32
DP7CPPRR7815	33
DP7CPPRR7818	33
DP7CPPRR7824	33
DP7CPPRR7830	33
DP7CPPRR7836	33
DP7CPPRR7842	33
DP7CPPRR7848	33
DP7CTTFR3615	28
DP7CTTFR3618	28
DP7CTTFR3624	28
DP7CTTFR3630	28
DP7CTTFR3636	28
DP7CTTFR3642	28
DP7CTTFR3648	28
DP7CTTFR3660	28
DP7CTTFR4215	28
DP7CTTFR4218	28
DP7CTTFR4224	28
DP7CTTFR4230	28
DP7CTTFR4236	28
DP7CTTFR4242	28
DP7CTTFR4248	28
DP7CTTFR4260	28
DP7CTTFR5015	29
DP7CTTFR5018	29
DP7CTTFR5024	29
DP7CTTFR5030	29
DP7CTTFR5036	29
DP7CTTFR5042	29
DP7CTTFR5048	29
DP7CTTFR5060	29
DP7CTTFR5715	29
DP7CTTFR5718	29
DP7CTTFR5724	29
DP7CTTFR5730	29
DP7CTTFR5736	29
DP7CTTFR5742	29
DP7CTTFR5748	29
DP7CTTFR5760	29
DP7CTTFR6415	30
DP7CTTFR6418	30
DP7CTTFR6424	30
DP7CTTFR6430	30
DP7CTTFR6436	30
DP7CTTFR6442	30
DP7CTTFR6448	30
DP7CTTFR6460	30
DP7CTTFR7815	30
DP7CTTFR7818	30
DP7CTTFR7824	30
DP7CTTFR7830	30
DP7CTTFR7836	30
DP7CTTFR7842	30
DP7CTTFR7848	30
DP7CTTLL3618	26
DP7CTTLL3624	26
DP7CTTLL3630	26
DP7CTTLL3636	26
DP7CTTLL3642	26
DP7CTTLL3648	26
DP7CTTLL3660	26
DP7CTTLL4218	26
DP7CTTLL4224	26
DP7CTTLL4230	26
DP7CTTLL4236	26
DP7CTTLL4242	26
DP7CTTLL4248	26
DP7CTTLL4260	26
DP7CTTLL5018	26
DP7CTTLL5024	26
DP7CTTLL5030	26
DP7CTTLL5036	26
DP7CTTLL5042	26
DP7CTTLL5048	26
DP7CTTLL5060	26
DP7CTTLL5718	27
DP7CTTLL5724	27
DP7CTTLL5730	27
DP7CTTLL5736	27
DP7CTTLL5742	27
DP7CTTLL5748	27
DP7CTTLL5760	27
DP7CTTLL6418	27
DP7CTTLL6424	27
DP7CTTLL6430	27
DP7CTTLL6436	27
DP7CTTLL6442	27
DP7CTTLL6448	27
DP7CTTLL6460	27
DP7CTTLL7818	27
DP7CTTLL7824	27
DP7CTTLL7830	27
DP7CTTLL7836	27
DP7CTTLL7842	27
DP7CTTLL7848	27
DP7CTTRR3615	24
DP7CTTRR3618	24
DP7CTTRR3624	24
DP7CTTRR3630	24
DP7CTTRR3636	24
DP7CTTRR3642	24
DP7CTTRR3648	24
DP7CTTRR3660	24
DP7CTTRR4215	24
DP7CTTRR4218	24
DP7CTTRR4224	24
DP7CTTRR4230	24
DP7CTTRR4236	24
DP7CTTRR4242	24
DP7CTTRR4248	24
DP7CTTRR4260	24
DP7CTTRR5015	24
DP7CTTRR5018	24
DP7CTTRR5024	24
DP7CTTRR5030	24
DP7CTTRR5036	24
DP7CTTRR5042	24
DP7CTTRR5048	24
DP7CTTRR5060	24
DP7CTTRR5715	25
DP7CTTRR5718	25
DP7CTTRR5724	25
DP7CTTRR5730	25
DP7CTTRR5736	25
DP7CTTRR5742	25
DP7CTTRR5748	25
DP7CTTRR5760	25
DP7CTTRR6415	25
DP7CTTRR6418	25
DP7CTTRR6424	25
DP7CTTRR6430	25
DP7CTTRR6436	25
DP7CTTRR6442	25
DP7CTTRR6448	25
DP7CTTRR6460	25
DP7CTTRR7815	25
DP7CTTRR7818	25
DP7CTTRR7824	25
DP7CTTRR7830	25
DP7CTTRR7836	25
DP7CTTRR7842	25
DP7CTTRR7848	25
DP7HIRKD24	204
DP7HIRKD30	204
DP7HIRKD36	204
DP7HIRKD42	204
DP7HIRKD48	204
DP7HIRKD60	204
DP7HIRKS24	204
DP7HIRKS30	204
DP7HIRKS36	204
DP7HIRKS42	204
DP7HIRKS48	204
DP7HIRKS60	204
DP7HLCWH	124
DP7HRRKD24	204
DP7HRRKD30	204
DP7HRRKD36	204
DP7HRRKD42	204
DP7HRRKD48	204

pattern no.	*page*
DP7HRRKD60	204
DP7HRRKS24	204
DP7HRRKS30	204
DP7HRRKS36	204
DP7HRRKS42	204
DP7HRRKS48	204
DP7HRRKS60	204
DP7PA362	121
DP7PA363	121
DP7PA364	121
DP7PA422	121
DP7PA423	121
DP7PA424	121
DP7PA502	121
DP7PA503	121
DP7PA504	121
DP7PA572	121
DP7PA573	121
DP7PA574	121
DP7PA642	121
DP7PA643	121
DP7PA644	121
DP7PA782	121
DP7PA783	121
DP7PA784	121
DP7PAWH2	121
DP7PAWH3	121
DP7PAWH4	121
DP7PC07	125
DP7PC07UH	126
DP7PC14	125, 126
DP7PC14UH	126
DP7PC21	125
DP7PC21UH	126
DP7PC28	125
DP7PC28UH	126
DP7PC36	125
DP7PC362	125
DP7PC36U	126
DP7PC36UH	126
DP7PC42	125
DP7PC422	125
DP7PC42U	126
DP7PC50	125
DP7PC502	125
DP7PC50U	126
DP7PC57	125
DP7PC572	125
DP7PC57U	126
DP7PC64	125
DP7PC642	125
DP7PC64U	126
DP7PC78	125
DP7PC782	125
DP7PC78U	126
DP7PCWH	125
DP7PCWH2	125
DP7PCWH42	125
DP7PCWH50	125
DP7PCWH57	125
DP7PCWH64	125
DP7PCWH78	125
DP7PCWHS14	125
DP7PCWHS142	125
DP7PCWHS21	125
DP7PCWHS212	125
DP7PCWHS28	125
DP7PCWHS282	125
DP7PCWHU	126
DP7PO36	124
DP7PO36CPF	152
DP7PO42	124
DP7PO42CPF	152
DP7PO50	124
DP7PO50CPF	152
DP7PO57	124
DP7PO57CPF	152
DP7PO64	124
DP7PO64CPF	152
DP7PO78	124
DP7POWH	124
DP7POWHCPF	152
DP7PP36S	200
DP7PP36T	200
DP7PP42S	200
DP7PP42T	200
DP7PP50S	200
DP7PP50T	200
DP7PP57S	200
DP7PP57T	200
DP7PP64S	200
DP7PP64T	200
DP7PP78S	200
DP7PP78T	200
DP7PT1	124
DP7PT2	124
DP7PT3	124
DP7PT4	124
DP7PTCP	152
DP7PTCPH	152
DP7PTS	124
DP7RCCH24	204
DP7RCCH30	204
DP7RCCH36	204
DP7RCCH42	204
DP7RCCH48	204
DP7RCCH60	204
DP7S	106, 107, 108, 109
DP7SPO14	124
DP7SPO21	124
DP7SPO28	124
DP7SS	112, 113, 114, 115
DP7SSWT1424	111
DP7SSWT1430	111
DP7SSWT1436	111
DP7SSWT1442	111
DP7SSWT1448	111
DP7SSWT2124	111
DP7SSWT2130	111
DP7SSWT2136	111
DP7SSWT2142	111
DP7SSWT2148	111
DP7SSWT2824	111
DP7SSWT2830	111
DP7SSWT2836	111
DP7SSWT2842	111
DP7SSWT2848	111
DP7SWT	104, 105
DP7SWTFK24	105
DP7SWTFK30	105
DP7SWTFK36	105
DP7SWTFK42	105
DP7SWTFK48	105
DP7SWTFKD	105
DPRD15736(L/R)L	101
DPRD15736(L/R)N	101
DPRD15742(L/R)L	101
DPRD15742(L/R)N	101
DPRD16436(L/R)L	101
DPRD16436(L/R)N	101
DPRD16442(L/R)L	101
DPRD16442(L/R)N	101
DPRD17836(L/R)L	101
DPRD17836(L/R)N	101
DPRD17842(L/R)L	101
DPRD17842(L/R)N	101
DPRD1JPM	101
DPS7V1418	54
DPS7V1424	54
DPS7V1430	54
DPS7V1436	54
DPS7V1442	54
DPS7V1448	54
DPS7V2118	54
DPS7V2124	54
DPS7V2130	54
DPS7V2136	54
DPS7V2142	54
DPS7V2148	54
DPS7V2818	54
DPS7V2824	54
DPS7V2830	54
DPS7V2836	54
DPS7V2842	54
DPS7V2848	54
DS1 OHL	232
DS1 VD	232, 267
DS1BS 24	231
DS1BS 30	231
DS1BS 36	231
DS1BS 42	231
DS1BS 48	231
DS1BS 54	231
DS1BS 60	231
DS1BS 66	231
DS1BS 72	231
DS1CS 36	229
DS1CS 42	229
DS1CS 48	229
DS1DW 30L	237
DS1DWDPL	243
DS1E30L	227
DS1E36L	227
DS1E42L	227
DS1E48L	227
DS1E54L	227
DS1E60L	227
DS1E66L	227
DS1E72L	227
DS1EAKIT	211
DS1LKKT	243
DS1O24L	211
DS1O30L	211
DS1O36L	211
DS1O42L	211
DS1O48L	211
DS1O54L	211
DS1O60L	211
DS1O66L	211
DS1O72L	211
DS1PBD	243, 371
DS1PCD	243, 371
DS1PF L18A	237
DS1PF L18B	237
DS1PF L24A	237
DS1PF L24B	237
DS1PF L30A	237
DS1PF L30B	237
DS1PFD	243, 371
DS1PFS	243, 371
DS1PM L18A	237
DS1PM L18B	237
DS1PM L18F	237
DS1PM L24A	237
DS1PM L24B	237
DS1PM L24F	237
DS1PST	243, 371
DS1S 24	229
DS1S 30	229
DS1S 36	229
DS1S 42	229
DS1S 48	229
DS1S 54	229
DS1S 60	229
DS1S 66	229
DS1S 72	229
DS1SWM 30	231
DS1SWM 36	231
DS1SWM 42	231
DS1SWM 48	231
DS1WM 24	231
DS1WM 30	231
DS1WM 36	231
DS1WM 42	231
DS1WM 48	231
DS2DW 30L	240
DS2DW 36L	240
DS2DWDPL30	243
DS2DWDPL36	243
DS2LKKT	243
DS2OD 36L	267
DS2OD 42L	267
DS2OD 48L	267
DS2OD 54L	267
DS2OD 60L	267
DS2OD 66L	267
DS2OD 72L	267
DS2PF L18A	239
DS2PF L18B	239
DS2PF L24A	239
DS2PF L24B	239
DS2PF L30A	239
DS2PF L30B	239
DS2PM L18A	239
DS2PM L18B	239
DS2PM L18F	239
DS2PM L24A	239
DS2PM L24B	239
DS2PM L24F	239
DS2PM24L	211

pattern no.	*page*
DS2PM30L	211
DS2PM36L	211
DS2PM42L	211
DS2PM48L	211
DS2PM54L	211
DS2PM60L	211
DS2PM66L	211
DS2PM72L	211
DS2PPTC	243, 371
DS2PPTN	243, 371
DS2UM30L	227
DS2UM36L	227
DS2UM42L	227
DS2UM48L	227
DS2UM54L	227
DS2UM60L	227
DS2UM66L	227
DS2UM72L	227
DS2XPB	239
DS3CMN3614	223
DS3CMN4214	223
DS3CMN4814	223
DS3CMN6014	223
DS3CMN7214	223
DS3CMSL3614L	224
DS3CMSL4214L	224
DS3CMSL4814L	224
DS3CMSL6014L	224
DS3CMSL7214L	224
DS3CMSS3614L	224
DS3CMSS4214L	223
DS3CMSS4814L	223
DS3CMSS6014L	223
DS3CMSS7214L	223
DS3CMSV3614L	225
DS3CMSV4214L	225
DS3CMSV4814L	225
DS3CMSV6014L	225
DS3CMSV7214L	225
DS3CMTS3614L	223
DS3CMTS4214L	223
DS3CMTS4814L	223
DS3CMTS6014L	223
DS3CMTS7214L	223
DS3ODNS	272, 276, 281, 286
DS3ODNS1573014	271
DS3ODNS1573014T	279
DS3ODNS1573614	271
DS3ODNS1573614T	279
DS3ODNS1574214	271
DS3ODNS1574214T	279
DS3ODNS1574814	271
DS3ODNS1574814T	279
DS3ODNS1576014	271
DS3ODNS1576014T	279
DS3ODNS1576614	271
DS3ODNS1576614T	279
DS3ODNS1577214	271
DS3ODNS1577214T	279
DS3ODNS1643014	274
DS3ODNS1643014T	284
DS3ODNS1643614	274
DS3ODNS1643614T	284
DS3ODNS1644214	274
DS3ODNS1644214T	284
DS3ODNS1644814	274
DS3ODNS1644814T	284
DS3ODNS1646014	274
DS3ODNS1646014T	284
DS3ODNS1646614	274
DS3ODNS1646614T	284
DS3ODNS1647214	274
DS3ODNS1647214T	284
DS3ODSL	273, 278, 283, 288
DS3ODSL1573014L	271
DS3ODSL1573014LT	279
DS3ODSL1573614L	271
DS3ODSL1573614LT	279
DS3ODSL1574214L	271
DS3ODSL1574214LT	279
DS3ODSL1574814L	271
DS3ODSL1574814LT	279
DS3ODSL1576014L	271
DS3ODSL1576014LT	279
DS3ODSL1576614L	271
DS3ODSL1576614LT	279
DS3ODSL1577214L	271
DS3ODSL1577214LT	279
DS3ODSL1643014L	274
DS3ODSL1643014LT	284
DS3ODSL1643614L	274
DS3ODSL1643614LT	284
DS3ODSL1644214L	274
DS3ODSL1644214LT	284
DS3ODSL1644814L	274
DS3ODSL1644814LT	284
DS3ODSL1646014L	274
DS3ODSL1646014LT	284
DS3ODSL1646614L	274
DS3ODSL1646614LT	284
DS3ODSL1647214L	274
DS3ODSL1647214LT	284
DS3ODSL2573021FL	272
DS3ODSL2573021FLT	281
DS3ODSL2573621FL	272
DS3ODSL2573621FLT	281
DS3ODSL2574221FL	272
DS3ODSL2574221FLT	281
DS3ODSL2574821FL	272
DS3ODSL2574821FLT	281
DS3ODSL2576021FL	272
DS3ODSL2576021FLT	281
DS3ODSL2576621FL	272
DS3ODSL2576621FLT	281
DS3ODSL2577221FL	272
DS3ODSL2577221FLT	281
DS3ODSL2643021FL	276
DS3ODSL2643021FLT	286
DS3ODSL2643621FL	276
DS3ODSL2643621FLT	286
DS3ODSL2644221FL	276
DS3ODSL2644221FLT	286
DS3ODSL2644821FL	276
DS3ODSL2644821FLT	286
DS3ODSL2646021FL	276
DS3ODSL2646021FLT	286
DS3ODSL2646621FL	276
DS3ODSL2646621FLT	286
DS3ODSL2647221FL	276
DS3ODSL2647221FLT	286
DS3ODSS	273, 278, 283, 288
DS3ODSS1573014L	271
DS3ODSS1573014LT	279
DS3ODSS1573614L	271
DS3ODSS1573614LT	279
DS3ODSS1574214L	271
DS3ODSS1574214LT	279
DS3ODSS1574814L	271
DS3ODSS1574814LT	279
DS3ODSS1576014L	271
DS3ODSS1576014LT	279
DS3ODSS1576614L	271
DS3ODSS1576614LT	279
DS3ODSS1577214L	271
DS3ODSS1577214LT	279
DS3ODSS1643014L	274
DS3ODSS1643014LT	284
DS3ODSS1643614L	274
DS3ODSS1643614LT	284
DS3ODSS1644214L	274
DS3ODSS1644214LT	284
DS3ODSS1644814L	274
DS3ODSS1644814LT	284
DS3ODSS1646014L	274
DS3ODSS1646014LT	284
DS3ODSS1646614L	274
DS3ODSS1646614LT	284
DS3ODSS1647214L	274
DS3ODSS1647214LT	284
DS3ODSS2573021FL	272
DS3ODSS2573021FLT	281
DS3ODSS2573621FL	272
DS3ODSS2573621FLT	281
DS3ODSS2574221FL	272
DS3ODSS2574221FLT	281
DS3ODSS2574821FL	272
DS3ODSS2574821FLT	281
DS3ODSS2576021FL	272
DS3ODSS2576021FLT	281
DS3ODSS2576621FL	272
DS3ODSS2576621FLT	281
DS3ODSS2577221FL	272
DS3ODSS2577221FLT	281
DS3ODSS2643021FL	276
DS3ODSS2643021FLT	286
DS3ODSS2643621FL	276
DS3ODSS2643621FLT	286
DS3ODSS2644221FL	276
DS3ODSS2644221FLT	286
DS3ODSS2644821FL	276
DS3ODSS2644821FLT	286
DS3ODSS2646021FL	276
DS3ODSS2646021FLT	286
DS3ODSS2646621FL	276
DS3ODSS2646621FLT	286
DS3ODSS2647221FL	276
DS3ODSS2647221FLT	286
DS3ODSV	273, 278, 283, 288
DS3ODSV1573014L	271
DS3ODSV1573014LT	280
DS3ODSV1573614L	271
DS3ODSV1573614LT	280
DS3ODSV1574214L	271
DS3ODSV1574214LT	280
DS3ODSV1574814L	271
DS3ODSV1574814LT	280
DS3ODSV1576014L	271
DS3ODSV1576014LT	280
DS3ODSV1576614L	271
DS3ODSV1576614LT	280
DS3ODSV1577214L	271
DS3ODSV1577214LT	280
DS3ODSV1643014L	275
DS3ODSV1643014LT	285
DS3ODSV1643614L	275
DS3ODSV1643614LT	285
DS3ODSV1644214L	275
DS3ODSV1644214LT	285
DS3ODSV1644814L	275
DS3ODSV1644814LT	285
DS3ODSV1646014L	275
DS3ODSV1646014LT	285
DS3ODSV1646614L	275
DS3ODSV1646614LT	285
DS3ODSV1647214L	275
DS3ODSV1647214LT	285
DS3ODSV2573021FL	272
DS3ODSV2573021FLT	282
DS3ODSV2573621FL	272
DS3ODSV2573621FLT	282
DS3ODSV2574221FL	272
DS3ODSV2574221FLT	282
DS3ODSV2574821FL	272
DS3ODSV2574821FLT	282
DS3ODSV2576021FL	272
DS3ODSV2576021FLT	282
DS3ODSV2576621FL	272
DS3ODSV2576621FLT	282
DS3ODSV2577221FL	272
DS3ODSV2577221FLT	282
DS3ODSV2643021FL	277
DS3ODSV2643021FLT	287
DS3ODSV2643621FL	277
DS3ODSV2643621FLT	287
DS3ODSV2644221FL	277
DS3ODSV2644221FLT	287
DS3ODSV2644821FL	277
DS3ODSV2644821FLT	287
DS3ODSV2646021FL	277
DS3ODSV2646021FLT	287
DS3ODSV2646621FL	277
DS3ODSV2646621FLT	287
DS3ODSV2647221FL	277
DS3ODSV2647221FLT	287
DS3PML30L	212
DS3PML36L	212
DS3PML42L	212
DS3PML48L	212
DS3PML60L	212
DS3PML66L	212
DS3PML72L	212
DS3PMNS3014	215
DS3PMNS3021	217
DS3PMNS3614	215
DS3PMNS3621	217
DS3PMNS4214	215
DS3PMNS4221	217
DS3PMNS4814	215
DS3PMNS4821	217
DS3PMNS6014	215

pattern no.	*page*
DS3PMNS6021	217
DS3PMNS6614	215
DS3PMNS6621	217
DS3PMNS7214	215
DS3PMNS7221	217
DS3PMS30L	211
DS3PMS36L	211
DS3PMS42L	211
DS3PMS48L	211
DS3PMS60L	211
DS3PMS66L	211
DS3PMS72L	211
DS3PMSL3014L	215
DS3PMSL3021FL	217
DS3PMSL3021PL	218
DS3PMSL3614L	215
DS3PMSL3621FL	217
DS3PMSL3621PL	218
DS3PMSL4214L	215
DS3PMSL4221FL	217
DS3PMSL4221PL	218
DS3PMSL4814L	215
DS3PMSL4821FL	217
DS3PMSL4821PL	218
DS3PMSL6014L	215
DS3PMSL6021FL	217
DS3PMSL6021PL	218
DS3PMSL6614L	215
DS3PMSL6621FL	217
DS3PMSL6621PL	218
DS3PMSL7214L	215
DS3PMSL7221FL	217
DS3PMSL7221PL	218
DS3PMSS3014L	215
DS3PMSS3021FL	217
DS3PMSS3021PL	218
DS3PMSS3614L	215
DS3PMSS3621FL	217
DS3PMSS3621PL	218
DS3PMSS4214L	215
DS3PMSS4221FL	217
DS3PMSS4221PL	218
DS3PMSS4814L	215
DS3PMSS4821FL	217
DS3PMSS4821PL	218
DS3PMSS6014L	215
DS3PMSS6021FL	217
DS3PMSS6021PL	218
DS3PMSS6614L	215
DS3PMSS6621FL	217
DS3PMSS6621PL	218
DS3PMSS7214L	215
DS3PMSS7221FL	217
DS3PMSS7221PL	218
DS3PMSV3014L	216
DS3PMSV3021FL	217
DS3PMSV3021PL	218
DS3PMSV3614L	216
DS3PMSV3621FL	217
DS3PMSV3621PL	218
DS3PMSV4214L	216
DS3PMSV4221FL	217
DS3PMSV4221PL	218
DS3PMSV4814L	216
DS3PMSV4821FL	217
DS3PMSV4821PL	218
DS3PMSV6014L	216
DS3PMSV6021FL	217
DS3PMSV6021PL	218
DS3PMSV6614L	216
DS3PMSV6621FL	217
DS3PMSV6621PL	218
DS3PMSV7214L	216
DS3PMSV7221FL	217
DS3PMSV7221PL	218
DS3PMT7S214L	215
DS3PMTS3614L	215
DS3PMTS4214L	215
DS3PMTS4814L	215
DS3PMTS6014L	215
DS3PMV30L	212
DS3PMV36L	212
DS3PMV42L	212
DS3PMV48L	212
DS3PMV60L	212
DS3PMV66L	212
DS3PMV72L	212
DS3SMN3614	221
DS3SMN4214	221
DS3SMN4814	221
DS3SMN6014	221
DS3SMN7214	221
DS3SMSL3614L	221
DS3SMSL4214L	221
DS3SMSL4814L	221
DS3SMSL6014L	221
DS3SMSL7214L	221
DS3SMSS3614L	221
DS3SMSS4214L	221
DS3SMSS4814L	221
DS3SMSS6014L	221
DS3SMSS7214L	221
DS3SMSV3614L	222
DS3SMSV4214L	222
DS3SMSV4814L	222
DS3SMSV6014L	222
DS3SMSV7214L	222
DS3SMT3614L	221
DS3SMT4214L	221
DS3SMT4814L	221
DS3SMT6014L	221
DS3SMT7214L	221
DS3WMN3614	219
DS3WMN4214	219
DS3WMN4814	219
DS3WMN6014	219
DS3WMN7214	219
DS3WMSL3614L	219
DS3WMSL4214L	219
DS3WMSL4814L	219
DS3WMSL6014L	219
DS3WMSL7214L	219
DS3WMSS3614L	219
DS3WMSS4214L	219
DS3WMSS4814L	219
DS3WMSS6014L	219
DS3WMSS7214L	219
DS3WMSV3614L	219
DS3WMSV4214L	219
DS3WMSV4814L	219
DS3WMSV6014L	219
DS3WMSV7214L	219
DS3WMTS3614L	220
DS3WMTS4214L	220
DS3WMTS4814L	220
DS3WMTS6014L	220
DS3WMTS7214L	220
DS4LC1ANL24N	248
DS4LC1ANL30N	248
DS4LC1ANL36N	248
DS4LC1ANL42N	248
DS4LC1ANL48N	248
DS4LC1ANL54N	248
DS4LC1ANL60N	248
DS4LC1ANL66N	248
DS4LC1ANL72N	248
DS4LC1ANS42N	245
DS4LC1ANS48N	245
DS4LC1ANS54N	245
DS4LC1ANS60N	245
DS4LC1ANS66N	245
DS4LC1ANS72N	245
DS4LC1ANV24N	252
DS4LC1ANV30N	252
DS4LC1ANV36N	252
DS4LC1ANV42N	252
DS4LC1ANV48N	252
DS4LC1ANV54N	252
DS4LC1ANV60N	252
DS4LC1ANV66N	252
DS4LC1ANV72N	252
DS4LC1BLL30L	248
DS4LC1BLL36L	248
DS4LC1BLL42L	248
DS4LC1BLL48L	248
DS4LC1BLL54L	248
DS4LC1BLL60L	248
DS4LC1BLL66L	248
DS4LC1BLL72L	248
DS4LC1BLS42L	245
DS4LC1BLS48L	245
DS4LC1BLS54L	245
DS4LC1BLS60L	245
DS4LC1BLS66L	245
DS4LC1BLS72L	245
DS4LC1BLV30L	252
DS4LC1BLV36L	252
DS4LC1BLV42L	252
DS4LC1BLV48L	252
DS4LC1BLV54L	252
DS4LC1BLV60L	252
DS4LC1BLV66L	252
DS4LC1BLV72L	252
DS4LC1BSL30L	248
DS4LC1BSL36L	248
DS4LC1BSL42L	248
DS4LC1BSL48L	248
DS4LC1BSL54L	248
DS4LC1BSL60L	248
DS4LC1BSL66L	248
DS4LC1BSL72L	248
DS4LC1BSS42L	245
DS4LC1BSS48L	245
DS4LC1BSS54L	245
DS4LC1BSS60L	245
DS4LC1BSS66L	245
DS4LC1BSS72L	245
DS4LC1BSV30L	252
DS4LC1BSV36L	252
DS4LC1BSV42L	252
DS4LC1BSV48L	252
DS4LC1BSV54L	252
DS4LC1BSV60L	252
DS4LC1BSV66L	252
DS4LC1BSV72L	252
DS4LC1BVL30L	249
DS4LC1BVL36L	249
DS4LC1BVL42L	249
DS4LC1BVL48L	249
DS4LC1BVL54L	249
DS4LC1BVL60L	249
DS4LC1BVL66L	249
DS4LC1BVL72L	249
DS4LC1BVS42L	245
DS4LC1BVS48L	245
DS4LC1BVS54L	245
DS4LC1BVS60L	245
DS4LC1BVS66L	245
DS4LC1BVS72L	245
DS4LC1BVV30L	253
DS4LC1BVV36L	253
DS4LC1BVV42L	253
DS4LC1BVV48L	253
DS4LC1BVV54L	253
DS4LC1BVV60L	253
DS4LC1BVV66L	253
DS4LC1BVV72L	253
DS4LC1CLL30L	250
DS4LC1CLL36L	250
DS4LC1CLL42L	250
DS4LC1CLL48L	250
DS4LC1CLL54L	250
DS4LC1CLL60L	250
DS4LC1CLL66L	250
DS4LC1CLL72L	250
DS4LC1CLS42L	246
DS4LC1CLS48L	246
DS4LC1CLS54L	246
DS4LC1CLS60L	246
DS4LC1CLS66L	246
DS4LC1CLS72L	246
DS4LC1CLV30L	254
DS4LC1CLV36L	254
DS4LC1CLV42L	254
DS4LC1CLV48L	254
DS4LC1CLV54L	254
DS4LC1CLV60L	254
DS4LC1CLV66L	254
DS4LC1CLV72L	254
DS4LC1CSL30L	250
DS4LC1CSL36L	250
DS4LC1CSL42L	250
DS4LC1CSL48L	250
DS4LC1CSL54L	250
DS4LC1CSL60L	250
DS4LC1CSL66L	250
DS4LC1CSL72L	250
DS4LC1CSS42L	246
DS4LC1CSS48L	246
DS4LC1CSS54L	246

pattern no.	*page*
DS4LC1CSS60L	246
DS4LC1CSS66L	246
DS4LC1CSS72L	246
DS4LC1CSV30L	254
DS4LC1CSV36L	254
DS4LC1CSV42L	254
DS4LC1CSV48L	254
DS4LC1CSV54L	254
DS4LC1CSV60L	254
DS4LC1CSV66L	254
DS4LC1CSV72L	254
DS4LC1CVL30L	250
DS4LC1CVL36L	250
DS4LC1CVL42L	250
DS4LC1CVL48L	250
DS4LC1CVL54L	250
DS4LC1CVL60L	250
DS4LC1CVL66L	250
DS4LC1CVL72L	250
DS4LC1CVS42L	246
DS4LC1CVS48L	246
DS4LC1CVS54L	246
DS4LC1CVS60L	246
DS4LC1CVS66L	246
DS4LC1CVS72L	246
DS4LC1CVV30L	254
DS4LC1CVV36L	254
DS4LC1CVV42L	254
DS4LC1CVV48L	254
DS4LC1CVV54L	254
DS4LC1CVV60L	254
DS4LC1CVV66L	254
DS4LC1CVV72L	254
DS4LC1DLL30L	251
DS4LC1DLL36L	251
DS4LC1DLL42L	251
DS4LC1DLL48L	251
DS4LC1DLL54L	251
DS4LC1DLL60L	251
DS4LC1DLL66L	251
DS4LC1DLL72L	251
DS4LC1DLS42L	247
DS4LC1DLS48L	247
DS4LC1DLS54L	247
DS4LC1DLS60L	247
DS4LC1DLS66L	247
DS4LC1DLS72L	247
DS4LC1DLV30L	255
DS4LC1DLV36L	255
DS4LC1DLV42L	255
DS4LC1DLV48L	255
DS4LC1DLV54L	255
DS4LC1DLV60L	255
DS4LC1DLV66L	255
DS4LC1DLV72L	255
DS4LC1DSL30L	251
DS4LC1DSL36L	251
DS4LC1DSL42L	251
DS4LC1DSL48L	251
DS4LC1DSL54L	251
DS4LC1DSL60L	251
DS4LC1DSL66L	251
DS4LC1DSL72L	251
DS4LC1DSS42L	247
DS4LC1DSS48L	247
DS4LC1DSS54L	247
DS4LC1DSS60L	247
DS4LC1DSS66L	247
DS4LC1DSS72L	247
DS4LC1DSV30L	255
DS4LC1DSV36L	255
DS4LC1DSV42L	255
DS4LC1DSV48L	255
DS4LC1DSV54L	255
DS4LC1DSV60L	255
DS4LC1DSV66L	255
DS4LC1DSV72L	255
DS4LC1DVL30L	251
DS4LC1DVL36L	251
DS4LC1DVL42L	251
DS4LC1DVL48L	251
DS4LC1DVL54L	251
DS4LC1DVL60L	251
DS4LC1DVL66L	251
DS4LC1DVL72L	251
DS4LC1DVS42L	247
DS4LC1DVS48L	247
DS4LC1DVS54L	247
DS4LC1DVS60L	247
DS4LC1DVS66L	247
DS4LC1DVS72L	247
DS4LC1DVV30L	255
DS4LC1DVV36L	255
DS4LC1DVV42L	255
DS4LC1DVV48L	255
DS4LC1DVV54L	255
DS4LC1DVV60L	255
DS4LC1DVV66L	255
DS4LC1DVV72L	255
DS4LC2ANL24N	257
DS4LC2ANL30N	257
DS4LC2ANL36N	257
DS4LC2ANL42N	257
DS4LC2ANL48N	257
DS4LC2ANL54N	257
DS4LC2ANL60N	257
DS4LC2ANL66N	257
DS4LC2ANL72N	257
DS4LC2ANV24N	261
DS4LC2ANV30N	261
DS4LC2ANV36N	261
DS4LC2ANV42N	261
DS4LC2ANV48N	261
DS4LC2ANV54N	261
DS4LC2ANV60N	261
DS4LC2ANV66N	261
DS4LC2ANV72N	261
DS4LC2BLL30L	257
DS4LC2BLL36L	257
DS4LC2BLL42L	257
DS4LC2BLL48L	257
DS4LC2BLL54L	257
DS4LC2BLL60L	257
DS4LC2BLL66L	257
DS4LC2BLL72L	257
DS4LC2BLV30L	261
DS4LC2BLV36L	261
DS4LC2BLV42L	261
DS4LC2BLV48L	261
DS4LC2BLV54L	261
DS4LC2BLV60L	261
DS4LC2BLV66L	261
DS4LC2BLV72L	261
DS4LC2BSL30L	257
DS4LC2BSL36L	257
DS4LC2BSL42L	257
DS4LC2BSL48L	257
DS4LC2BSL54L	257
DS4LC2BSL60L	257
DS4LC2BSL66L	257
DS4LC2BSL72L	257
DS4LC2BSV30L	261
DS4LC2BSV36L	261
DS4LC2BSV42L	261
DS4LC2BSV48L	261
DS4LC2BSV54L	261
DS4LC2BSV60L	261
DS4LC2BSV66L	261
DS4LC2BSV72L	261
DS4LC2BVL30L	258
DS4LC2BVL36L	258
DS4LC2BVL42L	258
DS4LC2BVL48L	258
DS4LC2BVL54L	258
DS4LC2BVL60L	258
DS4LC2BVL66L	258
DS4LC2BVL72L	258
DS4LC2BVV30L	262
DS4LC2BVV36L	262
DS4LC2BVV42L	262
DS4LC2BVV48L	262
DS4LC2BVV54L	262
DS4LC2BVV60L	262
DS4LC2BVV66L	262
DS4LC2BVV72L	262
DS4LC2CLL30L	259
DS4LC2CLL36L	259
DS4LC2CLL42L	259
DS4LC2CLL48L	259
DS4LC2CLL54L	259
DS4LC2CLL60L	259
DS4LC2CLL66L	259
DS4LC2CLL72L	259
DS4LC2CLV30L	263
DS4LC2CLV36L	263
DS4LC2CLV42L	263
DS4LC2CLV48L	263
DS4LC2CLV54L	263
DS4LC2CLV60L	263
DS4LC2CLV66L	263
DS4LC2CLV72L	263
DS4LC2CSL30L	259
DS4LC2CSL36L	259
DS4LC2CSL42L	259
DS4LC2CSL48L	259
DS4LC2CSL54L	259
DS4LC2CSL60L	259
DS4LC2CSL66L	259
DS4LC2CSL72L	259
DS4LC2CSV30L	263
DS4LC2CSV36L	263
DS4LC2CSV42L	263
DS4LC2CSV48L	263
DS4LC2CSV54L	263
DS4LC2CSV60L	263
DS4LC2CSV66L	263
DS4LC2CSV72L	263
DS4LC2CVL30L	259
DS4LC2CVL36L	259
DS4LC2CVL42L	259
DS4LC2CVL48L	259
DS4LC2CVL54L	259
DS4LC2CVL60L	259
DS4LC2CVL66L	259
DS4LC2CVL72L	259
DS4LC2CVV30L	263
DS4LC2CVV36L	263
DS4LC2CVV42L	263
DS4LC2CVV48L	263
DS4LC2CVV54L	263
DS4LC2CVV60L	263
DS4LC2CVV66L	263
DS4LC2CVV72L	263
DS4LC2DLL30L	260
DS4LC2DLL36L	260
DS4LC2DLL42L	260
DS4LC2DLL48L	260
DS4LC2DLL54L	260
DS4LC2DLL60L	260
DS4LC2DLL66L	260
DS4LC2DLL72L	260
DS4LC2DLV30L	264
DS4LC2DLV36L	264
DS4LC2DLV42L	264
DS4LC2DLV48L	264
DS4LC2DLV54L	264
DS4LC2DLV60L	264
DS4LC2DLV66L	264
DS4LC2DLV72L	264
DS4LC2DSL30L	260
DS4LC2DSL36L	260
DS4LC2DSL42L	260
DS4LC2DSL48L	260
DS4LC2DSL54L	260
DS4LC2DSL60L	260
DS4LC2DSL66L	260
DS4LC2DSL72L	260
DS4LC2DSV30L	264
DS4LC2DSV36L	264
DS4LC2DSV42L	264
DS4LC2DSV48L	264
DS4LC2DSV54L	264
DS4LC2DSV60L	264
DS4LC2DSV66L	264
DS4LC2DSV72L	264
DS4LC2DVL30L	260
DS4LC2DVL36L	260
DS4LC2DVL42L	260
DS4LC2DVL48L	260
DS4LC2DVL54L	260
DS4LC2DVL60L	260
DS4LC2DVL66L	260
DS4LC2DVL72L	260
DS4LC2DVV30L	264
DS4LC2DVV36L	264
DS4LC2DVV42L	264
DS4LC2DVV48L	264
DS4LC2DVV54L	264
DS4LC2DVV60L	264
DS4LC2DVV66L	264

pattern no.	*page*
DS4LC2DVV72L	264
DSCSWDB24	231
DSCSWDB30	231
DSCSWDB36	231
DSCSWDB42	231
DSCSWDB48	231
DT1ABY10242N	351
DT1ABY10248N	351
DT1ABY10842N	351
DT1ABY10848N	351
DT1ABY12042N	351
DT1ABY12048N	351
DT1ABY13242N	351
DT1ABY13248N	351
DT1ABY14442N	351
DT1ABY14448N	351
DT1ACX30	342
DT1ACX3017	342
DT1ACX3021	342
DT1ACX3036	342
DT1ACX3042	342
DT1ACX36	342
DT1ACX3617	342
DT1ACX3621	342
DT1ACX3636	342
DT1ACX3642	342
DT1ACX42	342
DT1ACX4217	342
DT1ACX4221	342
DT1ACX4236	342
DT1ACX4242	342
DT1ACX48	342
DT1ACX4817	342
DT1ACX4821	342
DT1ACX4836	342
DT1ACX4842	342
DT1ADX3030	343
DT1ADX303017	343
DT1ADX303021	343
DT1ADX303036	343
DT1ADX303042	344
DT1ADX3636	343
DT1ADX363617	343
DT1ADX363621	343
DT1ADX363636	343
DT1ADX363642	344
DT1ADX4242	343
DT1ADX424217	343
DT1ADX424221	343
DT1ADX424236	343
DT1ADX424242	344
DT1ADX4848	343
DT1ADX484817	343
DT1ADX484821	343
DT1ADX484836	343
DT1ADX484842	344
DT1ARY10236N	349
DT1ARY10242N	349
DT1ARY10248N	349
DT1ARY10836N	349
DT1ARY10842N	349
DT1ARY10848N	349
DT1ARY12042N	349
DT1ARY12048N	349
DT1ARY13242N	349
DT1ARY13248N	349
DT1ARY14442N	349
DT1ARY14448N	349
DT1ARY6024NS	333
DT1ARY6030NS	333
DT1ARY6036N	334
DT1ARY6624NS	333
DT1ARY6630NS	333
DT1ARY6636N	334
DT1ARY7224NS	333
DT1ARY7230NS	333
DT1ARY7236N	334
DT1ARY7824NS	333
DT1ARY7830NS	333
DT1ARY7836N	334
DT1ARY8424NS	333
DT1ARY8430NS	333
DT1ARY8436N	334
DT1ARY8442N	334
DT1ARY9024NS	333
DT1ARY9030NS	333
DT1ARY9036N	334
DT1ARY9042N	334
DT1ARY9624NS	333
DT1ARY9630NS	333
DT1ARY9636N	334
DT1ARY9642N	334
DT1ASX3030	341
DT1ASX303017	341
DT1ASX303021	341
DT1ASX303036	341
DT1ASX303042	341
DT1ASX3636	341
DT1ASX363617	341
DT1ASX363621	341
DT1ASX363636	341
DT1ASX363642	341
DT1ASX4242	341
DT1ASX424217	341
DT1ASX424221	341
DT1ASX424236	341
DT1ASX424242	341
DT1ASX4848	341
DT1ASX484817	341
DT1ASX484821	341
DT1ASX484836	341
DT1ASX484842	341
DT1ATY10236N	350
DT1ATY10242N	350
DT1ATY10248N	350
DT1ATY10836N	350
DT1ATY10842N	350
DT1ATY10848N	350
DT1ATY12042N	350
DT1ATY12048N	350
DT1ATY13242N	350
DT1ATY13248N	350
DT1ATY14442N	350
DT1ATY14448N	350
DT1ATY6024NS	335
DT1ATY6030NS	335
DT1ATY6036N	336
DT1ATY6624NS	335
DT1ATY6630NS	335
DT1ATY6636N	336
DT1ATY7224NS	335
DT1ATY7230NS	335
DT1ATY7236N	336
DT1ATY7824NS	335
DT1ATY7830NS	335
DT1ATY7836N	336
DT1ATY8424NS	335
DT1ATY8430NS	335
DT1ATY8436N	336
DT1ATY8442N	336
DT1ATY9024NS	335
DT1ATY9030NS	335
DT1ATY9036N	336
DT1ATY9042N	336
DT1ATY9624NS	335
DT1ATY9630NS	335
DT1ATY9636N	336
DT1ATY9642N	336
DT1BTL	345
DT1BTS	345
DT1BXL	345
DT1BXL17	345
DT1BXL21	345
DT1BXL36	345
DT1BXL42	345
DT1BXS	345
DT1BXS17	345
DT1BXS21	345
DT1BXS36	345
DT1BXS42	345
DT1CK4	346
DT1CRY6024N	337
DT1CRY6030N	337
DT1CRY6036N	337
DT1CRY6624N	337
DT1CRY6630N	337
DT1CRY6636N	337
DT1CRY7224N	337
DT1CRY7230N	337
DT1CRY7236N	337
DT1CRY7824N	337
DT1CRY7830N	337
DT1CRY7836N	337
DT1CRY8424N	337
DT1CRY8430N	337
DT1CRY8436N	337
DT1CRY9024N	337
DT1CRY9030N	337
DT1CRY9036N	337
DT1CRY9624N	337
DT1CRY9630N	337
DT1CRY9636N	337
DT1CTY6024N	338
DT1CTY6030N	338
DT1CTY6036N	338
DT1CTY6624N	338
DT1CTY6630N	338
DT1CTY6636N	338
DT1CTY7224N	338
DT1CTY7230N	338
DT1CTY7236N	338
DT1CTY7824N	338
DT1CTY7830N	338
DT1CTY7836N	338
DT1CTY8424N	338
DT1CTY8430N	338
DT1CTY8436N	338
DT1CTY9024N	338
DT1CTY9030N	338
DT1CTY9036N	338
DT1CTY9624N	338
DT1CTY9630N	338
DT1CTY9636N	338
DT1S	345
RO1 DPB	232
RS1 DPB	232

Selling Policy

This Selling Policy supercedes all previous selling policies. Prices, discounts and product offerings are subject to change without notice.

Terms & Conditions of Sales

Sales by Knoll, Inc. or Knoll North America Corp. ("Seller") of Knoll Product Lines (hereinafter "Products") within the United States and Canada are made only on the terms which are contained in this Selling Policy. Seller hereby gives notice of its objection to any different or additional terms and conditions. This sale is expressly conditional upon Purchaser's assent to the terms and conditions set forth below. Additional terms and conditions may apply to KnollStudio and KnollTextiles orders. These terms and conditions may be modified or supplemented only by a written document signed by an authorized representative of Seller. These terms and conditions supercede any prior and/or contemporaneous agreements or correspondence between Purchaser and Seller. Written quotations expire thirty (30) days from the date of issuance and can be withdrawn by written notice anytime during that period. Where Purchaser and Seller have entered into the Knoll Electronic Terms and Conditions, all orders, acknowledgements, invoices and other business communications placed or transmitted in accordance with the Knoll Electronic Terms and Conditions shall be deemed to be in writing and signed and shall be valid for all purposes as if they were originated and maintained in documentary form.

Ordering Information

All orders must be in writing. The product pattern number(s) contained on Seller's order acknowledgement shall be the final expression of the order.

Order Confirmation

A purchase order is not binding on Seller until Purchaser has received Seller's order confirmation or acknowledgment.

Pricing Policies

List prices are subject to change without notice.

List prices shall be those prices in effect on the date of receipt of a complete purchase order unless shipment is requested more than ninety (90) days after order entry in which case prices in effect on the date of shipment apply. List prices include specified freight costs. Unless specified in writing by Seller, no other charges are included in Seller's list prices.

Taxes

All sales, use, excise and other taxes applicable to the sale of the Products shall be paid by Purchaser. If Purchaser claims an exemption from any tax, Purchaser shall submit to Seller the appropriate exemption certificates.

Terms of Payment

Payment for one hundred percent (100%) of the net order amount is due within thirty (30) days of the date of invoice, which is issued upon shipment. In case of any discrepancies, such as shortages, and Seller is notified in writing within ten (10) days of receipt of Product, only that portion may be deducted and the balance paid. For orders greater than $100,000 net, a fifty percent (50%) deposit is due at the time of order placement, with the remainder due within thirty (30) days of the date of invoice.

KnollStudio orders less than $2,000 require payment for one hundred percent (100%) of the net order amount (including any applicable sales tax and charges for inside delivery, special packaging, etc.), due at time of order placement. For KnollStudio orders greater than $2,000, a one-half (50%) deposit is due at time of order placement with the remainder (including any applicable sales tax and charges for inside delivery, special packaging, etc.) due prior to shipment.

If, in the judgment of Seller, Purchaser's financial condition does not justify the terms of the payment, Seller may require full or partial payment in advance.

Past due accounts shall be charged one and one-half percent (1.5%) per month, or the highest rate permitted by law, whichever is less, and will be added to the outstanding balance. In the event Purchaser defaults on payment, Purchaser shall be liable for all collection costs, including reasonable attorney's fees and costs.

Changes and Cancellation

Purchase orders may not be changed or cancelled, in whole or in part, without prior written consent of Seller. Changes may effect delivery dates. Expenses incurred because of changes shall be charged to Purchaser. In the event of cancellations, Purchaser will be liable for reasonable cancellation charges established by Seller. Orders for special Product, orders including "COM" (hereinafter defined) material and orders pursuant to expedited delivery programs, may not be canceled.

Freight Prepaid

Freight is prepaid and included in the price of all Products, except KnollTextiles, within the 48 contiguous United States for orders placed with Knoll, Inc. and within Canada, excluding the Yukon, Northwest Territories, Nunavut and Newfoundland for orders placed with Knoll North America Corp. Packing is tested for rigorous motion and transportation but is not guaranteed to protect furniture from conditions over which the Seller has no control. If special packaging is required for any reason, please consult with your sales representative or dealer. Seller shall select the method of shipment and routing. All shipments shall be tailgate deliveries. Freight for all KnollTextiles orders is prepaid and added to the invoice.

Delivery/Freight Charges

Shipments outside the contiguous 48 United States and Canada shall be shipped F.O.B. Origin.

For shipments outside the contiguous United States and Canada, Purchaser is responsible for the cost of freight from point of embarkation, including any handling and transportation charges incidental to loading at the point of departure and unloading at the final destination.

Conditions beyond the control of Seller, including weather, available facilities and traffic conditions, may affect exact time of delivery. Seller shall not be responsible for specific carrier delivery date or time unless it has made a specific delivery commitment, in writing.

Nonstandard methods of shipment and/or additional services are available upon request. Purchaser will be billed for the differential cost of any special services in excess of standard surface carrier freight costs. Premium charges, at Purchaser's request, will be added for airfreight, exclusive use of vehicle and extra, export or special packaging. Accessorial charges will be added for inside delivery, extra labor, reconsignment and redelivery.

Partial shipments may be made and invoiced by Seller.

Claims

All shipments for all Knoll Products within the contiguous United States and Canada are F.O.B. Origin. Risk of loss passes to Purchaser at time of delivery to carrier. Purchaser shall inspect all Products upon receipt and notify Seller within ten (10) working days after receipt of any damage or defects which are, or should be, apparent from an inspection of the Product and its packaging. Failure of Purchaser to make a claim against carrier or notify Seller during the ten (10) working day period shall constitute acceptance of the Products and waiver of any apparent defects, errors or shortages. Seller will agree to repair or replace Product damaged in shipment if Purchaser has notified Seller of freight damage within ten (10) working days after receipt and assigns its rights against the carrier.

Seller's Security Interest

Until Seller receives the full payment for the Product, Seller shall have a security interest in the Product. Purchaser agrees to perform all acts, including but not limited to the execution and filing of documentation, which may be necessary to perfect and assure the security interest of Seller.

Returns

The return of Products without a written authorization by Seller shall not be accepted. To receive authorization for Product return, please call Customer Service. All Products that are returned pursuant to a valid authorization shall be subject to a twenty-five percent (25%) of list restocking charge. Products not currently offered for sale by Seller (including COM) shall not be authorized for return. All returned Products must be unused, in original condition and in the original Seller packing cartons. No refund or credit shall be given for damaged Products.

Held Orders/Storage

If Purchaser requests that an order be held or delayed, prices and terms and conditions in effect at the time of shipment shall apply. If Purchaser requests a delay after the time when Seller can defer production, Purchaser will be invoiced for the Product, payable in accordance with standard terms, when the order is ready for shipment. Seller may transfer the Product to storage, in which case all expenses incurred in connection with storage, including demurrage, preparation for storage, storage charges and handling shall be payable by Purchaser upon submission of invoices by Seller. Risk of loss to the Product shall pass to the Purchaser upon delivery of the Product into storage.

Customer's Own Material

A Purchaser who requests a fabric or other surface material not standard to Seller's line of Products ("COM") must submit samples of the requested material to Seller prior to entry of a purchaser order. Seller shall determine if the material is suitable to its manufacturing processes and meets any requirements of Underwriters Laboratories. If the COM is acceptable, Seller will then establish a price for using the COM or the Product in question. For a description of the procedures for submitting samples and testing, contact customer resources or your sales representative. Seller shall have no responsibility for the appearance, condition, performance, durability, colorfastness or any other physical attribute of the COM. Purchaser shall indemnify and hold Seller harmless for any damages, injuries or losses arising out of or related to use of the COM on the Product.

Warranty

Seller warrants to the original Purchaser only that the Products Seller manufactures and sells to Purchaser are free of defects in workmanship and materials, during the applicable warranty period set forth below.

Warranty period set forth below is for 24-hour, 7 days a week, multi shift use (includes parts and labor to repair).

Should any failure to conform with this limited warranty appear to a Product listed below during the applicable warranty period from the date of shipment, Seller shall, upon prompt written notice, repair or replace, at its option and costs, the affected part or parts.

Product and Period of Warranty

Lifetime: Antenna Workspaces, AutoStrada, Calibre, Crinion Open Table, Currents, Dividends Horizon, Equity, Morrison, Reff Profiles laminate, *Series 2 Storage, Template, Antenna Workspaces* and other non-wood components (except cascade edge worksurfaces, operational parts, controls, electrical, Lighting, *Series 2* Veneer Front Storage, special or custom products, see below)

12 Years: Chadwick, Essentials Work Chairs, Generation by Knoll, Life, Moment, MultiGeneration by Knoll, RPM and *Sapper* seating (except seating upholstery, textiles, leathers and finishes, see below).

10 Years: Antenna Workspaces, AutoStrada, Crinion Open Table, Reff Profiles wood components, *Series 2* Veneer Front Storage, cascade edge worksurfaces, *Wood Casegoods (Magnusson, The Graham Collection)* (except wood casegoods upholstered surfaces, see below), *Interaction* tables (except height adjustment mechanisms for *Counterforce,* crank-adjustable, and split-top tables and worksurfaces, see below), *Reuter* overheads, *Reuter* vertical storage, *KnollExtra* Sapper Monitor Arm Collection, Adjustable keyboard mechanisms and platforms, Communication Boards (except fabric board textiles, see below), Smokador collection (except leathers, see below), and Orchestra Universal Systems Accessories.

5 Years: Operational parts, controls, electrical, Lighting (except light ballasts, bulbs and power supply, see below), special or custom product, wood veneer products, *Currents* handcrank, *Interaction Counterforce, Interaction* crank-adjustable, and split-top mechanisms, *KnollStudio,* CPU storage and all universal storage drawers.

3 Years: Seating upholstery, textiles, leathers and finishes. Fabric boards textiles and Smokador Collection leathers.

2 Years: All other *KnollExtra* product

1 Year: Light ballasts, bulbs and power supply, seating upholstered armpads and soft armpads, wood casegoods upholstered surfaces.

This warranty does not apply to:

- Damage caused by a carrier other than the Seller.
- Normal wear and tear or acts or omissions of parties other than Seller (including user modification, improper use or installation of Products).
- COM or other third party materials applied to Products.
- Products not installed by or under the auspices of a Knoll Dealer.
- Dramatic temperature variations or exposure to unusual conditions.
- Changes in surface finishes, including colorfastness due to aging or exposure to light.
- Except as specifically noted above, textiles and upholstery supplied by *KnollTextiles* (consult current *KnollTextiles* price list for applicable warranty).

Natural variations occurring in wood, marble, and leather shall not be considered defects, and the Seller does not guarantee the colorfastness or matching of the colors, grains or textures, or surface hardness of such materials. The Seller also does not guarantee the colorfastness of fiberglass panel surfaces.

THE EXPRESS WARRANTIES CONTAINED HEREIN ARE IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY WARRANTIES OF MERCHANTABILITY AND FITNESS FOR PARTICULAR PURPOSE AND ALL OTHER WARRANTIES ARISING FROM COURSE OF DEALING OR USAGE OF TRADE.

The remedies provided above are the Purchaser's sole remedies for any failure of Seller to comply with its obligations regarding the workmanship of its Products. Correction of any nonconformity in the manner and for the period of time provided shall constitute complete fulfillment of all liabilities of Seller, with respect to or arising out of the Product furnished hereunder.

Delay/Force Majeure

Seller shall not be liable for failure to perform or for delay in performance due to fire, flood, strike or other labor difficulty, act of God, act of any governmental authority or of the Purchaser, riot, embargo, fuel or energy shortage, wrecks or delay in transportation, inability to obtain necessary labor, materials or manufacturing facilities from usual sources or failure of suppliers to meet their contractual obligations, or due to any cause beyond its reasonable control. If any such event occurs, Seller may extend delivery dates by a period of time necessary to overcome the effect of such delay, allocate available Product or cancel any purchase order.

Compliance with Law

PURCHASER IS SOLELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, ORDINANCES, REGULATIONS, RULES AND STANDARDS RELATING TO THE INSTALLATION, MAINTENANCE, USE AND OPERATION OF THE PRODUCTS.

Patents

Subject to the following provisions, Seller shall, at its own expense, defend or, at its option, settle any claim, suit or proceeding brought against the Purchaser, and/or its vendees, mediate and immediate, so far as based on an allegation that any Product or any part thereof furnished hereunder constitutes a direct or a contributory infringement of any claim of any patent of the United States or Canada. This obligation shall be effective only if Purchaser shall have made all payments then due hereunder and if Seller is notified promptly in writing and given authority, information and assistance for the defense of said claim, suit or proceeding. Seller shall pay all damages and costs awarded in such suit or proceedings so defended.

The foregoing indemnity does not apply to the following:

- Products supplied according to a design other than that of Seller, and which is required by the Purchaser.
- Combination of the Product with another product not furnished hereunder unless Seller is a contributory infringer.
- Any settlements of a suit or proceeding made without Seller's written consent.

Limitations of Liability

SELLER, ITS CONTRACTORS, AUTHORIZED DEALERS AND SUBCONTRACTORS OR SUPPLIERS OF ANY TIER SHALL NOT BE LIABLE TO PURCHASER FOR ANY SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES ARISING FROM A BREACH OF THIS AGREEMENT.

Purchaser's remedies set forth herein are exclusive and the liability of Seller with respect to the breach of this agreement or any contract entered into between the parties pursuant hereto shall not exceed the price of the Product or part on which such liability is based.

KnollKey Lock Program General Information

Following is the KnollKey lock policy, applicable to all products.

Knoll furniture can be ordered keyed-alike or random keyed. Key-alike and random keying instructions cannot be mixed on any single order. Only one of the two instructions can be used on an individual order. When an order is submitted with mixed (key-alike and random) instructions, Knoll will release the order as key-alike only and lock cores will have to be specified separately.

Key-alike

For the convenience of the user, furniture may be keyed alike at no charge. Write "Key-alike" in the description of your purchase order for any pedestal, overhead, file or other item you wish to have keyed alike.

Using the key-alike instructions, order cores and keys as line items on your purchase order. Do NOT submit a key-alike form. The Knoll East Greenville Lock Center will select key numbers from the standard range of K 001 - K 250. Key numbers will not be repeated unless over 250 sets are ordered. Lock cores keyed-alike will ship separately from the product, ready for field installation.

There is no charge for key-alike orders if placed with the furniture order.

IF THE KEY-ALIKE ORDER IS NOT PLACED AT LEAST TWO WEEKS PRIOR TO THE FURNITURE SHIP DATE, A $50 HANDLING CHARGE AND AIR FREIGHT CHARGES WILL APPLY.

If product is ordered and shipped random-keyed, additional lock cores for key-alike are billable.

Random-Keying

To specify product keyed-random, write "key-random" in the product description. Random-keyed product is shipped with the lock core factory installed. A shrouded key is included. Random means no effort has been made to match key numbers, or to make them different.

Keys

A Knoll shrouded key is shipped with every lock core. 250 Key numbers are available. For numbers above 250, contact Custom Product Development. Additional keys and key blanks are available. See service parts for more information.

Master Keying

Knoll locks can be controlled by means of a master key. There is no additional per-lock charge for master keying. A letter of approval from the client must accompany orders for master keys.

Installing Lock Cores

Lock cores can be installed or removed in the field by using a change key. Cores must be in the unlocked position to be removed. See service parts for change key pattern number and pricing.

Lock Distribution

All orders for key-alike lock cores/keys are packaged and shipped from the East Greenville Lock Center, regardless of where the pedestals, overhead, or other units are produced. Random keyed product will have cores factory-installed.

How to Specify Key-Alike

Following is an example of how to specify key-alike for a cluster of 10 workstations.

Step 1 - Using the project floorplan, count the number of locks in each workstation.



Step 2 - Count the number of workstations with the same quantity of locks. Group together the workstations with a like number of locks.

5 workstations with 2 locks per station
3 workstations with 4 locks per station
2 workstations with 5 locks per station

Step 3 - For the first group (5 sets of 2 locks), enter the number of workstations in the quantity column.

Qty	Pattern #	Description	Unit List	Ext. List
5				

Step 4 - Then enter the pattern number "KSPEC_ _" and add a suffix for the number of locks for that group (i.e., for 2 locks per station, add the suffix "2"). Up to 30 lock cores are available in a set (i.e., KSPEC 30).

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C

Step 5 - Repeat for other groups.

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C
3	KSPEC 4	Set of 4 cores/keys	N / C	N / C
2	KSPEC 5	Set of 5 cores/keys	N / C	N / C

Your Key instructions are complete.

Knoll will select key numbers for each set from 250 available numbers. Additional key numbers are available through Custom Product Development. **For additions to existing installations, specify desired key numbers in the description.**

Service Parts

Pattern #	Description	List Price
KKEY_ _ _	Shrouded Key Specify key number desired	$5
KBLANK	Shrouded Key Blank	$5
KSPECB_ _ _	Retrofit Universal Core/Key Specify key number desired	$22
KCHANGE	Change Key	$5
HLKRKMASTER*	Master Key	$7

*Note: A letter of approval on company letterhead from the client must accompany all orders for master keys.

General Ordering Information

The Products
This guide encompasses all standard products for this product group.

Sizes
Dimensions listed in this guide are indicated as:
H = height
W = width
D = depth
Dia. = diameter
Rad. = radius

Pricing
All prices shown are list.

How to Order
Select pattern numbers and quantities required for your complete installation. Product questions can be addressed in the specific sections of this guide or by contacting your sales representative or customer resource representative at 1-800-343-5665.

Next, select options (if required), along with colors and finishes appropriate to each product. Reference the Finishes and Fabrics pages for color designations.

On large installations, an item's "designated area" can be specified to assist in product organization and handling.

To expedite complete / correct entry of your order, be certain all pattern numbers, quantities, colors and area identifications are completely specified. Also, include complete purchase order numbers, bill-to and ship-to addresses, a contact name and specific factory shipping dates required.

Mail all orders to:
Knoll, Inc.
1235 Water Street
P.O. Box 157
East Greenville, PA 18041
Attention: Order Entry

Once your order is entered at Knoll, an acknowledgment will be mailed to you. You will be advised of your scheduled shipping date within five days of the original acknowledgment. If it is necessary to revise your order, please contact your customer resource representative.

Sustainability Statement

Sustainable design is a key component of Knoll's environmental focus. Our commitment to social responsibility and a healthy environment has prompted us to further articulate our longstanding environmental programs and, with encouragement and support from our colleagues in the industry, we have re-energized our focus on such "green" initiatives as life cycle analysis and LEED™ certification. Knoll is proud to have contributed to projects that have received LEED certification from the U.S. Green Building Council.

For the latest information on Knoll products that help our customers achieve LEED certification, log on to knoll.com, click on "About Knoll" and then "Environmental Focus."